


Link Union Station

Draft Preliminary Geotechnical Report

June 2024



The environmental review, consultation, and other actions required by applicable Federal environmental laws for this project are being, or have been, carried out by the State of California pursuant to 23 U.S.C. 327 and a Memorandum of Understanding dated July 23, 2019, and executed by the Federal Railroad Administration and the State of California.

(THIS PAGE INTENTIONALLY LEFT BLANK)

CONTENTS

ES.0	Executive Summary	v
1.0	Introduction	1
1.1	Purpose	2
1.2	Need	2
1.3	Project Location and Study Area	2
1.4	Project Alternatives	9
1.4.1	No Action Alternative	9
1.4.2	Build Alternative	10
1.4.3	Rail Yard Canopy Design Options	11
1.5	Project Implementation Approach	11
1.5.1	Interim Condition	11
1.5.2	Full Build-Out Condition	12
1.5.3	Full Build-Out with High-Speed Rail Condition	13
2.0	Report Purpose	15
3.0	Methodology	17
4.0	Literature Review	19
5.0	Site Conditions	21
5.1	Existing Facilities	21
5.1.1	Los Angeles County Metropolitan Transportation Authority Red Line Tunnel	22
6.0	Geologic and Geotechnical Conditions	25
6.1	Geologic Setting	25
6.2	Faulting and Seismicity	25
6.3	Seismic Design Criteria	26
6.4	Seismic Hazards	27
6.4.1	Fault Rupture	27
6.4.2	Seismic Ground Shaking	27
6.4.3	Liquefaction and Seismically Induced Settlement	27
6.4.4	Lateral Spreading	28
6.4.5	Seiches and Tsunamis	28
6.5	Subsurface Earth Materials	28
6.6	Groundwater	29
6.7	Collapsible and Expansive Soils	30
6.8	Corrosion Potential	30
6.9	Subsidence and Settlement	30
6.10	Flooding	31
6.11	Mineral Resources	31
6.12	Environmental Concerns	31
6.13	Methane Gas	32
7.0	Geotechnical Considerations	33
7.1	Foundation Type	33
7.2	Constructability Considerations	33
7.3	Finite Element Analysis Results	34
8.0	Recommendations	35

9.0 Next Steps.....37

10.0 References.....39

TABLES

Table 5-1. As-Built Information – Existing Structures.....23

Table 6-1. Nearby Faults.....26

FIGURES

Figure 1-1. Project Location and Regional Vicinity5

Figure 1-2. Project Study Area7

APPENDICES

- Appendix A: Exhibits
- Appendix B: As-Built Plans
- Appendix C: Existing Geotechnical Boring Logs

ACRONYMS

ADA	Americans with Disabilities Act
af	artificial fill
AOBB	Amtrak Office and Baggage Building
Authority	California High-Speed Rail Authority
bgs	below ground surface
BNSF	BNSF Railway
CBC	California Building Code
Caltrans	California Department of Transportation
CDMG	California Division of Mines and Geology
CGS	California Geological Survey
CIDH	cast-in-drilled-hole
CPT	cone penetrometer test
CP	Control Point
EIS	Environmental Impact Statement
FRA	Federal Railroad Administration
FTIP	Federal Transportation Improvement Program
HSB	Historic Station Building
HSR	High-Speed Rail
LAUS	Los Angeles Union Station
LOTB	log of test boring
Metro	Los Angeles County Metropolitan Transportation Authority
MOU	Memorandum of Understanding
MSL	mean sea level
NEPA	National Environmental Policy Act
P-S	compressional wave (P) – shear wave (S)
ppm	parts per million
Project	Link Union Station Project
PTC	Positive Train Control
ROW	right-of-way
RTP	regional transportation plans
SCAG	Southern California Association of Governments
SCRIP	Southern California Regional Interconnector Project
SCRTD	Southern California Rapid Transit District
SCS	Sustainable Communities Strategy
US-101	United States Highway 101
USGS	United States Geological Survey
VCE	Vertical Circulation Elements

(THIS PAGE INTENTIONALLY LEFT BLANK)

ES.0 Executive Summary

This report presents the results of the review of existing data for the Link Union Station Project (Project or proposed action) in Los Angeles, California. The purpose of the study was to review existing data at the site and provide preliminary geotechnical recommendations for the design and construction of the Project. The executive summary briefly summarizes the results of the review, findings, recommendations, and conclusions.

- The subsurface soils generally consisted of fill ranging from a few feet generally, to up to 30 feet in the station platform area. This fill is generally considered uncertified and may require special design considerations. Beneath the fill is a layer of alluvial soil consisting of sands, gravels, and cobbles over bedrock.
- The soils within the Project study area have a moderate to severe corrosion potential to buried metal structures, and the potential for sulfate attack on concrete is considered low.
- Groundwater is relatively shallow, at depths ranging from about 14 to 48 feet.
- No active or potentially active faults are known to cross the site, and the site is not located within a currently delineated State of California Alquist-Priolo Earthquake Fault Zone. Accordingly, the risk of surface rupture due to faulting is considered low. However, the Project study area may be subjected to strong ground shaking during its lifetime. The closest mapped fault is the Elysian Park (Upper) Fault located approximately 0.8 mile from the site.
- The California Geological Survey (CGS; CGS 1999) has identified the Project study area within an area designated as potentially liquefiable. Potential for liquefaction may exist within the Project footprint and would be addressed after future field investigations.
- The probability of other geologic hazards, such as tsunamis, seiches, deep seated landslides, or ground subsidence affecting the Project study area, is considered low.
- The proposed structures are likely to be lightly loaded structures or uninhabited structures that may be able to be founded on spread footings. However, heavy loads of major structures would likely require deep foundations including driven or drilled piles. Special consideration must be given to nearby structures, subsurface conditions, and loading in determining foundation types.
- Wet method or casing may be required for drilling, with relatively clean cohesionless soils and groundwater expected at relatively shallow depths. Encountering cobbles and possibly boulders should be expected, as well as possibly contaminated soils and groundwater.
- Future geotechnical exploration is recommended to better characterize the subsurface conditions and anticipated issues that would affect the proposed improvements. In general, additional explorations should be performed at the existing platform area within Los Angeles Union Station (LAUS), along the proposed United States Highway

101 (US-101) Viaduct structure and where lead tracks would provide entrance/exit to LAUS. Refer to Section 8.0 for details.

- Exploratory borings intended for the design of foundations and/or subterranean structures should extend to a minimum depth of 100 feet or into bedrock, whichever is shallower. The spacing of exploratory borings depend on the type of structure and proposed improvements. In general, a minimum of one exploratory boring per bridge support is recommended. Standard penetration test blow counts (N-values) should be obtained from these borings. Geotechnical laboratory testing of recovered soil samples should be performed, as necessary, to obtain engineering design parameters of the subsurface materials. Additionally, shear wave velocity measurements should be considered during future geotechnical exploration. Downhole compressional and shear waves (P-S) suspension logging is the preferable method for obtaining seismic design data at the Project study area due to the accurate measurement of the shear wave velocity value and site-specific conditions.
- Prior to conducting future geotechnical explorations, a geotechnical field work plan is recommended to be prepared to describe the scope of subsequent geotechnical investigation. Future geotechnical explorations should consider existing data, preliminary findings, and the recommendations, as described in Section 8.0.
- During final design, a final geotechnical report would be prepared, incorporating new findings and updated design recommendations, which would address soil-bearing capacity, earth pressures, seismic design parameters, foundation selection, and recommendations to reduce adverse conditions.

Based on this report, the Project is feasible from a geotechnical standpoint, provided the recommendations presented in this preliminary geotechnical report are incorporated into the Project design and construction.

1.0 Introduction

The Los Angeles County Metropolitan Transportation Authority (Metro), as the owner of Los Angeles Union Station (LAUS), is proposing the infrastructure improvements associated with the Link Union Station (Link US) Project (Project or proposed action) to address existing capacity constraints at LAUS. For the purposes of the National Environmental Policy Act (NEPA), Metro is serving as the local Project sponsor and joint lead agency.

Pursuant to 23 United States Code (USC) Section 327 and a memorandum of understanding (MOU) between the Federal Railroad Administration (FRA) and the State of California, effective July 23, 2019, under a program known as NEPA Assignment, the California High-Speed Rail Authority (CHSRA) is responsible for the federal review and approval of environmental documents for projects on the high-speed rail (HSR) system and other passenger rail projects that directly connect to the HSR system, including the Link US Project. For the purposes of the environmental impact statement (EIS) being prepared, CHSRA is serving as the federal lead agency with NEPA responsibilities pursuant to the requirements of the NEPA Assignment MOU. CHSRA and Metro are preparing the EIS in compliance with NEPA (42 USC Section 4321 et seq.), the Council on Environmental Quality (CEQ) regulations implementing NEPA (40 Code of Federal Regulations [CFR] Parts 1500–1508), FRA's Procedures for Considering Environmental Impacts (FRA's Environmental Procedures) (*Federal Register* [FR] 64(101), 28545-28556, May 26, 1999), 23 USC Section 139, and the NEPA Assignment MOU.^{1, 2}

Pursuant to the MOU requirements between FRA and the State of California, FRA's Environmental Procedures are being used to determine environmental effects of the No Action Alternative and the Build Alternative.

Below is an overview of the purpose and need, the Project study area, the No Action Alternative, and the major components associated with the on-site infrastructure improvements proposed at and within the vicinity of LAUS that are associated with the Build Alternative considered in the EIS.

¹ While this environmental document was being prepared, FRA adopted new NEPA compliance regulations (23 CFR 771). Those regulations only apply to actions initiated after November 28, 2018. See 23 CFR 771.109(a)(4). Because this environmental document was initiated prior to that date, it remains subject to FRA's Environmental Procedures rather than the Part 771 regulations.

² The CEQ issued new regulations, effective April 20, 2022, updating the NEPA implementing procedures at 40 CFR Parts 1500–1508. However, because this environmental document was initiated prior to the effective date, it is not subject to the new regulations and CHSRA is relying on the regulations as they existed on the date of the initial Notice of Intent, May 31, 2016. Therefore, all citations to CEQ regulations in this environmental document refer to the 1978 regulations and the 1986 amendment, 51 *Federal Register* 15618 (April 25, 1986).

1.1 Purpose

The purpose of the proposed action is to increase the regional and intercity rail service capacity of LAUS and to improve schedule reliability at LAUS through the implementation of a run-through tracks configuration and elimination of the current stub end tracks configuration while preserving current levels of freight rail operations, accommodating the planned HSR system in Southern California, increasing the passenger/pedestrian capacity and enhancing the safety of LAUS through the implementation of a new passenger concourse, meeting the multi-modal transportation demands at LAUS.

1.2 Need

The need for the proposed action is generated by the forecasted increase in regional population and employment; implementation of federal, state, and regional transportation plans (RTP) that provide for increased operational frequency for regional and intercity trains; and introduction of the planned HSR system in Southern California. Localized operational, safety, and accessibility upgrades in and around LAUS will be required to meet existing demand and future growth.

1.3 Project Location and Study Area

The Build Alternative consists of infrastructure improvements in Downtown Los Angeles in the vicinity of LAUS (Figure 1-1). LAUS is located at 800 Alameda Street in the City of Los Angeles, California. LAUS is bounded by United States Highway 101 (US-101) to the south, Alameda Street to the west, Cesar Chavez Avenue to the north, and Vignes Street to the east. The northern Project limit is at North Main Street (Mile Post 1.18) and the southern Project limit is in the vicinity of Control Point (CP) Olympic, south of Interstate 10 and Olympic Boulevard (Mile Post 142.70).

Figure 1-2 depicts the Project study area, which is generally used to characterize the affected environment, unless otherwise specified, and provide a geographic context for the existing and proposed infrastructure improvements at and within the vicinity of LAUS. The Project study area includes three main segments (Segment 1: Throat Segment, Segment 2: Concourse Segment, and Segment 3: Run-Through Segment). The existing conditions within each segment are summarized north to south below:


- **Segment 1: Throat Segment** – This segment, known as the LAUS throat, includes CP Chavez and the area north of the platforms at the LAUS rail yard, from North Main Street at the north to Cesar Chavez Avenue at the south. In the throat segment, all arriving and departing trains are required to traverse through a complex network of lead tracks, switches, and crossovers. Five lead tracks provide access into and out of the rail yard, except for one location near the Vignes Street Bridge, where it reduces to four lead tracks. Currently, special track work consisting of multiple turnouts and double-slip switches are used in the throat to direct trains into and out of the appropriate assigned terminal platform tracks. The Garden Tracks (stub-end tracks where private train cars are currently stored) are also located just north of the platforms. Land uses in the vicinity of the throat segment are residential, industrial, and institutional.

- **Segment 2: Concourse Segment** – This segment is between Cesar Chavez Avenue and US-101 and includes LAUS, the rail yard, the East Portal Building, the baggage handling building with associated parking areas and access roads, the ticketing/waiting halls, and the 28-foot-wide pedestrian passageway with connecting ramps and stairways below the rail yard. Land uses in the vicinity of the concourse segment are residential, commercial, and public.
- **Segment 3: Run-Through Segment** – This segment is south of LAUS and extends east to west from Alameda Street to the west bank of the Los Angeles River and north to south from Keller Yard to CP Olympic. This segment includes US-101, the Commercial Street/Ducommun Street corridor, Metro Red and Purple Lines Maintenance Yard (Division 20 Rail Yard), BNSF Railway (BNSF) West Bank Yard, Keller Yard, the main line tracks on the west bank of the Los Angeles River from Keller Yard to CP Olympic, and the Amtrak lead track connecting the main line tracks with Amtrak's Los Angeles Maintenance Facility in the vicinity of 8th Street. Land uses in the vicinity of the run-through segment are primarily industrial and manufacturing.

The Project study area has a dense street network ranging from major highways to local city streets. The roadways within the Project study area include the El Monte Busway, US-101, Bolero Lane, Leroy Street, Bloom Street, Cesar Chavez Avenue, Commercial Street, Ducommun Street, Jackson Street, East Temple Street, Banning Street, First Street, Alameda Street, Garey Street, Vignes Street, Main Street, Aliso Street, Avila Street, Bauchet Street, and Center Street.


(THIS PAGE INTENTIONALLY LEFT BLANK)

Figure 1-1. Project Location and Regional Vicinity



(THIS PAGE INTENTIONALLY LEFT BLANK)

Figure 1-2. Project Study Area



(THIS PAGE INTENTIONALLY LEFT BLANK)

1.4 Project Alternatives

The EIS includes an evaluation of the No Action Alternative and one build alternative (Build Alternative). The Build Alternative would include, but not be limited to, new lead tracks north of LAUS (Segment 1: Throat Segment), an elevated throat and rail yard with concourse-related improvements at LAUS (Segment 2: Concourse Segment), and 10 run-through tracks south of LAUS (Segment 3: Run-Through Segment).

1.4.1 No Action Alternative

NEPA (40 CFR 1502.14(d)) requires federal agencies to include an analysis of “the alternative of no action.” For NEPA purposes, the No Action Alternative is the baseline against which the effects of implementing the Build Alternative is evaluated against to determine the extent of environmental and community effects. For the No Action Alternative, the baseline year is 2016, and the horizon year is 2040.

The No Action Alternative represents the future conditions that would occur if the proposed infrastructure improvements and the operational capacity enhancements at LAUS were not implemented. The No Action Alternative reflects the foreseeable effects of growth planned for the area in conjunction with other existing, planned, and reasonably foreseeable projects and infrastructure improvements in the Los Angeles area, as identified in planning documents prepared by Southern California Association of Governments (SCAG), Metro, and/or Metrolink, including the 2023 Federal Transportation Improvement Program (FTIP) (SCAG 2023), *Final 2008 Regional Comprehensive Plan* (SCAG 2008), and the 2020 RTP/Sustainable Communities Strategy (SCS): Connect SoCal (SCAG 2020).

Conditions in the Project study area would remain similar to the existing condition, as described below:

- **Segment 1: Throat Segment** – Trains would continue to operate on five lead tracks that do not currently accommodate the planned HSR system. The tracks north of LAUS would remain at the current elevation, and the Vignes Street Bridge and Cesar Chavez Avenue Bridge would remain in place.
- **Segment 2: Concourse Segment** – LAUS would not be transformed from a stub end tracks station into a run-through tracks station, and the 28-foot-wide pedestrian passageway would be retained in its current configuration. No modifications to the existing passenger circulation routes or addition of vertical circulation elements (VCE; escalators and elevators) at LAUS would occur.
- **Segment 3: Run-Through Segment** – Commercial Street would remain in its existing configuration, and implementation of active transportation improvements would likely be implemented along Center Street in concert with the *Connect US Action Plan* (Metro 2015). No modifications to the BNSF West Bank Yard would occur.

1.4.2 Build Alternative

The key components associated with the Build Alternative are summarized north to south below:

- **Segment 1: Throat Segment (lead tracks and throat track reconstruction)** – The Build Alternative includes subgrade and structural improvements in Segment 1 of the Project study area (throat segment) to increase the elevation of the tracks leading to the rail yard. The Build Alternative includes the addition of one new lead track in the throat segment for a total of six lead tracks to facilitate enhanced operations for regional/intercity rail trains (Metrolink/Amtrak) and future operations for HSR trains within a shared track alignment. Regional/intercity and HSR trains would share the two western lead tracks in the throat segment. The existing railroad bridges in the throat segment at Vignes Street and Cesar Chavez Avenue would also be reconstructed. North of CP Chavez on the west bank of the Los Angeles River, the Build Alternative also includes safety improvements at the Main Street public at-grade railroad crossing (medians, restriping, signals, and pedestrian and vehicular gate systems) to facilitate future implementation of a quiet zone by the City of Los Angeles.
- **Segment 2: Concourse Segment (elevated rail yard and expanded passageway)** – The Build Alternative includes an elevated rail yard and expansion of the existing 28-foot-wide pedestrian passageway in Segment 2 of the Project study area (concourse segment). The rail yard would be elevated approximately 15 feet. New passenger platforms would be constructed on the elevated rail yard with associated VCEs (stairs, escalators, and elevators) to enhance safety elements and improve Americans with Disabilities Act (ADA) accessibility. Platform 1, serving the Gold Line, would be lengthened, and elevated to optimize east to west passenger circulation. The pedestrian passageway would be expanded at the current grade to a 140-foot width to accommodate a substantial increase in passenger capacity with new functionally modern passenger amenities while providing points of safety to meet applicable California Building Code (CBC) and National Fire Protection Association (NFPA) 130 Standards for Fixed Guideway Transit Systems. The expanded passageway and associated concourse improvements would facilitate enhanced passenger circulation and provide space for ancillary support functions (back-of-house uses, baggage handling, etc.), transit-serving retail, and office/commercial uses while creating an opportunity for an outdoor, community-oriented space with new plazas east and west of the elevated rail yard (East and West Plazas). Amtrak ticketing and baggage check-in services would be enhanced, and new baggage carousels would be constructed in a centralized location under the rail yard. A canopy would be constructed over the West Plaza up to 70 feet in height, and two design options are considered for canopies that would extend over the rail yard (Section 1.4.3).
- **Segment 3: Run-Through Segment (10 run-through tracks)** – The Build Alternative includes 10 new run-through tracks south of LAUS in Segment 3 of the Project study area (run-through segment). The Build Alternative includes common rail infrastructure from LAUS to the west bank of the Los Angeles River (vicinity of First Street

Bridge) to support run-through tracks for both regional/intercity rail trains and future HSR trains. At the BNSF West Bank Yard, dedicated lead tracks for Amtrak trains and BNSF trains, in combination with implementation of common rail infrastructure would result in permanent loss of freight rail storage track capacity at the north end of BNSF West Bank Yard (5,500 track feet).

The Build Alternative would also require modifications to US-101 and local streets (including potential street closures and geometric modifications); improvements to railroad signal, positive train control (PTC), and communications systems; modifications to the Gold Line light rail platform and tracks; modifications to the main line tracks on the west bank of the Los Angeles River; modifications to the Amtrak lead track; addition of access roadways to the railroad right-of-way (ROW); land acquisitions; addition of utilities; utility relocations, replacements, and abandonments; and addition of drainage facilities/water quality improvements.

1.4.3 Rail Yard Canopy Design Options

Two design options for canopies over the elevated platforms in the rail yard are considered in conjunction with the concourse-related improvements as part of the Build Alternative.

- **Rail Yard Canopy Design Option 1 (individual canopies)** – This design option would include replacing the existing historic butterfly canopies with individual canopies above each platform. New individual canopies would extend up to 25 feet above each platform and would be similar in form to the existing butterfly canopies but sized to fit the widened and lengthened platforms. Platform lengths would vary between 450 and 1,445 feet. Platforms would be up to 30 feet wide.
- **Rail Yard Canopy Design Option 2 (grand canopy)** – This design option would include replacing the existing historic butterfly canopies with a large grand canopy that would extend up to 75 feet above the elevated rail yard platforms. The grand canopy would be up to 1,500 feet long and wide enough to provide cover over all elevated platforms in the rail yard.

1.5 Project Implementation Approach

The implementation of infrastructure improvements would generally occur in three main phases that are evaluated as scenario years in the EIS: the interim condition, the full build-out condition and the full build-out with HSR condition. The infrastructure improvements for each of these scenarios are described below.

1.5.1 Interim Condition

The interim condition is when the run-through track infrastructure south of LAUS and the associated signal modifications, property acquisitions, and civil/structural improvements to facilitate new run-through service would be implemented. The interim condition does not include new lead tracks north of LAUS, or the elevated rail yard and new concourse-related improvements at LAUS. The interim condition aligns with a construction completion date as early as 2026.

A summary of the proposed activities associated with the interim condition is provided below.

- Acquire properties south of LAUS within the Project footprint.
- Relocate utilities north and south of LAUS.
- Acquire a portion of the BNSF West Bank Yard (majority north of First Street) and remove 5,500 feet of existing storage tracks at BNSF West Bank Yard.
- Construct special track work and modify signal/communication infrastructure north of LAUS.
- Construct a run-through track ramp on the southern extent of Platform 4 at LAUS.
- Construct a common viaduct/deck over US-101.
- Construct a common embankment from Vignes Street to Center Street south of LAUS.
- Construct common Center Street Bridge south of LAUS.
- Construct common embankment or new common bridge from Center Street to Amtrak Bridge south of LAUS.
- Construct common Amtrak Bridge south of LAUS.
- Construct Division 20 access road.
- Construct common rail embankment on the west bank of the Los Angeles River (from Amtrak Bridge to First Street Bridge).
- Construct new dedicated lead tracks for BNSF freight trains and Amtrak trains.
- Construct two run-through tracks from Platform 4 at LAUS to the main line tracks along the west bank of the Los Angeles River.

Some embankments and/or bridges south of LAUS could be constructed in a phased manner.

1.5.2 Full Build-Out Condition

The full build-out condition is when new lead tracks and the elevated throat north of LAUS, along with the elevated rail yard and concourse-related improvements at LAUS would be implemented. The full build-out condition aligns with a construction completion date as early as 2031.

A summary of the proposed activities associated with the full build-out condition is provided below.

- Construct new compatible lead tracks and reconstruct throat north of LAUS.
- Construct new bridges over Vignes Street and Cesar Chavez Avenue north of LAUS.
- Construct elevated rail yard, concourse-related improvements, and East/West Plazas at LAUS.

- Construct remaining run-through tracks for regional/intercity rail operations on previously constructed structures south of LAUS.

1.5.3 Full Build-Out with High-Speed Rail Condition

The full build-out with HSR condition is when HSR tracks and catenaries would be implemented through the Project limits to facilitate operation of the planned HSR system. CHSRA is responsible for construction and operation of the planned HSR system, and the EIS identifies where future HSR tracks, catenaries, and related operational infrastructure would be located throughout the Link US Project limits. Operation of HSR trains would occur on two of the lead tracks north of LAUS, Platforms 2 and 3 and associated Tracks 3 through 6 at LAUS, and common rail bridges and embankments south of LAUS. The full build-out with HSR condition corresponds to an HSR opening year consistent with CHSRA's 2022 Business Plan (as early as 2033).

(THIS PAGE INTENTIONALLY LEFT BLANK)

2.0 Report Purpose

The purpose of this report is to:

- Document existing geologic, geotechnical, and seismic conditions, including subsurface soils, groundwater, seismicity, corrosion potential, subsidence, and environmental concerns relevant to the Project.
- Facilitate the understanding of the existing geologic and geotechnical information at the Project site that would be used for the preliminary design of the proposed improvements and during the planning of future geotechnical exploratory investigations. During the planning of future geotechnical investigations, the existing available data and findings presented in this report would be taken into consideration to allocate resources where geotechnical information is missing and/or augment subsurface geotechnical information in other areas within the Project limits.
- Identify constructability conditions relevant to proposed improvements. The early identification of these conditions would provide the opportunity to consider alternatives during the planning, design, and construction phases.
- Provide preliminary recommendations for foundation selection, summarize key constructability-related subsurface conditions affecting the Project, and provide recommendations for future geotechnical investigations.

(THIS PAGE INTENTIONALLY LEFT BLANK)

3.0 Methodology

The methodology used in this report included the following tasks:

- **Literature Review** – Public agencies were contacted to obtain relevant geotechnical and geology reports for the Project site. Documents reviewed were obtained from the City of Los Angeles Department of Public Works, City of Los Angeles Department of Building and Safety, Caltrans, and Metro. The reviewed documents include published geologic maps; planning documents and hazard maps; as-built log of test borings (LOTB); and previous geotechnical and environmental reports for LAUS, Metro Red Line Tunnel, East Side Underpass Light Rail Transit (Gold Line Eastside Extension), and nearby developments. This review provided the basis for the evaluation of site conditions and geologic and geotechnical conditions present within the Project study area.
- **Site Conditions** – The existing site conditions present where infrastructure improvements are proposed were described. A site reconnaissance was performed to visually identify existing facilities, evaluate the accessibility to the site for future explorations, confirm desk study findings, and identify potential issues that could affect the proposed improvements.
- **Geologic and Geotechnical Conditions** – Relevant geologic and geotechnical data were compiled in this report, along with the findings for the proposed action. Topics covered included faulting and seismicity, seismic hazards, subsurface soil conditions, groundwater, and environmental-related issues.
- **Geotechnical Considerations** – Discussion and conclusions were provided regarding foundation selection, constructability conditions, and summary of finite element analysis results for the proposed improvements.
- **Recommendations** – Recommendations for additional geotechnical investigations were provided to better characterize the subsurface conditions where infrastructure improvements are proposed and to confirm the preliminary findings of this report.
- **Next Steps** – Discussion was provided for subsequent actions to follow this report.
- **References** – A list of references used in the preparation of this report was provided.

(THIS PAGE INTENTIONALLY LEFT BLANK)

4.0 Literature Review

Various documents were reviewed pertaining to the Project study area. Documents reviewed include published geologic maps; planning documents and hazard maps; LOTBs; and previous geotechnical and environmental reports for LAUS, Metro Red Line Tunnel, East Side Underpass Light Rail Transit (Gold Line Eastside Extension), and nearby developments (Exhibit 4-1 in Appendix A). A list of maps, reports, and documents reviewed is presented below.

Published geologic and hazard maps include the following:

- State of California - Special Studies Zones – Los Angeles Quadrangle, Official Map. (California Division of Mines and Geology [CDMG] 1977).
- State of California Seismic Hazard Zones – Los Angeles 7.5 Minute Quadrangle (CGS 1999).
- Los Angeles County Tsunami Inundation Maps (CGS 2009).
- Geologic Compilation of Quaternary Surficial Deposits in Southern California, Los Angeles 30'x 60' Quadrangle (CGS 2012).
- Quaternary Fault and Fold Database for the United States (United States Geological Survey [USGS] and CGS 2006).

Geotechnical information reviewed includes geotechnical reports for LAUS, as well as nearby developments, and as-built plan sheets (Appendix B) presenting LOTBs for nearby Caltrans structures. Pertinent LOTBs are provided in Appendix C, alphabetically by reference name. The complete list of documents reviewed is presented in Section 10.0. The following is a list of the most relevant geotechnical reports and documents considered in this report:

- *Final Environmental Impact Report/EIS, Run-Through Tracks Project* (Caltrans and FRA 2005).
- *Final Geotechnical Summary Report, SR-710 Tunnel Technical Study, Los Angeles County, California* (Caltrans 2010).
- *Geotechnical Investigation Report Volume I, Southern California Rapid Transit District [SCRTD], Metro Rail Project* (Metro 1981).
- *Geotechnical Report: Metro Rail Project-Design Unit A135, LOTBs SCRTD* (Metro 1983).
- *Union Station Area Aquifer Pump Tests Metro Rail Project* (Metro 1986).
- *Temporary Tunnel Excavation Support by Chemical Grouting. Grouting Soil Improvement and Geosynthetics Proceedings, GT Div. ASCE* (Gularte et al. 1992).
- *Geotechnical Engineering and Groundwater Study, Proposed Two Level Subterranean Parking Garage and Four Story Office* (Catellus Urban Development Corporation 1998).

- *Report of Phase I Environmental Site Assessment, Alameda District Plan* (Cordoba Corporation 1994).
- *Metro Rail Project, Main Yard and Shops Yard Leads* (Metro 1988).
- *The Phase I Subsurface Investigation at the Metro Rail A-130 Corridor* (Metro 1987a).
- *The Phase III Subsurface Investigation at the Metro Rail A-130 Corridor* (Metro 1987b).
- *The Phase IV Subsurface Investigation at the Metro Rail A-130 Corridor* (Metro 1987c).
- *Geotechnical Investigation, Proposed West Campus Infrastructure Project, Los Angeles, California, LOTBs* (Catellus Urban Development Corporation 2003).
- *Phase I Environmental Site Assessment and Limited Phase II Testing Selected Portions of the LAUS Property* (TPG Capital, L.P. 2011).

Technical memoranda addressing specific design considerations, including preliminary seismic design parameters for proposed improvements, the potential lowering of the intersection grade at Commercial Street and Center Street, and potential effects on the Metro Red Line Tunnel due to the proposed aerial structures, were also reviewed. The documents reviewed include the following:

- *Preliminary Draft Report for Seismic Design Parameters, Southern California Regional Interconnector Project (SCRIP)* (Metro 2015b).
- *Draft Technical Memorandum Static and Seismic Performance of Red Line Tunnel, SCRIP* (Metro 2016a).
- *Draft Technical Memorandum Impact of Lateral Pile Loading on Red Line Tunnel, SCRIP Project–Geotechnical Fatal Flaw Study* (Metro 2016b).

Pertinent findings and information contained within these maps, memoranda, and reports are discussed within the body of this study.

5.0 Site Conditions

5.1 Existing Facilities

LAUS is located in the northeastern portion of Downtown Los Angeles, on the property bounded by Alameda Street, Cesar Chavez Avenue, Vignes Street, and US-101 (Exhibit 5-1, Appendix A). In general, surface conditions across the Project study area are considered improved, consisting of commercial/industrial and residential developments.

A field reconnaissance was conducted August 15, 2014, of the Project footprint area and April 20, 2016, within the LAUS area to evaluate existing facilities and activities. The Project is located within a mixed industrial-commercial use area. Metro owns most of LAUS, including train platforms, rail tracks, and some nearby facilities. Other owners include the City and County of Los Angeles and private corporations. Specific site locations that were explored during these field visits included the Historic Station Building (HSB), Amtrak Office and Baggage Building (AOBB), LAUS train platforms, Gateway Station Building, Metro Red Line, Cesar Chavez Avenue Undercrossing (Bridge Number [No.] 53C-131), and the facilities in the vicinity of Commercial and Center Streets. The site overlies two major tunnels: one constructed for pedestrian access and the other for the Metro Red Line. A detailed description of the Metro Red Line Tunnel is provided in Section 5.1.1. The pedestrian tunnel is about 28 feet wide and traverses one floor level below the surface tracks and platforms connecting the AOBB and Gateway Station Building with the boarding platforms (Caltrans and FRA 2005).

The HSB is east of Alameda Street and adjacent to the Metropolitan Water District Building. It incorporates retail businesses, a waiting area for passengers, and ticket booths within its central portion. Driveways, an enclosed garden, and a subterranean parking garage are located within the HSB area. The eastern portion of the HSB constitutes the AOBB, used by Amtrak for luggage handling and storage area. Important features to consider for future geotechnical exploration activities include the underground tunnel for the Metro Red Line subway located north of the HSB and the connecting pedestrian tunnel underneath the LAUS train platforms to the AOBB area.

The LAUS train platforms, located on the central portion of LAUS, consist of 6 reinforced concrete platforms with access to 12 rail lines serving Metrolink and Amtrak trains. There is an additional platform located adjacent to the AOBB parking lot area that is in use by the Metro Gold Line. All the Amtrak/Metrolink platforms are accessed through the underground pedestrian tunnel via stairs and access ramps located on both sides of the pedestrian tunnel. The Gold Line platform is accessed via stairs or by an elevator located adjacent to the underground pedestrian tunnel. The surficial materials encountered on the rail tracks consist predominantly of ballast rock, and the areas surrounding the platforms are either concrete or paved surfaces.

The Gateway Station Building is located on the eastern portion of LAUS, adjacent to the train platforms and north of US-101. This building serves as the eastern entrance for the Metro subway lines, Metro buses, and Amtrak/Metrolink.

Commercial Street, located south of LAUS and parallel to US-101, was explored to identify potential issues with the proposed aerial structures on August 14, 2014. During this site visit,

personnel performed a reconnaissance of the street starting at Hewitt Street on the west end and terminating at the east end of Commercial Street near the Metro's ROW and railroad tracks. In addition, the intersection of Commercial Street and Central Street was visually explored to evaluate the potential lowering of the intersection grade. Observed land uses within the area consist of existing commercial and industrial establishments. The pavement condition ranges from poor to fair in most of the observed areas. Access to the Metro's ROW parallel to the Los Angeles River was not available on foot at the time of this visit, but future geotechnical exploration of these premises is considered accessible with the required entry permits.

Other facilities near the proposed infrastructure improvements include commercial buildings, parking lots, residential buildings, a Metro bus station, mechanic shops, major freeways and local streets, the Metro Gold Line Bridge, and underground utilities. Existing utility research in this area indicates existing storm drain, steam, air, petroleum products, fiber optic, sewer, electric, water, natural gas, and various other lines within LAUS and the surrounding area.

A summary of existing facilities and foundation information is provided in Table 5-1.

5.1.1 Los Angeles County Metropolitan Transportation Authority Red Line Tunnel

The Metro Red Line Tunnel is a twin cast-in-place concrete tunnel that runs in a northwest-to-southeast direction through LAUS. Each tunnel is nearly 20 feet in diameter with a nominal 12-inch thick concrete lining and located approximately 28 feet apart center-to-center. Within LAUS, this structure runs beneath the station's platforms and pedestrian tunnel. Southeast of LAUS, the Metro Red Line Tunnel begins at grade level, described as the east portal, and runs beneath the intersection of Commercial Street and Center Street, some private lots, and US-101. The construction of the tunnel segment located within LAUS was performed using the cut-and-cover method, and the excavations were supported by the implementation of tiebacks (pre-stressed soil anchors). After construction of the tunnel concrete box structure at LAUS, the tiebacks were abandoned in place (Metro 1988). The tunnel segment located southeast of LAUS was bored using a conventional tunnel boring machine. Horizontal and vertical grouting techniques were implemented for soil stabilization for the segments that run beneath the intersection of Commercial Street and Center Street and beneath US-101. The chemical grouting was applied around the Metro Red Line Tunnel, forming a binocular-shaped underground structure (Metro 2016a). The Metro Red Line Tunnel invert elevation ranges from about 265 feet mean sea level (MSL) near the east portal entrance and slopes down as it advances northwest with an average invert elevation of about 237 feet MSL beneath US-101 and LAUS. Photographs taken during the construction of the Metro Red Line Tunnel are presented on Exhibits 5-2 and 5-3 in Appendix A.

During the construction of the tunnel segment between the intersection of Commercial Street and Center Street and US-101, a fire incident was reported July 13, 1990. Based on the reviewed documents, the fire was initiated by a spark from the cutting torch used during the installation of high-density polyethylene membrane. During this fire, approximately 730 feet of tunnel lagging used for support was destroyed causing the collapse of this tunnel segment that, at the time of the fire, was ungrouted (Gularte et al. 1992).

Table 5-1. As-Built Information – Existing Structures

Structure	Approximate Foundation Elevation (feet MSL)	Foundation Type	Number of Piles	Average Tip Elevation (feet MSL)	Approximate Pile Length (feet)	Pile Construction Technique
<i>Los Angeles River Bridge and Overhead at Aliso Street (Bridge No. 53-0405) – Initial Construction (Approximately 1954)</i>						
Abutment/Pier 1A, 2A, 1B-17B, 19D, and 20D	270	16-inch diameter CIDH	Hundreds	255	15	Drilled in place
West and East Arch Abutments, Piers 24D and 25D, Abutment 1 – Pier 25	236 at Arch abuts, 267 at Piers	Spread Footing	—	—	—	—
Pier 26 – Abutment 28	255	7-gauge fluted 16-inch diameter cast-in-steel-shell	Hundreds	230	20 - 38	Driven
<i>Los Angeles Street Overcrossings (Bridge No. 53-0629) – Initial Construction (Approximately 1949)</i>						
All	259	Spread footing	—	—	—	—
<i>Alameda Street Overcrossing (Bridge No. 53-0782) – Initial Construction (Approximately 1952)</i>						
All	240	Spread footing	—	—	—	—
<i>Eastside Underpass [Gold Line] (Bridge No. 53-2975)– Initial Construction (Approximately 2004)</i>						
Abutment 1	288	4-foot diameter CIDH	6	210	78	Drilled in place
Bent 2 and Bents 6–9	262	8-foot diameter CIDH	1 each	190	72	

Table 5-1. As-Built Information – Existing Structures

Structure	Approximate Foundation Elevation (feet MSL)	Foundation Type	Number of Piles	Average Tip Elevation (feet MSL)	Approximate Pile Length (feet)	Pile Construction Technique
Bents 3–5	267	10-foot diameter CIDH	1 each	194	73	
Abutment 10	269	3-foot diameter CIDH	5	215	54	

Source: Caltrans n.d., 1949, 1954, and 2004

Notes:

No.=number; MSL=mean sea level, CIDH=cast-in-drilled-hole

6.0 Geologic and Geotechnical Conditions

6.1 Geologic Setting

The Project study area is located within the Los Angeles Basin near the boundary of the Transverse Ranges Province and the northern Peninsular Ranges Geomorphic Province. The mountain ranges include the Santa Monica and San Gabriel Mountains located northwest of the Project study area and the Palos Verdes Hills toward the southwest. The Transverse Ranges are characterized by an east to west trending complex group of mountain ranges and valleys. The Transverse Ranges are comprised predominantly of sedimentary rocks, Mesozoic granitic rocks, and ancient Precambrian rocks of all types. The northern Peninsular Ranges are characterized by a series of northwest to southwest trending mountains and faults. These mountain ranges are composed of metamorphosed sedimentary and volcanic rocks of Jurassic age that have been intruded by mid-Cretaceous plutonic rocks of the Southern California batholith and rimmed by Cenozoic sedimentary rocks (Gastil and Krummenacher 1981; Schoellhamer et al. 1981).

The Project footprint area is located west of the Los Angeles River on a gently sloping alluvial surface. Topography within the Project footprint area slopes downward from north to south with ground elevations ranging from about 295 to 274 feet above MSL. Based on the review of the Geologic Compilation of Quaternary Surficial Deposits in Southern California (CGS 2012), the Project footprint area is underlain by Holocene-age and Pleistocene alluvium deposits consisting of silty sands, sands and silts with varying amounts of gravel and cobbles (Exhibit 6-1 in Appendix A). Beneath the alluvium layers, Miocene Puente marine sedimentary formations are present within the Project footprint area (Bilodeau et al. 2007). Although not shown on the published map, artificial fill (af) is anticipated within the Project footprint area related to the construction of the existing structures and improvements.

6.2 Faulting and Seismicity

The review of available literature indicates there are no known active or potentially active faults that have been mapped within the Project study area and the Project study area is not located within an Alquist-Priolo Earthquake Fault Zone (see Exhibits 6-2 and 6-3 in Appendix A). The principal seismic hazard that could affect the site is ground shaking resulting from an earthquake occurring along one of several major active or potentially active faults in Southern California. Based on the review of the Caltrans Acceleration Response Spectrum Online (Caltrans 2016b), the USGS and CGS (USGS and CGS 2006) Quaternary Fault and Fold Database, and the Alquist-Priolo Special Studies Zone Map for Los Angeles Quadrangle (CDMG 1977), the closest active faults that could affect the site, approximate distances, fault lengths, and magnitudes are presented in Table 6-1.

Table 6-1. Nearby Faults

Fault Name	Distance from Site (Mile) ^b	Moment Magnitude ^c
Elysian Park (Upper) ^a	0.8	6.6
Hollywood	4.3	6.6
Puente Hills (Los Angeles) ^a	4.5	6.9
Raymond	4.6	6.7
Santa Monica	4.6	7.0
Verdugo	6.8	6.8
Newport Inglewood	8.4	7.2
Sierra Madre	11.0	7.2
Elsinore	11.6	6.9
Malibu Coast	16.7	6.6
Palos Verdes	17.7	7.2
San Gabriel	18.2	7.3
THUMS – Huntington Beach	19.6	6.6
Northridge Hills	19.3	6.4

Note:

^a *Blind thrust fault: Mapped by Caltrans Acceleration Response Spectrum Online but not mapped by USGS and CGS (Caltrans 2016b; USGS and CGS 2006)*

^b *Distance from site is approximate and measured from LAUS (USGS and CGS 2006)*

^c *Caltrans 2016b*

6.3 Seismic Design Criteria

To mitigate the effects of ground shaking produced by regional seismic events, seismic design should be performed in accordance with the applicable building codes. Seismic design criteria and recommendations relevant to the proposed improvements are included in a preliminary technical memorandum prepared by Earth Mechanics, Inc. (Metro 2015b).

6.4 Seismic Hazards

6.4.1 Fault Rupture

Based on available literature and reports, no active faults are known to traverse the Project study area and the Project study area is not located within a currently designated Alquist-Priolo Earthquake Fault Zone. The nearest special study zone as mapped by CDMG is approximately 5.5 miles from the Project location (CDMG 1977) (Exhibit 6-3 in Appendix A).

6.4.2 Seismic Ground Shaking

The Project is located within an active seismic region and is expected to experience ground shaking from an earthquake occurring along several major active or potentially active faults in Southern California (Section 6.2 for details). Consequently, the implementation of the proposed improvements may increase the number of people exposed to effects associated with seismically induced ground shaking. The seismic ground shaking hazard is considered moderate to high.

6.4.3 Liquefaction and Seismically Induced Settlement

Liquefaction is the loss of soil strength or stiffness due to a buildup of pore-water pressure during ground shaking. Liquefaction is associated primarily with loose (low-density), saturated, fine- to medium-grained, cohesionless soils. Effects of liquefaction can include sand boils, excessive displacements, bearing capacity failures, and lateral spreading. Seismically induced settlement consists of dry dynamic settlement (above groundwater) and liquefaction-induced settlement (below groundwater). This settlement occurs primarily within loose to moderately dense sandy soil due to reduction in volume during and shortly after an earthquake event.

Based on the review of the Seismic Hazard Zones map for the Los Angeles 7.5-Minute Quadrangle (CGS 1999), the Project study area is located within an area designated as potentially liquefiable (Exhibit 6-3 in Appendix A).

A review of existing borings from nearby projects and borings performed by others at LAUS and surrounding areas, the groundwater level ranges between depths of approximately 14 to 48 feet below ground surface (bgs) (corresponding groundwater elevations range from about 222 to 256 feet MSL). Historical groundwater depths as shallow as 13.5 feet below ground were reported (Catellus Urban Development Corporation 1998, 2003), but more recent measurements indicated a steady groundwater level decline (Section 6.6 for discussion). The soils encountered below groundwater are generally alluvial deposits consisting of medium dense to very dense sandy silts, silty sands, and sands with gravel that are not considered susceptible to liquefaction. However, there is evidence of thin interbedded loose materials within the upper 30 feet of the Project study area. These layers would need to be evaluated during future subsurface exploration to confirm their liquefaction potential for the site. In general, and from a preliminary standpoint, based on the available geotechnical data and groundwater assumptions (see Section 6.6), the potential for liquefaction and seismically induced settlement to occur within the Project study area is considered low.

6.4.4 Lateral Spreading

Lateral spreading is a type of landslide motion generally characterized by progressive cracking and ground motion near a slope face. Lateral spreading is generally associated with liquefiable soils, which allow the slope face and surrounding area to flow during or shortly after earthquake ground motions. Conditions favorable for lateral spreading are frequently found along streams and waterfronts or in loosely placed, saturated, sandy fill (Rauch 1997). The Los Angeles River is located southeast of LAUS; it is a channelized concrete channel. Based on the proposed improvements, as well as the known soil conditions, the potential for lateral spreading within the Project study area is considered low. The liquefaction potential should be further evaluated during the design phase of the Project, using site-specific information collected from future exploratory borings.

6.4.5 Seiches and Tsunamis

Seiches are large waves generated in enclosed bodies of water in response to ground shaking. Tsunamis are waves generated in large bodies of water by fault displacement or major ground movement. Based on the absence of enclosed bodies of water near the Project study area and the CGS Tsunami Inundation Map (CGS 2009), seiche and tsunami risks at the Project study area are considered negligible.

6.5 Subsurface Earth Materials

The review of existing geotechnical data, geologic maps, reports, and other pertinent information indicates the Project study area is underlain by varying amounts of artificial fill and young alluvium deposits ranging from loose to medium dense materials, such as silty sands/sandy silts, silt, and sands with varying amounts of gravel and cobbles. The artificial fill varies in composition but is generally known to contain construction debris, as well as imported natural earth materials. The compaction of this layer is uncertain and, therefore, this layer of fill is categorized as “uncertified fill.” Generally, in Los Angeles County, uncertified fill may not be used to support loads from structures, and the removal and recompaction of this layer should be anticipated for construction. In the review of existing data, the artificial fill layer varies from about 5 to 15 feet in thickness but may extend to depths as great as about 30 feet bgs in some locations. Within the concourse area, the artificial fill ranges from about 20 to 30 feet bgs. The young alluvium encountered within the Project study area consists primarily of coarse-grained deposits ranging in consistency from loose to very dense silty sands, clayey sands, and sands with varying amounts of gravel and cobbles. Interbedded fine-grained deposits consisting of soft to stiff sandy silts, silt, and clay were also observed within the young alluvium in the LAUS area (Metro 1983). Generally, the thickness of the young alluvium within the Project study area ranges from about a few feet to up to 85 feet.

The fill and younger alluvium deposits are underlain by the Puente Formation. The Puente Formation (bedrock) consists predominantly of interbedded siltstone and sandstone with thinly bedded claystone. The degree of weathering of the bedrock decreases with increasing depth. The upper several feet of the bedrock is weakly cemented and susceptible to softening or slaking in the presence of water; however, deeper beds are strongly cemented. Near the platforms/tracks

and the concourse passenger areas, bedrock was generally encountered at approximately elevation 200 feet MSL, which is about 95 feet below existing grade (Metro 1983). On the southeast side of LAUS and east of the intersection of Commercial Street and Central Street, bedrock is generally estimated at depths ranging from about 75 to 85 feet bgs. However, the borings performed for the Gold Line Eastside Extension Project located near the intersection of Alameda Street and Commercial Street encountered bedrock at depths ranging from 49 to 75 feet bgs or corresponding elevations ranging from 226 to 218 feet MSL. Other areas in the vicinity of the Project study area encountered bedrock at relatively shallow depths ranging from about 18 to 30 feet bgs or corresponding elevations ranging from 245 to 257 feet MSL in the southwestern portion of LAUS as described in the geotechnical exploratory borings (Catellus Urban Development Corporation 2003). Other data reviewed included borings located on Cesar Chavez Avenue, Keller Street, and Lyon Street, which did not encounter bedrock within their exploration depths (up to about 50 feet bgs).

In general, the Puente Formation is of low to moderate strength with locally hard, cemented, and interbedded concretions. Limited unconfined compressive strength tests performed for the Metro Red Line Tunnel indicates unconfined compressive strengths ranging from about 10 to 175 pounds per square inch, with an average value of about 80 pounds per square inch (Metro 1983). Based on the review of the report performed by others (Caltrans 2010), the unconfined compressive strength of the Puente Formation varies from about 50 to 750 pounds per square inch (Caltrans 2010). The strength of cemented layers and concretions vary from 4,000 to 15,400 pounds per square inch (Caltrans 2010). Cross sections utilizing selected boring logs obtained from the previous reports were prepared for LAUS and Commercial Street (Exhibits 6-4 and 6-5 in Appendix A).

6.6 Groundwater

Based on the review of previous reports and available data, the groundwater levels within the Project footprint area range between approximately 14 and 48 feet bgs (corresponding groundwater table elevations range from about 222 to 256 feet MSL). Historical groundwater depths as shallow as 13.5 feet below ground were reported (Catellus Urban Development Corporation 1998, 2003), but more recent measurements indicate a steady groundwater level decline. The groundwater quality at the Project study area is not specifically known, but the groundwater may contain inorganic constituents, as well as organic contaminants from solvent and petroleum hydrocarbon pollution associated with industrial activities in the area (Caltrans and FRA 2005). Underground facilities, as well as temporary excavations during construction, should anticipate encountering groundwater if greater than about 10 to 15 feet bgs. See Section 6.12 regarding potential groundwater contamination. For a preliminary evaluation, a design groundwater level of 35 feet bgs was considered in areas north of US-101 (from the station platform area northward) and 25 feet bgs elsewhere.

6.7 Collapsible and Expansive Soils

Collapsible soils are soils that undergo settlement upon wetting, even without the application of additional loads. Typical collapsible soils are low in plasticity and have relatively low moisture contents and densities. These soils are distributed throughout the southwestern United States, specifically in areas of young alluvial fans, debris flow sediments, and loess (wind-blown sediment) deposits. Expansive soils are generally plastic clays that can undergo a substantial increase in volume with increase in moisture content and a substantial decrease in volume with a decrease in moisture content. Expansive soils can cause uplift pressures that can lead to structural damage. Based on the review of available geotechnical reports (Section 4.0), collapsible soils and expansive soils have not been identified at the Project study area. Therefore, the soils at the Project study area have low collapse and expansion potential.

6.8 Corrosion Potential

Existing available data indicates soils located within LAUS exhibited sulfate concentrations ranging from 152 to 475 parts per million (ppm) and chloride concentrations ranging from 3,000 ppm to 4,600 ppm (Metro 1981). Caltrans Corrosion Guidelines (Caltrans, 2021) define a corrosive soil as a material in which any of the following conditions exist: a chloride content greater than 500 ppm; soluble sulfate content greater than 1,500 ppm; or a pH of 5.5 or less. Based on these guidelines established by Caltrans and existing data from previous reports, the soils within the Project study area have a moderate to severe corrosion potential to buried metal structures, and the potential for sulfate attack on concrete is considered low. However, future studies should further assess corrosion potential.

A geotechnical report prepared for the Metro Red Line Tunnel (Metro 1986) described severe corrosion to groundwater monitoring instrumentation and pump equipment exposed to the groundwater in the LAUS area. During this investigation, soils within LAUS were treated with hydrogen peroxide to reduce hydrogen sulfide content in the groundwater. The hydrogen peroxide treatment was successful in the reduction of hydrogen sulfide in the groundwater within LAUS (Metro 1986). The subsurface soils within the Project study area would be evaluated in the future, planned investigations for the potential for corrosion to concrete and ferrous metals to confirm previous findings.

6.9 Subsidence and Settlement

Ground subsidence is a process characterized by downward displacement of surficial materials caused by natural phenomena, such as removal of underground fluids, natural consolidation, or dissolution of underground minerals, or by man-made phenomena, such as underground mining or tunneling. The Project study area is located north of the Union Station Oil Field. The LAUS Run-Through Tracks Project Environmental Impact Report/EIS (Caltrans and FRA 2005) indicates the potential for subsidence due to the extraction of oil in the surrounding area near LAUS is considered low. It is anticipated that the proposed improvements would impose higher loads on the existing soils than presently exist; therefore, settlement, both long-term and

immediate, is anticipated to occur in low density, loose deposits of silts, clays and sands for those improvements proposed to rely upon the upper zones for support using shallow foundations. The review of existing soil boring logs indicates thin, interbedded loose deposits within the upper 30 feet of the artificial fill should be anticipated. Significant settlement was generally not a controlling issue in the reports reviewed. Proper compaction and/or the removal of fill soils should be considered for proposed improvements. Another alternative to consider is use of deep foundations which extend through the artificial fill soils and bear in firm strata.

6.10 Flooding

The Flood Insurance Rate Map 06037C1636F (Federal Emergency Management Agency 2015) depicted that the Project footprint area is located within Zone “X” (unshaded), an area designated to be outside the 500-year floodplain and protected by levee from 100-year floodplain. The potential for flooding for the proposed action is considered low.

6.11 Mineral Resources

The Project footprint area is underlain by man-made fill and alluvium materials, such as sand and gravel, which could be considered mineral resources and used as construction aggregates. However, the mining of such materials within an urbanized environment is not practical. Therefore, no significant effect on mineral resources would be attributed to the construction of the proposed action.

6.12 Environmental Concerns

Several environmental reports were reviewed regarding subsurface conditions. Due to the long history and varied uses of this area of Los Angeles, the Project study area is expected to have variable potential for contamination. The J. Byer Group reported encountering methane and hydrogen sulfide in their test wells near LAUS (Catellus Urban Development Corporation 1998). In one sample at Test Well No. CMW2, located west of the HSB, combustible gas readings were high enough to reach the lower explosive limit. Similar combustible gas conditions were encountered at the site when performing pump tests as reported by others (Metro 1986). Additionally, previous problems had been encountered at the site when performing a pump test related to entrained gases in the water (possibly methane), which may have been released by the underlying Puente Formation (Metro 1986). Groundwater contaminated with gas or other volatile organic compounds may be encountered during groundwater pumping on site. Other detailed recommendations for dewatering can be found in the J. Byer Group report (Catellus Urban Development Corporation 1998).

In addition, the area located south of Jackson Street and west of the Los Angeles River is mapped as an abandoned oil field (Union Station Oil Field); consequently, bedrock could contain hydrocarbon odor and stains (DOC 2023).

A boring performed near the Los Angeles River (Boring CEG-2) indicates the presence of natural oil, which was encountered at a depth of about 37 feet bgs (Metro 1981).

Soil and groundwater contamination at LAUS was found primarily in the eastern, northern, and southern portions of the property. The contaminants found in soil samples at LAUS included carbon disulfide, petroleum hydrocarbons, benzene, toluene, xylenes and potentially methylene choline in the upper 30 feet bgs. Twenty-eight volatile organic compounds were reported in groundwater samples, which include acetone, dicloroethane, dichloroethylene, tetrachloroethylene, toluene, methylene chloride, carbon disulfide, and various others (Cordoba Corporation 1994). Further studies (TPG Capital, L. P. 2011) suggest the highest concentrations of volatile organic compounds exist on the off-site portion of the Gateway Area, near the intersection of Vignes Street and Cesar Chavez Avenue, whereas the yard tracks are contaminated with petroleum hydrocarbons, lead, and semi-volatile organic compound from historic rail operations. Similar types of contaminants are expected to be found near LAUS, including the southern parts of the 1st Street Viaduct Bridge, Keller Street, Ramirez Street, Commercial Street, Center Street, and various other streets.

Soil and groundwater environmental investigations for the construction of the Metro Red Line Tunnel segment between the intersection of Commercial Street and Center Street and US-101 revealed low levels to nondetectable levels of soil and groundwater contaminants (Metro 1987a, 1987b, and 1987c).

Numerous on- and off-site contamination sources are known to exist or have existed at the site. Some of these sources and their contaminants are described in previous environmental documents (Cordoba Corporation 1994; TPG Capital, L.P. 2011). In general, the site is affected by volatile organic compounds from various sources, and nearby rail operation areas are affected by petroleum hydrocarbons, lead, and semi-volatile organic compound. The report prepared for the site determined that these areas affected by rail operations are generally limited to the upper 10 feet of materials below existing site grade (TPG Capital, L.P. 2011).

6.13 Methane Gas

Based on the review of the Methane and Methane Buffer Zone Map (City of Los Angeles 2004), portions of the Project study area are located within an area designated as Methane Zone. The areas within the Project limits affected by this designation are located south of US-101. Therefore, there is the potential for methane and other volatile gases to exist within the Project footprint area.

7.0 Geotechnical Considerations

7.1 Foundation Type

Based on the review of previous reports, anticipated loading characteristics of the proposed improvements and the soil stratigraphy within the Project study area, a combination of shallow foundations and deep (pile) foundations would likely be suitable to support proposed improvements. Reviewed reports indicate allowable bearing pressures for spread footings of between 3,000 and 4,000 pounds per square foot. Where conventional spread foundations are considered, proper treatment (removal and recompaction) of the uncertified artificial fill is required. Similarly, if loading capacity is required for pile foundations (especially for lateral loading), the uncertified fill should be removed and recompacted to meet or exceed the minimum compaction criteria for the proposed improvements, or these foundations are designed to not rely on these uncertified fill soils for lateral resistance.

The foundation type selection should account for the presence of adverse conditions, such as a shallow groundwater table, presence of dense to very dense granular materials and cobbles, caving of loose granular soils, the highly urbanized area surrounding the Project study area, potential soil corrosion, and potential for encountering contaminated soils. Heavy column and wall loads would be best supported by a deep foundation system. Feasible deep foundation types include steel piles driven to refusal into bedrock and cast-in-drilled-hole (CIDH) piles. Foundation types, such as CIDH piles and driven steel piles, would provide suitable support for the proposed structures with the proper design and construction methods. During the construction of pile foundations, difficult driving and/or drilling can be expected due to the presence of dense to very dense deposits, cobbles and bedrock at shallow depths within the Project footprint area. CIDH piles were the prevailing recommended foundation type among the more recent documents reviewed. Where axial load demands are high, utilizing methods such as base grouting of CIDH piles should be considered to increase compressive capacity.

However, the relatively shallow depth to the Puente Formation bedrock may make driven piles a feasible alternative. Consideration should be given to underground utilities; nearby structures; and existing tunnels, which may be sensitive to ground vibrations, corrosion of pile steel, and noise impacts if driven piles are to be considered.

7.2 Constructability Considerations

Some known constructability-related subsurface conditions exist at the Project study area. The intent of the planned future exploration is to better delineate these and other conditions near proposed improvements. Anticipated subsurface conditions at the Project footprint area that might affect the proposed improvements are summarized below:

- Presence of groundwater ranging from depths of about 14 to 48 feet bgs (corresponding groundwater table elevations range from about 222 to 256 feet MSL) is anticipated at LAUS.

- Environmental concerns exist, given the presence of contaminated soils and groundwater at LAUS.
- Corrosion potential of soils at LAUS is considered high.
- The effect of proposed improvements to the existing Metro Red Line Tunnel within LAUS and off-site areas must be considered (near the intersection of Commercial Street and Center Street).
- Difficult driving or drilling conditions for piles could be encountered at the site due to gravel and cobble layers and bedrock.
- Abandoned tiebacks (pre-stressed soil anchors) installed during the construction of the Metro Red Line Tunnel within LAUS could pose obstructions to deep foundations and other proposed improvements.

7.3 Finite Element Analysis Results

A finite element analysis was performed by Earth Mechanics, Inc. to evaluate the effect on the existing Metro Red Line Tunnel due to the potential street grade modification at the intersection of Commercial and Center Streets, which includes the lowering of the roadway by approximately 7 feet below existing grade. Based on the preliminary results provided in the technical memorandum by Earth Mechanics, Inc. (Metro 2016a), the lowering of Commercial Street and Center Street would not affect the structural integrity of the existing Metro Red Line Tunnel. In addition, Earth Mechanics, Inc. did not identify any fatal flaws when evaluating the tunnel performance under static and seismic conditions due to the proposed lowered grade (Metro 2016a).

Another analysis was performed (Metro 2016b) to evaluate the effect of lateral pile loading on the Metro Red Line Tunnel near the intersection of Commercial Street and Center Street due to the proposed aerial bridge structure. The two-dimensional finite element analysis considered a 10-foot diameter CIDH pile located at approximately 20 feet apart from the Metro Red Line Tunnel. Since lateral pile demands were not available, Earth Mechanics, Inc. provided a range of possible pile response using incremental lateral displacements for both fixed and free pile head conditions. Based on the analysis, the pile top shear force required to displace the pile 1 inch is approximately 1,700 kips and 3,500 kips for the free-head and fixed-head conditions, respectively (Metro 2016b). These results are considered preliminary, and further analysis would be required when more detailed design information becomes available.

8.0 Recommendations

Future geotechnical exploration is recommended to better characterize the subsurface conditions and anticipate issues that would affect the proposed improvements. In general, additional explorations should be performed at the existing platform area within LAUS, along the proposed US-101 Viaduct structure and where lead tracks would provide entrance/exit to LAUS. Special consideration should be given to the existing Metro Red Line Tunnel to identify any potential impacts that the proposed improvements might have on this underground structure. The subsurface soils and groundwater contain moderate to high levels of contamination, and the presence of combustible gases, including methane, may affect the drilling and sampling at the Project study area (Section 6.12).

Based on the existing Project study area conditions and the expected shallow depth to groundwater, a combination of hollow stem auger and mud rotary drilling methods may be used. Coring of bedrock, if encountered, should be considered to obtain bedrock design information. Subsurface materials contain varying amounts of gravel and range from medium dense to very dense, but these soils can be drilled and sampled to the required depths using conventional drilling technology. Exploratory borings intended for the design of foundations and/or subterranean structure should extend to a minimum depth of 100 feet or into bedrock, whichever is shallower. The spacing of exploratory borings depends of the type of structure and proposed improvements. In general, a minimum of one exploratory boring per bridge support is recommended. Standard penetration test blow counts (N-values) should be obtained from these borings. Geotechnical laboratory testing of recovered soil samples should be performed, as necessary, to obtain engineering design parameters of the subsurface materials.

Cone penetrometer tests (CPT) equipped with one or more geophone sensors and pushed to refusal should be considered in addition to the conventional borings, in particular at the platform areas and the proposed US-101 Viaduct structure. Per foot of exploration, CPTs are more cost-effective than soil borings, and they also provide more precise subsurface data useful for soil characterization, liquefaction analysis, seismic analysis, and pile capacity design. The state of the practice for CPTs has improved over the years and some CPTs can now be pushed through denser or coarse-grained alluvium than in the past but may still encounter relatively shallow refusal in very dense soil layers or bedrock. CPTs could be mobilized first and exploratory borings using a combination of hollow stem auger and mud rotary drilling methods could then be drilled to augment data where the CPTs could not reach sufficient depths. Seismic design parameters (shear wave velocity) can be obtained by using seismic CPTs, seismic refraction, and/or downhole P-S suspension logging. Due to the presence of dense granular materials, seismic CPTs might encounter shallow refusal, consequently limiting its capabilities to gather useful data for seismic analysis. Downhole P-S suspension logging is the preferable method for obtaining seismic design data at the Project study area due to the accurate measurement of the shear wave velocity value and site-specific conditions. The downhole P-S suspension logging can be performed in any exploratory boring planned for the Project. Noninvasive methods, such as seismic refraction, can also be considered to obtain seismic design data for the proposed improvements.

(THIS PAGE INTENTIONALLY LEFT BLANK)

9.0 Next Steps

The findings presented in this report were based solely on the review of published geologic maps and geologic sources, planning documents, and previous geotechnical reports for LAUS and nearby developments. The findings presented in this report are considered preliminary and would need to be re-evaluated during the Project's final design phase. Additional geotechnical investigations should be performed to provide site-specific design information for the proposed improvements and incorporate any modifications to the design of the Project. The recommended next steps are as follows:

- Delineate potential areas requiring further investigation by taking into consideration the findings presented in this report and the location of the proposed improvements.
- Plan and prepare a detailed geotechnical field work plan for proposed geotechnical investigation, which would be prepared by incorporating the preliminary findings of this report and the recommendations, as described in Section 8.0.
- Conduct additional geotechnical exploratory investigations to obtain additional subsurface soil information to be used to confirm preliminary findings and in the refinement of recommendations, which would reduce the risk of encountering unexpected subsurface conditions during the Project's design phase.
- Provide mitigation alternatives for the identified constructability-related subsurface conditions affecting the Project, as described in Section 7.2.
- During final design, prepare a final geotechnical report, incorporating new findings; refined Project alternatives; and updated design recommendations, which would address soil bearing capacity, earth pressures, seismic design parameters, foundation selection, and recommendations to reduce adverse conditions.

(THIS PAGE INTENTIONALLY LEFT BLANK)

10.0 References

- Bilodeau, L. William, Bilodeau, W. Sally, Gath, M. Eldon, Osborne, Proctor, J. Richard. 2007. Geology of Los Angeles: The Geological Society of America, Environmental and Engineering Geoscience, Vol. XVIII, No. 2, pp. 99-160.
- California Department of Conservation (DOC). 2023. Geologic Energy Management Division (CalGEM) Well Finder. Accessed June 12, 2023. <https://maps.conservation.ca.gov/doggr/wellfinder/>.
- California Department of Transportation (Caltrans). n.d. As-Built Plans and LOTBs for Alameda Street Underpass, Bridge No. 53-0782.
- 1949. As-Built Plans for Los Angeles Street Overcrossing, Bridge No. 53-0629.
- 1954. As-Built Plans and LOTBs for the Widening of L.A. River Bridge and OH at Aliso Street, Bridge No. 53-0405.
- 2004. As-Built Plans and LOTBs for the Eastside Light Rail Transit Project Bridge over HWY 101, Bridge No. 53-2975 and 53C-2148.
- 2010. *Final Geotechnical Summary Report, SR-710 Tunnel Technical Study, Los Angeles County, California*. http://libraryarchives.metro.net/DPGTL/710_Tunnel/SR-710_Tunnel_Final_Geotech_Summary_Report.pdf. Prepared by CH2M Hill.
- 2016a. California Transportation Plan 2040. https://dot.ca.gov/-/media/dot-media/programs/transportation-planning/documents/f0004899_ctp2040_a11y.pdf.
- 2016b. Caltrans Acceleration Response Spectrum Online (v2.3.07). Accessed March 4, 2016: http://dap3.dot.ca.gov/ARS_Online/.
- 2018. *California State Rail Plan: Connecting California*. http://www.dot.ca.gov/californiarail/docs/CSRP_PublicReleaseDraft_10112017.pdf.
- 2021. *Corrosion Guidelines*. Version 3.2. May 2021.
- California Department of Transportation (Caltrans) and Federal Railroad Administration (FRA). 2005. *Final Environmental Impact Report/Environmental Impact Statement, Run-Through Tracks Project*. http://www.dot.ca.gov/d7/env-docs/docs/UnionStation_Final_eireis.pdf.
- California Division of Mines and Geology (CDMG). 1977. State of California - Special Studies Zones - Los Angeles Quadrangle, Official Map, Los Angeles.
- California Geological Survey (CGS). 1999. State of California Seismic Hazard Zones - Los Angeles 7.5 Minute Quadrangle, Los Angeles County.
- 2009. Los Angeles County Tsunami Inundation Map. <http://www.conservation.ca.gov/cgs/Pages/Tsunami/Maps/LosAngeles.aspx>.

- 2012. Geologic Compilation of Quaternary Surficial Deposits in Southern California, Los Angeles 30'x 60' Quadrangle. http://www.conservation.ca.gov/cgs/Documents/Program-FWGP/CGS_Special_Report_217_REVISED.pdf.
- California High-Speed Rail Authority (Authority). 2022. *2022 Business Plan*.
<https://hsr.ca.gov/about/high-speed-rail-business-plans/2022-business-plan/>.
- Catellus Urban Development Corporation. 1998. *Geotechnical Engineering and Groundwater Study, Proposed Two Level Subterranean Parking Garage and Four Story Office*. Prepared by J. Byer Group, Inc.
- 2003. *Geotechnical Investigation, Proposed West Campus Infrastructure Project, Los Angeles, California, LOTBs*. Prepared by URS Corporation
- City of Los Angeles. 2004. City of Los Angeles Department of Public Works, Methane and Methane Buffer Zone Map.
- Cordoba Corporation. 1994. *Report of Phase I Environmental Site Assessment, Alameda District Plan, Los Angeles, California*. Prepared by Law/Crandall, Inc.
- Federal Emergency Management Agency. 2015. ARCGIS 100-year Flood Insurance Rate Maps, Panel 06037C1636F, revised September 25, 2008.
- Gastil, G. and Krummenacher, D. 1981. The Tectonic History of Peninsular California and Adjacent Mexico, The Geotechnical Development of California: Rubey Vol. I, Prentice - Hall, Inc., Englewood Cliffs, NJ, pp. 285-306.
- Gularte, F. B., Taylor, G. E., and Borden, R. H. 1992. Temporary Tunnel Excavation Support by Chemical Grouting. Grouting Soil Improvement and Geosynthetics Proceedings, GT Div. ASCE, New Orleans.
- Los Angeles County Metropolitan Transportation Authority (Metro). 1981. *Geotechnical Investigation Report Volume I. Southern California Rapid Transit District (SCRTD), Metro Rail Project*. Prepared by Converse Consultants, Inc., Earth Sciences Associates, and Geo/Resource Consultants.
- 1983. *SCRTD, Geotechnical Report, Metro Rail Project - Design Unit A135, LOTBs*. Prepared by Converse Consultants, Inc., Earth Sciences Associates, and Geo/Resource Consultants.
- 1986. *Union Station Area Aquifer Pump Tests. Metro Rail Project*. Prepared by Converse Consultants, Inc., Earth Sciences Associates, and Geo/Resource Consultants.
- 1987a. *The Phase I Subsurface Investigation at the Metro Rail A-130 Corridor, Los Angeles, California*. Prepared by The Earth Technology Corporation.
- 1987b. *The Phase III Subsurface Investigation at the Metro Rail A-130 Corridor, Los Angeles, California*. Prepared by The Earth Technology Corporation.
- 1987c. *The Phase IV Subsurface Investigation at the Metro Rail A-130 Corridor, Los Angeles, California*. Prepared by The Earth Technology Corporation.
- 1988. Metro Rail Project, Main Yard and Shops Yard Leads, Contract No. A130.
- 2015a. *Connect US Action Plan*. http://media.metro.net/projects_studies/union_station/images/LAUSMP_Action_Plan_Final_100515.pdf.

- 2015b. *Preliminary Draft Report for Seismic Design Parameters, Southern California Regional Interconnector Project (SCRIP)*. Los Angeles County, California. Prepared by Earth Mechanics, Inc.
- 2016a. *Draft Technical Memorandum Static and Seismic Performance of Red Line Tunnel, SCRIP*. Los Angeles County, California. Prepared by Earth Mechanics, Inc.
- 2016b. *Draft Technical Memorandum Impact of Lateral Pile Loading on Red Line Tunnel, SCRIP – Geotechnical Fatal Flaw Study*. Prepared by Earth Mechanics, Inc.

- Rauch, A. F. 1997. "An Empirical Method for Predicting Surface Displacements Due to Liquefaction Induced Lateral Spreading in Earthquakes." Ph.D. Dissertation, Virginia Polytechnic Inst. and State Univ.

- Schoellhamer, J. E., Woodford, A. O., Vedder, J. G., Yerkes, R.F., and Kinney, D.M. 1981. *Geology of the Northern Santa Ana Mountains, California*: U.S. Geological Survey Professional Paper 420-D, U.S. Geological Survey. Denver, Colorado.

- Southern California Association of Governments. 2008. *Final 2008 Regional Comprehensive Plan*.
- 2023. Federal Transportation Improvement Program.
- 2020. *2020 Regional Transportation Plan/Sustainable Communities Strategy: Connect So Cal*. <https://scag.ca.gov/read-plan-adopted-final-connect-socal-2020>.


- TPG Capital, L.P. 2011. *Phase I Environmental Site Assessment and Limited Phase II Testing Selected Portions of the Los Angeles Union Station Property, Los Angeles, California*. Prepared by URS Corporation

- United States Geological Survey (USGS) and California Geological Survey (CGS). 2006. *Quaternary Fault and Fold Database for the United States*. Accessed July 9, 2014. <http://earthquakes.usgs.gov/regional/qfaults/>.

(THIS PAGE INTENTIONALLY LEFT BLANK)


Appendix A: Exhibits

(THIS PAGE INTENTIONALLY LEFT BLANK)



LINK UNION STATION
EXISTING DATA - EXHIBIT 4-1

SCALE: AS SHOWN
DATE: 06-12-2016



LINK UNION STATION
SITE LOCATION MAP - EXHIBIT 5-1

SCALE AS SHOWN
DATE: 06-12-2016



Photo No. 1. False tunnel sets at the South Tunnel Portal of YR Tunnel (south of LAUS) with tunnel shield and mucking machine in the background. Photo taken: 01/30/90. Source: SCRTD, 1990a.



Photo No. 2. False tunnel sets and the jacking frame and struts for pushing the shield off of at the South Tunnel Portal (south of LAUS). Photo taken: 01/30/90. Source: SCRTD, 1990a.



Photo No. 3. Mezzanine floor slab in place with column reinforcement steel protruding. The reinforcement for lift No. 4 of mezzanine floor is being placed in the foreground. Photo Taken: 01/30/90. Source: SCRTD, 1990a.




Photo No. 4. Reinforcement steel being placed in the closing slab of box structure at the south tunnel portals. Photo taken: 07/30/90. Source: SCRTD, 1990a.



LINK UNION STATION
PHOTOGRAPHS - EXHIBIT 5-2

SCALE: AS SHOWN
DATE: 06-12-2016



NEG NO 8 ROLL NO _____
PICT NO 9
SCRTD - M.O.S. 1
PROJECT Main Yard and Shops -
Yard Leads
CONTRACT NO A-130
DATE 1-18-90
TAKEN BY D. EDGAR
LOCATION STA. 4R 98400 - TRACTION
POWER SUBSTATION.
COMMENT PICTURE SHOWS 2'
BOULDER IN CUT, ENCOUNTERED
BY HAYWOOD - BAKER.



NEG NO 6 ROLL NO _____
PICT NO 1
SCRTD - M.O.S. 1
PROJECT Main Yard and Shops -
Yard Leads
CONTRACT NO A-130
DATE 1-18-90
TAKEN BY D. EDGAR
LOCATION STA. 4R 98400 - T
POWER SUBSTATION.
COMMENT SENIOR INSPECTOR
McLUCKIE HOLDING MEAS
URING 4' BOULDER.

Photo No. 5. Boulders encountered at the Main Yard and Shops (currently LAUS). Photo taken: 01/18/90. Source: SCRTD, 1990b.



Photo No. 6. Interface between the box structure (LAUS area) on the YL side at Sta. 89+7 and the YL Tunnel (south of LAUS). Photo taken: 03/04/90. Source: SCRTD, 1990a.





Photo No. 7. Sub-ballast placed on the base of slab in the "U" wall structure area, East Portal Entrance (south of LAUS). Looking north towards LAUS. Photo taken: 07/30/90. Source: SCRTD, 1990a.




LINK UNION STATION
PHOTOGRAPHS - EXHIBIT 5-3

SCALE: AS SHOWN
DATE: 06-12-2016




Qyf	Young Alluvial Fan Deposits - unconsolidated to slightly consolidated, undissected to slightly dissected boulder, cobble, gravel, sand, and silt deposits issued from a confined valley or canyon	Qya	Young Alluvial Valley Deposits - unconsolidated to slightly consolidated, undissected to slightly dissected clay, silt, sand, and gravel along stream valleys and alluvial flats of larger rivers	Reference: CGS. 2012
Qof	Old Alluvial Fan Deposits - slightly to moderately consolidated, moderately dissected boulder, cobble, gravel, sand, and silt deposits issued from a confined valley or canyon	Qw	Alluvial Wash Deposits - unconsolidated sandy and gravelly sediment deposited in recently active channels of streams and rivers; may contain loose to moderately loose sand and silty sand	



LINK UNION STATION
FAULT MAP - EXHIBIT 6-2

SCALE: AS SHOWN
DATE: 06-12-2016




References: CDMG, 1977 & CGS, 1999



LINK UNION STATION
HAZARD MAP - EXHIBIT 6-3

SCALE: AS SHOWN
DATE: 06-12-2016



PLAN VIEW

Geotechnical Investigations

- CC et al, 1983
- Dames & Moore Inc., 1994
- Law Crandall, 1997
- URS, 2003

Source for Boring Information: HDR, 2014b, Preliminary Geotechnical Memorandum-Existing Data

Geologic Units

- af** Artificial Fill: Silty Sand and Clayey Sand; may contain Gravel and/or Cobbles
- Qyf** Alluvium: Sand, Silty Sand, Silt, and Clay; may contain Gravel and/or Cobbles
- Tp** Puente Formation: Siltstone, Claystone, and Siltstone/Sandstone

EXPLANATION

Group Symbol & Name					
	SW	Well-Graded SAND		CL	Lean CLAY
	SW	Well-Graded SAND with GRAVEL		ML	Sandy SILT
	SP-SM	Poorly-Graded SAND with SILT		GM	Silty GRAVEL
	SP-SM	Poorly-Graded SAND with SILT and GRAVEL		GP	Poorly-Graded GRAVEL
	SW-SM	Well-Graded SAND with SILT		GP	Poorly-Graded GRAVEL with SAND
	SC	Clayey SAND with GRAVEL		GP-GM	Poorly-Graded GRAVEL with SILT
	SM	Silty SAND		GW	Well-Graded GRAVEL with SAND
	SM	Silty SAND with GRAVEL		CBBL	Cobbles
	SP	Poorly-Graded SAND		ROCK	Bedrock
	SP	Poorly-Graded SAND with GRAVEL		CLST	Claystone
	PCC	Concrete		MLST	Siltstone
	CL-ML	Silty CLAY		AC	Asphalt
	CL	Sandy Lean CLAY		FILL	Fill


Group Symbol-SM

Groundwater Level


Soil Type 52-Blows / ft.

Material Change

Note: Abbreviation for soil group is based on ASTM D2487-11, Unified Soil Classification



PROFILE VIEW



PLAN VIEW

EXPLANATION

Geotechnical Investigations

- Caltrans, 1954
- Caltrans, 2004
- Converse Consultants, 1983
- Sladden Engineering, 2004

Geologic Units

- af** Artificial Fill: Silty Sand and Clayey Sand; may contain Gravel and/or Cobbles
- Qyf** Alluvium: Sand, Silty Sand, Silt and Clay; may contain Gravel and/or Cobbles
- Tp** Puente Formation: Siltstone, Claystone, and Siltstone/Sandstone

Group Symbol & Name

SW	Well-Graded SAND	CL	Lean CLAY
SW	Well-Graded SAND with GRAVEL	ML	Sandy SILT
SP-SM	Poorly-Graded SAND with SILT	GM	Silty GRAVEL
SP-SM	Poorly-Graded SAND with SILT and GRAVEL	GP	Poorly-Graded GRAVEL
SW-SM	Well-Graded SAND with SILT	GP	Poorly-Graded GRAVEL with SAND
SC	Clayey SAND with GRAVEL	GP-GM	Poorly-Graded GRAVEL with SILT
SM	Silty SAND	GW	Well-Graded GRAVEL with SAND
SM	Silty SAND with GRAVEL	CBBL	Cobbles
SP	Poorly-Graded SAND	ROCK	Bedrock
SP	Poorly-Graded SAND with GRAVEL	CLST	Claystone
PCC	Concrete	MLST	Siltstone
CL-ML	Silty CLAY	AC	Asphalt
CL	Sandy Lean CLAY	FILL	Fill

Group Symbol—SM

Groundwater Level

Note: Abbreviation for soil group is based on ASTM D2487-11, Unified Soil Classification


A14-001

GS Elev.: xx ft.
Projected: xx ft.

Soil Type

52—Blows / ft.

Material Change



(THIS PAGE INTENTIONALLY LEFT BLANK)

Appendix B: As-Built Plans

(THIS PAGE INTENTIONALLY LEFT BLANK)




As-Built Plans
Los Angeles River Bridge & OH at Aliso Street, Bridge
No. 53-0405

81

FILE NO.	STATE	PROJECT NO.	SHEET NO.	TOTAL SHEETS
7	CAL.			

DATE	BY	CHKD.	APP'D.
APRIL 2, 1954			

APRIL 2, 1954



INDEX TO PLANS

- A-1. Structure Plan
- A-2. Foundation Plan
- A-3. Grades
- A-4. Underground Utilities
- A-5. Abutment & Pile Layout
- A-6. N.W. Wingwall Layout & Details #1
- A-7. N.W. Wingwall Layout & Details #2
- A-8. S.W. Wingwall & Stairway
- A-9. East Abutment & Wingwalls
- A-10. Abutment Details
- A-11. Typical Section
- A-12. Girder Layout
- A-13. Girder Reinforcement #1
- A-14. Girder Reinforcement #2
- A-15. Defour Plan
- A-16. Type 1 Cantilever Retaining Wall
- A-17. Type 2 Cantilever Retaining Wall
- A-18. Stairway Rail
- A-19. Steel Railing #1
- A-20. Steel Railing #2
- A-21. Electroliner Details
- A-22. Pile Details
- A-23. Standard Details
- A-24. Railing Details For Retaining Wall

AS BUILT

CORRECTIONS BY *[Signature]*
DATE 12-14-55

AS BUILT PLANS
Contract No. 55-14V62
Date Completed
Document No. 70002012

T.B.M. Elev. 275.635'
Wire spike on S.E. corner Center and Aliso,
1.4' So. of B.C.R. on Center St. (So. of Bridge)

Note: All dimensions and lines dependent upon
existing structure shall be verified in the
field by the Contractor.
Bituminous Type Treatment (B.T.T.) is Asphalt Concrete.

STATE OF CALIFORNIA DEPARTMENT OF PUBLIC WORKS DIVISION OF HIGHWAYS			
WIDENING OF L.A. RIVER BRIDGE AT ALISO ST. A-CENTER STREET UNDERCROSSING STRUCTURE PLAN			
SCALE: A-1 Shown	BRIDGE 53-V05	FILE	DRAWING C-3243-1
PREL. DRAWING NO. P-3243			


I HEREBY CERTIFY THAT THIS IS A TRUE AND ACCURATE COPY OF THE ABOVE DOCUMENT TAKEN
UNDER MY DIRECTION AND CONTROL ON THIS DATE IN SAN FRANCISCO, CALIFORNIA PURSUANT TO
AUTHORIZATION BY THE DIRECTOR OF PUBLIC WORKS.
DATE _____ SIGNATURE _____ TITLE _____

67

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
7	CAL.				

SHEET NO.	DATE	BY	CHECKED	APPROVED
111	12	2	137	

101
A. J. M. M. M.
A. J. M. M. M.
A. J. M. M. M.




LOCATION MAP
No Scale

BRIDGE DEPARTMENT

DESIGN SECTION 5

DESIGN	BY	DATE
DETAILS	BY	DATE
QUANTITIES	BY	DATE
SPECIFICATIONS	BY	DATE



VICINITY PLAN

AS BUILT



CORRECTIONS BY: [Signature]
DATE: 12-11-55

AS BUILT PLANS
Contract No. 55-14V62
Date Completed
Document No. 70002012

SANTA ANA FREEWAY	
STATE OF CALIFORNIA DEPARTMENT OF PUBLIC WORKS DIVISION OF HIGHWAYS	
WIDENING OF LOS ANGELES RIVER BRIDGE & OVERHEAD AT ALISO STREET LOCATED IN THE CITY OF LOS ANGELES IN LOS ANGELES COUNTY	
VICINITY PLAN	
SCALE 1" = 100'	BRIDGE 53-405
FILE	DRAWING 1-3243-2

AS BUILT

CORRECTIONS BY *W.B. James*
DATE *10-11-53*



Contract No. 55-1462
Date Completed _____
Document No. 70002012

Fluorescent Type Treatment (BTT) is Asphalt Concrete
Live Loading H 20-S16-44

SANTA ANA FREEWAY

OFFICE OF ENGINEERING
STATE OF CALIFORNIA
DEPARTMENT OF PUBLIC WORKS
DIVISION OF HIGHWAYS

**WIDENING OF LOS ANGELES RIVER BRIDGE & OVERHEAD
AT ALISO STREET
LOCATED IN THE CITY OF LOS ANGELES IN LOS ANGELES COUNTY**

GENERAL PLAN


Except as noted
SCALE 1"=50'

BRIDGE 53-405

FILE

DRAWING-381

DATE	10-14-55
BY	J. J. G.
FOR	STATE OF CALIFORNIA
PROJECT	WIDENING OF L.A. RIV. BR. & OH AT ALISO STREET
APP'D	J. J. G.
DATE	10-14-55



I HEREBY CERTIFY THAT THIS IS A TRUE & ACCURATE COPY OF THE ABOVE DOCUMENT GIVEN UNDER MY DIRECTION AND CONTROL ON THIS DATE IN SACRAMENTO, CALIFORNIA PURSUANT TO AUTHORIZATION BY THE DIRECTOR OF PUBLIC WORKS.

DATE _____ SIGNATURE _____ TITLE _____


AS BUILT PLANS
Contract No. 55-14V62
Date Completed
Document No. 70002017

70

FED. ROAD DIST.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
2	CAL.				

Dist.	County	Route	Station	Sheet	Total
VII	LA	2	LA-5	5	159

APPROVED: APRIL 24, 1954




AS BUILT

CORRECTIONS BY: M.B. J...
DATE: 10-11-55


Test Boring By Bridge Dept.

Set of test borings...
...
Elev. 272.94



LEGEND OF EARTH MATERIALS	
GRAVEL	SILTY CLAY OR CLAYEY SILT
SAND	PEAT AND/OR ORGANIC CLAY
SILT	FILLED MATERIAL
CLAY	IGNEOUS ROCK
SANDY CLAY OR CLAYEY SAND	SEDIMENTARY ROCK
SANDY SILT OR SILTY SAND	METAMORPHIC ROCK

- LEGEND OF BORING OPERATIONS
- PLAN OF ANY BORING
 - PENETROMETER
 - 2 1/2" CONE PENETROMETER
 - SAMPLER BORING (DRY)
 - ROTARY BORING (WET)
 - AUGER BORING (DRY)
 - JET BORING
 - CORE BORING
 - TEST PIT



NOTES

THE CONTRACTOR'S ATTENTION IS DIRECTED TO SECTION 2, ARTICLE (C) OF THE STANDARD SPECIFICATIONS AND TO THE SPECIAL PROVISIONS ACCORDING TO THIS SET OF PLANS. CLASSIFICATION OF EARTH MATERIAL AS SHOWN ON THIS SHEET IS BASED UPON FIELD INSPECTION AND IS NOT TO BE CONSTRUED TO IMPLY MECHANICAL ANALYSIS. PENETROMETER BORINGS HAVING A RATE OF PENETRATION MEASURED IN SECONDS PER FOOT ARE DRIVEN WITH A NO. 2 MCKERNAN-TERRY AIR HAMMER AT 115 PSI.

STATE OF CALIFORNIA
DEPARTMENT OF PUBLIC WORKS
DIVISION OF HIGHWAYS

WIDENING OF LA RIVER BRIDGE ON ALISO ST.

LOG OF TEST BORINGS (1 of 3)

SCALE: HORIZ. 1" = 50' VERT. 1" = 10'

BRIDGE 53-405 FILE DRAWING C-3243-5

PREL. DRAWING NO. P-3243

71

FED. ROAD DIST. NO.	STATE	PROJECT NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
2	CAL.				

DATE	CREATED	REVISED	BY	REASON
VII	LA	2-11-55	6	39

101.78
APRIL 26 1954




AS BUILT PLANS
Contract No. 55-14V62
Date Completed
Document No. 20002012


AS BUILT

CORRECTIONS BY *W. J. Gammal*
DATE 10-11-55

BRIDGE DEPARTMENT




CLASSIFICATION OF MATERIAL BASED ON STANDARD GRADE SIZE LIMITS



LEGEND OF EARTH MATERIALS

GRAVEL	SILTY CLAY OR CLAYEY SILT
SAND	PEAT AND/OR ORGANIC CLAY
SILT	FILLED MATERIAL
CLAY	IGNEOUS ROCK
SANDY CLAY OR CLAYEY SAND	SEDIMENTARY ROCK
SANDY SILT OR SILTY SAND	METAMORPHIC ROCK

LEGEND OF BORING OPERATIONS



NOTES

THE CONTRACTOR'S ATTENTION IS DIRECTED TO SECTION 2, ARTICLE (C) OF THE STANDARD SPECIFICATIONS AND TO THE SPECIAL PROVISIONS ACCOMPANYING THIS SET OF PLANS. CLASSIFICATION OF EARTH MATERIAL AS SHOWN ON THIS SHEET IS BASED UPON FIELD INSPECTION AND IS NOT TO BE CONSTRUED TO IMPLY MECHANICAL ANALYSIS. PENETROMETER BORINGS HAVING A RATE OF PENETRATION MEASURED IN SECONDS PER FOOT ARE DRIVEN WITH A NO. 2 WISKERMAN-TERRY AIR HAMMER AT 115 PSI.

STATE OF CALIFORNIA
DEPARTMENT OF PUBLIC WORKS
DIVISION OF HIGHWAYS

WIDENING OF L.A. AV. BR. & ON AT 4.150 ST.


LOG OF TEST BORINGS (2 of 3)

SCALE: HORIZ. 1" = 50' VERT. 1" = 10'
BRIDGE 53-405 FILE DRAWING C-3243-6
PREL. DRAWING NO. P 2243

I HEREBY CERTIFY THAT THIS IS A TRUE AND ACCURATE COPY OF THE ABOVE DOCUMENT TAKEN UNDER MY DIRECTION AND CONTROL ON THIS DATE IN SACRAMENTO, CALIFORNIA PURSUANT TO AUTHORIZATION BY THE DIRECTOR OF PUBLIC WORKS.
DATE 11-11-55 SIGNATURE *W. J. Gammal* TITLE *Engineer*

72

PROJECT NO.	55-14V62
SHEET NO.	7
TOTAL SHEETS	139
DATE	10-11-55
BY	101
CHECKED	
APPROVED	





AS BUILT
CORRECTIONS BY: *W. J. James*
DATE: 10-11-55

Test Boring By Bridge Dept.

AS BUILT PLANS
Contract No. 55-14V62
Date Completed
Document No. 70002012

B.M. #6-5
Set conc. nail in lead SW corner powerline tower marked #7 East side L.A. River, 65' N. of Aliso St. Bridge, 13.5 East of river retaining wall, 35' West of Westly most R.R. tracks
Elev. 278.75


B.M. #12-1
Set conc. nail in lead SW corner powerline tower marked #7 East side L.A. River, 65' N. of Aliso St. Bridge, 13.5 East of river retaining wall, 35' West of Westly most R.R. tracks
Elev. 278.94



LEGEND OF EARTH MATERIALS

GRAVEL	SILTY CLAY OR CLAYEY SILT
SAND	PEAT AND/OR ORGANIC CLAY
SILT	FILLED MATERIAL
CLAY	IGNEOUS ROCK
SANDY CLAY OR CLAYEY SAND	SEDIMENTARY ROCK
SANDY SILT OR SILTY SAND	METAMORPHIC ROCK

- LEGEND OF BORING OPERATIONS
- PLAN OF ANY BORING
 - PENETROMETER
 - 2 1/2" C.W. PENETROMETER
 - SAMPLER BORING (DRY)
 - ROTARY BORING (WET)
 - AUGER BORING (DRY)
 - JET BORING
 - CORE BORING
 - TEST PIT



NOTES

THE CONTRACTOR'S ATTENTION IS DIRECTED TO SECTION 2, ARTICLE (C) OF THE STANDARD SPECIFICATIONS AND TO THE SPECIAL PROVISIONS ACCOMPANYING THIS SET OF PLANS. CLASSIFICATION OF EARTH MATERIAL AS SHOWN ON THIS SHEET IS BASED UPON FIELD INSPECTION AND IS NOT TO BE CONSTRUED TO IMPLY MECHANICAL ANALYSIS. PENETROMETER BORINGS HAVING A RATE OF PENETRATION MEASURED IN SECONDS PER FOOT ARE DRIVEN WITH A #2 MCKERNAN-TERRY AIR HAMMER AT 115 PSI.

STATE OF CALIFORNIA
DEPARTMENT OF PUBLIC WORKS
DIVISION OF HIGHWAYS

WIDE: 16' OF L.A. RIVER & 11' 11" 57 ST

LOG OF TEST BORINGS (3 of 3)

SCALE: 1" = 10'
BRIDGE 53-405 FILE
DRAWING C-3243-7

PREL. DRAWING NO. P-2243

I HEREBY CERTIFY THAT THIS IS A TRUE AND ACCURATE COPY OF THE ABOVE DOCUMENT TAKEN UNDER MY DIRECTION AND CONTROL ON THIS DATE IN SACRAMENTO, CALIFORNIA PURSUANT TO AUTHORIZATION BY THE DIRECTOR OF PUBLIC WORKS.




DATE: SIGNATURE: TITLE:

73

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FUNDAL. LEGAL	SHEET NO.	TOTAL SHEETS
7	CAL.				

DATE	COUNTY	ROUTE	SECTION	POST MILE	TOTAL MILES
10/1/55	Yuba	2	1	8	59

10/1/55
APRIL 25, 1955



LONGITUDINAL SECTION

AS BUILT PLANS
Contract No. 55-14V62
Date Completed
Document No. 20002012

AS BUILT
CORRECTIONS BY: *[Signature]*
DATE 10-11-55


STATE OF CALIFORNIA DEPARTMENT OF PUBLIC WORKS DIVISION OF HIGHWAYS			
WIDENING OF LA RIVER BRIDGE AT 4150 ST.			
ELEVATIONS - TOP OF CONCRETE DECK			
SCALE NO SCALE	BRIDGE 53-495	FILE	DRAWING C-3243-8
PREL. DRAWING NO. P. 3243-8			

I HEREBY CERTIFY THAT THIS IS A TRUE AND ACCURATE COPY OF THE ABOVE DOCUMENT TAKEN UNDER MY DIRECTION AND CONTROL ON THIS DATE IN SACRAMENTO, CALIFORNIA PURSUANT TO AUTHORIZATION BY THE DIRECTOR OF PUBLIC WORKS.

DATE _____ SIGNATURE _____ TITLE _____


74

PROJECT	DATE	BY	CHECKED
WIDENING OF L.A. RIVER BR.	10-11-35	M. B. Jones	
APPROVED			




ELEVATION LOOKING SOUTH

- SECTION 2 - RAIL WORK
1. RAIL I FROM PIER 2+10 TO PIER 17+10 TO REMAIN IN PLACE UNTIL WATERWAY IS OPENED AND RAIL I IS REMOVED.
 2. WHEN TEMPORARY GUARD RAIL AS SHOWN IN CENTER STREET UNDERPASSING, RAIL I FROM PIER 2+10 TO PIER 9+10 SHALL BE REMOVED AND REPLACED.
 3. DURING WORK ON NEW WEST ARCH, RAIL I AND DURING ERECTION OF PRESTRESSED SPAN, RAIL I FROM PIER 17+10 TO PIER 18+10 MAY BE REMOVED AND TEMPORARY GUARD RAIL SET UP IN PRESENT SIDEWALK AREA. FACE OF PORTABLE GUARD TO MATCH FACE OF EXISTING JURP.
 4. WHEN WIDENING WEST OF ARCH IS COMPLETED AND APPLYING TRAFFIC, RAIL I MAY BE REMOVED AND REPLACED FROM PIER 18 TO WEST ARCH ABUT.



ELEVATION LOOKING NORTH



NOTE:
All dimensions shown are for estimating only.
Dimensions are face to face of concrete.
For further details of temporary guard rail location see TEMPORARY GUARD RAIL


AS BUILT
CORRECTIONS BY M. B. Jones
DATE 10-11-35

AS BUILT PLANS
Contract No. 55-14V62
Date Completed
Document No. 70002012

STATE OF CALIFORNIA DEPARTMENT OF PUBLIC WORKS DIVISION OF HIGHWAYS			
WIDENING OF L.A. RIVER BR. E.O.H. AT ALISO STREET RAILING LAYOUT 'I'			
SCALE NONE	BRIDGE 3	FILE	DRAWING C-3243-9

PREL. DRAWING NO. P-3243-9

I HEREBY CERTIFY THAT THIS IS A TRUE AND ACCURATE COPY OF THE ABOVE DOCUMENT TAKEN UNDER MY DIRECTION AND CONTROL ON THIS DATE IN SACRAMENTO, CALIFORNIA PURSUANT TO AUTHORIZATION BY THE DIRECTOR OF PUBLIC WORKS.
DATE 10-11-35 SIGNATURE M. B. Jones TITLE



1. RAIL III ON ARCH TO REMAIN IN PLACE UNTIL ARCH WIDENING IS COMPLETED.
2. WHEN WORK IS BEING DONE ON EAST ARCH ABUT. AND THE WEST PORTION OF SECTION D, TEMPORARY GUARD RAIL WILL BE PLACED FROM PIER 20D TO STA. 15 +05.17@ 6° VIAD. AND THENCE TO WEST END OF EAST ARCH ABUT. AS SHOWN.
3. ~~RAIL~~ IV FROM PIER 20D TO PIER 25D TO REMAIN IN PLACE UNTIL ADJACENT WIDENING, INCLUDING NEW RAIL, IS COMPLETED. CLOSE GAPS LEFT BY REMOVAL OF POSTS AT PIERS WITH TEMPORARY RAIL.
4. RAIL IV FROM PIER 26E TO STA 224 +22.5 @ VIAD. TO REMAIN IN PLACE UNTIL WORK NEAR A VIADUCT FROM PIER 26F TO TUNNEL PORTAL IS COMPLETED.
5. RAIL III ON ARCH TO REMAIN IN PLACE UNTIL ARCH WIDENING IS COMPLETED AND CARRYING TRAFFIC.
6. RAIL III FROM EAST ARCH ABUT. TO END OF OFF RAMP MAY BE REMOVED AND REPLACED AT ANY TIME.
7. RAIL VI ON OFF RAMP MAY NOT BE REMOVED AND REPLACED WHILE WORK IS BEING DONE ON ADJACENT PORTION OF RAIL III.
8. RAIL IV TO REMAIN IN PLACE UNTIL WIDENING IS COMPLETED AND CARRYING TRAFFIC.
9. RAIL VI MAY BE REMOVED AND REPLACED AT ANY TIME.

DATE 10-11-55 U

AS BUILT PLANS
Contract No. 55-14V62
Date Completed _____
Document No. 20002012




STATE OF CALIFORNIA DEPARTMENT OF PUBLIC WORKS DIVISION OF HIGHWAYS			
WIDENING OF LA RIVER BR. & OH. AT ALISO STREET			
RAILING LAYOUT "2"			
SCALE NONE	BRIDGE 53-405	FILL	DRAWING C-3243-10

I HEREBY CERTIFY THAT THIS IS A TRUE AND ACCURATE COPY OF THE ABOVE DOCUMENT TAKEN UNDER MY DIRECTION AND CONTROL ON THIS DATE IN SACRAMENTO, CALIFORNIA PURSUANT TO AUTHORIZATION BY THE DIRECTOR OF PUBLIC WORKS.

DATE 11/1/71 SIGNATURE A. J. H. TITLE Asst. Dir.

DATE	CONVERTS	REVIEWS	DECTIONS	SHEET	TOTAL SHEETS
1/11	2	1	1	1	1

APR 2 1961



AS BUILT

CORRECTIONS BY W. B. James
DATE 10-18-55

DATE 10-18-55.

Note: All dimensions and lines dependent upon existing structure shall be verified in the field by the Contractor.

Bituminous Type Treatment (B.T.T.) is Asphalt Concrete

AS BUILT PLANS
Contract No. 55-14VC2
Date Completed _____
Document No. 70002012

Contract No. 55-14V62
Date Completed _____
Document No. 70002012

Contract NO. 55-14622
Date Completed _____
Document No. 70002012

Document No. 70002012

STATE OF CALIFORNIA			
DEPARTMENT OF PUBLIC WORKS			
DIVISION OF HIGHWAYS			
WIDENING OF L. A. RV BR. & Q.H. AT ALISO STREET			
B- WEST APPROACH			
STRUCTURE PLAN No. 2			
1"=20' <i>except as noted</i>	BRIDGE 53-405	FILE	DRAWING 3243-38
PHL. DRAWING NO. P-3243		<input checked="" type="checkbox"/> 1 <input checked="" type="checkbox"/> 2 <input checked="" type="checkbox"/> 3 <input type="checkbox"/> 4 <input type="checkbox"/> 5	

WIDENING OF L.A. RIV. BR. & Q.H. AT ALISO STREET
B- WEST APPROACH
STRUCTURE PLAN No. 2

SCALE 1"=20' except as noted	BRIDGE 53-405	FILE	DRAWING 3243-38
PIEL, DRAWING NO. P. 3243 XXXX XXXX XXXX XXXX 437			


As-Built Plans
Alameda Street Underpass, Bridge No. 53-0782

THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS IN THE FIELD BEFORE ORDERING OR FABRICATING ANY MATERIAL


Des.	Drawn	Rev.	Proj. No.	Proj. Name	Proj. Loc.	Proj. Date
07	L.A.	11/1/85	209	296	209	296
PROJECT (HIGHWAY)						
U.S. Highway 101						
NO. 25237						
DATE APPROVED: SEPTEMBER 16, 1985						

DESIGNED	CHECKED	SUPERVISED	PROJ. ENGR.
S. Fitch, D. Fournier	J. H. H. H.	R. H. H. H.	R. H. H. H.
DATE	DATE	DATE	DATE
5/1/86	5/1/86	5/1/86	5/1/86

PLAN B. ELEVATION



Note: For alignment of temporary k-railing see Shets 9 and 12.



NO CORRECTIONS
CORRECTIONS BY JOHN DISKIN
CONTRACT NO. 07-417803
DATE 1-3-91
27 MAR 91 S.B.S.

(State Project) ALAMEDA ST. U.P. WIDENING
BR. No. 53-782
(City Project) ALAMEDA STREET BETWEEN 400' NORTH OF
ARADIA STREET AND TEMPLE STREET
V.O. 61584

AS BUILT PLANS


Contract No. 07-417804
Date Completed 12-21-90
Document No.

I HEREBY CERTIFY THAT THIS IS A TRUE AND ACCURATE COPY OF THE ABOVE DOCUMENT TAKEN UNDER MY DIRECTION AND CONTROL ON THIS DATE IN SACRAMENTO, CALIFORNIA PURSUANT TO AUTHORIZATION BY THE DIRECTOR OF TRANSPORTATION


DATE 11/1/85 BY Donald Blackford

REVISION DESCRIPTION	DATE	BY	CHKD
REVISED FOR STATE CONTRACT and added State project title	5/1/86	PHL	PHL
DATE	12/21/90	DATE	12/21/90
CITY OF LOS ANGELES	CITY ENGINEER	CITY OF LOS ANGELES	CITY ENGINEER
DONALD C. TILLMAN		DONALD C. TILLMAN	






TYPICAL TENDON PROFILE
BETWEEN GIRDERS T&U
Scale: $\frac{1}{4}'' = 1'-0''$



TYPICAL TENDON PROFILE
BETWEEN GIRDERS A&B
Scale: $\frac{1}{2}'' = 1'-0''$

AS BUILT

CORRECTIONS BY JOHN DISKIN
CONTRACT NO. 07-47803
DATE 1-3-91
27. MAR 91



TYPICAL SECTION
Scale: $\frac{1}{4}'' = 1'-0''$

▽ PRESTRESSING NOTES

The following applies to each of the two bridge sections.
Each section contains five (5) girders.

- each section contains five (5) girders.
1. $P_{jack} = 4010$ kips total at jacking end, $A_j = \frac{P_{jack}}{.75FS}$
Total number of girders = 5
2. Design is based on $u = 0.25$ and $k = 0.0002$. P_{jack} specified at the jacking end includes friction loss, anchorage loss, creep and elastic shortening (total 50.24 ksi)
3. Tendons to be jacked to .75 f'_s and anchored at a minimum equivalent anchor set + 0.025 inches.
4. Contractor shall submit elongation and jacking calculations based on initial stress of .733 times jacking stress at non-stressing end.
5. The design is based on one end prestressing. Half of the prestressing steel in the member shall be stressed from one end and the other half from the opposite end. In the event the Contractor wishes to stress tendons simultaneously from both ends, he shall submit to the Engineer, for approval, details and supporting calculations prepared by a registered Civil or Structural Engineer by the State of California.

6. Distribution of prestressing force:
Unless otherwise noted, the prestressing force shall be distributed with an approximately equal amount in each tendon and shall be placed symmetrically about the cross section.
7. Stressing Sequence:
No more than $\frac{1}{8}$ of the prestressing force in any girder may be stressed before an equal force is stressed in the adjacent girders. At no time during the stressing operations will more than $\frac{1}{8}$ of the total prestressing force be applied eccentrically about the center of gravity of the section.
8. The Contractor shall install the C4 x 5.4 steel girder web braces at locations designated on the plans prior to prestressing. They shall remain in place. The Contractor shall submit shop drawings showing the connection details of the web braces to the existing girders, to have compression and/or tension, for the Engineer's approval.
9. Hazing Shall Be Grouted into Place a Minimum of 14 days Before Prestressing.

▽ Note: All reinforced concrete shall be normal Class A concrete except the new deck, sidewalk and railing base which shall be lightweight concrete. End bearing and harping blocks shall be 5000psi concrete.

▽ DESIGN DATA

Governing Code

AASHTO Standard Specifications for Highway Bridges
(1977 Eleventh Edition) including AASHTO Interim Specifications (1982)

Loads

Live load _____ HS 20-44 (WSB)
Lateral earth pressure 36 pcf EFP plus 2 ft. surcharge

Stresses

Lightweight concrete	$F'_c = 3250 \text{ psi at 28 days}$
Concrete not in prestressed area	$F'_c = 1300 \text{ psi}$
Concrete bearing f harping blocks	$F'_c = 3250 \text{ psi}$
	$F'_c = 1300 \text{ psi}$
Concrete bearing f harping blocks	$F'_c = 5000 \text{ psi at 28 days}$
Reinforcing steel	$F_y = 2,000 \text{ psi}$
Prestressed steel wire	$F_y = 24,000 \text{ psi}$
Temporary stress before loss due to creep and shrinkage	$F_s = 270,000 \text{ psi}$
	$0.70 F_s = 189,000 \text{ psi}$

▽ (State Project) ALAMEDA ST. U.P. WIDENING

BR. No. 53-782

▽ (City Project) ALAMEDA STREET BETWEEN 400' NORTH OF
ARCADIA STREET AND TEMPLE STREET

W.O. 61584


CITY OF LOS ANGELES
D. C. TILLMAN
CITY ENGINEER

June 28 09

AS BUILT PLANS

Contract No. 07-417804
Date Completed 12-21-90
Document No. _____

I HEREBY CERTIFY THAT THIS IS A TRUE AND ACCURATE COPY OF THE ABOVE DOCUMENT TAKEN
UNDER MY DIRECTION AND CONTROL ON THIS DATE IN SACRAMENTO, CALIFORNIA PURSUANT
AUTHORIZATION BY THE DIRECTOR OF TRANSPORTATION




Dist	County	Route	Post miles (road number)	Segment No.	Length (miles)
07.	L.A.	101/10	P. 372.8 S. 222.121	23	226

PROJECT: InGmail


REGISTERED GOLF COURSE

NO. 25537


DATE APPROVED _____




Var. 1-6"



SECTION C₁₀
Scale: $\frac{1}{2}'' = 1'-0''$



NORTHEAST CORNER
Scale: $\frac{1}{2}" = 1'-0"$



SECTION D
Scale: $\frac{1}{2}'' = 1'-0''$

SOUTHEAST ABUTMENT
Scale: $\frac{1}{2}$ " = 1'-0"

NO CORRECTIONS #501
AS BUILT
 CORRECTIONS BY JOHN DISKIN
 CONTRACT NO. CT-417803
 DATE 1-3-91
27 MAR 91 S.S.S.

▽(State Project) ALAMEDA ST. U.P. WIDENING BR. No. 53-782
▽(City Project) ALAMEDA STREET BETWEEN 400' NORTH OF
ARCADIA STREET & TEMPLE STREET W.O. 61584

CORNER DETAILS
EAST SIDE

DIV./DIST. ENGR.	DATE
Phil Skarpe	3-83

O.	REVISION DESCRIPTION
11	Revised for state contract and

CITY OF LOS ANGELES
DONALD C. TILLMAN CITY ENGINEER

DATE June 25, 1982

DATE _____
BY Philip H. Klein
DIVISION, EIGHT R.E. NO.


Contract No. 07-417804
Date Completed 12-21-90
Document No. _____

I HEREBY CERTIFY THAT THIS IS A TRUE AND ACCURATE COPY OF THE ABOVE DOCUMENT TAKEN UNDER MY DIRECTION AND CONTROL ON THIS DATE IN SACRAMENTO, CALIFORNIA PURSUANT TO AUTHORIZATION BY THE DIRECTOR OF TRANSPORTATION.

SCALES	HORIZ. 1" = As shown
	VERT. 1" = As shown

SHEET 10

INDEX NUMBER D-27658



As-Built Plans
Los Angeles Street Overcrossing, Bridge No. 53-0629

FED. ROAD DIST. NO.	STATE	PROJ. NO.	SHEET NO.	TOTAL SHEETS
2	CAL.			
DIVISION OF HIGHWAYS				
CITY	COUNTY	ROUTE	SECTION	SHEET TOTAL
VII	A.	101	LA-6	1 3
ENGINEER, BRIDGE & STRUCTURAL DESIGN				
Submitted Oct 17 1948				
Approved Jan 17 1949				
CITY ENGINEER, CITY OF LOS ANGELES				
DATE APPROVED February 28, 1949				
STATE ENGINEER, CALIFORNIA				

AS BUILT PLANS
Contract No. 14VC84
Date Completed
Document No. 70001957


REFERENCES
District Maps 5514
Field Books 18413, 19618, 20120, 20168
Sewer Plans D-3101, D-3104, D-7929, D-7930
Records of Los Angeles City Engineer

THIS SET OF PLANS IS THE PROPERTY OF THE CITY OF LOS ANGELES. IT IS TO BE USED FOR THE PROJECT AND NOT TO BE REPRODUCED OR COPIED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF THE CITY ENGINEER.

GENERAL NOTES
Specifications: Design: A.A.S.H.T.O. 1944 and subsequent revisions. Construction: Standard Specifications dated April, 1945 and special provisions accompanying this set of plans.
Design Data:
Live load: H-20-S16-44
E = 1000 pounds per sq. inch
F = 18000 pounds per sq. inch
n = 10
Maximum soil pressure: 3 tons per sq. ft.
Bench marks: See Sheet 1182
Note: Refer to "Cover Sheet" for Index to Specifications, Storm Drain, Sewer, and Utility Plans.

14VC84			
STATE OF CALIFORNIA DEPARTMENT OF PUBLIC WORKS DIVISION OF HIGHWAYS			
SANTA ANA PARKWAY LOS ANGELES STREET OVERCROSSINGS IN THE CITY OF LOS ANGELES, LOS ANGELES COUNTY			
GENERAL PLAN			
SCALE 1" = 20'	Sheet 53-629	FILE	DRAWING C-1738-L

INDEX TO PLANS	
SHEET NO.	TITLE
1	General Plan
2	Foundation Plan
3	Deck Layout & Approach Forms
4	Abutments No. 1 & 3
5	Abutments No. 1 & 3 - Details
6	Bent No. 2
7	Overcrossing Deck Plan & Girder Details
8	Overcrossing Deck Sections
9	Overcrossing Girder Details
10	Abutments No. 4 & 5
11	Inlet - Part III - Deck & Reinforcement Details
12	Inlet - Part IV - Girder Reinforcement Details
13	Inlet - Part II - Deck Reinforcement Details
14	Inlet - Part I - Deck Reinforcement Details
15	Inlet - Part I - Abutment Details
16	Inlet - Part I - Deck Reinforcement Details
17	Inlet - Part I - Abutment Details
18	Inlet - Part IV
19	Retaining Wall A - & B - Floating Slab
20	Standard Retaining Wall
21	Corner & Joint Details
22	Minor Details
23	Rating Details
24	Electrical Details - No. 1
25	Electrical Details - No. 2
26	Corner Walls - Plan and Details
27	Corner Walls - Reinforcement Details
28	Corner Walls - Misc. Details
29	Standard Counterfort Retaining Wall
30	Excavation Plan




I HEREBY CERTIFY THAT THIS IS A TRUE AND ACCURATE COPY OF THE ABOVE DOCUMENT TAKEN UNDER MY DIRECTION AND CONTROL ON THIS DATE IN SACRAMENTO, CALIFORNIA PURSUANT TO AUTHORIZATION BY THE DIRECTOR OF PUBLIC WORKS.
DATE 3/1/61 SIGNATURE [Signature] TITLE Asst. II


STATE OF CALIFORNIA
DEPARTMENT OF PUBLIC WORKS
DIVISION OF HIGHWAYS
BRIDGE DEPARTMENT

DIST.	COUNTY	ROUTE	SECTION
VII	L.A.	8	4A

BRIDGE ENGINEER *[Signature]*
DATE APPROVED *Apr. 29, 1949*



FLOATING SLAB
Scale: $\frac{3}{8}$ " = 1'-0"



SECTION E-E
Scale: $\frac{3}{4}$ " = 1'-0"

Note:
Refer to Contract Plans, Sheet No. 19,
for remaining details.

DRAWN BY: *WWS* DATE: *4-49*
CHECKED BY: *LP* DATE: *4-49*
[Signature]


SUPPLEMENTARY DRAWING	
LOS ANGELES ST. OVERPASS	
FLOATING SLAB REVISION	
SCALE: As Shown	FILE NO. 40-7-362
BRIDGE NO. 53-629	DRWG. NO. <i>SC-173B-1</i>

1840

STATE	COUNTY	ROUTE	SECTION	SHEET	TOTAL
CAL.	LOS ANGELES	101	2	37	

SUBMITTED Jan. 13, 1948
 ENGINEER OF BRIDGE & STRUCTURAL DESIGN
 APPROVED Jan. 17, 1949
Clayton A. Allen
 CITY ENGINEER CITY OF LOS ANGELES

DATE	APPROVED	BY
February 28, 1949		



AS BUILT PLANS
 Contract No. 141C84
 Date Completed
 Document No. 7000/1957

THIS SET OF PLANS HAS BEEN CHECKED TO CORRESPOND TO THE "AS BUILT" DATA. CLAYTON A. ALLEN, AS SUBMITTED BY RESIDENT ENGINEER. CLAYTON A. ALLEN.
 TRACINGS CORRECTED BY: DATE: 4-20-51

UTILITY LEGEND

ABOVE GROUND	BELOW GROUND
M.H. Manhole	L.A.W.D. Los Angeles Water Dept.
F.S. Fire Hydrant	B.P. & L. Bureau of Power & Light
T.S. Traffic Signal	L.A.G. Los Angeles Gas
T.P. Telephone Pole	S.S. Sanitary Sewer
E. Electric	S.D. Storm Drain
F.A. Fire Alarm	T.S. Traffic Signal
	P.T. & T. Pacific Tel. & Tel. Co.
	M.U.T.C. Western Union Telegraph Co.

NOTES
 1. Refer to interfering portions of sewer and storm drain systems. Excavation shall not be started until after the utility companies have arranged for "protection" by pipes supporting portions of utilities which are not removed by other's work. Be removed by contractor.
 2. Elevation of existing ground surface.
 3. Elevation of existing structure.
 4. Elevation of proposed structure.
 5. Elevation of proposed structure.

BENCH MARKS
 1. Bench mark in Lambie Stone 5' out from W.E. Cor. Los Angeles St. and Aliso St. Elev. 283.915.
 2. Brass bolt in Lambie Stone 5' out from N.W. Cor. Arcadia St. and Los Angeles St. Elev. 285.740.
 3. See E.B. 20120 records of the L.A. City Engineer for further information.


FOUNDATION PLAN
 Scale: 1" = 20'
 For pipes not shown see sanitary sewer and storm drain plans.
 For area available for use of Contractor see Sheet 30.

STATE OF CALIFORNIA DEPARTMENT OF PUBLIC WORKS DIVISION OF HIGHWAYS	
LOS ANGELES STREET OVERCROSSINGS	
FOUNDATION PLAN	
SCALE: 1"=20'	BRIDGE 53-629 ROAD 53-769
FILE	DRAWING C-1738-2


I HEREBY CERTIFY THAT THIS IS A TRUE AND ACCURATE COPY OF THE ABOVE DOCUMENT TAKEN UNDER BY DIRECTOR AND CONTROL ON THIS DATE IN SACRAMENTO, CALIFORNIA PURSUANT TO AUTHORIZATION BY THE DIRECTOR OF PUBLIC WORKS.
 DATE 5/11/51 SIGNATURE H. H. H. H. TITLE H. H. H.

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
2	CAL.			101	30


Submitted 10-13-1949
 Approved 10-17-1949
 Date approved 10-23-1949
 Engineer: [Signature]
 City Engineer: [Signature]




TYPICAL APPROACH APRON
 Scale 1/2" = 1'-0"



TYPICAL EDGE OF APRON WITHOUT CURB




SECTION A-A
 Scale 1/2" = 1'-0"




SECTION B-B
 Scale 1/2" = 1'-0"



SECTION C-C
 Scale 1/2" = 1'-0"



SECTION D-D
 Scale 1/2" = 1'-0"




CONCRETE DECK LAYOUT
 Scale 1" = 20'-0"

NOTE: Elevations are to top of concrete except as noted. See Street Plans for finish surface elevations.

* Elevation at top edge of Concrete Gutter

DETAILS OF DECK LAYOUT
 Scale 1" = 10'-0"



AS BUILT PLANS
 Contract No. 141C84
 Date Completed
 Document No. 70001957

THIS SET OF PLANS AND SPECIFICATIONS IS TO BE USED IN CONNECTION WITH THE CONTRACT FOR THE CONSTRUCTION OF THE LOS ANGELES STREET OVERCROSSINGS. THE ENGINEER'S OFFICE SHALL BE RESPONSIBLE FOR THE CORRECTION OF ANY ERRORS OR OMISSIONS.

STATE OF CALIFORNIA
 DEPARTMENT OF PUBLIC WORKS
 DIVISION OF HIGHWAYS

LOS ANGELES STREET OVERCROSSINGS

DECK LAYOUT & APPROACH APRONS

SCALE: As shown. SHEET: 101 OF 30. FILE: DRAWING: C-1738-3

I HEREBY CERTIFY THAT THIS IS A TRUE AND ACCURATE COPY OF THE ABOVE DOCUMENT TAKEN UNDER MY DIRECTION AND CONTROL ON THIS DATE IN SACRAMENTO, CALIFORNIA PURSUANT TO AUTHORIZATION BY THE DIRECTOR OF PUBLIC WORKS.






DATE 9/11/51 SIGNATURE: [Signature] TITLE: Asst. Dir.

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
2	CAL.				


DIST.	COUNTY	ROUTE	SECTION	POST MILE	TOTAL MILES
VII	L.A.	101		4	30

DATE APPROVED: February 28, 1943

Submittal No. 13
1/11/43
Jan. 17, 43
Eugene J. Smith



SECTION E-E
Scale 1/8" = 1'-0"
(N. End Abut. #3)
Note - For complete details and dimensions see Section B-B



BASE DETAIL
FULL SCALE


AS BUILT PLANS
Contract No. 141C84
Date Completed
Document No. 70001957

LOS ANGELES ST. OVERCROSSINGS
ABUTMENTS #1 & #3
SCALE AS SHOWN
BRIDGE #53-529
F.A.M.P. #3-769
FILE
DRAWING C-1736-4

I HEREBY CERTIFY THAT THIS IS A TRUE AND ACCURATE COPY OF THE ABOVE DOCUMENT TAKEN UNDER MY DIRECTION AND CONTROL ON THIS DATE IN SACRAMENTO, CALIFORNIA PURSUANT TO AUTHORIZATION BY THE DIRECTOR OF PUBLIC WORKS.
DATE 3/1/51 SIGNATURE [Signature] TITLE Chief

DATE APPROVED: February 28, 1949

DATE APPROVED: February 28, 1949



Note:
All fillets are G.O. unless otherwise noted

NOTE:
For Sections ...
see sheet ...

STATE OF CALIFORNIA
DEPARTMENT OF PUBLIC WORKS
DIVISION OF HIGHWAYS

LOS ANGELES STREET OVERCROSSINGS

ABUTMENTS "1 & "3 - DETAILS.

SCALE: AS SHOWN

BRIDGE
RAMPS

53-628
53-759

FILE

DRAWING C-1738-5


I HEREBY CERTIFY THAT THIS IS A TRUE AND ACCURATE COPY OF THE ABOVE DOCUMENT TAKEN UNDER MY DIRECTION AND CONTROL ON THIS DATE IN SACRAMENTO, CALIFORNIA PURSUANT TO AUTHORIZATION BY THE DIRECTOR OF PUBLIC WORKS.

DATE 5/15/61 SIGNATURE A. E. Eaton TITLE Asst. Dir.


Submitted Oct 19 1948
 ENGINEER, BRIDGE & STRUCTURAL DESIGN
 Approved Jan 17 1949
 CITY ENGINEER, CITY OF LOS ANGELES

Div. COUNTY ROUTE SECTION SHEET TOTAL
 VII L.A. 2 L.A. 5 30
 DATE APPROVED February 23, 1949


AS BUILT PLANS
 Contract No. 141C.84
 Date Completed
 Document No. 70001957




ELEVATION BENT No. 2
 Looking South
 Scale: 1\"/>



EXTERIOR FOOTING
 Scale: 1\"/>




INTERIOR FOOTING
 Scale: 1\"/>



Section M-M
 Scale: 1\"/>

Section N-N
 Scale: 1\"/>



Section P-P
 Scale: 1\"/>

THIS SET OF PLANS HAS BEEN CORRECTED TO
 REFLECT THE AS BUILT PRINTS, DATED
 ENGINEER'S SIGNATURE
 TRACING CORRECTED BY: DATE:

LOS ANGELES STREET OVERCROSSINGS


BENT No. 2

SCALE: AS SHOWN BRIDGE: 53-529 RAMP: 53-769 FILE DRAWING: C-1738-6

I HEREBY CERTIFY THAT THIS IS A TRUE AND ACCURATE COPY OF THE ABOVE DOCUMENT TAKEN
 UNDER MY DIRECTION AND CONTROL ON THIS DATE IN SACRAMENTO, CALIFORNIA PURSUANT TO
 AUTHORIZATION BY THE DIRECTOR OF PUBLIC WORKS.

DATE 5/1/51 SIGNATURE [Signature] TITLE Asst. Dir.

As-Built Plans
Eastside LRT Project Bridge over HWY 101, Bridge
No. 53-2975



submitted 8/5/08

INDEX TO BRIDGE PLANS

SHEET NO.	TITLE
1	GENERAL PLAN
2	INDEX TO PLANS
3	STRUCTURE PLAN No. 1
4	STRUCTURE PLAN No. 2
5	DECK CONTOURS No. 1
6	DECK CONTOURS No. 2
7	FOUNDATION PLAN
8	ABUTMENT 1 DETAILS No. 1
9	ABUTMENT 1 DETAILS No. 2
10	ABUTMENT 1 DETAILS No. 3
11	ABUTMENT 10 DETAILS No. 1
12	ABUTMENT 10 DETAILS No. 2
13	ABUTMENT 10 DETAILS No. 3
14	BENT 2 DETAILS
15	BENT 3 DETAILS
16	BENT 4 & 5 DETAILS
17	BENT 6 DETAILS
18	BENT 7, 8, & 9 DETAILS
19	COLUMN DETAILS No. 1
20	COLUMN DETAILS No. 2
21	3.0 M CIDH PILE DETAILS
22	2.4 M CIDH PILE DETAILS
23	TYPICAL SECTION No. 1
24	TYPICAL SECTION No. 2
25	TYPICAL SECTION No. 3
26	GIRDER LAYOUT No. 1
27	GIRDER LAYOUT No. 2
28	GIRDER LAYOUT No. 3
29	GIRDER REINFORCEMENT No. 1
30	GIRDER REINFORCEMENT No. 2
31	GIRDER REINFORCEMENT No. 3
32	GIRDER REINFORCEMENT No. 4
33	GIRDER DIAPHRAGM DETAILS
34	GIRDER CAMBER DIAGRAM
35	PTFE BEARING DETAILS FOR HINGE 5A
36	HINGE No. 5A DETAILS
37	HINGE No. 7A DETAILS
38	MISC DETAILS-HINGES NOS. 5A & 7A
39	CABLE RESTRAINER UNIT - TYPE 2
40	CABLE RESTRAINER UNIT - TYPE 2 DETAILS
41	JOINT SEAL ASSEMBLY (MR ≤ 100 mm)
42	JOINT SEAL DETAILS HINGE 5A (MR > 100 mm)
43	METAL SAFETY RAILING DETAILS
44	DRAINAGE DETAILS
45	OCS AND LIGHT POLE ANCHORS PLAN - 1
46	OCS AND LIGHT POLE ANCHORS PLAN - 2
47	OCS AND LIGHT POLE FOUNDATION DETAILS
48	WALKWAY AND OCS ANCHOR DETAILS
49	OCS POLE FOUNDATION DETAILS
50	OCS AND LIGHT POLE FOUNDATION SCHEDULE
51	TRACK DETAILS
52	STRAY CURRENT CONTROL No. 1
53	STRAY CURRENT CONTROL No. 2
54	STRAY CURRENT CONTROL No. 3
55	ALIGNMENT PLAN AND DATA
56	SURVEY CONTROL MONUMENTATION-METRIC
57	LOG OF BORINGS SHEET 1 OF 5
58	LOG OF BORINGS SHEET 2 OF 5
59	LOG OF BORINGS SHEET 3 OF 5
60	LOG OF BORINGS SHEET 4 OF 5
61	LOG OF BORINGS SHEET 5 OF 5


GENERAL NOTES LOAD FACTOR DESIGN

DESIGN:
CALTRANS BRIDGE DESIGN SPECIFICATIONS (LFD VERSION APRIL 2000)
(1996 AASHTO WITH INTERIM REVISIONS BY CALTRANS) AND LACMTA
DESIGN CRITERIA

ADDITIONAL DEAD LOADS (AD):
RAIL & PLINTHS, DUCTBANK/WALKWAY, OCS POLES

LIVE LOADING (LL):
LIGHT RAIL VEHICLES (LRV) & MAINTENANCE
VEHICLE (LP) (SEE LOADING DIAGRAMS)

LIGHT RAIL VEHICLE (LRV)



ESTIMATED LOADING DISTRIBUTION (kN)


	DISTR. TO CENTER TRUCK	P1	P2	TOTAL
UNLOADED	24%	82.83	52.31	435.93
	31%	75.20	67.57	435.93
FULLY LOADED	24%	108.98	82.29	600.51
	31%	101.42	96.97	600.51

MAX SPEED OF LIGHT RAIL VEHICLE = 25 km/h

LIGHT RAIL VEHICLE FOR SEISMIC:
THE MASS OF ONE 3-CAR TRAIN IS INCLUDED WITH THE DEADLOAD MASS OF THE STRUCTURE. NO OTHER ASPECT OF LIVE LOAD IS INCLUDED IN GROUP VII LOADING

No As-Built Changes

LIGHT RAIL MAINTENANCE VEHICLE (LP)




LOADING (kN)

	LOADED
P1	133.45
P2	200.17
P3	82.29

LIGHT RAIL VEHICLE (LRV) IMPACT:
VERTICLE = 30% OF LL, HORIZ = 10% OF LL
(NO IMPACT FOR LP LOADING)

SEISMIC LOADING (EQ):
MODIFIED SDC ARS CURVE FOR SOIL
PROFILE C (M= 7.25 ± 0.25)
(PEAK ROCK ACCELERATION = 0.6g WITH
20% INCREASE IN SPECTRA ACCELERATION
MODIFIED AS SHOWN BELOW)



REINFORCED CONCRETE:
SUPERSTRUCTURE SUBSTRUCTURE
Fy = 420 MPa Fy = 420 MPa
F'c = 35 MPa F'c = 25 & 28 MPa

TRANSVERSE DECK SLABS
(WORKING STRESS DESIGN)
Fy = 138 MPa
F'c = 8.3 MPa
N = 10

PRESTRESSED CONCRETE:
SEE "PRESTRESSING NOTES" IN
"GIRDER LAYOUT NO. 1" SHEET

ADDITIONAL ABBREVIATIONS

CS	CIRCULAR CURVE TO SPIRAL
EB	EASTBOUND
NIC	NOT IN THIS CONTRACT (BY OTHERS)
OCS	OVERHEAD CONTACT SYSTEM
SC	SPIRAL TO CIRCULAR CURVE
ST	SPIRAL TO TANGENT OR SHORT TANGENT
T/R	TOP OF RAIL
TRK	TRACK
TS	TANGENT TO SPIRAL
WB	WESTBOUND

QUANTITIES

	LUMP	SUM
CONTAMINATED MATERIAL HANDLING	243	m ³
STRUCTURE EXCAVATION (BRIDGE)	44	m ³
STRUCTURE EXCAVATION (TYPE Y) (AERIALY DEPOSITED LEAD)	370	m ³
STRUCTURE BACKFILL (BRIDGE)	142	m
1.2 m CAST-IN-DRILLED-HOLE CONCRETE PILING	109	m
2.4 m CAST-IN-DRILLED-HOLE CONCRETE PILING	67	m
3.0 m CAST-IN-DRILLED-HOLE CONCRETE PILING	83	m
900 mm CAST-IN-DRILLED-HOLE CONCRETE PILING		
PRESTRESSING CAST-IN-PLACE CONCRETE STRUCTURAL CONCRETE, BRIDGE FOOTING	LUMP	SUM
STRUCTURAL CONCRETE, BRIDGE	191	m ³
FLUTED RIB TEXTURE	2	360 m ²
JOINT SEAL (MR=30 mm)	36	m ²
JOINT SEAL ASSEMBLY (MR 70 mm)	10	m
JOINT SEAL ASSEMBLY (MR 90 mm)	10	m
JOINT SEAL ASSEMBLY (MR 101 mm - 160 mm)	10	m
BAR REINFORCING STEEL (BRIDGE)	982	000 kg
BAR REINFORCING STEEL (EPOXY COATED) (BRIDGE)	6	200 kg
MISCELLANEOUS METAL (RESTRAINER - CABLE TYPE)	1	334 kg
MISCELLANEOUS METAL (BRIDGE)	18	400 kg
METAL RAILING	667	m
PTFE BEARING	4	EA

ALL DIMENSIONS ARE IN
METERS UNLESS OTHERWISE SHOWN

DESIGN OVERSIGHT 7-10-03 SIGN OFF DATE DESIGN DETAIL SHEET (METRIC) REV. 3/1/98	DESIGN BY: CHU DETAILS BY: NGUYEN/PEARLMAN QUANTITIES BY: OVERSTREET	CHECKED XIE CHECKED LEE/PANDYA CHECKED VARGAS/DULOR	PREPARED FOR THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	DAK YAVORSKY PROJECT ENGINEER	BRIDGE NO. 53-2975 53C-2146 KILOMETER POST 1.07	EASTSIDE UNDERPASS (LRT) INDEX TO PLANS	REVISION DATES (PRELIMINARY STAGE ONLY) 12-13-2007 12-13-2007 12-13-2007	SHEET 2 OF 61
--	--	---	---	----------------------------------	---	--	---	---------------


2.5.2009

Date: 12-13-2007

DATE 02-12-07



REGISTERED CIVIL ENGINEER



The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

METROPOLITAN TRANSPORTATION AUTHORITY
ONE GATEWAY PLAZA
LOS ANGELES, CA. 90012

[illegible]

1. For OCS Pole Locations,
See "OCS AND LIGHT POLE
FOUNDATION SCHEDULE" Sheet - 50
2. For Eastbound Track Curve
Alignment,
See "TRACK ALIGNMENT PLAN
AND DATA" Sheet.

ALL DIMENSIONS ARE IN
METERS UNLESS OTHERWISE SHOWN

BRIDGE NO.
53-2975 53C-2148
KILOMETER POST
1.07


DISREGARD PRINTS BEARING
EARLIER REVISION DATES

REVISION DATES (PRELIMINARY STAGE ONLY)

SHEET	OF
3	61

USER	DATE	TIME
USER1	2023-10-27	14:30
USER2	2023-10-27	15:45
USER3	2023-10-28	09:15
USER4	2023-10-28	11:00
USER5	2023-10-29	13:20
USER6	2023-10-29	16:10
USER7	2023-10-30	08:45
USER8	2023-10-30	12:30
USER9	2023-10-31	10:15
USER10	2023-10-31	14:00

△					
△	12/25/05	Revised per RFI-198.02	VN	NP	
MARK	DATE	DESCRIPTION	BY	CHK'D	
		REVISIONS			



AS BUILT

CORRECTIONS BY BASSEM KABBARA

CONTRACT NO. 07-119944

DATE 02-12-2007

DIST	COUNTY	ROUTE	KILOMETER POST TOTAL PROJECT	SHEET NO	TOTAL SHEETS
7	LA	101	0.6/1.4	269R	326


REGISTERED CIVIL ENGINEER

PLANS APPROVAL DATE

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

EASTSIDE LRT PARTNERS
707 WILSHIRE BLVD. SUITE 2900
LOS ANGELES, CA 90017

METROPOLITAN TRANSPORTATION AUTHORITY
ONE GATEWAY PLAZA
LOS ANGELES, CA. 90012




DEVELOPED ELEVATION

1:250

Spiral Data
EB Track
L = 30.48 m
 $\Delta = 23^\circ 52' 23.67''$

Curve Data
EB Track
R = 36.576 m
 $\Delta = 44^\circ 33' 22.60''$
L = 28.4435 m



PLAN

1:250

NOTES:

1. For OCS Pole Locations, See "OCS AND LIGHT POLE FOUNDATION SCHEDULE" Sheet.
2. For Eastbound Track Curve Alignment, See "TRACK ALIGNMENT PLAN AND DATA" Sheet.

AS BUILT PLANS

Contract No. 07-119944

Reviewed By Engineer [Signature]
(N.P. Pandya)

Date: 12-13-2007

ALL DIMENSIONS ARE IN METERS UNLESS OTHERWISE SHOWN

DESIGN OVERSIGHT
7-10-03
SIGN OFF DATE
DESIGN DETAIL SHEET (METRIC) REV. 3/1/98

DESIGN	BY YANG/DULOR	CHECKED XIE
DETAILS	BY MUNOZ/PEARLMAN	CHECKED LEE/PANDYA
QUANTITIES	BY OVERSTREET	CHECKED VARGAS/DULOR

PREPARED FOR THE
STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

DAN YAVORSKY
PROJECT ENGINEER

BRIDGE NO.
53-2975
53C-2448
KILOMETER POST
1.07

EASTSIDE UNDERPASS (LRT)
STRUCTURE PLAN No. 2

CU 07225
EA 1199U1

DISREGARD PRINTS BEARING
EARLIER REVISION DATES

REVISION DATES (PRELIMINARY STAGE ONLY)

SHEET
4
OF
61

ORIGINAL SCALE IN MILLIMETERS
FOR REDUCED PLANS

FILE => aasp10004.dgn




DIST	COUNTY	ROUTE	KILOMETER POST TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
07	LA	101	0.6/1.4	271	326

REGISTERED CIVIL ENGINEER
6-7-04
PLANS APPROVAL DATE
The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.



EASTSIDE LRT PARTNERS
707 WILSHIRE BLVD. SUITE 2900
LOS ANGELES, CA 90017
METROPOLITAN TRANSPORTATION AUTHORITY
ONE GATEWAY PLAZA
LOS ANGELES, CA 90012
Caltrans now has a web site! To get to the web site, go to: <http://www.dot.ca.gov>



AS BUILT
CORRECTIONS BY BASSEM KARBARA
CONTRACT NO. 07-1199U4
DATE 07-12-2007

AS BUILT PLANS
Contract No. 07-1199U4
Reviewed By Engineer [Signature]
(N.P. Pandya)
Date: 12-13-2007


CONCRETE STRENGTH AND TYPE LIMITS


- No Scale
- STRUCTURE CONCRETE, BRIDGE (F'c = 28 MPa @28 DAYS)
 - STRUCTURE CONCRETE, BRIDGE (F'c = 35 MPa @28 DAYS)
 - CAST-IN-DRILL HOLE CONCRETE PILE, BRIDGE (F'c = 28 MPa @ 28 DAYS)
 - STRUCTURAL CONCRETE FOOTING, (F'c = 25 MPa @28 DAYS)


No As-Built Change

ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE SHOWN

DESIGN OVERSIGHT 7-10-03 SIGN OFF DATE	DESIGN BY CHU	CHECKED XIE	PREPARED FOR THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	DAN YAVORSKY PROJECT ENGINEER	BRIDGE NO. 53-2975 53C-2545 KILOMETER POST 1.07	EASTSIDE UNDERPASS (LRT) DECK CONTOURS No. 2
DESIGN DETAIL SHEET (METRIC REV. 3/1/80)	DETAILS BY NGUYEN/PEARLMAN	CHECKED LEE/PANDYA	QUANTITIES BY OVERSTREET	CHECKED VARGAS/DUCOR	CU 07225 EA 1199U1 FILE => abdkc0006.dgn	DISREGARD PRINTS BEARING EARLIER REVISION DATES
					REVISION DATES (PRELIMINARY STAGE ONLY)	SHEET 6 OF 61










DIST	COUNTY	ROUTE	KILOMETER POST TOTAL PROJECT	SHEET No	TOTAL SHEETS
07	LA	101	0.6/1.4	274	326

REGISTERED CIVIL ENGINEER
 6-07-04
 PLANS APPROVAL DATE
 The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

EASTSIDE LRT PARTNERS
 707 WILSHIRE BLVD. SUITE 2900
 LOS ANGELES, CA 90017

METROPOLITAN TRANSPORTATION AUTHORITY
 ONE GATEWAY PLAZA
 LOS ANGELES, CA. 90012

Caltrans now has a web site! To get to the web site, go to: <http://www.dca.ca.gov>



AS BUILT SECTION D-D AS BUILT PLANS
 1:25
 Contract No. 07-1199U4
 Reviewed By Engineer (N.P. Pandya)
 Date: 12-13-2007
 CORRECTIONS BY B. KABBARA
 CONTRACT NO. 07-1199U4
 DATE 02-12-2007
 ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE SHOWN

No As-Built Changes

DESIGN: DAN YAVORSKY	CHECKED: DAN YAVORSKY	DATE: 7-10-03
DESIGN: DAN YAVORSKY	CHECKED: DAN YAVORSKY	DATE: 7-10-03

DESIGN DETAIL SHEET (METRIC) REV. 3/1/90

PREPARED FOR THE
 STATE OF CALIFORNIA
 DEPARTMENT OF TRANSPORTATION

DAN YAVORSKY
 PROJECT ENGINEER

BRIDGE NO.: 53-2975
 330-240
 KILOMETER POST: 1.07

EASTSIDE UNDERPASS (LRT)
ABUTMENT 1 DETAILS No. 2

CU 07225
 EA 1199U1

FILE: \\adab11009.dgn

DISREGARD PRINTS BEARING
 EARLIER REVISION DATES

REVISION DATES (PRELIMINARY STAGE ONLY)

NO.	DATE	DESCRIPTION
1	07-10-03	ISSUED FOR PERMIT
2	07-10-03	ISSUED FOR PERMIT

SHEET 9 OF 61

Date: 12-13-2007



DIST	COUNTY	ROUTE	KILOMETER POST TOTAL PROJECT	SHEET No	TOTAL SHEETS
07	LA	101	0.6/1.4	275	326


REGISTERED CIVIL ENGINEER

6-07-04

PLANS APPROVAL DATE


The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

EASTSIDE LRT PARTNERS
707 WILSHIRE BLVD. SUITE 2900
LOS ANGELES, CA - 90017

METROPOLITAN TRANSPORTATION AUTHORITY
ONE GATEWAY PLAZA
LOS ANGELES, CA. 90012

Caltrans now has a web site! To get to the web site, go to: <http://www.dot.ca.gov>

CIDH pile Cut-off elev.
See "Foundation Plan" sheet




ELEVATION (1.2 M Ø CIDH PILE)

1:40


Notes:

1. Only staggered "Ultimate" butt splices are allowed in main CIDH pile reinforcement in this zone.
2. All hoops are "Ultimate" butt spliced continuous.



EXPANSIVE SOIL EXCLUSION ZONE

No Scale



SECTION A-A

No Scale



Structure backfill
(bridge)

For additional details see




AS BUILT PLANS

Contract No. 07-1199U4

Reviewed By Engineer (N.P. Pandya)


Date: 12-13-2007



EXCAVATION

ABUTMENT 1

BACKFILL



EXCAVATION

ABUTMENT 10

BACKFILL

LIMITS OF PAYMENT FOR STRUCTURE EXCAVATION & BACKFILL

No Scale

ALL DIMENSIONS ARE IN
MILLIMETERS UNLESS OTHERWISE SHOWN

DESIGN OVERSIGHT 7-10-03 SIGN OFF DATE		DESIGN BY: YANG / PANDYA DETAILS BY: NGUYEN / PEARLMAN QUANTITIES BY: OVERSTREET		CHECKED BY: XUE CHECKED BY: LEE / PANDYA CHECKED BY: VARGAS / DULOR		PREPARED FOR THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION		DAM YAVORSKY PROJECT ENGINEER		BRIDGE NO. 33-2975 SSC-2446 KILOMETER POST 1.07		EASTSIDE UNDERPASS (LRT) ABUTMENT 1 DETAILS No.3	
DESIGN DETAIL SHEET (METRIC REV. 3/1/98)				ORIGINAL SCALE IN MILLIMETERS FOR REDUCED PLANS				CU 07225 EA 11999U1		DISPERGARD PRINTS BEARING EARLIER REVISION DATES			
				0 10 20 30 40 50 60 70 80 90 100						REVISION DATES (PRELIMINARY STAGE ONLY) 10-19-03 07-06-03			
										SHEET 10 OF 61			

FILE => odab+1010.dgn

(THIS PAGE INTENTIONALLY LEFT BLANK)

Appendix C: Existing Geotechnical Boring Logs

(THIS PAGE INTENTIONALLY LEFT BLANK)

Existing Geotechnical Boring Logs

ARCADIS, 2014

SOIL DESCRIPTION

Soil descriptions on the exploration logs are based on visual observations and laboratory testing on selected samples.

MOISTURE

Dry	Little perceptible moisture
Damp	Below optimum moisture for compaction
Moist	Likely near optimum moisture content
Wet	Likely wet of optimum moisture content
Saturated	Probably below water table or in perched groundwater

SAMPLE TYPE SYMBOLS

MCS 2.0 = Modified California (ID 1.9 inch with liner)
CT = Cuttings
CR = Core Run
ST = Shelby Tube

TEST SYMBOLS


MC Moisture Content
GS Grain Size
AL Atterberg Limits
SG Specific Gravity
DT Density Test
OG Organic Content
CN Consolidation
UU Unconsolidated Undrained Triaxial
CU Consolidated Undrained Triaxial
UC Unconfined Compression
DS Direct Shear
K Permeability
PP Pocket Penetrometer in tons/ft²
CT Corrosivity Test
PID Photolionization Detector Reading
CA Chemical Analysis

KEY TO EXPLORATION LOGS



Date Start/Finish: 8/19/14 Drilling Company: Jet Drilling Driller's Name: Gary Buss Drilling Method: Hollow Stem Auger Rig Type: CME 75 Sampling Method: CA Modified Split Spoon	Northing: NA Easting: NA Casing Elevation: NA Borehole Depth: 50 ft Borehole Diameter: 8" Surface Elevation: NA Descriptions By: Brent Anderson	Well/Boring ID: B-01 Client: Los Angeles Metropolitan Transportation Authority Location: MTA Metro 410 Center Street Los Angeles, California
---	--	---

DEPTH	Sample ID	Sample Type	Recovery (feet)	Blow Counts	PID (ppm)	Lab Tests	USCS Code	Geologic Column	Stratigraphic Description
0									
	B-01-5	MCS 2.0			0.0				Gravel and asphalt debris.
							SW		WELL GRADED SAND FILL (20, 80, 0, 0), olive brown (2.5Y 4/3), dry, subangular, with little fine- to coarse-grained gravel.
5			1.5	4 5 12	0.0	GS, MC, DT	SW		WELL GRADED SAND (18, 84, 2, 0), brown (10YR 4/3), dry, medium- to coarse-grained, subangular to angular.
	B-01-10	MCS 2.0							
			1.5	11 18 15	0.0	DS	SW		WELL GRADED SAND (0, 95, 5, 0), brown (10YR 4/3), dry, medium-grained, subangular.
10									
	B-01-15	MCS 2.0							
			1.5	12 23 32	0.0	GS, MC, DT	SW		WELL GRADED SAND WITH GRAVEL (14, 82, 4, 0), light brownish gray (10YR 6/2), dry, medium- to very coarse-grained, angular.
15									

	Remarks: amsl = above mean sea level; bgs = below ground surface; Dia. = diameter; ft' = feet, NA = not applicable/available; ppm = parts per million (5, 95, 0, 0) = %(gravel, sand, silt, clay) ☒ = First Encountered Water ○ = Static Water		Water Level Data		
			Date	Depth	Elev.
			8/19/14	☒ 30 ft bgs	NA ft amsl
			NA	○ NA btoc	NA ft amsl

Client: Los Angeles Metropolitan Transportation Authority

Well/Boring ID: B-01

Site Location:

MTA Metro
410 Center Street
Los Angeles, California

Borehole Depth: 50 ft

DEPTH	Sample ID	Sample Type	Recovery (feet)	Blow Counts	PID (ppm)	Lab Tests	USCS Code	Geologic Column	Stratigraphic Description
20	B-01-20	MCS 2.0	1.5	17 45 50	0.0		SW		WELL GRADED SAND (20, 80, 0, 0), dark yellowish brown (10YR 4/4), dry, medium- to very coarse-grained, angular.
25	B-01-26	MCS 2.0	1.5	25 28 30		GS, MC, DT	SW		WELL GRADED SAND (16, 78, 6, 0), dark yellowish brown (10YR 4/4), dry, medium- to coarse-grained, subangular.
30	B-01-30	MCS 2.0	1.5	41 32 23	3.2	GS, MC, DT	GP		Poorly Graded GRAVEL, pulverized.
35	B-01-35	MCS 2.0	0.8	50 50		GS, MC, DT	GP		Same as above.



Remarks:

amsl = above mean sea level; bgs = below ground surface; Dia. = diameter; ft' = feet, NA = not applicable/available; ppm = parts per million

(5, 95, 0, 0) = %(gravel, sand, silt, clay)

☒ = First Encountered Water

○ = Static Water

Water Level Data

Date	Depth	Elev.
8/19/14	☒ 30 ft bgs	NA ft amsl
NA	○ NA btoc	NA ft amsl

Client: Los Angeles Metropolitan Transportation Authority

Well/Boring ID: B-01

Site Location:

MTA Metro
410 Center Street
Los Angeles, California

Borehole Depth: 50 ft

DEPTH	Sample ID	Sample Type	Recovery (feet)	Blow Counts	PID (ppm)	Lab Tests	USCS Code	Geologic Column	Stratigraphic Description
40	B-01-40	MCS 2.0	0.8	45 50	9.8		GP		Poorly Graded GRAVEL WITH SAND (55, 45, 0, 0), dark gray (10YR 4/1), wet, coarse gravel with medium- to very coarse-grained sand.
45	B-01-45	MCS 2.0	0.8	27 50	0.0		SP		POORLY GRADED SAND (25, 75, 0, 0), dark grayish brown (2.5Y 4/2), wet, medium- to coarse-grained, subangular, with some fine to coarse gravel, some larger rock fragments.
50	B-01-50	MCS 2.0	0.8	28 50	0.0		SP		POORLY GRADED SAND (0, 100, 0, 0), dark gray (2.5Y 4/1), wet, coarse-grained, subangular to angular, compacted.
55									Bottom of boring at 50 ft bgs.



Remarks:

amsl = above mean sea level; bgs = below ground surface; Dia. = diameter; ft' = feet, NA = not applicable/available; ppm = parts per million

(5, 95, 0, 0) = %(gravel, sand, silt, clay)

= First Encountered Water = Static Water

Water Level Data

Date	Depth	Elev.
8/19/14	30 ft bgs	NA ft amsl
NA	NA btoc	NA ft amsl

Client: Los Angeles Metropolitan Transportation Authority

Well/Boring ID: B-02

Site Location:

MTA Metro
410 Center Street
Los Angeles, California

Borehole Depth: 50 ft

DEPTH	Sample ID	Sample Type	Recovery (feet)	Blow Counts	PID (ppm)	Lab Tests	USCS Code	Geologic Column	Stratigraphic Description
20	B-02-19	MCS 2.0	0.9	22 28	0.0	GS, MC	SW		
	B-02-23	MCS 2.0	0.9	27 50-5"	0.0		GP		POORLY GRADED GRAVEL (66, 32, 2, 0), dark yellowish brown (10YR 4/4), dry, fine- to coarse-grained, fine gravel.
25	B-02-28	MCS 2.0	0.5	36 50-5"	0.0	GS, MC	GP		Same as above.
30	B-02-33	MCS 2.0	0.7	40 50-5"	1.7		SW		WELL GRADED SAND (5, 95, 0, 0), very dark gray (10YR 3/1), wet, fine- to coarse-grained, subangular, trace fine to medium gravel.
35									



Remarks:

amsl = above mean sea level; bgs = below ground surface; Dia. = diameter;
ft' = feet, NA = not applicable/available; ppm = parts per million

(5, 95, 0, 0) = %(gravel, sand, silt, clay)

☒ = First Encountered Water ○ = Static Water

Water Level Data

Date	Depth	Elev.
8/26/14	☒ NA ft bgs	NA ft amsl
NA	○ NA btoc	NA ft amsl




Client: Los Angeles Metropolitan Transportation Authority

Well/Boring ID: B-02

Site Location:

MTA Metro
410 Center Street
Los Angeles, California

Borehole Depth: 50 ft

DEPTH	Sample ID	Sample Type	Recovery (feet)	Blow Counts	PID (ppm)	Lab Tests	USCS Code	Geologic Column	Stratigraphic Description
40	B-02-39	MCS 2.0	1.3	45 48 50-2"	0.0		SW		Same as above.
45	B-02-43	MCS 2.0	0.3	50 50-3"			SW		WELL GRADED SAND (30, 70, 0, 0), very dark gray (10YR 3/1), wet, fine- to coarse-grained, subrounded, trace medium gravel and crushed rock.
50	B-02-49	MCS 2.0	1.2	50 45 45	0.0		SP		POORLY GRADED SAND (0, 98, 2, 0), very dark gray (10YR 3/1), wet, fine- to medium-grained, subrounded, trace silt.
55									Bottom of boring at 50 ft bgs.





Remarks:

amsl = above mean sea level; bgs = below ground surface; Dia. = diameter;
ft' = feet, NA = not applicable/available; ppm = parts per million

(5, 95, 0, 0) = %(gravel, sand, silt, clay)


 = First Encountered Water  = Static Water

Water Level Data

Date	Depth	Elev.
8/26/14	 NA ft bgs	NA ft amsl
NA	 NA btoc	NA ft amsl


Date Start/Finish: 8/20/14	Northing: NA Easting: NA Casing Elevation: NA	Well/Boring ID: B-03
Drilling Company: Jet Drilling		Client: Los Angeles Metropolitan Transportation Authority
Driller's Name: Gary Buss		
Drilling Method: Hollow Stem Auger	Borehole Depth: 5 ft Borehole Diameter: 8" Surface Elevation: NA	Location: MTA Metro 410 Center Street Los Angeles, California
Rig Type: CME 75	Descriptions By: Brent Anderson	
Sampling Method: CA Modified Split Spoon		

DEPTH	Sample ID	Sample Type	Recovery (feet)	Blow Counts	PID (ppm)	Lab Tests	USCS Code	Geologic Column	Stratigraphic Description
0									
					0.0		SP		POORLY GRADED SAND (0, 85, 15, 0), dry, fine grained, rounded.
					0.0		SP		POORLY GRADED SAND (0, 100, 0, 0), slightly moist, fine to medium grained, subangular.
5									Boring terminated @ 5 ft bgs due to unknown obstruction.
10									
15									

 Infrastructure · Water · Environment · Buildings	Remarks: amsl = above mean sea level; bgs = below ground surface; Dia. = diameter; ft' = feet, NA = not applicable/available; ppm = parts per million (5, 95, 0, 0) = %(gravel, sand, silt, clay) ☒ = First Encountered Water ○ = Static Water			Water Level Data		
	Date	Depth	Elev.	Date	Depth	Elev.
	NA	☒ NA ft bgs	NA ft amsl	NA	○ NA btoc	NA ft amsl

Date Start/Finish: 8/22/14	Northing: NA Easting: NA Casing Elevation: NA	Well/Boring ID: B-04
Drilling Company: Jet Drilling		Client: Los Angeles Metropolitan Transportation Authority
Driller's Name: Gary Buss		
Drilling Method: Hollow Stem Auger	Borehole Depth: 20 ft Borehole Diameter: 8" Surface Elevation: NA	Location: MTA Metro 410 Center Street Los Angeles, California
Rig Type: CME 75	Descriptions By: Brent Anderson	
Sampling Method: CA Modified Split Spoon		

DEPTH	Sample ID	Sample Type	Recovery (feet)	Blow Counts	PID (ppm)	Lab Tests	USCS Code	Geologic Column	Stratigraphic Description
0									
									Decomposed brick mixed with fill, sand and trace fine gravel, metal debris.
5									Unknown fill objects impeding auger rods, concrete structure.
10									
15									Approximately 1' of concrete.

 Infrastructure · Water · Environment · Buildings	Remarks: amsl = above mean sea level; bgs = below ground surface; Dia. = diameter; ft' = feet, NA = not applicable/available; ppm = parts per million (5, 95, 0, 0) = %(gravel, sand, silt, clay) ☒ = First Encountered Water ○ = Static Water	Water Level Data		
		Date	Depth	Elev.
		NA	☒ NA ft bgs	NA ft amsl
		NA	○ NA btoc	NA ft amsl

Client: Los Angeles Metropolitan Transportation Authority

Well/Boring ID: B-04

Site Location:

MTA Metro
410 Center Street
Los Angeles, California

Borehole Depth: 20 ft

DEPTH	Sample ID	Sample Type	Recovery (feet)	Blow Counts	PID (ppm)	Lab Tests	USCS Code	Geologic Column	Stratigraphic Description
20									
									Boring terminated @ ~20' bgs due to broken auger.
25									
30									
35									



Remarks:

amsl = above mean sea level; bgs = below ground surface; Dia. = diameter;
ft' = feet, NA = not applicable/available; ppm = parts per million

(5, 95, 0, 0) = %(gravel, sand, silt, clay)



= First Encountered Water








= Static Water

Water Level Data

Date	Depth	Elev.
NA	NA ft bgs	NA ft amsl
NA	NA btoc	NA ft amsl

Date Start/Finish: 8/22/14 - 8/25/14 Drilling Company: Jet Drilling Driller's Name: Gary Buss Drilling Method: Mud Rotary Rig Type: CME 75 Sampling Method: CA Modified Split Spoon	Northing: NA Easting: NA Casing Elevation: NA Borehole Depth: 49 ft Borehole Diameter: 8" Surface Elevation: NA Descriptions By: Brent Anderson (8/22) James Gonzales (8/25)	Well/Boring ID: B-05 Client: Los Angeles Metropolitan Transportation Authority Location: MTA Metro 410 Center Street Los Angeles, California
--	--	---

DEPTH	Sample ID	Sample Type	Recovery (feet)	Blow Counts	PID (ppm)	Lab Tests	USCS Code	Geologic Column	Stratigraphic Description
0									
	B-05-5	MCS 2.0	1.5		0.0	CT	SP		POORLY GRADED SAND Fill (5, 95, 0, 0), brown (10YR 4/3), dry, medium dense, fine-grained, subrounded.
									Concrete slab.
	B-05-10	MCS 2.0	1.2	5 6 10	0.0		SW		WELL GRADED SAND (25, 75, 0, 0), very dark gray (7.5YR 3/1), fine- to coarse-grained, subangular, organic matter present.
									WELL GRADED SAND (2, 89, 9, 0), very dark brown (10YR 2/2), medium- to coarse-grained, subrounded to

 <i>Infrastructure · Water · Environment · Buildings</i>	Remarks: amsl = above mean sea level; bgs = below ground surface; Dia. = diameter; ft' = feet, NA = not applicable/available; ppm = parts per million Drilled to 17.5 ft bgs on 8/22/14. (5, 95, 0, 0) = %(gravel, sand, silt, clay) ⊖ = First Encountered Water ○ = Static Water				Water Level Data		
	Date		Depth		Elev.		
	8/25/14		⊖ NA ft bgs		NA ft amsl		
	NA		○ NA btoc		NA ft amsl		

Client: Los Angeles Metropolitan Transportation Authority

Well/Boring ID: B-05

Site Location:

MTA Metro
410 Center Street
Los Angeles, California

Borehole Depth: 49 ft

DEPTH	Sample ID	Sample Type	Recovery (feet)	Blow Counts	PID (ppm)	Lab Tests	USCS Code	Geologic Column	Stratigraphic Description
20	B-05-19	MCS 2.0	1.5	38 23	0.0	GS	SW		subangular, trace fine subangular gravel, trace silt.
	B-05-24	MCS 2.0	1.5	22 31 50	0.0	GS	SW		WELL GRADED SAND (0, 90, 8, 2), very dark brown (10YR 2/2), medium- to coarse-grained, subrounded to subangular, trace fine subangular gravel, trace silt.
25	B-05-28	MCS 2.0	0.4	50-5"	0.0		SW		WELL GRADED SAND (20, 80, 0, 0), very dark grayish brown (10YR 3/2), medium- to coarse-grained, subrounded, fine to medium gravel.
	B-05-33	MCS 2.0	0.75	50 50-3"	0.0		SW		Same as above.
30									
35									



Remarks:

amsl = above mean sea level; bgs = below ground surface; Dia. = diameter; ft' = feet, NA = not applicable/available; ppm = parts per million

Drilled to 17.5 ft bgs on 8/22/14.

(5, 95, 0, 0) = %(gravel, sand, silt, clay)

☒ = First Encountered Water ○ = Static Water

Water Level Data

Date	Depth	Elev.
8/25/14	☒ NA ft bgs	NA ft amsl
NA	○ NA btoc	NA ft amsl

Client: Los Angeles Metropolitan Transportation Authority

Well/Boring ID: B-05

Site Location:

MTA Metro
410 Center Street
Los Angeles, California

Borehole Depth: 49 ft

DEPTH	Sample ID	Sample Type	Recovery (feet)	Blow Counts	PID (ppm)	Lab Tests	USCS Code	Geologic Column	Stratigraphic Description
40	B-05-38	MCS 2.0	0.9	40 50-5"	0.0		SW		WELL GRADED SAND (35, 65, 0, 0), very dark gray (10YR 3/1), medium- to coarse-grained, subrounded, fine to medium gravel, rounded.
45	B-05-43	MCS 2.0	1.5	20 37 48			SW		WELL GRADED SAND (20, 79, 1, 0), very dark gray (10YR 3/1), subrounded, fine to coarse gravel, subangular, trace silt.
50	B-05-48	MCS 2.0	1.5	28 44 49			SW		Same as above.
55									Bottom of boring at 49 ft bgs.



Remarks:

amsl = above mean sea level; bgs = below ground surface; Dia. = diameter; ft' = feet, NA = not applicable/available; ppm = parts per million

Drilled to 17.5 ft bgs on 8/22/14.






(5, 95, 0, 0) = %(gravel, sand, silt, clay)

☒ = First Encountered Water ○ = Static Water

Water Level Data

Date	Depth	Elev.
8/25/14	☒ NA ft bgs	NA ft amsl
NA	○ NA btoc	NA ft amsl

Date Start/Finish: 8/25/14 Drilling Company: Jet Drilling Driller's Name: Gary Buss Drilling Method: Mud Rotary Rig Type: CME 75 Sampling Method: CA Modified Split Spoon	Northing: NA Easting: NA Casing Elevation: NA Borehole Depth: 49 ft Borehole Diameter: 8.25" Surface Elevation: NA Descriptions By: Ali Zafarani	Well/Boring ID: B-06 Client: Los Angeles Metropolitan Transportation Authority Location: MTA Metro 410 Center Street Los Angeles, California
--	---	--

0	B-06-9	MCS 2.0	1.5	16 17 21	0.0		SW		4" Asphalt at surface. Aggregate Base Fill.
5									6" Concrete slab.
							SW		WELL GRADED SAND (5, 95, 0, 0), brown (7.5YR 4/3), moist, fine- to coarse-grained, subrounded, fine to medium gravel, trace silt.
10									
	B-06-13	MCS 2.0	0.45	50-5"	0.0		SW		WELL GRADED SAND (5, 95, 0, 0), very dark gray (10YR 3/1), moist, medium- to coarse-grained, subangular, trace fine gravel, trace pulverized cobbles.
15									
							SW		WELL GRADED SAND (24, 72, 4, 0), very dark grayish brown (10YR 3/2), dry, fine- to coarse-grained, subrounded, fine

Client: Los Angeles Metropolitan Transportation Authority

Well/Boring ID: B-06

Site Location:

MTA Metro
410 Center Street
Los Angeles, California

Borehole Depth: 49 ft

DEPTH	Sample ID	Sample Type	Recovery (feet)	Blow Counts	PID (ppm)	Lab Tests	USCS Code	Geologic Column	Stratigraphic Description
20	B-06-19	MCS 2.0	1.35	19 20	0.0	GS, MC	SW	gravel.	
	B-06-23	MCS 2.0	0.75	28 50-3"			SW	Same as above.	
25	B-06-29	MCS 2.0	1.2	38 35 42	0.0	GS, MC	SW	WELL GRADED SAND (2, 92, 6, 0), very dark gray (10YR 3/1), moist, fine- to coarse-grained, subangular, trace gravel.	
	B-06-34	MCS 2.0	1.2	30 39 43	0.0		SW	Same as above.	
30									
35									



Remarks:

amsl = above mean sea level; bgs = below ground surface; Dia. = diameter;
ft' = feet, NA = not applicable/available; ppm = parts per million

(5, 95, 0, 0) = %(gravel, sand, silt, clay)

☒ = First Encountered Water ○ = Static Water

Water Level Data

Date	Depth	Elev.
8/25/14	☒ NA ft bgs	NA ft amsl
NA	○ NA btoc	NA ft amsl

Client: Los Angeles Metropolitan Transportation Authority

Well/Boring ID: B-06

Site Location:

MTA Metro
410 Center Street
Los Angeles, California

Borehole Depth: 49 ft

DEPTH	Sample ID	Sample Type	Recovery (feet)	Blow Counts	PID (ppm)	Lab Tests	USCS Code	Geologic Column	Stratigraphic Description
40	B-06-43	MCS 2.0	0.0						No Recovery.
		MCS 2.0	0.45	50-5"	0.0		SW		WELL GRADED SAND (5, 95, 0, 0), black (10YR 2/1), wet, fine- to coarse-grained, subrounded, trace fine gravel.
45	B-06-48	MCS 2.0	1.35	40 42 50	2.1		SW		WELL GRADED SAND (5, 95, 0, 0), black (10YR 2/1), wet, fine- to coarse-grained, subrounded, trace medium gravel.
50									Bottom of boring at 49 ft bgs.
55									



Remarks:

amsl = above mean sea level; bgs = below ground surface; Dia. = diameter; ft' = feet, NA = not applicable/available; ppm = parts per million

(5, 95, 0, 0) = %(gravel, sand, silt, clay)

☒ = First Encountered Water ○ = Static Water

Water Level Data

Date	Depth	Elev.
8/25/14	☒ NA ft bgs	NA ft amsl
NA	○ NA btoc	NA ft amsl





Client: Los Angeles Metropolitan Transportation Authority

Well/Boring ID: B-07

Site Location:

MTA Metro
410 Center Street
Los Angeles, California

Borehole Depth: 50 ft bgs


DEPTH	Sample ID	Sample Type	Recovery (feet)	Blow Counts	PID (ppm)	Lab Tests	USCS Code	Geologic Column	Stratigraphic Description
20	B-07-20	MCS 2.0	1.5	25 28 35	0.0	GS, MC	SW		WELL GRADED SAND (7, 88, 5, 0), dark reddish brown (5YR 3/2), dry, fine- to coarse-grained, subrounded.
25	B-07-25	MCS 2.0	0.9	27 50-5"	0.0	GS, MC	SW		WELL GRADED SAND (20, 80, 0, 0), dark reddish brown (5YR 3/3), dry, fine- to very coarse-grained, angular, some fine to coarse gravel, trace crushed rock, mica.
30	B-07-30	MCS 2.0	1.5	28 47 40		GS, MC	GP		POORLY GRADED GRAVEL (53, 41, 6, 0), very dark gray (10YR 3/1), wet, medium- to coarse-grained, subrounded, fine to medium gravel.
35	B-07-30	MCS 2.0	0.4	50-5"			GP		Same as above, saturated.




Remarks:



amsl = above mean sea level; bgs = below ground surface; Dia. = diameter; ft' = feet, NA = not applicable/available; ppm = parts per million

(5, 95, 0, 0) = %(gravel, sand, silt, clay)

 = First Encountered Water

 = Static Water

Water Level Data

Date	Depth	Elev.
8/21/14	 28 ft bgs	NA ft amsl
NA	 NA btoc	NA ft amsl

Client: Los Angeles Metropolitan Transportation Authority

Well/Boring ID: B-07

Site Location:

MTA Metro
410 Center Street
Los Angeles, California

Borehole Depth: 50 ft bgs

DEPTH	Sample ID	Sample Type	Recovery (feet)	Blow Counts	PID (ppm)	Lab Tests	USCS Code	Geologic Column	Stratigraphic Description
40	B-07-40	MCS 2.0	0.7	44 50-2"	0.0		SW		WELL GRADED SAND WITH GRAVEL (40, 60, 0, 0), very dark gray (10YR 3/1), wet, fine- to coarse-grained, subangular, fine to coarse gravel.
45	B-07-45	MCS 2.0	1.5	20 33 50	0.0		SP		POORLY GRADED SAND (0, 100, 0, 0), dark gray (10YR 4/1), wet, fine-grained, subangular.
50	B-07-50	MCS 2.0	1.5	14 20 20			SW		WELL GRADED SAND (5, 95, 0, 0), dark gray (10YR 4/1), wet, fine- to medium-grained, subangular.
55									Bottom of boring at 50 ft bgs.



Remarks:

amsl = above mean sea level; bgs = below ground surface; Dia. = diameter; ft' = feet, NA = not applicable/available; ppm = parts per million

(5, 95, 0, 0) = %(gravel, sand, silt, clay)


☒ = First Encountered Water ○ = Static Water

Water Level Data

Date	Depth	Elev.
8/21/14	☒ 28 ft bgs	NA ft amsl
NA	○ NA btoc	NA ft amsl

Date Start/Finish: 8/21/14 Drilling Company: Jet Drilling Driller's Name: Gary Buss Drilling Method: Hollow Stem Auger Rig Type: CME 75 Sampling Method: CA Modified Split Spoon	Northing: NA Easting: NA Casing Elevation: NA Borehole Depth: 44 ft bgs Borehole Diameter: 8" Surface Elevation: NA Descriptions By: Brent Anderson	Well/Boring ID: B-08 Client: Los Angeles Metropolitan Transportation Authority Location: MTA Metro 410 Center Street Los Angeles, California
---	--	---

DEPTH	Sample ID	Sample Type	Recovery (feet)	Blow Counts	PID (ppm)	Lab Tests	USCS Code	Geologic Column	Stratigraphic Description
0									
5	B-08-5	MCS 2.0	0.5		0.0		SP		POORLY GRADED SAND Fill (5, 95, 0, 0), brown (10YR 4/3), dry, fine-grained, subrounded.
10	B-08-10	MCS 2.0	1.5	9 14 20	0.0	GS, MC	SW		WELL GRADED SAND (30, 66, 4, 0), reddish gray (5YR 5/2), dry, fine- to coarse-grained, rounded, little fine gravel.
15	B-08-15	MCS 2.0	1.5	20 23 40	0.0		SW		Same as above, micaceous.

	Remarks: amsl = above mean sea level; bgs = below ground surface; Dia. = diameter; ft' = feet, NA = not applicable/available; ppm = parts per million (5, 95, 0, 0) = %(gravel, sand, silt, clay) ∇ = First Encountered Water ○ = Static Water		Water Level Data		
			Date	Depth	Elev.
			8/21/14	30 ft bgs	NA ft amsl
			NA	NA btoc	NA ft amsl

Client: Los Angeles Metropolitan Transportation Authority

Well/Boring ID: B-08

Site Location:

MTA Metro
410 Center Street
Los Angeles, California

Borehole Depth: 44 ft bgs

DEPTH	Sample ID	Sample Type	Recovery (feet)	Blow Counts	PID (ppm)	Lab Tests	USCS Code	Geologic Column	Stratigraphic Description
20	B-08-20	MCS 2.0	1.5	26 32 40	0.0	GS, MC	SW		WELL GRADED SAND (43, 52, 5, 0, reddish brown (5YR 4/3), dry, medium- to coarse-grained, fine subrounded gravel.
25	B-08-25	MCS 2.0	0.9	43 50-5"		GS, MC	SW		Crushed micaceous rock.
30	B-08-30	MCS 2.0	0.25	50-3"	0.0		SW		WELL GRADED SAND (10, 90, 0, 0), very dark grayish brown (10YR 3/2), moist, fine- to coarse-grained, subrounded.
35	B-08-35	MCS 2.0	0.4	50-5"			SW		WELL GRADED SAND (30, 70, 0, 0), very dark gray (10YR 3/1), wet, medium- to coarse-grained, subrounded.



Remarks:

amsl = above mean sea level; bgs = below ground surface; Dia. = diameter; ft' = feet, NA = not applicable/available; ppm = parts per million

(5, 95, 0, 0) = %(gravel, sand, silt, clay)

☒ = First Encountered Water ○ = Static Water

Water Level Data

Date	Depth	Elev.
8/21/14	☒ 30 ft bgs	NA ft amsl
NA	○ NA btoc	NA ft amsl

Client: Los Angeles Metropolitan Transportation Authority

Well/Boring ID: B-08

Site Location:

MTA Metro
410 Center Street
Los Angeles, California

Borehole Depth: 44 ft bgs

DEPTH	Sample ID	Sample Type	Recovery (feet)	Blow Counts	PID (ppm)	Lab Tests	USCS Code	Geologic Column	Stratigraphic Description
40	B-08-40	MCS 2.0	1.5	20 25 50-3"	0.0		SP		POORLY GRADED SAND (15, 85, 0, 0), very dark gray (10YR 3/1), wet, medium- to coarse-grained, subrounded.
45									Bottom of boring at 44 ft bgs due to refusal.
50									
55									



Remarks:

amsl = above mean sea level; bgs = below ground surface; Dia. = diameter;
ft' = feet, NA = not applicable/available; ppm = parts per million

(5, 95, 0, 0) = %(gravel, sand, silt, clay)

☒ = First Encountered Water

○ = Static Water

Water Level Data

Date	Depth	Elev.
8/21/14	☒ 30 ft bgs	NA ft amsl
NA	○ NA btoc	NA ft amsl

Date Start/Finish: 8/14/14 - 8/20/14 Drilling Company: Jet Drilling Driller's Name: Gary Buss Drilling Method: Hollow Stem Auger Rig Type: CME 75 Sampling Method: CA Modified Split Spoon	Northing: NA Easting: NA Casing Elevation: NA Borehole Depth: 45 ft bgs Borehole Diameter: 8" Surface Elevation: NA Descriptions By: Brent Anderson	Well/Boring ID: B-09 Client: Los Angeles Metropolitan Transportation Authority Location: MTA Metro 410 Center Street Los Angeles, California
---	--	---

0								
	B-09-5	MCS 2.0	0.5		0.0	GS, MC	SP	POORLY GRADED SAND Fill (0, 90, 10, 0), dark yellowish brown (10YR 3/4), dry, fine- to medium-grained, subrounded.
							SP	POORLY GRADED SAND (6, 93, 1, 0), dark yellowish brown (10YR 3/4), dry, fine- to medium-grained, subangular to angular.
	B-09-10	MCS 2.0	1.5	9 12 25	0.0	DS	SP	Same as above, increased silt (0, 90, 10, 0).
	B-09-15	MCS 2.0	1.5	16 28 24	0.0	GS, MC	SW	WELL GRADED SAND (17, 79, 4, 0), brown (10YR 5/3), dry, fine- to coarse-grained, subangular, trace fine gravel.

Site Location:

MTA Metro
410 Center Street
Los Angeles, California

Borehole Depth: 45 ft bgs

DEPTH	Sample ID	Sample Type	Recovery (feet)	Blow Counts	PID (ppm)	Lab Tests	USCS Code	Geologic Column	Stratigraphic Description
20	B-09-20	MCS 2.0	1.5	27 18 27	0.0		SW		Same as above.
25	B-09-25	MCS 2.0	1.5	20 25 33	0.0	GS, MC	SW		WELL GRADED SAND (4, 92, 4, 0), brown (10YR 5/3), dry, fine- to coarse-grained, subangular.
30	B-09-30	MCS 2.0	1.5	20 30 36	0.0		SP		POORLY GRADED SAND (5, 95, 0, 0), yellowish brown (10YR 5/6), moist, medium- to coarse-grained, subrounded.
35	B-09-35	MCS 2.0	1.5	41 50 50	0.0	GS, MC	SP		POORLY GRADED SAND (20, 73, 7, 0), yellowish brown (10YR 5/6), wet, medium- to coarse-grained, subrounded.



Remarks:

amsl = above mean sea level; bgs = below ground surface; Dia. = diameter; ft' = feet, NA = not applicable/available; ppm = parts per million

(5, 95, 0, 0) = %(gravel, sand, silt, clay)

☒ = First Encountered Water ○ = Static Water

Water Level Data

Date	Depth	Elev.
8/20/14	☒ 35 ft bgs	NA ft amsl
NA	○ NA btoc	NA ft amsl

Client: Los Angeles Metropolitan Transportation Authority

Well/Boring ID: B-09

Site Location:

MTA Metro
410 Center Street
Los Angeles, California

Borehole Depth: 45 ft bgs

DEPTH	Sample ID	Sample Type	Recovery (feet)	Blow Counts	PID (ppm)	Lab Tests	USCS Code	Geologic Column	Stratigraphic Description
40	B-09-40	MCS 2.0	0.75	50 50-3"	0.0		SW		WELL GRADED SAND (10, 90, 0, 0), very dark gray (10YR 3/1), wet, fine- to coarse-grained, subrounded, trace fine and coarse gravel.
45	B-09-45	MCS 2.0	1.25	20 20 50-3"	0.0		SW		Same as above, increased gravel (25, 75, 0, 0).
50									Bottom of boring at 45 ft bgs due to sheared rod.
55									



Remarks:

amsl = above mean sea level; bgs = below ground surface; Dia. = diameter; ft' = feet, NA = not applicable/available; ppm = parts per million




(5, 95, 0, 0) = %(gravel, sand, silt, clay)




☒ = First Encountered Water ○ = Static Water

Water Level Data

Date	Depth	Elev.
8/20/14	☒ 35 ft bgs	NA ft amsl
NA	○ NA btoc	NA ft amsl

Date Start/Finish: 8/29/14 Drilling Company: Jet Drilling Driller's Name: Gary Buss Drilling Method: Hollow Stem Auger Rig Type: CME 75 Sampling Method: CA Modified Split Spoon	Northing: NA Easting: NA Casing Elevation: NA Borehole Depth: 50 ft bgs Borehole Diameter: 8" Surface Elevation: NA Descriptions By: Brent Anderson	Well/Boring ID: B-10 Client: Los Angeles Metropolitan Transportation Authority Location: MTA Metro 410 Center Street Los Angeles, California
---	--	---

DEPTH	Sample ID	Sample Type	Recovery (feet)	Blow Counts	PID (ppm)	Lab Tests	USCS Code	Geologic Column	Stratigraphic Description
0									
5	B-10-5	MCS 2.0	0.5		0.0	MC, DS	SP		POORLY GRADED SAND WITH GRAVEL (50, 50, 0, 0), dark yellowish brown (10YR 4/4), dry, medium-grained sand, fine to coarse gravel.
10	B-10-10	MCS 2.0	1.5	24 32 32	0.0	GS, MC	GP		POORLY GRADED GRAVEL (54, 39, 7, 0), pale brown (10YR 6/3), dry, fine- to medium-grained, subrounded.
15	B-10-15	MCS 2.0	1.5	20 28 34	0.0		GP		Same as above, increasing grain size.

 ARCADIS <i>Infrastructure · Water · Environment · Buildings</i>	Remarks: amsl = above mean sea level; bgs = below ground surface; Dia. = diameter; ft' = feet, NA = not applicable/available; ppm = parts per million (5, 95, 0, 0) = %(gravel, sand, silt, clay)  = First Encountered Water  = Static Water				Water Level Data		
	Date		Depth		Elev.		
	8/29/14		31 ft bgs		NA ft amsl		
	NA		NA btoc		NA ft amsl		

Client: Los Angeles Metropolitan Transportation Authority

Well/Boring ID: B-10

Site Location:

MTA Metro
410 Center Street
Los Angeles, California

Borehole Depth: 50 ft bgs

DEPTH	Sample ID	Sample Type	Recovery (feet)	Blow Counts	PID (ppm)	Lab Tests	USCS Code	Geologic Column	Stratigraphic Description
20	B-10-20	MCS 2.0	1.5	25 28 44	0.0	GS, MC	GP		POORLY GRADED GRAVEL (58, 38, 4, 0), light brownish gray (2.5Y 6/2), dry, medium- to very coarse-grained, subrounded.
25	B-10-25	MCS 2.0	1.5	33 45 30	0.0	GS, MC	SW		WELL GRADED SAND (15, 85, 0, 0), light yellowish brown (2.5Y 6/3), slightly moist, fine- to very coarse-grained, subangular.
30	B-10-29	MCS 2.0	1.5	30 36 40	0.0	GS, MC	SP		POORLY GRADED SAND (20, 73, 7, 0), dark gray (7.5YR 4/1), wet, medium-grained, subrounded.
35	B-10-35	MCS 2.0	1.5	20 25 38	0.0	GS, MC	SP		POORLY GRADED SAND (32, 60, 8, 0), dark gray (7.5YR 4/1), wet, medium-grained, subrounded. 30% fine to coarse gravel.



Remarks:

amsl = above mean sea level; bgs = below ground surface; Dia. = diameter; ft' = feet, NA = not applicable/available; ppm = parts per million

(5, 95, 0, 0) = %(gravel, sand, silt, clay)

= First Encountered Water

= Static Water

Water Level Data

Date	Depth	Elev.
8/29/14	31 ft bgs	NA ft amsl
NA	NA btoc	NA ft amsl

Site Location:

MTA Metro
410 Center Street
Los Angeles, California

Borehole Depth: 50 ft bgs

DEPTH	Sample ID	Sample Type	Recovery (feet)	Blow Counts	PID (ppm)	Lab Tests	USCS Code	Geologic Column	Stratigraphic Description
40	B-10-40	MCS 2.0	0.75	38 50-3"	0.0		SP		POORLY GRADED SAND (0, 100, 0, 0), dark gray (7.5YR 4/1), wet, medium-grained, subrounded.
45	B-10-45	MCS 2.0	0.8	50 50-4"	0.0		SP		Same as above, 5% medium gravel.
50	B-10-50	MCS 2.0	0.9	50 50-5"	0.0		SP		Same as above, slight increase in grain size.
55									Bottom of boring at 50 ft bgs.



Remarks:

amsl = above mean sea level; bgs = below ground surface; Dia. = diameter; ft' = feet, NA = not applicable/available; ppm = parts per million



(5, 95, 0, 0) = %(gravel, sand, silt, clay)

☒ = First Encountered Water ○ = Static Water

Water Level Data


Date	Depth	Elev.
8/29/14	☒ 31 ft bgs	NA ft amsl
NA	○ NA btoc	NA ft amsl

Existing Geotechnical Boring Logs Caltrans (Undated)



Existing Geotechnical Boring Logs

Caltrans, 1954



MICROFILM




PREL. DRAWING NO. P-3243

AS BUILT

CORRECTIONS BY *M. J. James*
DATE 10-11-55


BRIDGE DEPARTMENT

FIELD STUDY
DRAWN
CHECKED
APPROVED
DATE




Test Boring By Bridge Dept.


CLASSIFICATION OF MATERIAL BASED ON STANDARD GRADE SIZE LIMITS



LEGEND OF EARTH MATERIALS



LEGEND OF BORING OPERATIONS



NOTES

THE CONTRACTOR'S ATTENTION IS DIRECTED TO SECTION 2, ARTICLE (C) OF THE STANDARD SPECIFICATIONS AND TO THE SPECIAL PROVISIONS ACCOMPANYING THIS SET OF PLANS. CLASSIFICATION OF EARTH MATERIAL AS SHOWN ON THIS SHEET IS BASED UPON FIELD INSPECTION AND IS NOT TO BE CONSTRUED TO IMPLY MECHANICAL ANALYSIS. PENETROMETER BORINGS HAVING A RATE OF PENETRATION MEASURED IN SECONDS PER FOOT ARE DRIVEN WITH A #2 WHELAN-TERRY AIR HAMMER AT 115 PSI.

STATE OF CALIFORNIA
DEPARTMENT OF PUBLIC WORKS
DIVISION OF HIGHWAYS

WIDENING OF L.A. RIV. BR. & OH. AT ALISO ST.

LOG OF TEST BORINGS (2 of 3)

SCALE: 1" = 10' BRIDGE 53-405 FILE DRAWING C-3243-6

PREL. DRAWING NO. P-3243

Existing Geotechnical Boring Logs

Caltrans, 2004

02

REGISTERED PROFESSIONAL ENGINEER

Kul Bhushan


No. G.E. 144

Exp. 12/31/05

GEOTECHNICAL

STATE OF CALIFORNIA

sheet.



90 _____ ELEV. 89.8 m

87 _____

84 _____

81 _____

78 _____

75 _____

72 _____

69 _____

66 _____

SK-1

9/152 61 R-1

9 35 S-2

12/152 61 R-3

7 35 S-4

5/152 61 R-5

23 35 S-6

50/102 61 R-7

50/76 35 S-8

50/102 61 R-9

72 35 S-10

35/152 61 R-11

50/102 35 S-12

REF/85 61 R-13

REF/106 35 S-14


9m R of EB Track

Sta. 32+74

CONTINUED



TYPE OF SAMPLER	OUTSIDE DIAMETER (mm)	INSIDE DIAMETER (mm)	TYPE OF HAMMER	WEIGHT OF HAMMER (kN)	HEIGHT OF DROP (mm)
California Ring	76.2	61.5	Automatic	0.623	762
TYPE OF SAMPLER	50.8	34.9	Automatic	0.623	762




BORING G-501 CONTINUED

Depth (m)	Sample No.	Soil Description	Test Results
66.3	58/182	61 R-15	12.8 37.3 (AL) (GS)
66.3	67	35 S-16	-- 38.7 (PP)
63.1	58/76	61 R-17	15.4 26.8 (PP)
63.1	58/127	35 S-18	-- 34.1
60.9	REF/138	61 R-19	15.6 25.8
57.9	58/182	35 S-28	-- 28.5

06/01/2002

Bottom of boring at El. 58.9 m
 Groundwater encountered at El. 75.3 m
 Borehole back-filled with grout, cold asphalt patched.




NOTE: Classification of earth material as shown on this sheet is based upon field inspection and is not to be construed to imply mechanical analysis.

N. NGHIEM
FIELD INVESTIGATION BY:
DATE:

D. YAVORSKY
PROJECT ENGINEER

EASTSIDE LRT PROJECT BRIDGE OVER HWY 101
LOG OF TEST BORINGS SHEET 1 OF 5



84 ELEV. 84.1 m Sta. 33+44 4m R of EB Track G-503 127 mm

50 35 S-1 -- 13.4 (WA)

8 35 S-2 -- 30.1 (GS)

81 52 35 S-3 -- 9.5

58 35 S-4 -- 11.7 (WA)

78 50/76 35 S-5 -- 11.6

36/114mm 35 S-6 -- 8.5

75 50/76 35 S-7 -- 17.1 (GS)

50/89 35 S-8 -- 10.3 (WA)

72 50/140 35 S-9 -- 9.5

50/102 35 S-10 -- 10.3 (WA)

69 REF/51 35 NSR

66 57 35 S-11 -- 40.4 (AL) (GS)



63 REF/152 35 S-12 -- 36.0

60 50/140 35 S-13 -- 39.8

57

305mm Asphalt
ALLUVIUM (Gall):
Gravelly SAND (SP),
gray, fine to coarse grained, fine to medium gravel
Silty SAND (SM),
dense, brown, fine to coarse grained
- becomes loose
- denser
Poorly Graded SAND to Silty SAND (SP-SM),
very dense, brown, fine to coarse grained
Well Graded SAND to Silty SAND (SW-SM),
very dense, brown, some gravels
@ 6.4 m, approximately 203mm cobbles
- less gravelly
@ 9.4 m, 127mm cobble
@ 10.4 m, heavy chatter
- becomes bluish gray
- egg odor
@ 11.7 m, 381mm cobble
- becomes gray
@ 15.2 m, cobble
- fine to medium gravel
BEDROCK, PUENTE FORMATION (Tp):
Elastic SILT (MH),
hard, dark brown, silty, petroleum odor
Elastic SILT (MH),
hard, dark brown, silty, petroleum odor

CONTINUED IN INSET



All dimensions and elevations are in meters except as noted

<div>Benjamin Be Nguyen</div> <div>DESIGN OVERSIGHT</div> <div>7-10-03</div> <div>SIGN OFF DATE</div>		<div>DRAWN BY</div> <div>K. FERNANDES</div> <div>CHECKED BY</div> <div>C. SCHEYHING</div>	<div>N. NGHIEM</div> <div>FIELD INVESTIGATION BY:</div> <div>DATE:</div>	<div>PREPARED FOR THE</div> <div>STATE OF CALIFORNIA</div> <div>DEPARTMENT OF TRANSPORTATION</div>	<div>D. YAVORSKY</div> <div>PROJECT ENGINEER</div>	<div>BRIDGE NO.</div> <div>53-2975</div> <div>53C-2148</div> <div>KILOMETER POST</div> <div>1.07</div>	<div>EASTSIDE LRT PROJECT BRIDGE OVER HWY 101</div> <div>LOG OF TEST BORINGS SHEET 2 OF 5</div>									
TRIC) (REV 2/1/00)		<div>ORIGINAL SCALE IN MILLIMETERS</div> <div>FOR REDUCED PLANS</div> <div><div></div><div>0102030405060708090100</div></div>			<div>CU 07225</div> <div>EA 1199U1</div>		<div>DISCARD PRINTS BEARING</div> <div>EARLIER REVISION DATES</div> <div><div></div><div>04-25-0307-08-03</div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><</div>									



Horizontal Datum: NAD83 1996.35 EPOCH, California
State Plane Zone 5.
Vertical Datum: NAVD 88



METROPOLITAN TRANSPORTATION AUTHORITY ONE GATEWAY PLAZA LOS ANGELES, CA. 90012	
EASTSIDE LRT 707 WILSHIRE LOS ANGELES, CA	PARTNERS BLVD. SUITE 2900 90017

USERNAME => trojance	DATE PLOTTED => 06-JUN-2004	TIME PLOTTED => 11:38
----------------------	-----------------------------	-----------------------

All dimensions and elevations are in meters except as noted

<div> DESIGN OVERSIGHT Be Nguyen 7-10-03 SIGN OFF DATE</div>	DRAWN BY	K. FERNANDES	N. NGHIEM	PREPARED FOR THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	D. YAVORSKY PROJECT ENGINEER	BRIDGE NO.	EASTSIDE LRT PROJECT BRIDGE OVER HWY 101
	CHECKED BY	C. SCHEYHING	FIELD INVESTIGATION BY: DATE: _____			53-2975 53C-2148 KILOMETER POST 1.07	



CU	07225
EA	1199U1

DISREGARD PRINTS BEARING
EARLIER REVISION DATES

REVISION DATES (PRELIMINARY STAGE ONLY)

	SHEET	OF
	59	61

FILE => q11tb3059.doc

02

REGISTERED PROFESSIONAL ENGINEER

Kul Bhushan


No. G.E. 144

Exp. 12/31/05

GEOTECHNICAL

STATE OF CALIFORNIA

sheet.



PROFILE
VERTICAL SCALE: 1:100
HORIZONTAL SCALE: NONE



All dimensions and elevations are in meters except as noted

ORIGINAL SCALE IN MILLIMETERS
FOR REDUCED PLANS

CU 07
EA 1035F1

DISREGARD PRINTS BEARING
EARLIER REVISION DATES

REVISION DATES (PRELIMINARY STAGE ONLY)

SHEET	OF
60	61

```
FILE => alltb4060.dgn
```

USERNAME => trpierce	DATE PLOTTED => 09-JUN-2004	TIME PLOTTED => 11:38
----------------------	-----------------------------	-----------------------

02

REGISTERED PROFESSIONAL ENGINEER

Kul Bhushan

No. G.E. 144

Exp. 12/31/05

GEOTECHNICAL



STATE OF CALIFORNIA

sheet.

EASTSIDE LRT PARTNERS
707 WILSHIRE BLVD. SUITE 2900
LOS ANGELES, CA 90017



Horizontal Datum: NAD83 1996.35 EPOCH, California
State Plane Zone 5.
Vertical Datum: NAVD 88



LEGEND OF EARTH MATERIALS


	GRAVEL		CLAYEY SILT
	SAND		PEAT and/or ORGANIC MATERIAL
	SILT		FILL MATERIAL
	CLAY		COBBLE
	SANDY CLAY or CLAYEY SAND		INDURATED ROCK
	SANDY SILT or SILT and SAND		SEDIMENTARY ROCK
	SILTY CLAY		METAMORPHIC

Shown on this sheet is based upon field and laboratory recognition symbols.

CONSISTENCY CLASSIFICATION FOR SOILS			According to the Standard Penetration Test	
Soil Type	Soil Resistance (Blows/ 0.3m)	Soil Consistency	Soil Type	Soil Resistance (Blows/ 0.3m)
Very Loose	0-4	Gravelly	Very Loose	0-2
Loose	5-10	Loose	Loose	2-4
Medium Dense	11-20	Medium Dense	Firm	5-8
Dense	31-50	Dense	Very stiff	9-15
Very Dense	50	Very Dense	Hard	16-30
				>31

NOTE: Classification of earth material as shown in this table is based on the results of inspection and is not to be construed as a guarantee of quality.


NOTE: Classification of earth material as shown on this sheet is based upon field inspection and is not to be construed to imply mechanical analysis.



PROFILE
VERTICAL SCALE: 1:100
HORIZONTAL SCALE: NONE

PLATE 5

All dimensions and elevations are in meters except as noted



<div><div><div>Be Nguyen</div><div>Be Nguyen</div></div><div>DESIGN OVERSIGHT</div><div>7-10-03</div><div>SIGN OFF DATE</div></div>		<div>DRAWN BY</div> <div>K. FERNANDES</div> <div>CHECKED BY</div> <div>C. SCHEYHING</div>	<div>N. NGHIEM</div> <div>FIELD INVESTIGATION BY:</div> <div>DATE:</div>	<div>PREPARED FOR THE</div> <div>STATE OF CALIFORNIA</div> <div>DEPARTMENT OF TRANSPORTATION</div>	<div>D. YAVORSKY</div> <div>PROJECT ENGINEER</div>	<div>BRIDGE NO.</div> <div>53-2975</div> <div>53C-2148</div> <div>KILOMETER POST</div> <div>1.07</div>	<div>EASTSIDE LRT PROJECT BRIDGE OVER HWY 101</div> <div>LOG OF TEST BORINGS SHEET 5 OF 5</div>
<div>TC) (REV 2/1/00)</div>			<div>ORIGINAL SCALE IN MILLIMETERS</div> <div>FOR REDUCED PLANS</div> <div><div></div><div>0102030405060708090100</div></div>	<div>CU 07225</div> <div>EA 1199U1</div>	<div>DISREGARD PRINTS BEARING</div> <div>EARLIER REVISION DATES</div> <div><div></div><div>04-15-0107-08-01</div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><</div>		

Existing Geotechnical Boring Logs

City of Los Angeles, 1993

LOG OF TEST BORING

PROJECT: 140-4046

DATE: Nov. 18, 1992

BORING NO.: 1

ELEV.: 265'

BORING LOCATION: 124' W/O N. Myers St. & 76' S/O SCF E. 1st St.

DRILL RIG TYPE: CME-75 HT using 8" diameter hollow stem augers


DRILLER: Cooksey

LOGGER: C. Kunes

ENGINEER: Yew/Adams

DEPTH TO STANDING WATER: none

DEPTH TO WATER SEEPAGE: none

ELEVATION DEPTH	SOIL SYMBOLS SAMPLER SYMBOLS AND BLOWS/INCHES	USCS	Field Description	Standard Pen. Readings 1st 6" / 2nd 6" / 3rd 6"
265 - 0		SP	Brown poorly graded sand with gravel. Trace of silt. Moist and dense.	
260 - 5				8 / 6 / 9
255 - 10		SW- SM	Light brown to tan, well graded sand with silt, granitic gravel and cobbles. Dry to moist and dense.	6 / 9 / 10
250 - 15		SP- SM	Light brown to tan poorly graded sand with silt and gravel. Gravel content ranges from 8% to 42%. Moist and dense to very dense.	18 / 14 / 19
245 - 20				19 / 33 / 18
240 - 25				26 / 30 / 24
235 - 30				

LOG OF TEST BORING

PROJECT: 140-4046

DATE: Nov. 13, 1992

BORING NO.: 2

ELEV.: 250'

BORING LOCATION: W/S L.A. River channel, below 1st St. Bridge

DRILL RIG TYPE: CME-75 HT using 8" diameter hollow stem augers

DRILLER: Cooksey

LOGGER: C. Kunesh

ENGINEER: Yew/Adams

DEPTH TO STANDING WATER: none

DEPTH TO WATER SEEPAGE: none

ELEVATION DEPTH	SOIL SYMBOLS SAMPLER SYMBOLS AND BLOWS/INCHES	USCS	Field Description	Standard Pen. Readings 1st 6" / 2nd 6" / 3rd 6"
250 - 0			12" PCC.	
245 - 5		SP-SM	Brown to rusty brown poorly graded sand with silt and gravel. Gravel content is 29%. Moist and dense. Encountered granitic cobbles from 4' to 10'.	18 / 20 / 31
240 - 10		GW-GM	Brown to rusty brown well graded gravel with silt, sand and granitic cobbles. Sand content is 31%. Moist and dense.	25 / 27 / 27
			- No Water -	

LOG OF TEST BORING

PROJECT: 140-4046

DATE: Nov. 17, 1992

BORING NO.: 2A

ELEV.: 250'

BORING LOCATION: W/S River channel, below 1st St. Bridge, 17' N/O T.H. 2

DRILL RIG TYPE: CME-75 HT using 8" diameter hollow stem augers


DRILLER: Cooksey

LOGGER: C. Kunes

ENGINEER: Yew/Adams

DEPTH TO STANDING WATER: none

DEPTH TO WATER SEEPAGE: none

ELEVATION DEPTH	SOIL SYMBOLS SAMPLER SYMBOLS AND BLOWS/INCHES	USCS	Field Description	Standard Pen. Readings 1st 6" / 2nd 6" / 3rd 6"
250 0			12" PCC.	
245 5		SP- SM	Brown to rusty brown poorly graded sand with silt and gravel. Gravel content is about 29%. Moist and dense. Encountered cobbles from 4' to 8'. - No Water -	

Existing Geotechnical Boring Logs

City of Los Angeles, 1994a

Legend:

Symbol: Description:



Poorly graded sand with gravel. Trace of silt.



Well graded sand with silt, granitic gravel and cobbles.



Poorly graded sand with silt and gravel.



Well graded gravel with silt, sand and granitic cobbles.



Representative sample (disturbed)



Depth to perched water



PCC.




Water at depth indicated during drilling



Rig refusal or end of boring

Notes:

1. Exploratory borings were drilled on November 13, 17, & 18, 1992 with a CME-75 HT drill rig using 8" diameter hollow stem augers.
2. Free water was not encountered during the drilling of this project.
3. The boring locations and elevations were provided by Geotechnical Services.
4. Abbreviations used on logs: HT = high torque
 N/O = north of NCF = north curb face C/L = center line
 S/O = south of SCF = south curb face BCR = begin curb return
 E/O = east of ECF = east curb face PL = property line
 W/O = west of WCF = west curb face ELEV. = elevation
 OVA = organic vapor analyzer LEL = lower explosive limit
 AC = asphalt concrete PCC = Portland cement concrete
5. A maximum blow count value of 75 per 6 inch increment was used for the Standard Penetration Test.



CITY OF LOS ANGELES
 DEPARTMENT OF GENERAL SERVICES
 STANDARDS DIVISION

TEST BORING LOCATIONS

Lab No. 140-4046 Ref. No. 00573
 Date: 3-10-93
 CADD BY R.B.

Project Title : 1ST STREET VIADUCT OVER L.A. RIVER-SUPPLEMENTAL.

LOG OF TEST BORING

LAB. NO.: 140- 4046 PROJECT: FIRST STREET VIADUCT OVER L.A. RIVER-SUPPLEMENTAL
 BORING NO.: 3 ELEVATION: 265' DRILLING DATE: January 21, 1993
 BORING LOCATION: 25' N/O NCF 1st St. frontage road & 46' W/O ECF Center St.
 DRILL RIG TYPE: CME-75HT using 8" diameter hollow stem augers
 DEPTH TO STANDING WATER: none DEPTH TO WATER SEEPAGE: none
 DRILLER: Cooksey LOGGER: C. Kunes ENGINEER: B. Adams

ELEVATION / DEPTH (ft)	SOIL SYMBOLS, SAMPLER SYMBOLS AND BLOWS/INCHES	USCS	Field Description	Moisture %	Density Pcf
265 0			10" AC pavement in good condition.		
		SM	Brown silty sand. Few gravels and red brick fragments. Fill material to 2.5'. Moist. Color changes to light brown at 2.5'.		
260 5					
		ML	Brown silt. Little amount of clay. Moist and firm.		
255 10	14/12	SW	Gray well graded sand. Few granitic gravel. Moist and dense. Moisture decreasing with depth.	6.3	107
	20/12			3.7	116
250 15	26/12		Encountered a 1' lense of poorly graded gravel with sand at 15'.	2.5	120
	10/12	ML	Brown-gray silt. Little to some fine sand. Moist and firm.	16.1	98
245 20	23/12	SW	Gray-brown well graded sand with silt and gravels. Gravel is granitic. Moist and dense.	2.6	119
	15/12		Encountered a 1' poorly graded sand lense at 22'.	7.6	101
240 25	30/12			3.2	118
	37/12			3.1	115
235 30	50/7			2.1	126
230 35			No Water		

LOG OF TEST BORING

LAB. NO.: 140- 4046

PROJECT: FIRST STREET VIADUCT OVER L.A. RIVER-SUPPLEMENTAL

BORING NO.: 4

ELEVATION: 265'

DRILLING DATE: January 22, 1993

BORING LOCATION: 7' W/O C/L N. Myers St. & approx. C/L 1st St. frontage Road

DRILL RIG TYPE: CME-75 using 8" diameter hollow stem augers

DEPTH TO STANDING WATER: none

DEPTH TO WATER SEEPAGE: none

DRILLER: Cooksey

LOGGER: C. Kunesch

ENGINEER: Zadoorian

ELEVATION / DEPTH (ft)	SOIL SYMBOLS, SAMPLER SYMBOLS AND BLOWS/INCHES	USCS	Field Description	Moisture %	Density Pcf
265 0					
		SM	6" AC pavement in good condition. Brown silty sand. Few gravels and red brick fragments. Fill material. Moist.		
260 5		SW/SP	Brown well to poorly graded sand. Trace of silt. Few granitic gravel. Silt content decreasing with depth. Moist and dense to very dense.		
255 10	14/12			2.9	127
	22/12		Encountered 1' lense of well graded gravel with sand at 12.5'.	1.9	123
250 15	40/12			2.8	125
	29/12			2.5	118
245 20	48/12			3.0	127
	50/12			1.7	135
240 25	30/12			2.4	112
	17/12			2.9	124
235 30	50/12			2.1	132
230 35			No Water		

Existing Geotechnical Boring Logs

City of Los Angeles, 1994b

LOG OF TEST BORING

9402300H2

LAB. NO.: 140- 4340

PROJECT: PIPER TECHNICAL CENTER

BORING NO.: H-2

ELEVATION: 280'

DRILLING DATE: 07-14-94

(CONTAMINATION)

BORING LOCATION: 188' S/o and 13' W/o Northwest corner of building #1 (Police garage)

DRILL RIG TYPE: CME-55 using 8" diameter hollow stem augers.

DEPTH TO STANDING WATER: none

DEPTH TO WATER SEEPAGE: none

DRILLER: Myles

LOGGER: Redlin

ENGINEER: Burnett

ELEVATION / DEPTH (ft)	SOIL SYMBOLS, SAMPLER SYMBOLS AND BLOWS/INCHES	OVA (PPM)	USCS	Field Description
280 0				4" AC pavement in fair condition. Sand/gravel base.
275 5	5/12	0		FILL MATERIAL To 15'. Light brown poorly graded sand with some silt and a little gravel. Moist and loose to dense. Encountered 2' silty lense at 15'. Encountered coarse gravel and small cobbles at 20'. Encountered silty sand at 25'. No petrochemical odor.
270 10	3/12	0		
265 15	10/12	0		
260 20	14/12	0		
255 25	20/12	0		
250 30				---
245 35				No water

LOG OF TEST BORING

940230 H12

LAB. NO.: 140- 4340

PROJECT: PIPER TECHNICAL CENTER

BORING NO.: H-9A

ELEVATION: 280'

DRILLING DATE: 08-31-94

(CONTAMINATION)

BORING LOCATION: 56' S/o and 32' W/o NW corner of column QR at Space 120' Building #2

DRILL RIG TYPE: CME-55 using 8" diameter hollow stem augers.


DEPTH TO STANDING WATER: none

DEPTH TO WATER SEEPAGE: none

DRILLER: L. Cooksey

LOGGER: J. Kunesh

ENGINEER: Burnett

ELEVATION / DEPTH (ft)	SOIL SYMBOLS, SAMPLER SYMBOLS AND BLOWS/INCHES	OVA (PPM)	USCS	Field Description
280 0				4" AC pavement in good condition. Crushed aggregate base with some sand.
275 5				FILL MATERIAL. Grayish-brown silty sand with some gravel. Slight petrochemical odor from 8' depth. No sampling at 5' and 10' depths per engineer present. Concrete fragments present from 11' to 13' depth. Granite cobble lodged in split spoon sampler at 16' depth. Petrochemical odor decreasing with depth. Moist and dense.
270 10				
265 15	40/12	7	SP	Brown poorly graded sand with some granitic gravel and cobbles. Sand color becoming lighter with depth. Trace of petrochemical odor present. Moist and dense.
260 20	16/12	8		
255 25				--- No water ---
250 30				
245 35				

LOG OF TEST BORING

940230421

LAB. NO.: 140- 4340

PROJECT: PIPER TECHNICAL CENTER

BORING NO.: H-18

ELEVATION: 280'

DRILLING DATE: 08-25-94

(CONTAMINATION)

BORING LOCATION: 61' W/o and 11' N/o Diesel Pump at back of building #1 Space 150

DRILL RIG TYPE: CME-75 using 8" diameter hollow stem augers.

DEPTH TO STANDING WATER: none

DEPTH TO WATER SEEPAGE: none

DRILLER: L. Cooksey

LOGGER: Redlin

ENGINEER: Burnett

ELEVATION / DEPTH (ft)	SOIL SYMBOLS, SAMPLER SYMBOLS AND BLOWS/INCHES	OVA (PPM)	USCS	Field Description
280 0				5" AC pavement in fair condition.
				Sand/gravel base.
				FILL MATERIAL. Gray/brown silty sand with some clay binders, gravel and a few red brick fragments. Moist and fairly loose. Slight petrochemical odor at 10'.
275 5	4/12			
270 10	11/12			
265 15	13/12			
260 20	11/12		SP-SM	Light brown/tan poorly graded sand. Moist and fairly loose. No petrochemical odor. Encountered some gravel at 25'. Sand is becoming coarser with depth.
255 25	10/12			
250 30				--- No water ---
245 35				

Existing Geotechnical Boring Logs

City of Los Angeles, 1994c

LOG OF TEST BORING

LAB. NO.: 140- 4413 **PROJECT:** ALAMEDA SEWER REHABILITATION AT LOS ANGELES ST.
BORING NO.: B-1A **ELEVATION:** 287' **DRILLING DATE:** 12-28-94
BORING LOCATION: 3.5' W/o ECF Alameda St. and 92' S/o SCF Union Station Parking Ent.
DRILL RIG TYPE: CME-75 using 8" diameter hollow stem augers.
DEPTH TO STANDING WATER: None **DEPTH TO WATER SEEPAGE:** None
DRILLER: Adams **LOGGER:** A. Gharai **ENGINEER:** None Present

ELEVATION / DEPTH (ft)	SOIL SYMBOLS, SAMPLER SYMBOLS AND BLOWS/INCHES	USCS	Field Description	Moist. %	Dens. Pcf
0			9" AC pavement in good condition.		
285	7/12		FILL MATERIAL. Light brown poorly graded sand with some silt and gravel. Concrete slurry present from 4.5' to 6' depth.	3.1	122
5	43/12			7.2	116
280		SP	POSSIBLE FILL MATERIAL from existing sewer line. Light brown sand with some granitic gravel and traces of silt. Moist and loose.		
10	6/12			3.7	111
275		ML	Light green silt with clay. Moist and firm. Density increasing with depth.		
15	18/12			28.0	96
270					
20	28/12			23.1	104
265			--- No water. ---		
25					
260					
30					
255					
35					
250					

LOG OF TEST BORING

LAB. NO.: 140- 4413 PROJECT: ALAMEDA SEWER REHABILITATION AT LOS ANGELES ST.

BORING NO.: B-2 ELEVATION: 287' DRILLING DATE: 12-28-94

BORING LOCATION: 3.5' W/o ECF Alameda St. and 24' S/o SCF Union Station Parking Exit

DRILL RIG TYPE: CME-75 using 8" diameter hollow stem augers.

DEPTH TO STANDING WATER: None DEPTH TO WATER SEEPAGE: None

DRILLER: Adams

LOGGER: A. Gharai

ENGINEER: None Present

ELEVATION / DEPTH (ft)	SOIL SYMBOLS, SAMPLER SYMBOLS AND BLOWS/INCHES	USCS	Field Description	Moist. %	Dens. Pcf
0			9" AC pavement in good condition.		
285	2/12		FILL MATERIAL. Light brown silty sand with some gravel. Wood fragments (plywood) present at 3' depth. PVC pipe and concrete slurry present at 5' depth. Concrete fragments, sand and cobbles present from 10' to 15' depth. Moist.	10.2	100
5					
280					
10	13/12				
275					
15	17/12			27.8	96
270		ML	Light green/brown silt with sand and clay. Moist and firm. Moisture increasing with depth.		
20	29/12			32.9	91
265			--- No water. ---		
25					
260					
30					
255					
35					
250					

Existing Geotechnical Boring Logs

City of Los Angeles, 1996

KEY TO SYMBOLS

Symbol Description

STRATA




AC pavement




Silty sand.



Fine to very fine sandy silt.



Well graded sands. Few granitic gravel.



Well to poorly graded sand. Trace of silt.

MISCELLANEOUS



End of Boring

SAMPLERS



Split spoon sampler

KEY TO SYMBOLS


Notes:

1. Exploratory borings were drilled on January 21, 1993 with a CME-75 HT drill rig and on January 22, 1993 with a CME-75 drill rig using 8" diameter hollow stem augers.
2. Free water was not encountered during the drilling of this project.
3. The boring locations and elevations were provided by Geotechnical Services.
4. Test Holes No. 1 & 2 were drilled on November 17th & 18th, 1992.
5. Abbreviations used on logs:

N/O = north of	NCF = north curb face	NE = northeast
S/O = south of	SCF = south curb face	NW = northwest
E/O = east of	ECF = east curb face	SE = southeast
W/O = west of	WCF = west curb face	SW = southwest
C/L = center line	PL = property line	
AC = asphalt concrete	PCC = Portland cement concrete	
OVA = organic vapor analyzer	LEL = lower explosive limit	
	HT = high torque	

LOG OF TEST BORING

LAB. NO.: 140- 4536 PROJECT: 1ST STREET VIADUCT OVER L.A. RIVER-SEISMIC RETROFIT
 BORING NO.: H-2 ELEVATION: 270' DRILLING DATE: 02-15-96 (CONTAMINATION)
 BORING LOCATION: 5' N/o SCF 1st St. (N/s Frontage Rd.) and 48' E/o ECF Santa Fe Ave.
 DRILL RIG TYPE: CME-75 using 6" diameter conventional flight augers.
 DEPTH TO STANDING WATER: None DEPTH TO WATER SEEPAGE: None
 DRILLER: Ramirez LOGGER: Redlin ENGINEER: Burnett

ELEVATION / DEPTH (ft)	SOIL SYMBOLS, SAMPLER SYMBOLS AND BLOWS/INCHES	OVA (PPM)	USCS	Field Description
70 0		0	SM-ML	6" AC pavement in poor condition. Light brown silty sand/sandy silt with some clay binders. Sand is fine in texture. Moist and firm. No petrochemical odor.
65 5			SP	Light tan sand with a little silt and gravel. Moist and dense. Sand is becoming coarser in texture with depth. Gravel content is increasing with depth. No petrochemical odor.
60 10				No free water.
55 15				
50 20				
45 25				
40 30				
35 35				

LOG OF TEST BORING

LAB. NO.: 140- 4536 PROJECT: 1ST STREET VIADUCT OVER L.A. RIVER-SEISMIC RETROFIT
 BORING NO.: H-1 ELEVATION: 270' DRILLING DATE: 02-15-96 (CONTAMINATION)
 BORING LOCATION: 11' E/o WCF Center St. and 53' S/o SCF 1st St. (N/s Frontage Rd.) under bridge
 DRILL RIG TYPE: CME-75 using 6" diameter conventional flight augers.
 DEPTH TO STANDING WATER: None DEPTH TO WATER SEEPAGE: None
 DRILLER: Ramirez LOGGER: Redlin ENGINEER: Burnett

ELEVATION / DEPTH (ft)	SOIL SYMBOLS, SAMPLER SYMBOLS AND BLOWS/INCHES	OVA (PPM)	USCS	Field Description
270 0		0	SM	6" AC pavement in poor condition. FILL MATERIAL. Light brown silty sand with some clay binders and a trace of gravel. Sand is fine in texture. Moist and firm. Encountered some red brick fragments at 2.5' depth.
265 5			ML	Light brown sandy silt with some clay binders. Moist and firm. No petrochemical odor.
260 10			SP	Light tan sand with some gravel. Moist and dense. No petrochemical odor.
255 15				<p>--- No free water. ---</p> <p>Used break down mast under bridge.</p>
250 20				
245 25				
240 30				
235 35				

LOG OF TEST BORING

LAB. NO.: 140- 4536 PROJECT: 1ST STREET VIADUCT OVER L.A. RIVER-SEISMIC RETROFIT

BORING NO.: H-5 ELEVATION: 275' DRILLING DATE: 02-15-96 (CONTAMINATION)

BORING LOCATION: 45' W/o ECF Myers St. and 53' S/o SCF 1st St. (N/s Frontage Rd.)- under bridge

DRILL RIG TYPE: CME-75 using 6" diameter conventional flight augers.


DEPTH TO STANDING WATER: None

DEPTH TO WATER SEEPAGE: None

DRILLER: Ramirez


LOGGER: Redlin

ENGINEER: Burnett

ELEVATION / DEPTH (ft)	SOIL SYMBOLS, SAMPLER SYMBOLS AND BLOWS/INCHES	OVA (PPM)	USCS	Field Description
275 0				
		0	SP	6" AC pavement in poor condition. Light brown/tan poorly graded sand. Sand is fine in texture. Moist and dense. Sand is becoming coarser in texture with depth. No petrochemical odor.
270 5		0		
265 10		0		Encountered gravel and small cobbles at 10' depth.
260 15				--- No free water. --- Used break down mast under bridge.
255 20				
250 25				
245 30				
240 35				

LOG OF TEST BORING

LAB. NO.: 140- 4536 **PROJECT:** 1ST STREET VIADUCT OVER L.A. RIVER-SEISMIC RETROFIT
BORING NO.: H-4 **ELEVATION:** 275' **DRILLING DATE:** 02-15-96 **(CONTAMINATION)**
BORING LOCATION: 28' S/o SCF 1st St. (N/s Frontage Rd.) and 104' W/o ECF Myers St.- under bridge
DRILL RIG TYPE: CME-75 using 6" diameter conventional flight augers.
DEPTH TO STANDING WATER: None **DEPTH TO WATER SEEPAGE:** None
DRILLER: Ramirez **LOGGER:** Redlin **ENGINEER:** Burnett

ELEVATION / DEPTH (ft)	SOIL SYMBOLS, SAMPLER SYMBOLS AND BLOWS/INCHES	OVA (PPM)	USCS	Field Description
75 0			CL-ML	6" AC pavement in poor condition.
		0	SP	POSSIBLE FILL MATERIAL (due to presense of disturbed soil matrix) Light brown silty clay/clayey silt with some sand and gravel pockets. Moist and firm. No petrochemical odor.
70 5		0		Light brown/tan sand with some gravel. Moist and dense. Gravel content is increasing with depth. No petrochemical odor.
65 10		0		Encountered small cobbles at 10' depth.
60 15				---
				No free water.

				Used break down mast under bridge.
55 20				
50 25				
45 30				
40 35				

LOG OF TEST BORING

LAB. NO.: 140- 4536 PROJECT: 1ST STREET VIADUCT OVER L.A. RIVER-SEISMIC RETROFIT
 BORING NO.: H-3 ELEVATION: 271' DRILLING DATE: 02-15-96 (CONTAMINATION)
 BORING LOCATION: 59' E/o ECF Center St. and 54' S/o SCF 1st St. (N/s Frontage Rd.) under bridge
 DRILL RIG TYPE: CME-75 using 6" diameter conventional flight augers.
 DEPTH TO STANDING WATER: None DEPTH TO WATER SEEPAGE: None
 DRILLER: Ramirez LOGGER: Redlin ENGINEER: Burnett

ELEVATION / DEPTH (ft)	SOIL SYMBOLS, SAMPLER SYMBOLS AND BLOWS/INCHES	OVA (PPM)	USCS	Field Description
270	4/12	0	SP-SM	6" AC pavement in poor condition. POSSIBLE FILL MATERIAL (due to low blow count and location near bridge footing) Light brown poorly graded sand with some silt and gravel. Moist and loose.
265	3/12	0		Encountered some small cobbles at 7' depth.
260	6/12	0		
255				No free water.
250				Used break down mast under bridge.
245				
240				
235				

Existing Geotechnical Boring Logs
Converse Consultants/Earth Sciences Associates
Geo/Resource Consultants, 1983 and 1986

GEOLOGIC EXPLANATION

GEOLOGIC UNITS

QUATERNARY

PLEISTOCENE HOLOCENE

- A1 YOUNG ALLUVIUM (Granular): Includes clean sands, silty sands, gravelly sands, sandy gravels, and locally contains cobbles and boulders. Primarily dense, but ranges from loose to very dense.
- A2 YOUNG ALLUVIUM (Fine-grained): Includes clays, clayey silts, sandy silts, sandy clays, clayey sands. Primarily stiff, but ranges from firm to hard.
- A3 OLD ALLUVIUM (Granular): Includes clean sands, silty sands, gravelly sands, and sandy gravels. Primarily dense, but ranges from medium dense to very dense.
- A4 OLD ALLUVIUM (Fine-grained): Includes clays, clayey silts, sandy silts, sandy clays, and clayey sands. Primarily stiff, but ranges from firm to hard.
- SP SAN PEDRO FORMATION: Predominantly clean, cohesionless, fine to medium-grained sands, but includes layers of silts, silty sands, and fine gravels. Primarily dense, but ranges from medium dense to very dense. Locally impregnated with oil or tar.

TERTIARY

MIOCENE PLIOCENE

- C FERNANDO AND PUENTE FORMATIONS: Claystone, siltstone, and sandstone; thinly to thickly bedded. Primarily low hardness, weak to moderately strong. Locally contains very hard, thin cemented beds and cemented nodules. Locally contains gas and oil.

SYMBOLS

- ? --- Geologic contact: approximately located, queried where inferred.
- ? --- Fault: approximately located; queried where inferred; arrows indicate probable movement; attitude in profile is an apparent dip and is not corrected for scale distortion.
- 40 Dip of bedding: from unoriented core samples; bedding attitudes may not be correctly oriented to the plane of the profile, but represent dips to illustrate regional geologic trends; number gives true dip in degrees, as encountered in boring.
- ▼ Perched water level: approximately located; queried where inferred.
- ▼ Permanent water level: approximately located; queried where inferred.
- Boring - CEG (1981)
- Boring - CCI/ESA/GRC (1983, 1984 & 1985)
- ⊕ Boring - Woodward - Clyde (1977)
- ⊙ Boring - Kaiser Engineers (1962)
- ⊖ Boring - Other (USGS 1977 and various foundation studies)
- Boring - Nuclear Regulatory Commission (1980)
- } See appropriate Woodward - Clyde and Kaiser report(s).
- } Borings not drilled for Metro Rail Project. Logs not available in Metro Rail Transit Consultants' office.

NOTES

- 1) The geologic sections are based on interpolation between borings and were prepared as an aid in developing design recommendations. Actual conditions encountered during construction may be different. Geologic sections are plotted for AR (Outbound) track.
- 2) Track alignment plan and profiles are approximate.
- 3) Borings projected more than 200' to the profile line were considered in some of the interpretation of subsurface conditions. However, final interpretation is based on numerous factors and may not reflect the boring logs as presented on Drawings No. K-001.
- 4) Displacements shown along faults are graphic representations. Actual vertical offsets are unknown.
- 5) Additional information on observation wells (OW) and pump wells (PW), located in the Union Station vicinity, is presented in the report titled "Union Station Area Aquifer Pump Test", dated November 11, 1986.
- 6) CONTRACTOR SHOULD BE AWARE OF THE PRESENCE OF COBBLES AND BOULDERS AT LOWER DEPTHS IN THE BORINGS, ABOVE THE PUENTE FORMATION

REVISIONS

- 1) Added supplemental borings to plan and geologic section.
- 2) The following data was added to boring logs

- Boring 5-1 : Drill Rig - Failing 1500
- Boring 5-2 : Drill Rig - Failing 1500
- Boring 5-3 : Drill Rig - Failing 1500
- Boring 5-4 : Drill Rig - Failing 1500
- Boring 5-5 : Drill Rig - Failing 1500



THE PREPARATION OF THIS DRAWING HAS BEEN FINANCED IN PART THROUGH A GRANT FROM THE U. S. DEPARTMENT OF TRANSPORTATION, URBAN MASS TRANSPORTATION ADMINISTRATION, UNDER THE URBAN MASS TRANSPORTATION ACT OF 1964, AS AMENDED, AND IN PART BY THE TAXES OF THE CITIZENS OF LOS ANGELES COUNTY AND OF THE STATE OF CALIFORNIA										DESIGNED BY _____		SOUTHERN CALIFORNIA RAPID TRANSIT DISTRICT		LA CBD TO NORTH HOLLYWOOD UNION STATION		CONTRACT NO. A136			
										DRAWN BY _____		METRO RAIL PROJECT				DRAWING NO. K-002			
										CHECKED BY _____		CCI/ESA/GRC				REV. 0			
										IN CHARGE _____		General Geotechnical Consultants		DMJM/PBQD/KE/HWA		SCALE NONE			
										DATE 2-13-87		SUBMITTED _____		APPROVED _____		SHEET NO. 48			
REV. DATE BY SUB APP DESCRIPTION										EXPLANATIONS, NOTES AND REVISIONS									

THIS BORING LOG IS BASED ON FIELD CLASSIFICATION AND VISUAL
SUN DRY INSPECTION. BUT IS NOT MEANT TO BE USED AS A
LABORATORY CLASSIFICATION TESTS WHERE AVAILABLE. THIS LOG
IS APPLICABLE ONLY AT THIS LOCATION AND TIME. CONDITIONS
MAY DIFFER AT OTHER LOCATIONS OR TIME.

Converse Consultants, Inc.
Earth Sciences Associates
Geo/Resource Consultants
BORING LOG 5-1

Proj: DESIGN UNIT A135 Date Drilled: 2-4-83 Ground Elev. 279.1'
Drill Rig: Logged By: B. Inghram Total Depth: 85.0'
Hole Diameter: 4 3/4" Hammer Weight & Fall: 320 lbs. 2 3/4"

DEPTH	LOG	MATERIAL CLASSIFICATION	SAMPLE	REMARKS
0	SM	0.0-0.4 ASPHALT PAVEMENT	RD	
0	SM	0.4-2.0 FILL SILTY SAND, mottled brown, moist, dense	1-1	DR
2	SM	ALLUVIUM 2.0-4.0 SILTY SAND/SANDY SILT: red-brown moist, medium dense, fine sand with silt, slightly porous		
4	SM	4.0-8.0 SILTY SAND: gray brown, moist, medium dense, fine sand with silt and trace gravel to 1"	1-2	DR RD
8	SM	8.0-70.0 GRAVELLY SAND		
10			100	SS Refusal at 5'
12			RD	
14				
16				
18				
20				

Sheet 1 of 4

DEPTH	LOG	MATERIAL CLASSIFICATION	SAMPLE	REMARKS
20	SM	8.0-70.0 GRAVELLY SAND (continued)		NO RECOVERY
22			RD	
24				
26				
28				
30				
32			1-3	DR RD POOR RECOVERY
34		Intermittent lenses of increased gravel content		
36				
38				
40				
42			1-4	DR RD Sulphur odor in sample Poor Recovery
44				

Sheet 2 of 4

DEPTH	LOG	MATERIAL CLASSIFICATION	SAMPLE	REMARKS
44	SM	8.0-70.0 GRAVELLY SAND (continued)		
46			1-5	DR RD Sulphur odor Poor Sample Recovery
48				
50				
52				
54				
56				
58			1-6	DR RD No Recovery
60				
62				
64				
66			1-6	DR RD Slight Sulphur Odor Poor Sample Recovery
68				
70				
72				
74				
76				
78				
80				
82				
84			1-7	DR RD Sulphur Odor Poor Recovery
86				

Sheet 3 of 4

DEPTH	LOG	MATERIAL CLASSIFICATION	SAMPLE	REMARKS
68	SM	8.0-70.0 GRAVELLY SAND (continued)		
70		70.0-79.5 Boulders		
72				
74				
76				No Recovery
78				Refusal
80				
82		BEDROCK 79.5-85.0 SANDY CLAYSTONE AND CLAYEY SANDSTONE, olive-gray, moist, fresh, thinly laminated, friable strength, friable to low hardness. Tends to fracture along laminations	1-8	DR RD
84			1-9	DR
86				
88				
90				
92				

Sheet 4 of 4

THIS BORING LOG IS BASED ON FIELD CLASSIFICATION AND VISUAL
SUN DRY INSPECTION. BUT IS NOT MEANT TO BE USED AS A
LABORATORY CLASSIFICATION TESTS WHERE AVAILABLE. THIS LOG
IS APPLICABLE ONLY AT THIS LOCATION AND TIME. CONDITIONS
MAY DIFFER AT OTHER LOCATIONS OR TIME.

Converse Consultants, Inc.
Earth Sciences Associates
Geo/Resource Consultants
BORING LOG 5-2

Proj: DESIGN UNIT A135 Date Drilled: 2-3-83 Ground Elev. 292.7'
Drill Rig: Logged By: B. Inghram Total Depth: 85.0'
Hole Diameter: 4 3/4" Hammer Weight & Fall: 320 lbs. 2 3/4"

DEPTH	LOG	MATERIAL CLASSIFICATION	SAMPLE	REMARKS
0	SM	0.0-0.4 Concrete Slab	RD	
0	SM	0.4-0.8 BASE CONCRETE		
2	SM	0.8-14.0 FILL CLAYEY SILT AND SILTY CLAY, mottled brown and green-gray, moist, stiff with trace gravel and fine sand	2-1	DR RD
4	SM			
6	SM			
8	SM			
10	SM	becoming hard	70	SS
12	SM		100	RD
14	SM	13.0 Rock or Concrete	100	SS SPT REFUSAL AT 0"
16	SM			
18	SM	14.0-19.0 ALLUVIUM SILTY SAND: gray-brown, moist, medium dense, fine to very fine sand with silt	8	SS
20	SM	19.0-72.0 GRAVELLY SAND	14	RD

Sheet 1 of 4

DEPTH	LOG	MATERIAL CLASSIFICATION	SAMPLE	REMARKS
20	SM	19.0-72.0 GRAVELLY SAND (continued) gray, dense, medium to coarse sand, gravel to 2"	2-2	DR RD Disturbed Sample
22				
24				
26				
28				
30				
32				
34				
36				
38				
40				
42				
44				

Sheet 2 of 4

DEPTH	LOG	MATERIAL CLASSIFICATION	SAMPLE	REMARKS
44	SM	19.0-72.0 GRAVELLY SAND (continued) color change observed to dark gray		
46			2-3	DR RD Slight sulphur odor poor sample recovery
48				
50				
52				
54				
56				
58				
60				
62				
64				
66				
68				
70				
72				
74				
76				
78				
80				
82				
84				
86				
88				
90				
92				

Sheet 3 of 4

DEPTH	LOG	MATERIAL CLASSIFICATION	SAMPLE	REMARKS
68	SM	19.0-72.0 GRAVELLY SAND (continued) decreasing gravel content		
70			2-4	DR RD slight sulphur odor
72	SM	72.0-83.0 SAND: dark gray; very dense; medium sand with trace gravel to 2"		
74				
76				
78				
80			100	SS sulphur odor refusal at 5'
82				
84				
86				
88				
90				
92				

Sheet 4 of 4



REV.	DATE	BY	SUB	APP	DESCRIPTION

THE PREPARATION OF THIS DRAWING HAS BEEN FINANCED IN PART THROUGH A GRANT FROM THE U. S. DEPARTMENT OF TRANSPORTATION, URBAN MASS TRANSPORTATION ADMINISTRATION, UNDER THE URBAN MASS TRANSPORTATION ACT OF 1964, AS AMENDED, AND IN PART BY THE TAXES OF THE CITIZENS OF LOS ANGELES COUNTY AND OF THE STATE OF CALIFORNIA					
REV.	DATE	BY	SUB	APP	DESCRIPTION
1	1/31/83	JAN	WJA		INITIAL ISSUE

DESIGNED BY	
DRAWN BY	DKM/JAP
CHECKED BY	J.A. [Signature]
IN CHARGE	R.M. [Signature]
DATE	30 NOV. 83

N/A

SOUTHERN CALIFORNIA RAPID TRANSIT DISTRICT METRO RAIL PROJECT	
CCI/ESA/GRC General Geotechnical Consultants	DMJM/PEQD/KE/HWA GENERAL CONSULTANTS
SUBMITTED: R.M. [Signature]	APPROVED: [Signature]

LA CBD TO NORTH HOLLYWOOD UNION STATION BORING LOGS 5-1 & 5-2	
---	--

CONTRACT NO.	A136
DRAWING NO.	K-003
REV.	0
SCALE	NO SCALE
SHEET NO.	49

DEPTH	SOIL	MATERIAL CLASSIFICATION	WATER CONTENT	FLUIDITY	REMARKS
0		0-0-0 ASPHALT PAVEMENT		SC	
1	GM	FILL			
2		0-8-4.6 GRAVEL: gravel to 2-1/2", sub-angular to subrounded		GM	No sample recovery
3				RD	
4					
5	SM	4.6-14.0 CLAYEY SILT, green gray, moist, stiff, with variable sand content	3-1	SM	
6				SC	
7					
8					
9					
10		very stiff to hard		SC	
11				SC	
12				SC	
13					
14	SM	14-19.0 SILTY SAND, gray brown, moist, dense, fine to very fine sand with silt		SM	
15				SC	
16				SC	
17				SC	
18				SC	
19					
20	SM	19-0-74.0 GRAVELLY SAND		SC	

Sheet 1 of 4

BORING LOG 5-4

DEPTH FEET	MATERIAL CLASSIFICATION	ANAL.	NO.	TESTS	REMARKS
0	0-0.3 ASPHALT PAVEMENT				RD
0.3-3.5	M. FILL 0-3-3.5 SANDY SILT: dark brown, moist, stiff, with fine to medium sand, trace gravel and brick chunks	4-1			DR
3.5-4.0	CONCRETE BLOCK				RD
4	SM. ALLUVIUM 4-0-7.0 SILTY SAND: gray brown, moist, dense, fine to very fine sand with silt	3-1	BT TS LA	SS	
7-0-18.0	SAND: gray, moist, dense, clean fine sand				WD
4-2					DR
3-2			S LA	SS	
					WD
18-0-28.0	GRAVELLY SAND: brown/gray/white, moist, medium to coarse sand with gravel to 2", subrounded to sub- angular grains				

Sheet 1 of 4

Project	DESIGN UNIT A-135	Date Drilled	2-2-83	Hole No.	5-2
DEPTH FEET	MATERIAL CLASSIFICATION	LOG NO.	LOG NO.	LOG NO.	REMARKS
20	19-24' 0" GRAVELLY SAND, continued brown, very dense, medium to coarse sand and gravel to 3" subangular to subrounded			UP	No sample recovery
22				RD	
24					24-28' intermittent drill rig chatter
26	sand and gravel strata				
28					
30					
32				UP	poor sample recovery
34				RD	
36					
38					
40				UP	sulphur odor
42				RD	drill rig chatter at 41'
44					Sheet 7 of 4

Project	DESIGN UNIT #173	Date Drilled	1-31-83	Hole No.	5-4
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44	1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44	MATERIAL CLASSIFICATION	UNIT WT	# - A - B - C - D - E - F - G - H - I - J - K - L - M - N - O - P - Q - R - S - T - U - V - W - X - Y - Z - AA - AB - AC - AD - AE - AF - AG - AH - AI - AJ - AK - AL - AM - AN - AO - AP - AQ - AR - AS - AT - AU - AV - AW - AX - AY - AZ - BA - BB - BC - BD - BE - BF - BG - BH - BI - BJ - BK - BL - BM - BN - BO - BP - BQ - BR - BS - BT - BU - BV - BW - BX - BY - BZ - CA - CB - CC - CD - CE - CF - CG - CH - CI - CJ - CK - CL - CM - CN - CO - CP - CQ - CR - CS - CT - CU - CV - CW - CX - CY - CZ - DA - DB - DC - DD - DE - DF - DG - DH - DI - DJ - DK - DL - DM - DN - DO - DP - DQ - DR - DS - DT - DU - DV - DW - DX - DY - DZ - EA - EB - EC - ED - EE - EF - EG - EH - EI - EJ - EK - EL - EM - EN - EO - EP - EQ - ER - ES - ET - EU - EV - EW - EX - EY - EZ - FA - FB - FC - FD - FE - FF - FG - FH - FI - FJ - FK - FL - FM - FN - FO - FP - FQ - FR - FS - FT - FU - FV - FW - FX - FY - FZ - GA - GB - GC - GD - GE - GF - GG - GH - GI - GJ - GK - GL - GM - GN - GO - GP - GQ - GR - GS - GT - GU - GV - GW - GX - GY - GZ - HA - HB - HC - HD - HE - HF - HG - HH - HI - HJ - HK - HL - HM - HN - HO - HP - HQ - HR - HS - HT - HU - HV - HW - HX - HY - HZ - IA - IB - IC - ID - IE - IF - IG - IH - II - IJ - IK - IL - IM - IN - IO - IP - IQ - IR - IS - IT - IU - IV - IW - IX - IY - IZ - JA - JB - JC - JD - JE - JF - JG - JH - JI - JJ - JK - JL - JM - JN - JO - JP - JQ - JR - JS - JT - JU - JV - JW - JX - JY - JZ - KA - KB - KC - KD - KE - KF - KG - KH - KI - KJ - KK - KL - KM - KN - KO - KP - KQ - KR - KS - KT - KU - KV - KW - KX - KY - KZ - LA - LB - LC - LD - LE - LF - LG - LH - LI - LJ - LK - LL - LM - LN - LO - LP - LQ - LR - LS - LT - LU - LV - LW - LX - LY - LZ - MA - MB - MC - MD - ME - MF - MG - MH - MI - MJ - MK - ML - MN - MO - MP - MQ - MR - MS - MT - MU - MV - MW - MX - MY - MZ - NA - NB - NC - ND - NE - NF - NG - NH - NI - NJ - NK - NL - NM - NO - NP - NQ - NR - NS - NT - NU - NV - NW - NX - NY - NZ - OA - OB - OC - OD - OE - OF - OG - OH - OI - OJ - OK - OL - OM - ON - OO - OP - OQ - OR - OS - OT - OU - OV - OW - OX - OY - OZ - PA - PB - PC - PD - PE - PF - PG - PH - PI - PJ - PK - PL - PM - PN - PO - PP - PQ - PR - PS - PT - PU - PV - PW - PX - PY - PZ - QA - QB - QC - QD - QE - QF - QG - QH - QI - QJ - QK - QL - QM - QN - QO - QP - QQ - QR - QS - QT - QU - QV - QW - QX - QY - QZ - RA - RB - RC - RD - RE - RF - RG - RH - RI - RJ - RK - RL - RM - RN - RO - RP - RQ - RR - RS - RT - RU - RV - RW - RX - RY - RZ - SA - SB - SC - SD - SE - SF - SG - SH - SI - SJ - SK - SL - SM - SN - SO - SP - SQ - SR - SS - ST - SU - SV - SW - SX - SY - SZ - TA - TB - TC - TD - TE - TF - TG - TH - TI - TJ - TK - TL - TM - TN - TO - TP - TQ - TR - TS - TT - TU - TV - TW - TX - TY - TZ - UA - UB - UC - UD - UE - UF - UG - UH - UI - UJ - UK - UL - UM - UN - UO - UP - UQ - UR - US - UT - UU - UV - UW - UX - UY - UZ - VA - VB - VC - VD - VE - VF - VG - VH - VI - VJ - VK - VL - VM - VN - VO - VP - VQ - VR - VS - VT - VU - VV - VW - VX - VY - VZ - WA - WB - WC - WD - WE - WF - WG - WH - WI - WJ - WK - WL - WM - WN - WO - WP - WQ - WR - WS - WT - WU - WV - WW - WX - WY - WZ - XA - XB - XC - XD - XE - XF - XG - XH - XI - XJ - XK - XL - XM - XN - XO - XP - XQ - XR - XS - XT - XU - XV - XW - XX - XY - XZ - YA - YB - YC - YD - YE - YF - YG - YH - YI - YJ - YK - YL - YM - YN - YO - YP - YQ - YR - YS - YT - YU - YV - YW - YX - YY - YZ - ZA - ZB - ZC - ZD - ZE - ZF - ZG - ZH - ZI - ZJ - ZK - ZL - ZM - ZN - ZO - ZP - ZQ - ZR - ZS - ZT - ZU - ZV - ZW - ZX - ZY - ZZ	REMARKS
20	SW				

Project		Date Drilled		Hole No.	
DESIGN UNIT A135		2-2-84		5-2	
DEPTH FEET	MATERIAL CLASSIFICATION	LOG	W - M -	C S	REMARKS
44	19 0.74 0 GRAVELLY SAND continued			RD	
46					
48					
50		3-2		DR	sulphur odor in sample
52	sand and gravel strata			RD	
54					53' intermittent dril rig chatter to 58'
56					
58					
60					
62				DR	slight sulphur odor in sample
64				PE	your recovery
66					
68					
70					

Sheet 3 of 4

Project		DESIGN UNIT: A135	Date Drilled	1-31-83	Hole No.		5-4
DEPTH FEET	LOG	MATERIAL CLASSIFICATION	SOIL TYPE	W % 20	W % 40	W % 60	REMARKS
44	Sw	41 0-88 0 GRAVELLY SAND continued					
46						SS	Refusal at 17"
48						RD	
50							
52							
54							
56							
58							
60		50 5' clay interbeds	4-5			OK	sulphurous odor in sample
62						RD	
64							
66							
68							
70							
72							
74							
76							
78							
80							
82							
84							
86							
88							
90							
92							
94							
96							
98							
100							
102							
104							
106							
108							
110							
112							
114							
116							
118							
120							
122							
124							
126							
128							
130							
132							
134							
136							
138							
140							
142							
144							
146							
148							
150							
152							
154							
156							
158							
160							
162							
164							
166							
168							
170							
172							
174							
176							
178							
180							
182							
184							
186							
188							
190							
192							
194							
19							

Project		DESIGN UNIT A135	Date Drilled	2-2-83	Hole No.	5-3
DEPTH	DIAMETER	MATERIAL CLASSIFICATION	NO.	TEST	REMARKS	
68	54	19 0 74 0 GRAVELLY SAND continued		NO		
70			3-3	DR	slight sulphur odor in sample	
72				NO		
74	50	74 0 80 0 SAND: dark gray, medium dense to dense, fine to very fine, # (includes silty sand lenses)				
76						
78						
80			3-4	DR	sulphur odor in sample	
82		End of Boring 80 0'				
84						
86						
88						
90						
92						

Sheet 4 of 4

Project		DESIGN UNIT A125	Date Drilled	1-31-83	Hole No.	3-4
DEPTH Feet		MATERIAL CLASSIFICATION	TEST Feet	TEST Feet	TEST Feet	REMARKS
68	DP	68-0-75.0 SAND, gray, dense, micaceous, fine to very fine sand			RD	
70			4-7		DP	sulphur/hydrothermal odor in sample
72					RD	
74						
76	DP	75-0-80.0 GRAVELLY SAND, gravel to 1-1/2" gray, dense to very dense				
78						
80			4-8		DP	
		End of Boring 80.0'				
82						
84						
86						
88						
90						
92						

Sheet 4 of 4

CONTRACT NO		A136
DRAWING NO	K-004	REV C
SCALE NO SCALE		
SHEET NO		50

THIS BORING LOG IS BASED ON FIELD CLASSIFICATION AND VISUAL
SOIL DESCRIPTION, BUT IS SUBJECT TO REVISION IN PARTS OF
LABORATORY CLASSIFICATION TESTS WHEN AVAILABLE. THIS LOG
IS APPLICABLE ONLY AT THE LOCATION AND TIME INDICATED
MAY VARY AT OTHER LOCATIONS OR TIME.

Converse Consultants, Inc.
Earth Sciences Associates
Geo/Resource Consultants
BORING LOG 5-5

Proj: DESIGN UNIT A-135 Date Drilled: 2/1/83 Ground Elev: 280.8'
Drill Rig: Logged By: A. Inghram Total Depth: 100.0'
Hole Diameter: 4 3/4" Hammer Weight & Fall: 322 lb, 28"

DEPTH (ft)	TEST	MATERIAL CLASSIFICATION	WATER	WATER CONTENT (%)	REMARKS
0	SM	0.0-0.7 ASPHALT Pavement		RD	
0.7	SM	0.7-5.5 FILL - SANDY SILT & SILTY SAND Mottled and intermixed, moist, stiff, medium dense w/brick debris	16	SS	
5.5	SM	ALUVIUM		RD	
5.5-11.0	SM	SILTY SAND Gray-brown, moist, medium dense, fine to very fine sand with silt	5-1	RD	
11.0-14.0	SP	SAND Gray-brown, moist, medium dense to dense, poorly graded fine sand with trace silt	10	SS	
14.0-62.0	SM	GRAVELLY SAND Brown, dense, medium to coarse sand with gravel to 2", subangu- lar to subrounded grains	5-2	RD	
62.0	SP	62.0-78.0 SAND (Cont'd)		RD	
78.0	SP	78.0-90.0 Boulders		RD	
90.0	SP	90.0-100.0 CLAYSTONE (see next page)		RD	

Sheet 1 of 5

DEPTH (ft)	TEST	MATERIAL CLASSIFICATION	WATER	WATER CONTENT (%)	REMARKS
20	SM	14.0-62.0 GRAVELLY SAND (Cont'd)		RD	refusal at 5"
25	SM	25.5-26.0 lens of fine sand	5-3	RD	
30	SM	30.0 color change to dark gray	25	SS	slight gas odor refusal at 9"
35	SM		5-4	RD	slight gas odor
40	SM		25	SS	refusal at 15"

Sheet 2 of 5

DEPTH (ft)	TEST	MATERIAL CLASSIFICATION	WATER	WATER CONTENT (%)	REMARKS
44	SM	14.0-62.0 GRAVELLY SAND (Cont'd)		RD	
48	SM			RD	
52	SM			RD	
56	SM			RD	
60	SM			RD	
64	SM			RD	
68	SM			RD	
72	SM			RD	
76	SM			RD	
80	SM			RD	
84	SM			RD	
88	SM			RD	
92	SM			RD	
96	SM			RD	
100	SM			RD	

Sheet 3 of 5

DEPTH (ft)	TEST	MATERIAL CLASSIFICATION	WATER	WATER CONTENT (%)	REMARKS
68	SP	62.0-78.0 SAND (Cont'd)		RD	
70	SP		5-6	RD	sulphur odor
72	SP			RD	
74	SP			RD	
76	SP			RD	
78	SP			RD	
80	SP			RD	
82	SP			RD	
84	SP			RD	
86	SP			RD	
88	SP			RD	
90	SP			RD	
92	SP			RD	
94	SP			RD	
96	SP			RD	
98	SP			RD	
100	SP			RD	

Sheet 4 of 5

DEPTH (ft)	TEST	MATERIAL CLASSIFICATION	WATER	WATER CONTENT (%)	REMARKS
92	SP	90.0-100.0 CLAYSTONE (Cont'd) olive-gray color, moist, plastic to friable strength, soft to friable hardness, thinly laminated with silty claystone and sandstone blades, tends to fracture along laminations		RD	
100	SP	End of Boring 100.0 ft.	5-7	RD	piezometer set to 100' - perforated in lowest 40'

Sheet 5 of 5

THE BORING LOG IS BASED ON FIELD CLASSIFICATION AND VISUAL
SOIL DESCRIPTION, BUT IS SUBJECT TO REVISION IN PARTS OF
LABORATORY CLASSIFICATION TESTS WHEN AVAILABLE. THIS LOG
IS APPLICABLE ONLY AT THE LOCATION AND TIME INDICATED
MAY VARY AT OTHER LOCATIONS OR TIME.

Converse Consultants, Inc.
Earth Sciences Associates
Geo/Resource Consultants
BORING LOG 6A

Proj: DESIGN UNIT A135 Date Drilled: 2-10-83 Ground Elev: 290.0'
Drill Rig: BIRKBEIT AUGER Logged By: D. Gillelette Total Depth: 55.0'
Hole Diameter: 36" Hammer Weight & Fall: NA

DEPTH (ft)	TEST	MATERIAL CLASSIFICATION	WATER	WATER CONTENT (%)	REMARKS
0	SP	ALUVIUM		RD	0.0-15.0 belting and aving
2	SP	0.0-22.0 SAND AND GRAVEL light brown, medium to coarse sand with silt, little gravel to 1.2", subrounded, trace cobbles and boulders, moist, medium dense		RD	
12	SP	12.0-13.0 clay with trace gravel		RD	
15	SP	15.5-16.0 clay		RD	
19	SP	19.5-19.8 gravel lens		RD	

Sheet 1 of 3





DEPTH (ft)	TEST	MATERIAL CLASSIFICATION	WATER	WATER CONTENT (%)	REMARKS
20	SP	0.0-22.0 SAND AND GRAVEL continued		RD	
22	SM	22.0-55.0 SILTY SAND, olive gray, fine sand, slightly micaceous, moist to very moist, medium dense		RD	water seeps at 22.0'
28	SM	28.0 dark greenish gray		RD	

Sheet 2 of 3





DEPTH (ft)	TEST	MATERIAL CLASSIFICATION	WATER	WATER CONTENT (%)	REMARKS
44	SM	22.0-55.0 SILTY SAND continued		RD	
48	SM			RD	
52	SM			RD	
56	SM			RD	
60	SM			RD	
64	SM			RD	
68	SM			RD	
72	SM			RD	
76	SM			RD	
80	SM			RD	
84	SM			RD	
88	SM			RD	
92	SM			RD	
96	SM			RD	
100	SM			RD	

Sheet 3 of 3

THE PREPARATION OF THIS DRAWING HAS BEEN FINANCED IN PART THROUGH A GRANT FROM THE U. S. DEPARTMENT OF TRANSPORTATION, URBAN MASS TRANSPORTATION ADMINISTRATION, UNDER THE URBAN MASS TRANSPORTATION ACT OF 1964, AS AMENDED, AND IN PART BY THE TAXES OF THE CITIZENS OF LOS ANGELES COUNTY AND OF THE STATE OF CALIFORNIA.										DESIGNED BY DRAWN BY CHECKED BY IN CHARGE DATE										SOUTHERN CALIFORNIA RAPID TRANSIT DISTRICT METRO RAIL PROJECT										LA CBD TO NORTH HOLLYWOOD UNION STATION BORING LOGS 5-5 & 6A										CONTRACT NO. A136 DRAWING NO. K-005 SCALE NO SCALE SHEET NO. 51									
REV. DATE BY SUB APP DESCRIPTION										REV. DATE BY SUB APP DESCRIPTION										CCI/ESA/GRC General Geotechnical Consultants SUBMITTED: R.M. P...										DMJM/PBOD/KE/HWA GENERAL CONSULTANTS APPROVED: ...										N/A									



THE PREPARATION OF THIS DRAWING HAS BEEN FINANCED IN PART THROUGH A GRANT FROM THE U.S. DEPARTMENT OF TRANSPORTATION, URBAN MASS TRANSPORTATION ADMINISTRATION, UNDER THE URBAN MASS TRANSPORTATION ACT OF 1984, AS AMENDED, AND IN PART BY THE TAXES OF THE CITIZENS OF LOS ANGELES COUNTY AND OF THE STATE OF CALIFORNIA.										DESIGNED BY		SOUTHERN CALIFORNIA RAPID TRANSIT DISTRICT		LA CBD TO NORTH HOLLYWOOD UNION STATION		CONTRACT NO. A136	
										DRAWN BY		METRO RAIL PROJECT				DRAWING NO. K-006	
										CHECKED BY		N/A				REV. 0	
										IN CHARGE						SCALE NO SCALE	
										DATE		020CT89				SHEET NO. 52	
												SUBMITTED		APPROVED			
												METRO RAIL TRANSIT CONSULTANTS		DMJM/PBQD/KE/HWA			
												GENERAL CONSULTANTS					



THE PREPARATION OF THIS DRAWING HAS BEEN FINANCED IN PART THROUGH A GRANT FROM THE U. S. DEPARTMENT OF TRANSPORTATION, URBAN MASS TRANSPORTATION ADMINISTRATION, UNDER THE URBAN MASS TRANSPORTATION ACT OF 1964, AS AMENDED, AND IN PART BY THE TAXES OF THE CITIZENS OF LOS ANGELES COUNTY AND OF THE STATE OF CALIFORNIA										DESIGNED BY		SOUTHERN CALIFORNIA RAPID TRANSIT DISTRICT		LA CBD TO NORTH HOLLYWOOD UNION STATION		CONTRACT NO. A136	
										DRAWN BY		METRO RAIL PROJECT				DRAWING NO. K-007	
										CHECKED BY		METRO RAIL TRANSIT CONSULTANTS				REV. 0	
										IN CHARGE		DMJM/PBQD/KE/HWA				SCALE NO SCALE	
										DATE		SUBMITTED				SHEET NO. 53	
REV. DATE BY SUB APP DESCRIPTION										02OCT89		APPROVED					

[illegible]

						THE PREPARATION OF THIS DRAWING HAS BEEN FINANCED IN PART THROUGH A GRANT FROM THE U S DEPARTMENT OF TRANSPORTATION, URBAN MASS TRANSPORTATION ADMINISTRATION, UNDER THE URBAN MASS TRANSPORTATION ACT OF 1964, AS AMENDED, AND IN PART BY THE TAXES OF THE CITIZENS OF LOS ANGELES COUNTY AND OF THE STATE OF CALIFORNIA						DESIGNED BY _____		SOUTHERN CALIFORNIA RAPID TRANSIT DISTRICT						LA CBD TO NORTH HOLLYWOOD				CONTRACT NO. AI36					
												DRAWN BY _____		METRO RAIL PROJECT						UNION STATION				DRAWING NO. K-008		REV. 0			
												CHECKED BY _____		N/A						METRO RAIL TRANSIT CONSULTANTS DMJM PBQD KE/HWA A JOINT VENTURE		DMJM/PBQD/KE/HWA A JOINT VENTURE GENERAL CONSULTANTS		BORING LOG 5 & CLASSIFICATION CRITERIA				SCALE NO SCALE	
						10/2/89 JAR WJA INITIAL ISSUE						IN CHARGE _____												SHEET NO. 54					
REV. DATE BY SUB. APP. DESCRIPTION						REV. DATE BY SUB. APP. DESCRIPTION						DATE 02OCT89		SUBMITTED _____				APPROVED 											

THIS BORING LOG IS BASED ON FIELD CLASSIFICATION AND WHEN SOON IS RECORDED BUT IS MODIFIED TO INCLUDE RESULTS OF LABORATORY CLASSIFICATION TESTS WHEN AVAILABLE. THE LOG IS A SUMMARY OF THE LOCATION AND THE CONDITIONS MAY VARY AT OTHER LOCATIONS ON THE

Converse Consultants, Inc.
Earth Sciences Associates
Geo/Resource Consultants

BORING LOG 5

Project: DESIGN UNIT A135 Date Drilled: 1-2-80 Hole No.: 5
Drill Rig: falling 1500 Logged By: Stephen M. Telle Total Depth: 150.0'
Hole Diameter: 6 7/8" x 7/8" Hammer Weight & Fall: 140 lb x 30"

DEPTH (FEET)	MATERIAL CLASSIFICATION	LOG	REMARKS
0	0.3-32.0 SANDY GRAVEL: (continued)		
0	0.3-32.0 SANDY GRAVEL: primarily gravel up to 8" with medium to coarse sand; poorly graded		moderate to heavy rig chatter from 3.0
2			
4			
6			
8			
10			
12			
14			
16			
18			
20			

Sheet 1 of 1

DEPTH (FEET)	MATERIAL CLASSIFICATION	LOG	REMARKS
20	0.3-32.0 SANDY GRAVEL: (continued)		moderate to heavy rig chatter from 3.0
22			
24			
26			
28			
30			
32			
34			
36			
38			
40			
42			
44			

Sheet 2 of 2

DEPTH (FEET)	MATERIAL CLASSIFICATION	LOG	REMARKS
44	0.3-32.0 SANDY GRAVEL: (continued)		heavy rig shaking to 52.0
46			
48			
50			
52	52.0-55.0 GRAVELLY SAND: medium dark gray; medium to coarse sand with gravel up to 3 inch; some odor	1-1 47 53	0.5-1.5 recovery refusal at 10"
54			
56	55.0-64.2 SANDY GRAVEL:		rig shaking from 55.0 to 60.0
58			
60			
62			
64			
66			
68			
70			
72			
74			
76			
78			
80			
82			
84			
86			
88			
90			
92			
94			
96			
98			
100			
102			
104			
106			
108			
110			
112			
114			
116			
118			
120			
122			
124			
126			
128			
130			
132			
134			
136			
138			
140			
142			
144			
146			
148			
150			

Sheet 3 of 2

DEPTH (FEET)	MATERIAL CLASSIFICATION	LOG	REMARKS
64	55.0-64.2 SANDY GRAVEL: (continued)		
66			
68			
70			
72			
74			
76			
78			
80			
82			
84			
86			
88			
90			
92			
94			
96			
98			
100			
102			
104			
106			
108			
110			
112			
114			
116			
118			
120			
122			
124			
126			
128			
130			
132			
134			
136			
138			
140			
142			
144			
146			
148			
150			

Sheet 4 of 2

DEPTH (FEET)	MATERIAL CLASSIFICATION	LOG	REMARKS
82	64.2-150.0 CLAYSTONE: (continued)		pocket penetrometer 4.5 tsf 2-9-81
84	primarily claystone from 93.5 to 100.4	Box 1	2.2/2.5 recovery
86			
88			
90	thin sandstone lamina at 96.8; 97.1'		1.9/2.5 recovery
92			
94			
96			
98			
100			
102			
104			
106			
108			
110			
112			
114			
116			
118			
120			
122			
124			
126			
128			
130			
132			
134			
136			
138			
140			
142			
144			
146			
148			
150			

Sheet 1 of 1

DEPTH (FEET)	MATERIAL CLASSIFICATION	LOG	REMARKS
110	64.2-150.0 CLAYSTONE: (continued)		pocket penetrometer 4.5 tsf 2-9-81
112	primarily claystone with alternating very thin to medium lamina of sandstone; micaceous fossiliferous claystone	Box 3	2.2/2.5 recovery
114			
116			
118			
120			
122			
124			
126			
128			
130			
132			
134			
136			
138			
140			
142			
144			
146			
148			
150			

Sheet 2 of 1

DEPTH (FEET)	MATERIAL CLASSIFICATION	LOG	REMARKS
140	64.2-150.0 CLAYSTONE: (continued)		pocket penetrometer in sand lens 3.5
142	very thin to medium alternating lamina of claystone; sandstone and silty claystone; variable thickness of lamina; primary claystone to 142.5; very fine sandstone from 142.5-142.8; 143.1-145.2		1.9/2.5 recovery
144			
146			
148			
150			
152			
154			
156			
158			
160			
162			
164			
166			
168			
170			
172			
174			
176			
178			
180			
182			
184			
186			
188			
190			
192			
194			
196			
198			
200			
202			
204			
206			
208			
210			
212			
214			
216			
218			
220			
222			
224			
226			
228			
230			
232			
234			
236			
238			
240			
242			
244			
246			
248			
250			

Sheet 2 of 1

RECORD DRAWING

THE PREPARATION OF THIS DRAWING HAS BEEN FINANCED IN PART THROUGH A GRANT FROM THE U. S. DEPARTMENT OF TRANSPORTATION, URBAN MASS TRANSPORTATION ADMINISTRATION, UNDER THE URBAN MASS TRANSPORTATION ACT OF 1964, AS AMENDED, AND IN PART BY THE TAXES OF THE CITIZENS OF LOS ANGELES COUNTY AND OF THE STATE OF CALIFORNIA.		DESIGNED BY DRAWN BY CHECKED BY DATE		SOUTHERN CALIFORNIA RAPID TRANSIT DISTRICT METRO RAIL PROJECT		LA CBD TO NORTH HOLLYWOOD UNION STATION BORING LOG 5		CONTRACT NO. A-135 DRAWING NO. K-003 SCALE NO SCALE SHEET NO. 39	
REV. DATE BY SUB. APP. DESCRIPTION		REV. DATE BY SUB. APP. DESCRIPTION		CC/ESA/GRC General Geotechnical Consultants SUBMITTED R.M. Pina		DMJM/PBOD/KE/HWA GENERAL CONSULTANTS APPROVED [Signature]			

THIS BORING LOG IS BASED ON FIELD CLASSIFICATION AND VISUAL
DESCRIPTION. IT IS REQUESTED TO INCLUDE RESULTS OF
LABORATORY CLASSIFICATION TESTS WHEN AVAILABLE. THIS LOG
IS APPLICABLE ONLY AT THE LOCATION AND TIME SHOWN
AND NOT AT OTHER LOCATIONS OR TIME.

Converse Consultants, Inc.
Earth Sciences Associates
Geo/Resource Consultants

BORING LOG 4

Proj: DESIGN UNIT A135 Date Drilled: 2-9-81 Ground Elev.: 228'
Drill Rig: Falling 1500 Logged By: Stephen H. Tests Total Depth: 150.0'
Hole Diameter: 4 7/8" Hammer Weight & Fall: 140 lb. 9'30"

DEPTH (FEET)	MATERIAL CLASSIFICATION	REMARKS
0-0.2	CONCRETE	
0.2-14.0	Fill: Primarily crushed asphalt and brick	
14.0-21.0	ALLUVIUM SP 14.0-21.0 GRAVELLY SAND: olive-black; fine to medium sand and gravel; unit: very dense; all odor	
21.0-101.5	21.0-101.5 SANDY GRAVEL: (continued) Numerous cobbles and boulders	
101.5-150.0	101.5-150.0 CLAYSTONE: (continued) massive; soft to friable hard- ness; plastic to weak strength; fresh; tends to fracture along bedding planes; primarily clay stone with alternating very thin to thin sandstone laminae 119.3-119.9 intensely fractured	

DEPTH (FEET)	MATERIAL CLASSIFICATION	REMARKS
14.0-21.0	14.0-21.0 GRAVELLY SAND: (continued)	
21.0-101.5	21.0-101.5 SANDY GRAVEL: (continued)	
101.5-150.0	101.5-150.0 CLAYSTONE: (continued)	

DEPTH (FEET)	MATERIAL CLASSIFICATION	REMARKS
21.0-101.5	21.0-101.5 SANDY GRAVEL: (continued)	
101.5-150.0	101.5-150.0 CLAYSTONE: (continued)	

DEPTH (FEET)	MATERIAL CLASSIFICATION	REMARKS
21.0-101.5	21.0-101.5 SANDY GRAVEL: (continued)	
101.5-150.0	101.5-150.0 CLAYSTONE: (continued)	

DEPTH (FEET)	MATERIAL CLASSIFICATION	REMARKS
21.0-101.5	21.0-101.5 SANDY GRAVEL: (continued)	
101.5-150.0	101.5-150.0 CLAYSTONE: (continued)	

DEPTH (FEET)	MATERIAL CLASSIFICATION	REMARKS
101.5-150.0	101.5-150.0 CLAYSTONE: (continued)	
150.0-150.0	150.0-150.0 CLAYSTONE: (continued)	

DEPTH (FEET)	MATERIAL CLASSIFICATION	REMARKS
101.5-150.0	101.5-150.0 CLAYSTONE: (continued)	
150.0-150.0	150.0-150.0 CLAYSTONE: (continued)	

NOTES:

- DRILL THREE PROPOSED BORINGS TO AT LEAST 5 FEET INTO BEDROCK.
- TAKE SOIL SAMPLES AT EVERY 5-FOOT INTERVALS TO AT LEAST 60 FEET DEPTH
REQUIRED AT CLOSER DEPTHS. AFTER 60 FEET TAKE SAMPLES AT EVERY 10-FOOT I
VALS OR AS REQUIRED. TAKE N-VALUES (STANDARD PENETRATION TEST) WHILE SAW
USING A SPLIT SPOON OR EQUIVALENT CALIFORNIA SAMPLER.
- DETERMINE GROUND WATER DEPTHS, DURING AND AFTER DRILLING TO LOCATE EXI
GROUNDWATER LEVEL IN EACH BORING. MONITOR FOR PRESENCE OF GAS/OIL.
- PERFORM NECESSARY LABORATORY TESTING ON RELATIVELY UNDISTURBED SOIL SAMPL
DETERMINE MOISTURE/DENSITY, C AND U VALUES, SETTLEMENT PARAMETERS, PERMEAB
PARAMETERS AND GRAIN SIZE DISTRIBUTION. CONTRACTOR SHALL PROVIDE ADDIT
SOIL TEST DATA, IF REQUIRED BY THE DISTRICT ON ITS DESIGNEE. ALL SAMPLES
BE TESTED AND STORED IN A RECOGNIZED SOILS LABORATORY. SAMPLES SHAI
PRESERVED FOR ONE MONTH AFTER COMPLETION OF TESTINGS AND THEN THE SA
SHOULD BE TRANSFERRED TO THE DISTRICT ON ITS DESIGNEE. SOIL TESTS SHAI
PERFORMED AS PER APPROPRIATE ASTM CRITERIA.
- TEST WATER AND SOIL SAMPLES FOR MEASURING LEVELS OF PRIORITY POLLUTANTS.
AT LEAST FIVE SOIL SAMPLES (COLLECTED IN AIRTIGHT GLASS JARS) AND TWO
SAMPLES FOR FOLLOWING CHEMICAL ANALYSIS IN A STATE APPROVED LABORATORY
604, 608, 624, 625, 6020, 6020, 6040, 6080, 6240 AND 6270-APHA 209B.
- COLLECT AND DISPOSE OF ALL SPOIL AS APPROPRIATE, MEETING CITY AND STATE R
REQUIREMENTS.
- CONTRACTOR MAY USE THESE BORINGS TO PROVIDE OBSERVATION WELLS. IN THAT
BORINGS SHALL BE COVERED WITH TIMBER OR METAL PLATE FOR SITE SAFETY UNTIL
ARE INSTALLED. CONTRACTOR MUST ENSURE BEFORE DRILLING SPECIFIED REQUIRED
FOR INSTALLING AND DEVELOPING WELLS.
- CHECK PRESENCE OF POLYCHLORINATED BIPHENOLS ALONG THE TRACK AREA IN THE UP
TO 5 FEET OF SUBSOIL, IN THE THREE BORINGS OR NEAR BY.
- FINAL BORING LOGS SHOULD BE PREPARED BY A GEOTECHNICAL ENGINEER. SOILS
BE IDENTIFIED BY USING THE UNIFIED SOILS CLASSIFICATION SYSTEM.
- FIELD AND LABORATORY WORK SHALL BE CARRIED OUT UNDER THE FULL SUPERVISION
GEOTECHNICAL ENGINEER REGISTERED IN THE STATE OF CALIFORNIA, WHO WILL PR
SEAL AND SIGNATURE ON ALL PERTINENT DOCUMENTS. FIELD AND TEST DATA SHAI
MADE AVAILABLE TO THE DISTRICT ON ITS DESIGNEE IMMEDIATELY UPON COMPLE

RECORD DRAWING

THE PREPARATION OF THIS DRAWING HAS BEEN FINANCED IN PART THROUGH A GRANT FROM THE U. S. DEPARTMENT OF TRANSPORTATION, URBAN MASS TRANSPORTATION ADMINISTRATION, UNDER THE URBAN MASS TRANSPORTATION ACT OF 1964, AS AMENDED, AND IN PART BY THE TAXES OF THE CITIZENS OF LOS ANGELES COUNTY AND OF THE STATE OF CALIFORNIA				DESIGNED BY DRAWN BY CHECKED BY DATE				SOUTHERN CALIFORNIA RAPID TRANSIT DISTRICT METRO RAIL PROJECT CCI/ESA/GRC General Geotechnical Consultants SUBMITTED				LA CBD TO NORTH HOLLYWOOD UNION STATION BORING LOG 4 CONTRACT NO. A-135 DRAWING NO. K-002 SCALE NO SCALE SHEET NO. 38			
NO REVISIONS INDICATED ON CMG 15 BUILT MARK UPS RECEIVED 2-1-91				REVISED PER AC/135-3 REVISED PER CR 7-507 REVISED PER CR 5-208				APPROVED				APPROVED			

B.4 SAMPLING AND LOGGING PROCEDURES

Logging and sampling were performed in the field by the geologist. The following describes sampling equipment and procedures and notations used on the lithologic logs to indicate drilling and sampling modes.

B.4.1 Sampling

In the overburden at about 10-foot intervals, the Converse ring sampler was driven using a down-hole 450-pound slip-jar hammer. The Converse sampler was followed with the standard split spoon sample (SPT) driven with a 140-pound hammer with a 30 inch stroke. Where the Puente Formation was encountered, the borings were sampled using a Pitcher-Barrel and Converse ring sampler at 20-foot intervals.

The most common cause for loss of samples or altering the sample interval was when gravels were encountered at the desired sampling depth. Standard penetration blow count information can often be misleading in this type of formation, and it is difficult to recover an undisturbed sample. Therefore at some locations borings were advanced until drill response and cutting suggested a change in formation.

The following symbols were used on the logs to indicate the type of sample and the drilling mode:

<u>Log Symbol</u>	<u>Sample Type</u>	<u>Type of Sampler</u>
B	Bag	-
J	Jar	Split Spoon
C	Can	Converse Ring
S	Shelby Tube	Pitcher Barrel
Box	Box	Pitcher Barrel, Core Barrel

<u>Log Symbol</u>	<u>Drilling Mode</u>
AD	Auger Drill
RD	Rotary Drill
PB	Pitcher Barrel Sampling
SS	Split Spoon
DR	Converse Drive Sample
C	Coring

B.4.2 Field Classification of Soils

All soil types were classified in the field by the site geologist using the "Unified Soil Classification System". Based on the characteristics of the soil, this system indicates the behavior of the soil as an engineering construction material.* Although particle size distribution estimates were based on volume rather than weight, the field estimates should fall within an acceptable range of accuracy.

Table A-1 shows the correlation of standard penetration information and the physical description of the consistency of clays (hand-specimen) and the compactness of sands used by the field geologists for describing the materials encountered.

TABLE A-1 Correlation of N-Values and Consistency/Compactness of Soil Obtained in the Field

N-Values (blows/foot)	Hand-Specimen (clay only)	Consistency (clay or silt)	Compactness (sand only)	N-Values (blows/foot)
0 - 2	Will squeeze between fingers when hand is closed	Very soft	Very loose	0 - 4
2 - 4	Easily molded by fingers	Soft	Loose	4 - 10
4 - 8	Molded by strong pressure of fingers	Firm	---	---
8 - 16	Dented by strong pressure of fingers	Stiff	Medium dense	10 - 30
16 - 32	Dented only slightly by finger pressure	Very stiff	Dense	30 - 50
32+	Dented only slightly by pencil point	Hard	Very dense	50+

B.4.3 Field Description of the Formations

The description of the formations is subdivided in two parts: lithology and physical condition. The lithologic description consists of:

- ° rock name;
- ° color of wet core (from GSA rock color chart);
- ° mineralogy, textural and structural features; and
- ° any other distinctive features which aid in correlating or interpreting the geology.

The physical condition describes the physical characteristics of the rock believed important for engineering design consideration. The form for the description is as follows:

Physical condition: _____ fractured, minimum _____,
 maximum _____, mostly _____; _____ hardness;
 _____ strength; _____ weathered.

* For a more complete discussion of the Unified Soil Classification System, refer to Corps of Engineers, Technical Memorandum No. 3-357, March 1953, or Department of the Interior, Bureau of Reclamation, Earth Manual, 1963.

Converse Consultants

Boring Log PT-1

THIS LOG IS APPLICABLE ONLY AT THIS LOCATION AND TIME.

CONDITIONS MAY DIFFER AT OTHER LOCATIONS OR TIME.

PROJECT SC RTD 83-1101-11 DATE DRILLED 5/15, 16, 17, 18/83 HOLE NO. PT-1
 LOCATION 194' E/O ALAMEDA 5/0 NACRY AT N edge of Union Stn Paul L GROUND ELEV. 279.1
 DRILLING CONTRACTOR Roscoe Moss LOGGED BY DAN Gillette DEPTH TO GROUND WATER 20.0
 TYPE OF RIG Cable Tool HOLE DIAMETER 14-15 inch HAMMER WEIGHT AND FALL NA 3/11
 SURFACE CONDITIONS Asphalt Parking Lot TOTAL DEPTH 82.5 NO. CORE BOXES NA

DEPTH	CLASS.	FIELD DESCRIPTION	SAMPLE	SPT (6")	DRILL MODE	RUN NO.	CORE REC. %	REMARKS
0.0	AF	0.0-1.5 ARTIFICIAL FILL			PUMP			ASPHALT PAVING Top 3"
2	SP	1.5-60.0 SAND AND GRAVEL			TEST			
4		MODERATE REDDISH			HOLE			
6		BROWN (10R 4/6); contains			NO SAMPLES			
8		50-75% SAND			REQUIRED			
10.0					RD			
12.0					↓			
14.0								
16.0								
18.0								
20.0								
22.0								
24.0								
26.0								
28.0								
30.0								
32.0								
34.0								
36.0								
38.0								
40.0								
42.0								
44.0								
46.0								
48.0								
50.0								
52.0								
54.0								
56.0								
58.0								
60.0								
62.0								
64.0								
66.0								
68.0								
70.0								
72.0								
74.0								
76.0								
78.0								
80.0								
82.0								
84.0								
86.0								
88.0								
90.0								
92.0								
94.0								
96.0								
98.0								
100.0								




PROJECT SC RTD 83-1101-11 DATE DRILLED 3/15, 16, 17, 18/83 HOLE NO. PT-1

DEPTH	CLASS.	FIELD DESCRIPTION	SAMPLE	SPT (bl)	DRILL MODE	RUN NO.	CORE REC. %	REMARKS
10.0	SP	1.5-60.0 SAND AND GRAVEL			RD ↓			
2								
4								
6								
8								
50.0								
2								
4								
6								
8								
60.0		60.0-80.0 SAND AND BOULDERS light gray (N 7); contains 40-80% SAND AND Granitic Boulders						
2								
4								
6								
8								
70.0								
2								
4								
6								
8								
80.0	TP	80.0-82.0 SILTSTONE AND CLAYSTONE OLIVE BLACK (SY 2/1)						
82.0		END BORING 82.5						

SHEET 2 OF 3

SUMMARY BORING NO. PT-1

83-1101-11
 PROJECT SC RTD STATION HOLE YES DATE DRILLED 3/15, 16, 17, 18/83
 OVERBURDEN DEPTH (FT.) 0.0 TO 80.0.
 BEDROCK DEPTH (FT.) 80.0 TO 82.5 (T.D.).
 WATER PRESS. TEST No; INTERVAL(S) — TO —, — TO —.
 GROUND WATER DEPTH (FT.) 20.6 DATE 3/15/83; 19.7 DATE 3/21/83. { RAINFALL 3/17, 3/20
 USE 20.0 AS MEAN
 GAS No; DEPTH FIRST NOTICED —, DATE —.
 E-LOG No.
 DOWN-HOLE SURVEY No.
 CROSS-HOLE SURVEY No.
 PVC CASING (I.D.): 4" No TO —; 3" No TO —; 2" No TO —.
 Steel CASING - CORROSION —.
 GROUND ELEVATION REF. —.



THIS BORING LOG IS BASED ON FIELD CLASSIFICATION AND VISUAL SOIL DESCRIPTION, BUT IS MODIFIED TO INCLUDE RESULTS OF LABORATORY CLASSIFICATION TESTS WHERE AVAILABLE. THIS LOG IS APPLICABLE ONLY AT THIS LOCATION AND TIME. CONDITIONS MAY DIFFER AT OTHER LOCATIONS OR TIME.



Converse Consultants, Inc.
Earth Sciences Associates
Geo/Resource Consultants

BORING LOG SITE #1
PUMP 10/11

Proj: 83-1140-06 Date Drilled 6/18-20/86 Ground Elev. 279
Drill Rig GUS DELTA 4 SCOPE KELLY Logged By MBS Total Depth 88'
Hole Diameter 24" BUCKET Hammer Weight & Fall (NO SAMPLING PERFORMED)

DEPTH	USCS	MATERIAL CLASSIFICATION	SAMPLE	BLOWS (6")	DRILL MODE	REMARKS
0	///	0.0-0.3 ASPHALTIC PAVEMENT	(NO SAMPLING)			0700
0.3-6.0	ML	SANDY SILT w/ DEBR (FIL)	(0-20-80)		24" BUCKET AUGER	FILL RED BRICK LAYER @ 2'
2		SILT WITH FINE SAND, SOME CLAY BINDER, MOIST, LOOSE - MEDIUM DENSE, MISC. DEBR AND RUBBLE DECREASING WITH DEPTH, OLIVE BROWN COLOR			AD ↓	
4						
6	SW	6.0-70.0 GRAVELLY SAND	(35-65-0)			6' ADDED DRILLING FLUID (SUPERCOL (20%) AND WATER MIX) BUILT SOIL BERM TO CONTAIN FLUIDS AT SURFACE
8		FINE TO COARSE SAND WITH GRAVELS, OCCASSIONAL COBBLES TO 5", CLASTS SUBROUNDED TO ROUNDED, RIVER DEPOSITS				
10						DRILLING FLUID IN BORING WASHING OUT MANY OF THE FINES IN EACH BUCKET
12		OCCASSIONAL DRILL RIG CHATTER FROM COBBLES AND GRAVELS				
14	SW					
16	(SW)	OCCASSIONAL COBBLES TO 14" SUBROUNDED TO ROUNDED PREDOMINANTLY GRAVELLY SAND				
18						
20						Sheet 1 of 4

Project 83-1140-06

Date Drilled 6-18-86

Hole No. PUMP WELL

DEPTH	USCS	MATERIAL CLASSIFICATION	SAMPLE	BLOWS (6")	DRILL MODE	REMARKS
20		GRAVELLY SAND WITH OCCASSIONAL COBBLES - CONTINUED	✓		AD ↓	
22		INTERBEDDED LENSES OF COARSE GRAVEL AND SMALL COBBLES ALTERNATING WITH LENSES OF SANDS AND GRAVELLY SANDS				H ₂ S ODOR ↓
24						
26						
28		28' COBBLES WITH POSSIBLE SMALL BOULDERS, DIFFICULT DRILLING, DRILL RIG CHATTER, COBBLES TO 14"				(0900) PLACED NEW TEETH ON 24" BUCKET
30						
32		INTERBEDDED THIN LAYERS OF CLAY AND SILT, OLIVE GRAY TO GRAY, PREDOMINANTLY SAND AND GRAVELLY SANDS WITH COBBLES, AVERAGE COBBLE SIZE 3-6", OCCASSIONAL COBBLES TO 14"	(40-60)			
34						
36						
38						
40		OCCASSIONAL CLAYEY GRAVEL LAYERS VARIABLE THICKNESS, 1-2', OLIVE GRAY COLOR WITH H ₂ S ODOR				
42						
44						Sheet <u>2</u> of <u>4</u>

Project 83-1140-06 Date Drilled 6-18-86 Hole No. SITE #1
PUMP WELL

DEPTH	USCS	MATERIAL CLASSIFICATION	SAMPLE	RUN NO.	DRILL MODE	REMARKS
44	SW	<u>GRAVELLY SANDS - CONTINUED</u>	Ø		AD ↓	(1000)
46		FINE TO COARSE SAND WITH GRAVEL, OCCASSIONAL COBBLES FROM 6"-14", SUBROUNDED TO ROUNDED.				
48		INTERBEDDED THIN LENSES OF CLAY AND SILTY CLAY - VARIABLE, PREDOMINANTLY GRAVELLY SANDS				
50						
52						
54						(1100)
56						HYDRAULIC LEAK DEVELOPING ON DRILL RIG RING GEAR
58						
60		<u>GRAVELLY SANDS - CONTINUED,</u> OCCASSIONAL SMALL COBBLES				
62						
64						
66						(1200)
68						Sheet <u>3</u> of <u>4</u>

Project 83-1140-06

Date Drilled

6-18

Pump Well
Hole No. SITE #1

DEPTH	USCS	MATERIAL CLASSIFICATION	SAMPLE	RUN NO.	DRILL MODE	REMARKS
68		GRAVELLY SANDS - CONTINUED INCREASING FINES			AD ↓	
70	SC CL	70.0 - 74.0 GRAVELLY SAND w/ CLAY MIXTURE OF SAND AND GRAVEL WITH A CLAY / SILTY CLAY BINDER, GRAY, DENSE, H ₂ S ODOOR IN FINER MATERIALS, OCCASSIONAL COBBLES, CLASTS SUBANGULAR TO SUBROUND	(35-4025)			ADDED ±20lbs OF SUPERCOL TO DRILLING FLUID IN BORING. (1320)
72						
74	GW	74.0 - 80.0 COBBLES WITH SANDY GRAVEL SURROUNDED TO ROUNDED COBBLES TO 12", COBBLES GENERALLY 4"-8", SOME SANDY GRAVEL CONSISTING OF MEDIUM TO COARSE SANDS AND GRAVELS, RIVER DEPOSITS, H ₂ S ODOOR GRADATIONAL CONTACT				PLACED NEW TEETH (2nd SET) ON 24" (1400) BUCKET 6-18-86 74'- SHUTDOWN AT 1430, NEED SPECIAL BUCKETS TO REMOVE COBBLES, SECURED SITE 6-20-86 ATTEMPTED TO BREAK THROUGH ROCK IN BOTTOM OF BORING APPEARS TO BE LARGE COBBLE OR BOULDER, USING CHOPPING BUCKET AND LARGE SINGLE TOOTH WITH NO SUCCESS 6-21-86 USING CORING BUCKET TO ADVANCE THROUGH ROCK, HOLE REMAINED OPEN PAST TWO DAYS WITH A MINIMUM OF DRILLING FLUID
76						
78						
80		80.0 - 88' BEDROCK CLAYSTONE / SILTSTONE PUENTE FORMATION OLIVE GRAY SILTSTONE AND CLAYSTONE, MEDIUM PLASTICITY, AQUICLUDE MATERIAL				EASY DRILLING (0900) THROUGH SILTSTONE/ CLAYSTONE (0930)
82						
84						
86						
88		END OF BORING 88' USED 1 BAG SUPERCOL (50lbs) FOR BORING INSTALLED PUMP WELL CASINGS CONSISTING OF 12" AND 2" MACHINE SLOTTED PVC CASINGS FROM APPROX 7' TO 87' 0-7' NON SLOTTED CASING ENDS CAPPED, WELL CENTRALIZERS AT 7' 40', 87', BACKFILLED AROUND SLOTTED CASING WITH (SW) SAND CONSISTING OF IMPORTED DESIGN FILTER MIX FROM 5'-88', MONITORED BACKFILLING WITH TAPE SOUNDINGS				
90						
92						Sheet 4 of 4



THIS LOG IS APPLICABLE ONLY AT THIS LOCATION AND TIME.

CONDITIONS MAY DIFFER AT OTHER LOCATIONS OR TIME.

PROJECT SCRTD - UNION STATION DATE DRILLED 2/4/83 HOLE NO. 5-1 (1983)
 LOCATION NORTHEAST CORNER OF PUBLIC PARKING LOT GROUND ELEV. 279.1'
 DRILLING CONTRACTOR CONVERSE - LAS VEGAS LOGGED BY B. INGRAM DEPTH TO GROUND WATER 20.3
 TYPE OF RIG _____ HOLE DIAMETER 4 1/4" HAMMER WEIGHT AND FALL 320# 36" 2-8-83
 SURFACE CONDITIONS A.C. PARKING AREA TOTAL DEPTH 85.0 NO. CORE BOXES _____

DEPTH	CLASS.	FIELD DESCRIPTION	SAMPLE	SPT (6")	DRILL MODE	RUN NO.	CORE REC. %	REMARKS
0.0	SM	0.0 - 0.4' ASPHALT PAVEMENT			RD			SET UP 7:00 AM
		0.4 - 2.0 FILL - SILTY SAND						BEGIN DRILLING 7:30 AM
		MOTTLED BRN, MOIST, DENSE	1-1		CCI			WEATHER: CLEAR, WARM
		VARIABLE COMPOSITION	12K		DR			
2.0	SM/ML	YOUNG ALLUVIUM			RD			SLIGHTLY POROUS
		2.0 - 4.0 SILTY SAND/SANDY SILT						
4.0	SM	RED-BRN., MOIST, M. DENSE						
		V. FINE SAND - 50-60%						
		SILT - 40-50%						
		4.0 - 8.0 SILTY SAND	1-2		CCI			
			6K		DR			
6.0		GRAY-BRN., MOIST, M. DENSE			RD			
		FINE SAND WITH 20% SILT						
		AND TRACE GRAVEL TO 1"						
8.0	SW	8.0 - 70.0 GRAVELLY SAND						
10.0				5"	100 SPT			
				REFUSAL	RD			
12.0								
14.0								
16.0								
18.0								
20.0								

DEPTH	CLASS.	FIELD DESCRIPTION	SAMPLE	SPT (blows)	DRILL MODE	RUN NO.	CORE REC. %	REMARKS
20.0	SW	8.0-70.0 <u>GRAVELLY SAND</u> (CONTINUED)	50K		CCI DR			DELICATE SAMPLE, DIFFICULTY EXTRUDING - SAMPLE DESTROYED
22.0					RD			
24.0								
26.0								
28.0								
30.0			1-3 45K		CCI DR			POOR RECOVERY, DELICATE SAMPLE 3 RINGS ONLY
32.0					RD			
34.0		INTERMITTENT LENSES OF INCREASED GRAVEL CONTENT						
36.0								
38.0								
40.0			1-4 55K		CCI DR			SULPHUR ODOR IN SAMPLE POOR RECOVERY, 2 RINGS ONLY
42.0					RD			
44.0								SHEET <u>2</u> OF <u>5</u>

PROJECT SCRTD - UNION STATION DATE DRILLED 2/4/83 SITE #1
OBSERVATION WELL #1
HOLE NO. _____

DEPTH	CLASS.	FIELD DESCRIPTION	SAMPLE	SPT (blows)	DRILL MODE	RUN NO.	CORE REC. %	REMARKS
44.0	SW	8.0 - 70.0 <u>GRAVELLY SAND</u> (CONTINUED)			RD			SULPHUR ODOR POOR SAMPLE RECOVERY - 2 RINGS ONLY
			1-5		CCI DR			
46.0			57K		RD			
48.0								
50.0			80K		CCI DR			GRAVELLY SAMPLE - FELL OUT OF SAMPLER
					RD			
52.0								
54.0			1-6		CCI DR			SLIGHT SULPHUR ODOR POOR SAMPLE RECOVERY 5 RINGS ONLY
56.0			100K - 10"		RD			
58.0								
60.0								
62.0								
64.0								
66.0			1-7		CCI DR			SULPHUR ODOR POOR RECOVERY 4 RINGS ONLY
			100K - 10"		RD			
68.0								

DEPTH	CLASS.	FIELD DESCRIPTION	SAMPLE	SPT (blows)	DRILL MODE	RUN NO.	CORE REC. %	REMARKS
68.0	SW	8.0-70.0 <u>GRAVELLY SAND</u> (CONTINUED)			RD			
70.0	B	70.0-79.5 <u>BOULDERS</u> GRANITIC-TYPE CUTTINGS						
72.0								
74.0								
76.0				100K - 0" REFUSAL				ATTEMPTED TO SAMPLE - COULD NOT DRIVE SAMPLER TOO HARD TO SAMPLE
78.0								
80.0	CL/ SC	<u>PUENTE FORMATION</u> 79.5-85.0 <u>SANDY CLAYSTONE</u> <u>AND CLAYEY SANDSTONE</u>	1-8 50K		CCI DR			
82.0		OLIVE-GRAY COLOR, MOIST, FRESH THINLY LAMINATED, BEDDING PLANNES DIP ~ 50° (SAMPLES NOT ORIENTED).			RD			
84.0		FRIABLE. STRENGTH, FRIABLE TO LOW HARDNESS. TENDS TO FRACTURE ALONG LAMINATIONS	1-9 40K		CCI DR			
		END BORING 85.0 FT PIEZOMETER SET TO 85.0' PERFORATED INTERVAL: 45'-85'						

THIS BORING LOG IS BASED ON FIELD CLASSIFICATION AND VISUAL SOIL DESCRIPTION, BUT IS MODIFIED TO INCLUDE RESULTS OF LABORATORY CLASSIFICATION TESTS WHERE AVAILABLE. THIS LOG IS APPLICABLE ONLY AT THIS LOCATION AND TIME. CONDITIONS MAY DIFFER AT OTHER LOCATIONS OR TIME.



Converse Consultants, Inc.
Earth Sciences Associates
Geo/Resource Consultants

BORING LOG SITE #1
 O.W.-4

Proj: 83-1140-06 MRTL PUMP TEST UNION STATION AREA Date Drilled 3/1-3/86 Ground Elev. 281'
 Drill Rig FAILING 1500 ROTARY WASH Logged By Emir Utush Total Depth 24'
 Hole Diameter 4 7/8" Hammer Weight & Fall 250# @ 30"

DEPTH	LOGS	MATERIAL CLASSIFICATION	SAMPLE	RUN NO.	DRILL MODE	REMARKS
0		0-0.5' ASPHALTIC PAVEMENT AND BASE			C	
ML		0.5'-5' <u>SANDY SILT</u> BROWN, MOIST, VERY FINE SAND AND SILT			AD	
2						
4						
5	SP	5'-6' <u>GRAVELLY SAND</u> , BROWN				
6						
GP		6'-13' <u>SANDY GRAVEL</u> LIGHT BROWN AND GRAY, MEDIUM TO COARSE SAND, POORLY GRADED, COBBLES TO 4", SUBROUNDED, MOIST, LOOSE TO MEDIUM DENSE, TRACE FINES			RD	INSTALLED CASING MIXED REVERT
8						
10			C-1		DR	
12					RD	
13	SP	13'-15' <u>SAND</u> YELLOWISH BROWN, GRANITIC FRAGMENTS, MEDIUM TO COARSE, TRACE FINE GRAVEL				
14						
15						
16	GP SP	15'-20' <u>SAND AND GRAVEL</u> YELLOWISH BROWN, MEDIUM TO COARSE SAND, COARSE GRAVEL AND SMALL COBBLES, SAND LENSES, TRACE SILT AND CLAY, POORLY GRADED WITH TRACE FINES	C-2		DR	
18					RD	
20		APPROXIMATE GROUNDWATER LEVEL: 20.0'				Sheet 1 of 4

Project 83-1140-06
MRTZ PUMP TEST

Date Drilled

2/28 - 3/3/86

Hole No.

SITE #1
O.W.-4

DEPTH	USCS	MATERIAL CLASSIFICATION	SAMPLE	BLOWS (6")	DRILL MODE	REMARKS
20	GM	20'-22' <u>SANDY GRAVEL</u> DARK GRAY, SILT, COARSE GRAVEL TO 3"			RD	
			C-3		DR	3/28/86
22	SM	22'-30' <u>SILTY SAND</u> DARK GRAY TO GREENISH GRAY, COARSE SAND			RD	3/3/86 CAVING TO 17.5' REDRILLED BORING
24						
26		COARSE GRAVEL, ANGULAR, MEDIUM SAND, LENSES OF SANDY SILT AND CLAY	C-4		DR	
28					RD	HYDROGEN SULFIDE ODOR ↓
30	SP	30'-34' <u>SAND</u> GRAY, MEDIUM TO COARSE SAND, POORLY GRADED, LITTLE GRAVEL, TRACE SILT.	C-5		DR	
32						
34	GP	34-35.6 <u>SANDY GRAVEL</u>			RD	DRILL RIG CHATTER
36	SP	35.6-40 <u>SAND</u> GRAY, MEDIUM TO COARSE SAND, GRAVEL TO 1.5", TRACE SILT, H ₂ S ODOR	C-6		DR	
38	SP GP				RD	DRILL RIG CHATTER
40	SP	40-45.5 <u>SAND</u> GRAY, MEDIUM TO COARSE SAND			DR	SAMPLES NOT RECOVERED
42	SM SP	SAND SILT LENSE WITH CLAY BINDER	C-7		DR	
44					RD	Sheet 2 of 4

Project 83-1140-06 MRTCL PUMP TEST Date Drilled 3/3/86 Hole No. Site #1 O.W. - 4

DEPTH	USCS	MATERIAL CLASSIFICATION	SAMPLE	RUN NO.	DRILL MODE	REMARKS
44	SP	40'-45.5' <u>SAND</u> - CONTINUED				HYDROGEN SULPHIDE ODOR - CONTINUED
46	GM GP	45.5'-47' <u>SANDY GRAVEL</u> WITH SILT, SUBROUND GRAVEL TO 1/2", GREEN CLAYEY SILT			RD	DRILL RIG CHATTER
48	SP	47'-49' <u>SAND</u> GRAY, MEDIUM TO COARSE	C-8		DR	
50	GP SP GP	49'-51' <u>SANDY GRAVEL</u> TRACE FINES OCCASSIONAL SAND LENSES			RD	DRILL RIG CHATTER
52	GM SM	51'-52.8' <u>SILTY SAND AND GRAVEL</u>				
54	SW	52.8'-57' <u>SAND</u> GRAY, MODERATELY TO POORLY GRADED, MEDIUM TO COARSE SAND, TRACE SILT	C-9		DR	
56					RD	
58	GP	57'-58' <u>SANDY GRAVEL</u>				DRILL RIG CHATTER
60	SW SM	58'-60' <u>SILTY SAND</u> GRAY, FINE TO MEDIUM SAND MODERATELY GRADED, TRACE SILT	C-10		DR	H ₂ S ODOR
62	SM	60'-67.4' <u>SILTY SAND</u> GREENISH-GRAY VERY FINE SAND, TRACE CLAY, POORLY GRADED, DELAYING PLANT MATERIAL			RD	
64			C-11		DR	
66					RD	
68	GM GP	LENSE OF SILTY GRAVEL WITH CLAY 67.4'-70.0' <u>SANDY GRAVEL</u>				DRILL RIG CHATTER Sheet <u>3</u> of <u>4</u>

Project 83-1140-06
MRTL PUMP TEST

Date Drilled

3/3/86

Hole No. SITE #1
O.W. - 4

DEPTH	USCS	MATERIAL CLASSIFICATION	SAMPLE	RUN NO.	DRILL MODE	REMARKS
68	GP	67.4-70' <u>SANDY GRAVEL</u> GRAY, COARSE, TRACE FINES			RD	
70	SW	70'-72' <u>GRAVELLY SAND</u> GRAY, FINE TO COARSE SAND, SOME SILT, GRAVELS TO 3" MODERATELY WELL GRADED, COBBLES	C-12		DR	SMALL COBBLE IN SAMPLER TIP
72	GP	72'-78' <u>SANDY GRAVEL</u> GRAY, COARSE, COBBLES AND BOULDERS, TRACE FINES			RD	DRILL RIG CHATTER
74						
76						
78	SM	78'-79' <u>SANDY SILT</u> BROWNISH GREEN, POORLY GRADED, TRANSITION ZONE				
80	TP	79'-84' <u>BEDROCK - PUENTE FORMATION</u> <u>SILTSTONE / CLAYSTONE</u> OLIVE GRAY, STIFF, TRACE VERY FINE SAND				
82						
84		END OF BORING 84' - INSTALLED PIEZOMETER 0'-10' NON SLOTTED 2" PVC CASING 10'-79' MACHINE SLOTTED 2" CASING, 0.20" SLOTS, END CAPPED - FLUSHED CASING AND BORING WITH CLEAN WATER (\pm 1000 GALLONS) - BACKFILLED BORING WITH #3 MONTEREY SAND, 12-100# SACS - SEALED TOP 5' WITH CONCRETE GROUT AND BENTONITE, INSTALLED 2.5' CASING AND WELL COVER.				
86						
88						
90						
92						

Sheet 4 of 4

THIS BORING LOG IS BASED ON FIELD CLASSIFICATION AND VISUAL SOIL DESCRIPTION, BUT IS MODIFIED TO INCLUDE RESULTS OF LABORATORY CLASSIFICATION TESTS WHERE AVAILABLE. THIS LOG IS APPLICABLE ONLY AT THIS LOCATION AND TIME. CONDITIONS MAY DIFFER AT OTHER LOCATIONS OR TIME.



Converse Consultants, Inc.
Earth Sciences Associates
Geo/Resource Consultants

SITE #2
BORING LOG PUMP WELL

83-1140-06
MRTL PUMP TEST
Proj: UNION STATION AREA Date Drilled 3/3-6/86 Ground Elev. 279.5
Drill Rig INGERSOLL RAND TH60 Logged By MARK SCHLUTER Total Depth _____
Hole Diameter 10" REAMED TO 24" Hammer Weight & Fall (NO SAMPLING PERFORMED)

DEPTH	USCS	MATERIAL CLASSIFICATION	SAMPLE	BLOWS (6")	DRILL MODE	REMARKS
0		0.0 - 9.0 <u>FILL</u> GRAVELLY SAND, SILT, AND SANDY SILT, TRACE AMOUNT OF DEBRI AND RUBBLE INCLUDING FRAGMENTS OF CONCRETE, BRICK, METAL	(NO SAMPLING)			STARTED DRILLING AT (0945) 3-3-86 3/3/86 AIR-LIFTED CUTTING WITH DRILL RIG COMPRESSOR FROM 0-10' 3/3/86 (1240) STARTED REAMING BORING WITH MODIFIED 24" DRILL BIT AIR ROTARY 3/4/86 (0730) DRILLED OUT HOLE WITH 12" TRI-CONE BIT TO CLEAN OUT FALLEN GRAVELS AND COBBLES FROM 24" REAMING DRILLED TO 110' WITH 12" BIT. (1100)
2						
4						
6						
8						
10		9.0 - 85' <u>GRAVELLY SAND</u> MEDIUM TO COARSE SAND, SOME GRAVELS, TRACE SILT BORING LOGGED BASED ON ROTARY WASH CUTTING, GRAVELS AND COBBLES BROKEN UP DURING DRILLING.				3/3/86 DRILLED TO 10', SET UP FOR 10" ROTARY WASH DRILLING 3-3-86 ATTACHED 10" TRI-CONE BIT TO 10' LONG REAMING SECTION AND STARTED ROTARY WASH DRILLING OF PILOT HOLE. ROTARY WASH RD DRILLED 10" PILOT HOLE TO 100' 3-3-86 ADDED SUPERCOL GUAR GUM TO DRILLING FLUID.
12						
14						
16		16' - DRILL RIG CHATTER GRAVELS AND COBBLES PROGRESS SLOWED				3/3/86 (1340) AT 16" WITH 24" MODIFIED DRILL BIT
18						
20						

83-1140-06
MRTC PUMP TEST
Project UNION STATION AREA

Date Drilled

3/3-6/86

SITE #2
Hole No. PUMP WELL

DEPTH	USCS	MATERIAL CLASSIFICATION	SAMPLE	BLOWS 16"	DRILL MODE	REMARKS
20		9.0-85' GRAVELLY SANDS — CONTINUED —	(NO SAMPLING)		RD ↓	3/3/86 (1030) AT 20' WITH 10" TRI-CONE BIT.
22						
24						
26		25' - DRILL RIG CHATTER - 10" BIT COBBLES AND GRAVELS				3/3/86 (1040) AT 25' WITH 10" TRI-CONE BIT
28						3/3/86 (1510) AT 28' WITH MODIFIED 24" BIT, GRAVELS AND COBBLES FALLING INTO PILOT HOLE, PULLED 24" MODIFIED BIT OUT OF HOLE AND ATTACHED 12" TRI-CONE BIT TO CLEAN OUT PILOT HOLE
30						
32						
34						
36						
38						
40						
42						
44						

83-1140-06
MRTCL PUMP TEST
Project UNION STATION AREA

Date Drilled

3/3-6/86

SITE #2
Hole No. PUMP WELL

DEPTH	USCS	MATERIAL CLASSIFICATION	SAMPLE	RUN NO.	DRILL MODE	REMARKS
44		9.0-85' GRAVELLY SANDS - CONTINUED -	(NO SAMPLING)		RD ↓	
46						
48						
50						3/4/86 (1430) AT 50' WITH 24" MODIFIED DRILL BIT
52						
54						
56						
58						
60						3/5/86 (0820) AT 60', STARTED DRILLING WITH NEW 24" MODIFIED DRILL BIT, 2ND BIT USED. GRAVELS AND COBBLES FALLING INTO CLEANED OUT PILOT HOLE AS 24" BIT IS ADVANCED
62						
64						
66						
68						

83-1140-06
MRTL PUMP TEST
Project UNION STATION AREA

Date Drilled

3/3-6/86

Site #2
Hole No. PUMP WELL

DEPTH	USCS	MATERIAL CLASSIFICATION	SAMPLE	RUN NO.	DRILL MODE	REMARKS
68		9.0 - 85' <u>GRAVELLY SANDS</u> - CONTINUED -	(NO SAMPLING)			
70					RD ↓	3/4/86 (1630) AT 70' WITH MODIFIED DRILL BIT, WELDED WINGS WORN DOWN TO NUBS (14") PULLED RODS AND BIT TO ATTACH SECOND MODIFIED DRILL BIT ON 3/5/86 A.M. (SEE 3/5/86 AT 60')
72						
74						
76						
78						
80						3/3/86 (1145) AT 80' WITH PILOT HOLE USING 10" TRI-CONE BIT.
82						3/5/86 (1400) AT 80' WITH 2ND 24" MODIFIED DRILL BIT, PROGRESSES SLOW, GRAVELS AND COBBLES ACCUMULATING IN PILOT BORING
84						
86		85' - 110' <u>BEDROCK</u> <u>PUNTE FORMATION</u> <u>SILTSTONE / CLAYSTONE</u> OLIVE GRAY COLOR				
88						3/5/86 (1450) AT 88' WITH WORN 20" MODIFIED BIT, DRILLING MUCH EASIER IN BEDROCK, STILL SOME DRILL RIG CHATTER FROM GRAVELS AND COBBLES THAT FELL INTO PILOT BORING
90						
92						

Sheet 4 of 5

Project 83-1140-06
MRTL PUMP TEST
UNION STATION AREA

Date Drilled

3/3-6/86

Site #2
Hole No. PUMP WELL

DEPTH	USCS	MATERIAL CLASSIFICATION	SAMPLE	RUN NO.	DRILL MODE	REMARKS
92		85'-110' <u>BEDROCK</u> <u>PUENTE FORMATION</u> SILTSTONE / CLAYSTONE - CONTINUED -	(NO SAMPLING)		RD ↓	
94						
96						
98						
100						-3/3/86 (1220) COMPLETED 10" PILOT HOLE TO 100', REMOVED DRILL RODS AND BIT AND STARTED REAMING 24" HOLE, USING 14.75" TRH- CONE BIT MODIFIED WITH WELDED WINGS TO 24"
102						
104						
106						
108						
110		END OF BORING 110' 4/5/86 (1500) FLUSHED BORING WITH DRILLING FLUID TO REMOVE CUTTINGS (1535) - ADDED FRESH WATER TO THIN DOWN SUPERCOL GUAR GUM DRILLING FLUID. - CONTINUED TO FLUSH BORING WITH CLEAN WATER FROM WATER TRUCK - BOTTOM OF BORING SOUNDED @ 87' WITH TAP (SOFT BOTTOM) (1605) INSTALLED 12" AND 2" MACHINE SLOTTED CASING INTO BORING 0-7' NON SLOTTED 7'-87' MACHINE SLOTTED BACKFILLED AROUND CASING WITH FILTER MIXED SAND, REPEATEDLY SOUNDED DEPTH TO SAND DURING BACKFILL 4/6/86 (0800) STARTED "AIR-LIFT" DEVELOPMENT OF PUMP WELL				3/4/86 (1100) COMPLETED PILOT HOLE CLEAN-OUT WITH 12" BIT TO 110', PULLED OUT AND ATTACHED 24" MODIFIED BIT 3/5/86 (1500) AT 110' WITH WORN 20" MODIFIED BIT, HEAVY DRILL RIG CHATTER - GRAVELS, COBBLES ACCUMULATED IN PILOT HOLE, LAST 20' - EASIER DRILLING IN BEDROCK
112						
114						
116						Sheet 5 of 5

THIS BORING LOG IS BASED ON FIELD CLASSIFICATION AND VISUAL SOIL DESCRIPTION, BUT IS MODIFIED TO INCLUDE RESULTS OF LABORATORY CLASSIFICATION TESTS WHERE AVAILABLE. THIS LOG IS APPLICABLE ONLY AT THIS LOCATION AND TIME. CONDITIONS MAY DIFFER AT OTHER LOCATIONS OR TIME.




Converse Consultants, Inc.
Earth Sciences Associates
Geo/Resource Consultants

BORING LOG ^{SITE #2}
OW-1

83-1140-06
 Proj: MRTC PUMP TEST
UNION STATION AREA Date Drilled 2/24-25/86 Ground Elev. 279'
 Drill Rig FAILING 1500 ROTARY WASH Logged By EMIR UTUSH Total Depth 94'
 Hole Diameter 4 7/8" Hammer Weight & Fall 250# @ 30"

DEPTH	USCS	MATERIAL CLASSIFICATION	SAMPLE	RUN NO.	DRILL MODE	REMARKS
0	FILL (Af)	0-2' <u>GRAVELY SAND - (FILL)</u>			AD/C	FILL
2	FILL (Af)	2-7' <u>SILT - (FILL)</u> , DARK BROWN GRADING INTO OLIVE GREEN, LITTLE FINE-TO-MEDIUM GRAVEL AND SAND				PIECE OF METAL AT 3.5'
4						
6						
8	SM/ML	7-9' <u>SANDY SILT</u> , LIGHT OLIVE BROWN, SOME GRAVEL AND FINE SAND. GRADATIONAL FILL CONTACT.				3" SMALL COBBLE
10	SP/GP	9'-28' <u>GRAVELY SAND / SANDY GRAVEL</u> ANGULAR TO SUBROUNDED GRAVEL WITH MEDIUM TO COARSE SAND, TRACE FINES	C-1		DR	
12	SP/GP	COARSE SAND AND GRAVEL			RD	SET 12.5' OF CASING ADDED 1/2 BAG OF JOHNSON REVERT STRONG DRILL RIG CHATTER AT 11'
14						
16	SP/GP	MEDIUM TO COARSE SAND LENSE				DRILL RIG CHATTER STOPPED FROM 16'-17'
18						
20						Sheet <u>1</u> of <u>5</u>

Project 83-1140-06 MZTC PUMP TEST Date Drilled 2-24-86 Hole No. OW-1 SITE #2

DEPTH	USCS	MATERIAL CLASSIFICATION	SAMPLE	BLOWS (6")	DRILL MODE	REMARKS
20	GP	<u>SANDY GRAVEL - (CONTINUED)</u> WHITE AND GRAY COBBLES WITH COARSE SAND, TRACE SILT AND CLAY	C-2		DR	
22					RD	SOFT ZONE @ 22'
24			C-3		DR	
26	GP SP	 GROUND WATER AT 25.7' LEVEL MEASURED @ 1100 A.M. ON 3/3/86				VARIABLE DRILL RIG CHATTER ↓
28	SM ML	28'-30' FINE SAND AND SILT TRACE CLAY, SLIGHTLY DAMP, DARK GREEN, TRACE ORGANICS	C-4		DR	
30	GP	30'-31' <u>SANDY GRAVEL</u>			RD	DRILL RIG CHATTER AT 30'
32	ML AND GP	31'-36' <u>SILT AND SANDY GRAVEL</u> INTERBEDDED LENSES OF SILT AND SANDY GRAVEL, SILT - DARK GREEN, TRACE CLAY SANDY GRAVEL - COARSE GRAVEL AND SAND, LITTLE FINES IN SANDS, SILT SEAMS	C-5		DR	2" COBBLE FRAGMENT IN DRIVE SAMPLE
34					RD	
36	GP	36'-39.5' <u>SANDY GRAVEL</u> SAND AND GRAVEL WITH COBBLES AND BOULDERS				STRONG DRILL RIG CHATTER AT 36' VERY STRONG DRILL RIG CHATTER AT 37' - BOULDER?
38			NO REMARKS		DR	
40	ML	39.5'-40.5' <u>SILT (?) SOFT ZONE</u>			RD	VERY STRONG DRILL RIG CHATTER 39.5'
42	GP	40.5'-43.5' <u>SANDY GRAVEL</u> SAND AND GRAVEL WITH COBBLES AND BOULDERS				INCREASING RESISTANCE GASTEL METER READING - NO COMBUSTIBLE GAS AT SURFACE ABOVE DRILLING FLUID
44	GP	43.5'-45.5' <u>SANDY GRAVEL</u>	C-7		DR	Sheet <u>2</u> of <u>5</u>

Project 83-1140-06 MRTZ PUMP TEST Date Drilled 2-24-86 Hole No. 062-1 SITE #2

DEPTH	USCS	MATERIAL CLASSIFICATION	SAMPLE	RUN NO.	DRILL MODE	REMARKS
44	GP	<u>SANDY GRAVEL - CONTINUED</u> MOTTLED WHITE AND GRAY, CLASTS SUBANGULAR TO SUBROUND, TRACE SILT WITH CLAY			DR	
46	SP	<u>45.5'-49.5' GRAVELLY SAND</u> LIGHT GRAY AND WHITE, COARSE SAND, TRACE SILT, SOME GRAVEL			RD	STRONG DRILL RIG CHATTER AT 45'
48						
50	SP	<u>49.5'-52.5' SAND</u> GRAY, LITTLE GRAVEL, TRACE SILT, MEDIUM TO COARSE SAND	C-8		DR	
52					RD	
54	SP	<u>52.5'-57.5' SAND</u> SAND WITH INTERBEDDED SANDY GRAVEL LENSES				VARIABLE DRILL RIG CHATTER AT: 52.5', 53.5', 54'
56	GP	MEDIUM TO COARSE SAND, CLASTS SUBANGULAR TO SUB-ROUNDED	C-9		DR	
58	GP	<u>57.5'-61.5' GRAVEL</u> GRAVELS WITH SOME MEDIUM TO COARSE SAND			RD	DRILL RIG CHATTER AT 57.5' AND 60'
60						
62	SM/ML	<u>61.5'-69.5' SAND AND SILT</u> DARK GREEN, FINE SAND AND SILT, TRACE CLAY, TRACE SMALL GRAVEL, H ₂ S ODOR IN SAMPLE	C-10		DR	LOST DRILLING FLUID CIRCULATION SMELL OF HYDROGEN SULPHIDE IN SAMPLE
64					RD	CAVING - BORING CAVED TO 7'
66						
68						

Project 83-1140-06 MRTL PUMP TEST Date Drilled 2/24-25/86 Hole No. Site #2 OW-1

DEPTH	USCS	MATERIAL CLASSIFICATION	SAMPLE	RUN NO.	DRILL MODE	REMARKS
68	SP ML	SAND AND SILT - CONTINUED			RD	
70	GP	69.5'-71' <u>SAND</u> GRAY, MEDIUM COARSE, TRACE SMALL GRAVEL	C-11		DR	
72	GP	71'-76.5' <u>SANDY GRAVEL</u>			RD	DRILL RIG CHATTER AT 71'
74		(SP) SAND LENSE AT 74'				DECREASED DRILL RIG CHATTER AT 74' AND 75.5'
76		(SP) SAND LENSE AT 76'				
78	GP	76.5'-77.5' <u>GRAVELLY SAND</u>				DRILL RIG CHATTER AT 77.5'
80		(SP) AND (GP) SAND AND GRAVEL LENSES				
82	GM GP	80.5'-84.5' <u>SANDY GRAVEL</u> FINE TO COARSE SAND, SUBGROUNDED FINE TO MEDIUM GRAVEL, TRACE BLuish GRAY SILT AND CLAY	C-12		DR	2-24-86 2-25-86
84		GRADATIONAL CONTACT			RD	
86	TP	84.5'-94.0' <u>BEDROCK-SILTSTONE/CLAYSTONE</u> PUENTE FORMATION, OLIVE GREEN, SOFT, MOIST, INTERBEDDED FINE SAND LAYERS				
88		VERY FINE SAND INTERBEDS THINLY BEDDED TO LAMINATED DIPPING AT APPROX. 40°	NO RECOVERY		DR	
90		STIFF TO VERY STIFF			RD	
92			C-14		DR	ADDED 1 GAL (25#) OF REVERT Sheet <u>4</u> of <u>5</u>

Project 83-1140-06
MRTZ PUMP TEST

Date Drilled

2/25/86

Site #2
Hole No. OW-1

DEPTH	USCS	MATERIAL CLASSIFICATION	SAMPLE	RUN NO.	DRILL MODE	REMARKS
92	TP	<u>BEDROCK - SILTSTONE / CLAYSTONE</u> <u>CONTINUED</u> PUENTE FORMATION			RD	
94		END OF BORING 94.0' - FLUSHED BORING - INSTALLED PIEZOMETER 0'-10' NON SLOTTED 2" CASING 10'-89' MACHINE SLOTTED 2" CASING, 0.20" SLOTS, END CAPPED BACKFILLED BORING WITH #3 MONTEREY SAND, 6-100# SACS - FLUSHED PIEZOMETER WITH FRESH WATER. - INSTALLED WELL COVER AND SEALED TOP 4.5' WITH CONCRETE GROUT AND BENTONITE.				
96						
98						
100						
102						
104						
106						
108						
110						
112						
114						
116						

THIS BORING LOG IS BASED ON FIELD CLASSIFICATION AND VISUAL SOIL DESCRIPTION, BUT IS MODIFIED TO INCLUDE RESULTS OF LABORATORY CLASSIFICATION TESTS WHERE AVAILABLE. THIS LOG IS APPLICABLE ONLY AT THIS LOCATION AND TIME. CONDITIONS MAY DIFFER AT OTHER LOCATIONS OR TIME.



Converse Consultants, Inc.
Earth Sciences Associates
Geo/Resource Consultants

SITE #2

BORING LOG O.W.-2

Proj: 83-1140-06 MRTC PUMP TEST UNION STATION AREA Date Drilled 2/25-27/86 Ground Elev. 280'
 Drill Rig FAIRING 1500 ROTARY WASH Logged By EMIR UTUSH Total Depth 84'
 Hole Diameter 4 7/8" Hammer Weight & Fall 250* @ 30"

DEPTH	LOGS	MATERIAL CLASSIFICATION	SAMPLE	RUN NO.	DRILL MODE	REMARKS
0	FILL (AF)	0-4' SAND AND GRAVEL - (FILL) WITH DARK BROWN SILT			AD/C	FILL
2						
4	FILL (AF)	4-7' SILT - (FILL) BROWN, DRY, LOOSE				PIECES OF METAL, NAILS, GLASS AND SLAG-LIKE MATERIAL AT 4'
6		SLIGHTLY DAMP LITTLE CLAY BINDER AT 7'				LARGE BENT METAL SPIKE AT 5'
8	ML	7-8' SILT - BROWN, SLIGHTLY DAMP, TRACE CLAY, SOFT				
10	SP	8-10' SAND - LIGHT BROWN, DAMP, LOOSE TO MEDIUM DENSE, LITTLE FINE GRAVEL, POORLY GRADED	C-1		DR	SET 11.5' OF CASING ADDED JOHNSON REVERT
12	GP	10-16' SANDY GRAVEL BROWN TO LIGHT GRAY. GRAVEL - COARSE, SUB-ROUNDED SAND - POORLY GRADED WITH LITTLE SILT			RD	
14		LARGE GRAVEL AT 13'				
16			C-2		DR	POOR RECOVERY
18	SP	16'-20.5' GRAVELLY SAND LIGHT BROWN TO SPECKLED YELLOW/GREY, WET, MEDIUM DENSE, POORLY GRADED MEDIUM TO COARSE SAND, MEDIUM GRAVEL TO 3/4", TRACE SILT			RD	
20						Sheet 1 of 4

Project 83-1140-06
MRTC PUMP TEST

Date Drilled

2/25/86

Hole No.

 SITE #2
O.W.-2

DEPTH	USCS	MATERIAL CLASSIFICATION	SAMPLE	BLOWS (6")	DRILL MODE	REMARKS
20	SP	GRAVELLY SAND				
		20.5'-24' <u>SANDY GRAVEL</u>				
	GP	LIGHT BROWN WITH GRAY AND YELLOW,				
22	GM	MEDIUM TO COARSE GRAVEL,				
		POORLY GRADED SAND, LITTLE SILT				
	ML	25' THIN CLAY SILT SEAM, SOME				
		SAND				
24	GP					
	SM	24'-26.8' <u>SILTY SAND</u>				
		BROWN, MEDIUM DENSE, WET,				
		SOME GRAVEL, TRACE CLAY	C-3		DR	GROUNDWATER AT 25.9'
26	SP	26.8'-30.2' <u>SAND</u>				LEVEL MEASURED @ 1158 A.M. ON 3/3/86
		GRAY, MEDIUM TO COARSE SAND,				
		SOME GRAVEL, TRACE SILT,				
28		POORLY GRADED				CAVING FROM 26' TO 31'
		SLEIGHT INCREASE IN SILT			RD	
30	GP	30.2'-30.7' <u>GRAVEL</u>				INCREASED DRILL RIG CHATTER
32	GM	30.7'-37'				SMOOTH
34		<u>SANDY GRAVEL</u>				
		WITH SILT, GRAY, LOOSE TO	C-4		DR	
	GP	MEDIUM DENSE				DRILL RIG CHATTER AT 35'
36	GM					
38	GP	37'-45' <u>SANDY GRAVEL</u>				
		COARSE SAND AND GRAVEL				
		COBBLE AND BOULDER ZONES			RD	STRONG DRILL CHATTER AT 38'
40						
		LENSES OF COBBLES AND BOULDERS				
		- VARIABLE -				STRONG, DRILL CHATTER AT 41'
42						
						STRONG DRILL CHATTER AT 42'
44						Sheet <u>2</u> of <u>4</u>

Project 83-1140-06 MRTZ PUMP TEST Date Drilled 2/25-26/86 Hole No. Site #2 O.W.-2

DEPTH	USCS	MATERIAL CLASSIFICATION	SAMPLE	RUN NO.	DRILL MODE	REMARKS
44	GP	<u>SANDY GRAVEL</u>			RD	
	SP	45'-46' <u>GRAVELLY SAND</u>				
46	GP	46-51.4' <u>GRAVEL</u> GRAY, WITH SAND AND SOME SILT, COARSE GRAVEL TO COBBLE SIZE CLASTS, COARSE SAND	C-5		DR	
48	GP/SP					
50		<u>SANDY GRAVEL</u> COARSE SAND, TRACE FINES			RD	
52	SP	51.4'-56' <u>GRAVELLY SAND</u> GRAY, COARSE SAND, POORLY GRADED, LITTLE SILT				
54		<u>H₂S ODOR IN SAMPLE</u>				
56	SP	56'-58' <u>SAND</u> GRAY, MEDIUM DENSE, FINE TO MEDIUM SAND, TRACE SILT <u>H₂S ODOR IN SAMPLE</u>	C-6		DR	
58	GP	58'-61' <u>SANDY GRAVEL</u> GRAY				
60						
62	SM/ML	61'-70' <u>SAND AND SILT</u> DARK GREEN TO GRAY, LOOSE TO MEDIUM DENSE, SOME CLAY AND GRAVEL, VERY FINE SAND, TRACE ORGANICS (PLANT ROOTLETS)			RD	
64						
66			C-7		DR	
68					RD	

Sheet 3 of 4

Project 83-1140-06 MRTC PUMP TEST Date Drilled 2/26-27/86 Hole No. Site#2 O.W.-2

DEPTH	USCS	MATERIAL CLASSIFICATION	SAMPLE	RUN NO.	DRILL MODE	REMARKS
68	ML	<u>SAND AND SILT</u> - CONTINUED -				
70	SP	70'-71' <u>SAND</u> MEDIUM COARSE, LITTLE GRAVEL			RD	
72	GP	71'-72' <u>SANDY GRAVEL</u> COARSE SAND AND GRAVEL, COBBLES AND BOULDERS				STRONG DRILL RIG CHATTER
74						
76			X		DR	NO RECOVERY
78					RD	STRONG DRILL RIG CHATTER
80						LOST DRILLING FLUID CIRCULATION MIXED IN ADDITIONAL REVERT CAVING UP TO 32' ADDING ADDITIONAL REVERT
82	GM GP	81'-82' <u>SANDY GRAVEL</u> WITH SILT, LUMPS OF DARK GRAY/GREEN SILT WITH CLAY BINDER				82' LOSING FLUID ADDED TOTAL 3 SACS OF REVERT, DRILLED TO 84' AND INSTALLED 2" CASING
84	GP	82'-84' <u>SANDY GRAVEL</u> COARSE SAND AND GRAVEL, LITTLE FINES				
86		END OF BORING 84.0 (BORING CLOSE TO BEDROCK) -INSTALLED PIEZOMETER 0-12' NON SLOTTED 2" CASING 12'-81' MACHINE SLOTTED 2" CASING 0.20" SLOTS, END CAPPED				
88		-FLUSHED BORING AND CASING WITH CLEAN WATER (±400 GALLONS), CONTINUED TO FLUSH, WATER NOT RETURNING TO SURFACE - LOST TO FORMATION, PUMPED DOWN ADDITIONAL WATER AND 1 GALLON OF BLEACH (±800 GALLONS)				
90		- BACKFILLED BORING WITH #3 MONTEREY SAND; 8 - 100# SACS - INSTALLED WELL COVER AND SEALED TOP 5' WITH CONCRETE GROUT AND BETONITE,				
92						Sheet <u>4</u> of <u>4</u>

THIS BORING LOG IS BASED ON FIELD CLASSIFICATION AND VISUAL SOIL DESCRIPTION, BUT IS MODIFIED TO INCLUDE RESULTS OF LABORATORY CLASSIFICATION TESTS WHERE AVAILABLE. THIS LOG IS APPLICABLE ONLY AT THIS LOCATION AND TIME. CONDITIONS MAY DIFFER AT OTHER LOCATIONS OR TIME.



Converse Consultants, Inc.
Earth Sciences Associates
Geo/Resource Consultants

SITE #2

BORING LOG O.W.-3

83-114D-06
MRTEL PUMP TEST
Proj: UNION STATION AREA Date Drilled 2/28-3/1/86 Ground Elev. 280'
Drill Rig FAILING 1500 ROTARY WASH Logged By EMIR UTUSH Total Depth 85'
Hole Diameter 4 7/8" Hammer Weight & Fall 250# @ 30"

DEPTH	USCS	MATERIAL CLASSIFICATION	SAMPLE	RUN NO.	DRILL MODE	REMARKS
0	FILL (AF)	0.0'-8' <u>SILTY SAND</u> BROWN, DRY, LOOSE, BROKEN BRICK FRAGMENTS, TOP 6" ASPHALT AND BASE SUBGRADE			AD	CORED THROUGH ASPHALTIC PAVEMENT FILL
2						
4						
6						
8	ML	8'-11' <u>SANDY SILT</u> SILT WITH VERY FINE SAND, BROWN, LOOSE, TRACE CLAY, POSSIBLE FILL?	C-1		DR	
10					RD	SET CASING AND ADDED REVERT TO DRIVING FLUID
12	GP	11'-17' <u>SANDY GRAVEL</u> LIGHT GRAY TO LIGHT BROWN, GRANITIC CLASTS, POORLY GRADED, CLASTS SUBANGULAR TO SUBROUND				DRILL RIG CHATTER
14						
16						
18	SP	17-18.4 <u>SAND</u> GRAY TO LIGHT BROWN, LOOSE, WITH SILT AND GRAVEL	C-2		DR	
	GP	INCREASING GRAVELS			RD	DRILL RIG CHATTER AT 19'
20	GM	18.4-23 <u>SILTY GRAVEL</u>				Sheet <u>1</u> of <u>4</u>

Project 83-1140-06
MRTZ PUMP TEST

Date Drilled

2/28/86

Hole No. SITE #2
O.W.-3

DEPTH	USCS	MATERIAL CLASSIFICATION	SAMPLE	BLOWS (6")	DRILL MODE	REMARKS
20	GM	18.4'-23' <u>SILTY SAND AND GRAVEL</u>			RD	
	SM	SILT WITH COARSE SAND AND GRAVEL, LUMPS OF GRAY/GREEN CLAY	C-3		DR	
22					RD	DRILL RIG CHATTER @ 22'
24	GP	23'-26' <u>SANDY GRAVEL</u>	C-4		DR	
		SAND AND GRAVEL, POORLY GRADED, COARSE, TRACE SILT				
26	SP	26'-29' <u>GRAVELLY SAND</u>			RD	GROUNDWATER ▼ AT 26.8' — LEVEL MEASURED AT 1050 A.M. ON 3/3/86
		COARSE, POORLY GRADED, LITTLE SILT				
30	GP	29'-30.6' <u>SANDY GRAVEL</u>				DRILL RIG CHATTER AT 29'
		COARSE GRAVEL, SUBANGULAR TO SUBROUNDED				
32	SP	30.6'-31' <u>SILT GRAVEL WITH TRACE CLAY</u>				
		31'-33.5' <u>SAND</u>	C-5		DR	
		GRAY, MODERATELY GRADED, MEDIUM TO COARSE SAND, SOME FINE SAND, TRACE SILT				
34	GM	33.5'-43.0' <u>SANDY GRAVEL</u>			RD	ADDING ADDITIONAL REVERT TO THICKEN FLUID. ROCK FRAGMENTS AND GRAVELS ACCUMULATING IN BOTTOM OF BORING, ATTEMPTING TO FLUSH WITH THICKENED FLUID DRILL RIG CHATTER
		WHITE TO GRAY WITH CLAYEY SILT INCLUSIONS, SOME SILT, POORLY GRADED COARSE SAND				
40			C-6		DR	
		GRAY, COARSE GRAVEL TO 3", COARSE SAND WITH SILT, DENSE			RD	
44	GP	43'-47' <u>SANDY GRAVEL</u>				DRILL RIG CHATTER AT 43'
		SOME SILT, COARSE GRAVEL				Sheet <u>2</u> of <u>4</u>

Project 83-1140-06 MRTC PUMP TEST Date Drilled 2/28/86 Hole No. SITE #2 O.W.-3

DEPTH	USCS	MATERIAL CLASSIFICATION	SAMPLE	RUN NO.	DRILL MODE	REMARKS
44		43'-47' <u>SANDY GRAVEL</u> SOME SILT, COARSE GRAVEL				
46	GP				RD	DRILL RIG CHATTER
48	GM	47'-49' <u>SANDY GRAVEL</u> WITH SILT, GREEN CLAYED SILT				
50	SP SM	49'-52' <u>SAND</u> GRAY, DENSE, SOME SILT AND GRAVEL, COARSE TO MEDIUM COARSE SAND, POORLY GRADED.	C-7		DR	
52	GP SP	52'-61' <u>SANDY GRAVEL</u> MIXTURE OF SAND AND GRAVEL, TRACES FINES, OCCASSIONAL LENSES OF GRAVELS AND COBBLES			RD	OCCASSIONAL DRILL RIG CHATTER
54						54'- STRONG DRILL RIG CHATTER
56						
58						VARIABLE DRILL RIG CHATTER ↓
60						
62	SP	61'-64' <u>SAND</u> GRAY, MEDIUM COARSE SAND, SOME GRAVEL, TRACE FINES	C-8		DR	LOOSE SAMPLE
64	GP	OCCASSIONAL GRAVEL/COBBLE LENSES			RD	
66	SM ML	64'-69' <u>SAND AND SILT</u> DARK GRAYISH GREEN, FINE SAND AND SILT, POORLY GRADED, TRACE ORGANICS (PLANT ROOTS), TRACE GRAVEL.	C-9		DR	
68					RD	

Project 83-1140-06 MRTC PUMP TEST Date Drilled 2/28-3/1/86 Hole No. Site #2 O.W.-3

DEPTH	USCS	MATERIAL CLASSIFICATION	SAMPLE	RUN NO.	DRILL MODE	REMARKS
68	SM ML	64'-69' <u>SAND AND SILT</u> DARK GREEN TO GRAY, FINE SAND, LITTLE GRAVEL				
70	GP	69'-71' <u>SANDY GRAVEL</u>			RD	DRILL RIG CHATTER
72	SP	71'-74' <u>SAND</u> GRAY, COARSE SAND LITTLE GRAVEL				
74	GP	74'-84' <u>GRAVEL</u> COARSE GRAVEL TO 2", WITH MEDIUM TO COARSE SAND, TRACE SILT, GRAY COLOR	C-10		DR	DRILL RIG CHATTER ↓
76						STARTED LOSING DRILLING FLUID TO FORMATION, MIXING IN ADDITIONAL REVERT
78					RD	2/28/86 3/1/86
80		<u>SANDY GRAVEL</u> SUBROUND TO WELL ROUNDED PEBBLES				CAVING TO 72', MIXED ADDITIONAL REVERT, BOTTOM OF BORING CAVING
82						
84	TP	84'-85' BEDROCK-PUENTE FORMATION OLIVE GRAY SILTSTONE/CLAYSTONE				DRILLED TO 85' AND INSTALLED CASING
86		END OF BORING 85' -INSTALLED PIEZOMETER 0-10' NON SLOTTED 2" PVC CASING 10'-78.5' MACHINE SLOTTED 2" CASING 0.20" SLOTS, END CAPPED				
88		-FLUSHED CASING AND BORING WITH CLEAN WATER (±1800 GALLONS WITH ±650 GALLONS RETURNING) RETURN FLUID REDUCED AS BORING WAS FLUSHED. ADDED 1/2 QUART BLEACH.				
90		-BACKFILLED BORING WITH #3 MONTEREY SAND				
92		-INSTALLED WELL COVER AND CASING TOP 2.5', SEALED TOP 5' WITH CONCRETE GROUT AND BENTONITE				Sheet <u>4</u> of <u>4</u>

Converse Consultants



SITE #2
OBSERVATION WELL #4

Boring Log 5-5 (1983)

THIS LOG IS APPLICABLE ONLY AT THIS LOCATION AND TIME.
CONDITIONS MAY DIFFER AT OTHER LOCATIONS OR TIME.

PROJECT SCRTD - Union Sta. DATE DRILLED 2/1/83 HOLE NO. 5-5
LOCATION LOADING DOCK AT INT. VIGNES & RACINE STS GROUND ELEV. 280.8'
DRILLING CONTRACTOR CONVERSE - LAS VEGAS LOGGED BY B. INGRAM DEPTH TO GROUND WATER 27.9
TYPE OF RIG _____ HOLE DIAMETER 4 1/4" HAMMER WEIGHT AND FALL 320# 36" (28-2-
SURFACE CONDITIONS A.C. PARKING AREA TOTAL DEPTH 100.0 NO. CORE BOXES _____

DEPTH	CLASS.	FIELD DESCRIPTION	SAMPLE	SPT (6")	DRILL MODE	RUN NO.	CORE REC. %	REMARKS
0.0		0.0 - 0.3 - ASPHALT PAVEMENT			RD			SET UP 2:45 PM 1/31
	ML & SM	0.3 - 5.5 - FILL - SANDY SILT & SILTY SAND		16	S			BEGIN DRILLING 7:15 AM
2.0		MOTTLED & INTERMIXED MOIST, STIFF / M. DENSE W/ BRICK DEBRIS		25	P			WEATHER: CLEAR, WARM 2/1/83
				57	T			
4.0					RD			DRILLED TO 5' WITH 7" BIT FOR PIEZO INSTALLATION. 4 3/4" BIT BELOW
6.0	SM	5.5 - 11.0 - YOUNG ALLUVIUM SILTY SAND	5-1 3K		CCI DR			CONTACT CONTAINED WITHIN SAMPLE
		GRAY-BRN, MOIST, MED. DENSE FINE TO V. FINE SAND - 76% 30% SILT			RD			
8.0								
10.0				10	S			
	SP	11.0 - 14.0 - SAND		12	P			
12.0		GRAY-BRN, MOIST, M. DENSE TO DENSE POORLY GRADED FINE SAND W/ TRACE SILT		25	T			
					RD			
14.0								
	SW	14.0 - 62.0 - GRAVELLY SAND						
16.0		BROWN, DENSE WELL GRADED - MED TO COARSE CLEAN SAND - 70% GRAVEL TO 2" - 30% SUBANGULAR TO SUBROUND GRAINS, GRANITIC COMP.	5-2 50K		CCI DR			GRAVELLY - DISTURBED SAMPLE
					RD			
18.0								
20.0								
22.0								
24.0								
26.0								
28.0								

SHEET 1 OF 6

PROJECT SCRTD - UNION STA. DATE DRILLED 2/1/83 HOLE NO. 5-5(1983)

DEPTH	CLASS.	FIELD DESCRIPTION	SAMPLE	SPT (6')	DRILL MODE	RUN NO.	CORE REC. %	REMARKS
20.0	SW	14.0-22.0 <u>GRAVELLY SAND</u> (CONTINUED)	5°	100	SPT			
22.0			RECAL		RD			
24.0								
26.0		25.5-26.0 - LENSE OF FINE SAND IN SAMPLE	5-3	36K	CCI DR			
28.0					RD			
30.0		30.0 COLOR CHANGE TO DK. GRAY INCREASED MAFIC CONTENT: GRANITIC/DIORITIC COMP.	3"	75 100	SPT T			SLIGHT GAS ODOR
32.0			RECAL		RD			
34.0								
36.0			5-4	40K	CCI DR			SLIGHT GAS ODOR GRAVELLY SAMPLE - ONLY 5 GOOD RINGS
38.0					RD			
40.0			J-1	25	S			
42.0			7"	75 100	P T			
44.0			RECAL		RD			

PROJECT SCRTD - UNION STA. DATE DRILLED 2/1/83 HOLE NO. 5-5 (1983)

DEPTH	CLASS.	FIELD DESCRIPTION	SAMPLE	SPT (6")	DRILL MODE	RUN NO.	CORE REC. %	REMARKS
44.0		14.0 - 62.0 <u>GRAVELLY SAND</u>			RD			
		(CONTINUED)						
46.0								
48.0								
50.0								
			75K		CCI DR			SULPHUR ODOR POOR SAMPLE RECOVERY - REMAINING SAMPLE DESTROYED IN HANDLING
52.0					RD			
54.0								
		GRAD. DECREASING GRAVEL CONTENT ↓						
56.0								
58.0								
60.0			5-5 50K		CCI DR			SLIGHT SULPHUR ODOR
					RD			
62.0	SP	62.0 - 78.0 <u>SAND</u>						
		DARK GRAY, DENSE POORLY GRADED UNIFORM FINE TO VERY FINE GRAINED MICACEOUS						
64.0								
66.0								
68.0								

PROJECT SCRTD - UNION STA. DATE DRILLED 2/1/83 HOLE NO. 5-5 (1983)


DEPTH	CLASS.	FIELD DESCRIPTION	SAMPLE	SPT (6")	DRILL MODE	RUN NO.	CORE REC. %	REMARKS
66.0	SP	62.0-78.0 <u>SAND</u> (CONTINUED)			RD			
70.0			5-6		CCI DR			STRONGER SULFUR ODOR
			5DK		RD			POOR SAMPLE RECOVERY: 4 1/2 RINGS ONLY
72.0								
74.0								
76.0								
78.0		78.0-90.0 <u>BOULDERS</u>						78.0 - CHANGE IN DRILLING CONDITIONS - V. HARD DRILLING, FULL WT. OF RIG (10TON) ON BIT. TOO HARD TO SAMPLE TO 90.0'
80.0		CUTTINGS: MED. TO COARSE SUBANGULAR GRAINS GRANITIC COMPOSITION	60K-1"		CCI DR			NO SAMPLE RECOVERY
			REFUSAL		RD			
82.0								
84.0								
86.0			100K-0"		RD			ATTEMPTED TO SAMPLE - UNSUCCESSFUL
			REFUSAL					
88.0			J-2					JAR SAMPLE OF CUTTINGS TAKEN
			CUTTINGS					
90.0	CL	<u>PUENTE FORMATION</u>						EASY DRILLING FROM 90.0'
		90.0-100.0 <u>CLAYSTONE</u>						CLAYSTONE CUTTINGS OBTAINED
92.0		(SEE NEXT PAGE)						SHEET <u>4</u> OF <u>6</u>

PROJECT SCRTD - UNION STA DATE DRILLED 2/1/83 HOLE NO. 5-5 (1983)

DEPTH	CLASS.	FIELD DESCRIPTION	SAMPLE	SPT (blows)	DRILL MODE	RUN NO.	CORE REC. %	REMARKS
92.0	CL	90.0-100.0 CLAYSTONE			RD			
		(CONTINUED)						
94.0		OLIVE-GRAY COLOR, MOIST.						
		PLASTIC TO FRAGILE STRENGTH.						
		SOFT FRAGILE HARDNESS,						
96.0		THINLY LAMINATED W/ SILTY CLAYSTONE - 20% SANDSTONE BLED.						
		TENDS TO FRACTURE ALONG LAMINATIONS						
98.0								
100.0			5-7 SBK		CCI DR			
		END BORING 100.0 FT						
		PIEZOMETER SET TO 100'						
		PERFORATED IN LOWEST 40'						

SUMMARY BORING NO. 5-5 (1983)

PROJECT SCRTD STATION HOLE UNION STA. DATE DRILLED 2/1/83
OVERBURDEN DEPTH (FT.) 0.0 TO 90.0
BEDROCK DEPTH (FT.) 90.0 TO 100.0 (T.D.).
WATER PRESS. TEST No; INTERVAL(S) — TO —, — TO —.
GROUND WATER DEPTH (FT.) 28.0 DATE 2/3/83; 27.9 DATE 2/8/83.
GAS YES; DEPTH FIRST NOTICED 30', DATE —. (SULPHUR ODOR)
E-LOG No.
DOWN-HOLE SURVEY No.
CROSS-HOLE SURVEY No.
PVC CASING (I.D.): 4" — TO —; 3" — TO —; 2" 0.4 TO 100.0.
GROUND ELEVATION REF. —



1983 UNION STATION BORING LOGS

DESIGN UNIT A135

BORING LOGS FOR HOLE NUMBERS 5-2, 5-3 and 5-4

Converse Consultants



Boring Log 5-2

THIS LOG IS APPLICABLE ONLY AT THIS LOCATION AND TIME.
CONDITIONS MAY DIFFER AT OTHER LOCATIONS OR TIME.

PROJECT SCRTD - UNION STATION DATE DRILLED 2/3/83 HOLE NO. 5-2
LOCATION BETWEEN TRACKS & BARRAGE BUILDING GROUND ELEV. 292.7'
DRILLING CONTRACTOR CONVERSE-LS VEGAS LOGGED BY B. INGRAM DEPTH TO GROUND WATER _____
TYPE OF RIG _____ HOLE DIAMETER 4 3/4" HAMMER WEIGHT AND FALL 320 #, 36"
SURFACE CONDITIONS A.S. / CONCRETE PAVED AREA TOTAL DEPTH 85.0' NO. CORE BOXES _____

DEPTH	CLASS.	FIELD DESCRIPTION	SAMPLE	SPT (16')	DRILL MODE	RUN NO.	CORE REC. %	REMARKS
0.0		0.0-0.4' CONCRETE SLAB			RD			SET UP 7:00 AM
		0.4-0.8' BASE COURSE						BEGIN DRILLING 7:30 AM
	ML & CL	0.8-14.0' FILL - CLAYEY SILT AND SILTY CLAY	2-1 8K		CCR DR			WEATHER: OVERCAST, COOL
2.0		MOTTLED BRN & GREEN-GRAY, MOIST, STIFF.			RD			
4.0		W/ TRACE GRAVEL AND 10% FINE SAND						
6.0								
8.0								
10.0								
12.0				8 11 24	SPT T RD			
13.0		ROCK OR CONCRETE ENCOUNTERED			100-GR. REPAIR			
14.0	SM	YOUNG ALLUVIUM						Tried to sample with SPT - could not drive.
		14.0-19.0 SILTY SAND						
16.0		GRAY-BRN, MOIST, MED. DENSE FINE TO V. FINE SAND W/ 20% SILT		6 7 14	SPT T RD			
18.0								
19.0		19.0-72.0 GRAVELLY SAND						
20.0	SW	(SEE NEXT PAGE)						

SHEET 1 OF 5

PROJECT SCRTD - UNION STATION DATE DRILLED 2/3/83 HOLE NO. 5-2

DEPTH	CLASS.	FIELD DESCRIPTION	SAMPLE	SPT (F)	DRILL MODE	RUN NO.	CORE REC. %	REMARKS
20.0	SW	17.0 - 22.0 GRAVELLY SAND	2-2		CCT DR			DISTURBED SAMPLE - 4 RINGS ONLY
		(CONTINUED)	25K		RD			
22.0		GRAY, DENSE						
		WELL GRADED - MED. TO						
		COARSE SAND, GRAVEL TO						
		2", PERCENTAGES						
		VARYING WITH DEPTH						
		GRANITIC COMPOSITION						
24.0								
26.0								
28.0								
30.0								
			5" REF	70 100 SPT RD				RUSTY STAINED GRAINS IN SAMPLE - OXYDIZING ENVIRONMENT
32.0								
34.0								
36.0								
		INCREASING CONTENT OF FINE & V. FINE GRAINED SAND						
38.0								
40.0			50K		CCT DR			No SAMPLE RECOVERY
					RD			
42.0								
44.0								

PROJECT SCRTD-UNION STATION DATE DRILLED 2/3/83 HOLE NO. 5-2

DEPTH	CLASS.	FIELD DESCRIPTION	SAMPLE	SPT (ft)	DRILL MODE	RUN NO.	CORE REC. %	REMARKS
4.4.0	SW	19.0 - 72.0 <u>GRAVELLY SAND</u>			RD			
		(CONTINUED)	2-3		CCI DR			SLIGHT SULPHUR ODOR, GRAY SAMPLE -
46.0		COLOR CHANGE OBSERVED - TO DK. GRAY	75K		RD			REDUCING ENVIRONMENT POOR SAMPLE RECOVERY - - 4 DISTURBED RINGS ONLY
48.0								
50.0								
52.0								
54.0								
56.0			80K		CCI DR			No SAMPLE RECOVERY
58.0					RD			
60.0			75K		CCI DR			No SAMPLE RECOVERY
62.0		GRAVEL CONTENT DECREASES W/ DEPTH ↓			RD			
64.0								
66.0			5-5" 100 SPT REFUSAL		RD			
68.0								

SHEET 3 OF 5

PROJECT SCRTD - UNION STATION DATE DRILLED 2/3/83 HOLE NO. 5-2

DEPTH	CLASS.	FIELD DESCRIPTION	SAMPLE	SPT (ft)	DRILL MODE	RUN NO.	CORE REC. %	REMARKS
68.0	SW	19.0-72.0 <u>GRAVELLY SAND</u>			RD			
70.0		(CONTINUED) DECREASING GRAVEL CONTENT	2-4 60K		CCI DR			SLIGHT SULPHUR ODOR
72.0	SP	72.0-83.0 <u>SAND</u>			RD			EASIER DRILLING
74.0		DARK GRAY, DENSE, POORLY GRAINED PREDOM. MED GRAINED TRACE GRAVEL TO 2"						
76.0			5"	100	SPT RD			SULPHUR ODOR
78.0		SAND BECOMES MORE FINE - GRAINED						
80.0		FINE TO V.FINE GRAINED	2-5 50K		CCI DR			SULPHUR ODOR DISTURBED SAMPLE - ONLY 5 RINGS
82.0		THIN LENSES OF SILTY SAND			RD			
84.0		83.0-84.0 <u>BOULDERS</u> GRANITIC-TYPE CUTTINGS	50K-0"		CCI			HARD DRILLING TRIED TO SAMPLE - COULD NOT DRIVE SAMPLER
		END BORING 84.0 FT	PERICAL					

SUMMARY BORING NO. 5-2

PROJECT SCRTD STATION HOLE UNION STATION DATE DRILLED 2/3/83.

OVERBURDEN DEPTH (FT.) 0.0 TO 84.0 (T.D.)

BEDROCK DEPTH (FT.) TO (T.D.).

WATER PRESS. TEST No; INTERVAL(S) TO , TO .

GROUND WATER DEPTH (FT.) DATE ; DATE .
ROTARY WASH BORING - COULD NOT DETERMINE

GAS Yes; DEPTH FIRST NOTICED 45', DATE 2/3/83. - SULPHUR ODOR


E-LOG No.

DOWN-HOLE SURVEY No.

CROSS-HOLE SURVEY No.

PVC CASING (I.D.): 4" NONE TO ; 3" TO ; 2" TO .

GROUND ELEVATION REF. .



Converse Consultants



Boring Log 5-3

THIS LOG IS APPLICABLE ONLY AT THIS LOCATION AND TIME.
CONDITIONS MAY DIFFER AT OTHER LOCATIONS OR TIME.

PROJECT SCRTD - UNION STATION DATE DRILLED 2/2/93 HOLE NO. 5-3
LOCATION BETWEEN TRACKS & BAGGAGE BLDG. GROUND ELEV. 292.8'
DRILLING CONTRACTOR CONVERSE - LAS VEGAS LOGGED BY B. INGRAM DEPTH TO GROUND WATER _____
TYPE OF RIG _____ HOLE DIAMETER 4 1/4" HAMMER WEIGHT AND FALL 320#, 36"
SURFACE CONDITIONS A.C. PAVED AREA TOTAL DEPTH 80.0' NO. CORE BOXES _____

DEPTH	CLASS.	FIELD DESCRIPTION	SAMPLE	SPT (6")	DRILL MODE	RUN NO.	CORE REC. %	REMARKS
0.0		0.0 - 0.8' ASHALT PAVEMENT			RD			SET UP 7:00 AM
0.8	GW	0.8 - 4.6' FILL - GRAVEL			CCI OR			BEGIN DRILLING 7:30 AM
2.0		WELL GRADED GRAVEL TO 2 1/2", COMPOSITION VARIABLE SUBANGULAR TO SUBROUNDED	20K		RD			WEATHER: COOL, RAINING
4.0								NO SAMPLE RECOVERY
4.6	ML	4.6 - 14.0 CLAYEY SILT			CCI OR			LOST CIRCULATION OF DRILLING FLUID
6.0		GREEN-GRAY, MOIST, STIFF CONSISTENCY VARIABLE SAND CONTENT (LOCALLY 3-30%)	3-1 15K		RD			
8.0								
10.0		TO VERY STIFF CONSISTENCY						
12.0				15	S			
				25	P			
				45	T			
14.0					RD			
14.0	SM	YOUNG ALLUVIUM						
14.0		14.0 - 19.0 SILTY SAND						
16.0		GRAY-BROWN, MOIST, MED. DENSE. FINE TO V. FINE SAND WITH 20% SILT		20	S			
				13	P			
				20	T			
18.0					RD			
19.0								
19.0	SW	19.0 - 74.0 GRAVELLY SAND						
20.0		(SEE NEXT PAGE)						

SHEET 1 OF 5

PROJECT SCRTD - Union Sta. DATE DRILLED 2/2/83 HOLE NO. 5-3

DEPTH	CLASS.	FIELD DESCRIPTION	SAMPLE	SPT (blows)	DRILL MODE	RUN NO.	CORE REC. %	REMARKS
20.0	SW	19.0 - 74.0 <u>GRAVELLY SAND</u>	37K		CCT DR			No SAMPLE RECOVERY
		(CONTINUED)			RD			
22.0		BROWN, VERY DENSE, WELL GRADED - MED. TO COARSE SAND (70%), GRAVEL TO 3" (30%) SUBANGULAR TO SUBROUNDED GRAINS, GRANITE COMP.						
24.0		ALTERNATING SAND & GRAVEL STRATA						24-28' INTERMITTENT RIG CHATTER
26.0								
28.0								
30.0			20K-9"		CCT DR			POOR SAMPLE RECOVERY LARGE GRAVEL - SAMPLE DESTROYED BY HANDLING
32.0					RD			
34.0								
36.0								
38.0								
40.0		CHANGE OF SAMPLE COLOR TO DARK GRAY	5TK		CCT DR			SULPHUR ODOR LARGE GRAVEL IN SAMPLE - SAMPLE DESTROYED BY HANDLING
42.0					RD			
44.0								RIG CHATTER AT 43'
								SHEET <u>2</u> OF <u>5</u>

PROJECT SCRTD - UNION STA. DATE DRILLED 2/2/83 HOLE NO. 5-3

DEPTH	CLASS.	FIELD DESCRIPTION	SAMPLE	SPT (F)	DRILL MODE	RUN NO.	CORE REC. %	REMARKS
44.0	SW	19.0-74.0 <u>GRAVELLY SAND</u>			RD			
		(CONTINUED)						
46.0								
48.0								
50.0			3-2 41K		CCI DR			SULPHUR ODOR IN SAMPLE
52.0		ALTERNATING SAND AND GRAVEL STRATA			RD			
54.0								53' INTERMITTENT RIG CHATTER TO 58'
56.0								
58.0								
60.0			82K		CCI DR			SLIGHT SULPHUR ODOR IN SAMPLE
62.0					RD			POOR RECOVERY - SAMPLE DESTROYED BY HANDLING
64.0								
66.0		LESS GRAVEL, LENSES FURTHER APART						
68.0								

PROJECT SCRTD - UNION STA DATE DRILLED 2/2/83 HOLE NO. 5-3

DEPTH	CLASS.	FIELD DESCRIPTION	SAMPLE	SPT (blows)	DRILL MODE	RUN NO.	CORE REC. %	REMARKS
68.0	SW	19.0-74.0 <u>GRAVELLY SAND</u> (CONTINUED)			RD			
70.0		(SAND STRATA SAMPLED)	3-3 85K		CCI DR			SLIGHT SULPHUR ODOR IN SAMPLE
72.0					RD			
74.0	SP	74.0-80.0 <u>SAND</u> DARK GRAY, MED. DENSE TO DENSE; POORLY GRADED, UNIFORM FINE TO V. FINE GRAINED, MICACLOUS SILTY SAND LENSES						74' EASIER DRILLING
76.0								
78.0								
80.0			3-4 35K		CCI DR			SULPHUR ODOR IN SAMPLE
		END BORING 80.0 FT						

SUMMARY BORING NO. 5-3

PROJECT SCRTD STATION HOLE UNION STATION DATE DRILLED 2/2/83

OVERBURDEN DEPTH (FT.) 0.0 TO 80.0 (T.D.)

BEDROCK DEPTH (FT.) TO (~~7.0~~)

WATER PRESS. TEST No; INTERVAL(S) TO , TO .

GROUND WATER DEPTH (FT.) DATE ; DATE .
ROTARY WASH BORING - COULD NOT DETERMINE

GAS Yes; DEPTH FIRST NOTICED 40', DATE 2/2/83 - SULPHUR ODOR


E-LOG No

DOWN-HOLE SURVEY No

CROSS-HOLE SURVEY No

PVC CASING (I.D.): 4" TO NONE; 3" TO ; 2" TO

GROUND ELEVATION REF.



Converse Consultants



Boring Log 5-4

THIS LOG IS APPLICABLE ONLY AT THIS LOCATION AND TIME.
CONDITIONS MAY DIFFER AT OTHER LOCATIONS OR TIME.

PROJECT SCRTD DATE DRILLED 1/31/83 HOLE NO. 5-4
LOCATION LOADING DOCK INT. VIGNES & RAMIREZ STREETS GROUND ELEV. 287.6'
DRILLING CONTRACTOR CONVERSE - LAS VEGAS LOGGED BY B. INGRAM DEPTH TO GROUND WATER _____
TYPE OF RIG _____ HOLE DIAMETER 4 3/4" HAMMER WEIGHT AND FALL 320 #, 36"
SURFACE CONDITIONS A.P. PARKING AREA TOTAL DEPTH 80.0' NO. CORE BOXES _____

DEPTH	CLASS.	FIELD DESCRIPTION	SAMPLE	SPT (6")	DRILL MODE	RUN NO.	CORE REC. %	REMARKS
0.0	ML	0.0-0.3 ASPHALT PAVEMENT			RD			BEGIN DRILLING 8:15AM
		0.3-3.5 FILL - SANDY SILT						WEATHER: CLEAR, WARM
		DARK BRN, MOIST, STIFF	4-1		CCT DR			
2.0		SILT - 50%, FINE TO MED. SAND	16K		RD			
		40%, 10% GRAVEL & BLOCK CHUNKS						
4.0		3.5-4.0 CONCRETE BLOCK						
	SM	4.0-7.0 YOUNG ALLUVIUM - SILTY SAND						
		GRAY - BRN, MOIST, DENSE	J-1	30	S			
6.0		FINE TO VERY FINE - 70%, SILT - 30%		18	P			
				24	T			
	SP	7.0-18.0 SAND			RD			
8.0		GRAY, MOIST, DENSE.						
		CLEAN, UNIFORM FINE SAND						
10.0			J-2		CCT DR			
			17K		RD			
12.0		BECOMES COARSER: TO MED. GRAINED						
14.0								
16.0			J-2	5	S			
				4	P			
				11	T			
18.0	SW	18.0-28.0 GRAVELLY SAND			RD			
		BRN / GRAY / LIGHT MOIST DENSE						
		MED. TO COARSE CLEAN SAND - 60%, GRAVEL TO 2" - 40%, SUBGRAINED TO SUBANGULAR GRAINS.						
20.0		GRANITIC / CRYSTALLINE COMPOSITION						

PROJECT SCRTD - UNION STA. DATE DRILLED 1/31/83 HOLE NO. 5-4

DEPTH	CLASS.	FIELD DESCRIPTION	SAMPLE	SPT (6")	DRILL MODE	RUN NO.	CORE REC. %	REMARKS
20.0	SW	18.0-28.0 <u>GRAVELLY SAND</u> (CONTINUED)	4-3 75K		CCI DR			HIGHLY DISTURBED SAMPLE DUE TO LG. GRAVEL PIECES IN SAMPLE BARREL
22.0					RD			
24.0								
26.0			5" REFUSAL	100 SPT	RD			
28.0	SP/CL	28.0-41.0' <u>SAND/SILTY CLAY</u> GRAY, MOIST, DENSE CLEAN SAND; INTERBEDS OF DARK GRAY, STIFF, MOIST SILTY CLAY TO 31.5'	4-4 55K		CCI DR			
30.0					RD			
32.0	SP	31.5' <u>END CLAY INTERBEDS</u>						
34.0								
36.0			J-3	57 55 70	S P T			
38.0					RD			
40.0			30K 0" REFUSAL					No SAMPLE RECOVERY
42.0	SW	41.0-68.0 <u>GRAVELLY SAND</u> DARK GRAY, VERY DENSE SUBROUNDED GRAINS, WELLGRADED V.FINE TO COARSE SAND - 75% GRAVEL TO 1" - 25% HIGHLY MICACEOUS - DIORITIC COMPOSITION						
44.0								

PROJECT SCRTD - UNION STA. DATE DRILLED 1/31/83 HOLE NO. 5-4

DEPTH	CLASS.	FIELD DESCRIPTION	SAMPLE	SPT (F)	DRILL MODE	RUN NO.	CORE REC. %	REMARKS
44.0	SW	41.0-68.0 <u>GRAVELLY SAND</u>			RD			
		(CONTINUED)		75	S			
46.0				78	P			
			5'-100		T			
					RD			
48.0								
50.0								
		50.5' CLAY INTERBEDS	4'-5		CCI			4 RINGS ONLY
		DECREASING GRAVEL	70K		DR			
		(TO $\approx 15\%$)			RD			SULPHUREOUS ODOR IN SAMPLE
52.0								
54.0								
			3'-100		SPT			SULPHUREOUS ODOR
56.0			REFUSAL		RD			
58.0								
60.0			1-6		CCI			SULPHUR MICROTHERMAL
			15'-9"		DR			ODOR
					RD			
62.0								
64.0								
				105	S			SULPHUR ODOR
66.0			1'-50		P			
					T			
					RD			
68.0								

SHEET 3 OF 5

PROJECT SCRTD-UNION ST.4. DATE DRILLED 1/31/83 HOLE NO. 5-4

DEPTH	CLASS.	FIELD DESCRIPTION	SAMPLE	SPT (6")	DRILL MODE	RUN NO.	CORE REC. %	REMARKS
68.0	SP	68.0-75.0 <u>SAND</u>			KV			
		GRAY, DENSE						
		UNIFORM MICACEOUS						
70.0		FINE TO VERY FINE GRAINED	47 25K		CCI DR			SULPHUR/HYDROTHERMAL ODOR IN SAMPLE
72.0					RD			
74.0								
76.0	SW	75.0-80.0 <u>GRAVELLY SAND</u>						
		20% GRAVEL TO 1 1/2"						
		GRAY, DENSE TO V. DENSE						
78.0								
80.0			4-8 75K		CCI DR			STOP DRILLING 2:30 PM
		END BORING 80.0 FT						

SUMMARY BORING NO. 5-4

PROJECT 83-1101-41 STATION HOLE UNION STA. DATE DRILLED 1/31/83

OVERBURDEN DEPTH (FT.) 0.0 TO 80.0 (T.D.)

BEDROCK DEPTH (FT.) NOT ENCOUNTERED TO (T.D.)

WATER PRESS. TEST No; INTERVAL(S) — TO —, — TO —

GROUND WATER DEPTH (FT.) ROTARY WASH - COULD NOT DETERMINE DATE —; — DATE —

GAS Yes; DEPTH FIRST NOTICED 50', DATE 1/31 - SULFUR OIL


E-LOG No

DOWN-HOLE SURVEY No

CROSS-HOLE SURVEY No

PVC CASING (I.D.): 4" (NONE) TO —; 3" — TO —; 2" — TO —

GROUND ELEVATION REF. —



Existing Geotechnical Boring Logs
The Earth Technology Corporation, 1987c

APPENDIX C
SITE BORING LOGS

BOREHOLE LOG

METRO RAIL TRANSIT

Project Name: _____
 Project Number: 87-600-0033 Field Log of Borehole Number: BH-201 Sheet 1 of 2

Borehole Location: Traffic Island off 101 Fwy		Elevation and Datum: 277.4 feet	
Drilling Agency: DRILL LINE	Driller: Gregg Deluca John Hale	Date Started: 1-8-87	Date Finished: 1-8-87
Drilling Equipment: B-53		Completion: 46.5 Depth (feet)	Rock Depth: (feet)
Method of Drilling: Hollow Stem Auger - 6 Inch Dia.		Number of Samples: 6	Dist.: _____ Undist.: 6 Core: _____
Borehole Size: 8 Inch		Water Depth (ft): 29	First: _____ Compl.: _____ 24 hrs.
Type of Perforation Backfill: None		Logged By: _____	
Type of Seal: 5% Bentonite Cement Grout		Checked by: _____	
		Sharon Lagas Barbara Fontes	

Depth (feet)	Description	Graphic Log		Samples				Remarks
		Lithology	OVA (ppm)	Number	Type	Blow Count	Drilling Rate/Time	
	Dry, dark brown, silty fine to medium size grain sand with some small gravel	SM					9:30	Baseline OVA reading at 2 ppm. Traffic island has been disturbed during freeway construction
5	5-6.5' Same as above with small chips of brick	SM	1	1	Z	12/26/26	10:00	OVA Readings at Baseline
7	7' Hit debris (possibly brick)							
10	10-11.5' Dry, dark brown, silty, fine to medium size sand	SM	1	2	Z	18/22/32	10:08	OVA Readings at Baseline
15	15-16.5' Dry, brown to light brown silty sand with gravel	SM	-	3	Z	14/9/7	10:13	OVA Readings at Baseline No recovery for OVA
20	20' No recovery-cobble, gravel		-			NOTE	10:20	OVA Readings at Baseline
25	25' No recovery - 5" chunk of concrete		-			NOTE	10:30	Possibility of disturbed soil to 25 ft. OVA readings at Baseline
30	Groundwater encountered at approximately 29 feet							

BOREHOLE LOG

Project name: METRO RAIL TRANSIT

Project Number: 87-600-0033 Field Log of Borehole Number: BH-201 Sheet 2 of 2

Depth (feet)	Description	Graphic Log		Samples			Remarks
		Lithology	OVA (ppm)	Number	Type	Blow Count	
30-31.5'	Wet, gray, fine to medium size sand	SP	70	4	16/32/37	10:37	OVA Readings at Baseline, sample has oily film and slight oily odor with sheen
35-36.5'	Wet, gray, medium to coarse grained sand	SP	-	5	10/22/50	10:54	OVA Readings at Baseline No recovery for OVA
40'	No recovery - cobble, gravel	-	-	-	50/6"	11:04	
45-46.0'	Wet, dark gray, fine to medium size sand	SP	8	6	5/50	11:18	OVA Readings at Baseline
46.5'	Hit boulder End Hole					11:25	Collected water samples
55'	Note: On this and all logs that follow, there are missing blow counts at some sampling intervals. In those cases, blow counts were not recorded due to other demands on personnel time.						
60'							
65'							
70'							

BOREHOLE LOG

METRO RAIL TRANSIT

Project Name: _____
 Project Number: 87-600-0033 Field Log of Borehole Number: BH-202 Sheet 1 of 2




Borehole Location: Traffic Island off 101 FWY				Elevation and Datum: 277.3 ft			
Drilling Agency: DRILL LINE		Driller: Gregg DeLuca John Hale		Date Started: 1/8/87		Date Finished: 1/8/87	
Drilling Equipment: B-53				Completion: 50 Depth (feet)		Rock Depth: (feet)	
Method of Drilling: Hollow Stem Auger - 6 Inch Dia.				Number of Samples: 8		Dist.: 8 Undist.: 8 Core:	
Borehole Size: 8 Inch				Water Depth (ft): 29		First: 24 hrs. Compl.: 24 hrs.	
Type of Perforation Backfill: None				Logged By: Sharon Lagas		Checked by: Barbara Fontes	
Type of Seal: 5% Bentonite Cement Grout							

Depth (feet)	Description	Graphic Log		Samples				Remarks
		Lithology	OVA (ppm)	Number	Type	Blow Count	Drilling Rate/Time	
	Dry, dark brown, silty fine to medium size sand with gravel. Hit concrete @ 1'	SM Fill					1:30	Baseline OVA Reading @2 ppm
5-6.5'	Dry, light brown, fine to medium size sand with some silt	SM	2	1	8/12/13	1:40		OVA Readings at Baseline
10-10.5'	Dry, brown, silty, fine to medium size sand with clay	SC	1	2	8/4/16	1:45		OVA Reading at Baseline
10.5-11.5'	Dry, light brown, medium to coarse grained sand with gravel	SP						
15-16.5'	Dry, light brown, medium to coarse sand with gravel	SP	4	3	23/40/25	1:50		OVA Readings at Baseline
17.5'	Hit cobble							
20-21.0'	Same as above							
		SP	2	4	28/50	1:58		OVA Readings at Baseline, oily film on sand
25-25.5'	Dry, light brown, medium to coarse sand which grades into a brown-gray silty clay	SP/CL	6	5	14/23	2:06		OVA Readings at Baseline
25.5-26.0'	Moist, brown-gray, medium to coarse sand Groundwater encountered at approximately 29 feet	SP						

BOREHOLE LOG

METRO RAIL TRANSIT

Project name: _____
 Project Number: 87-600-0033 Field Log of Borehole Number: BH-202 Sheet 2 of 2

Depth (feet)	Description	Graphic Log		Samples			Remarks
		Lithology	OVA (ppm)	Number	Type	Blow Count	
30-31.5'	Wet, gray, medium to coarse grained sand	SP	16	6		13/35/50	2:15 OVA Readings at Baseline
35'	No Recovery	-	-	-	-	8/16/40	2:20
40-41.5'	Wet, gray, medium to coarse grained sand	SP	10	7		8/16/47	2:28 OVA Readings at Baseline
45'	Hit boulder	SP	-	8		30/50	2:42 OVA Readings at Baseline No recovery for OVA
45.5'-46.5'	Wet, dark gray, fine to medium size sand						
50'	Hammer broke, ended hole						3:15 No water sample
55'							
60'							
65'							
70'							

BOREHOLE LOG

Project Name: METRO RAIL TRANSIT
 Project Number: 87-600-0033 Field Log of Borehole Number: BH-203 Sheet 1 of 2

Borehole Location: <u>Traffic Island off 101 FWY</u>		Elevation and Datum: <u>276.5 ft</u>	
Drilling Agency: <u>DRILL LINE</u>	Driller: <u>Gregg Deluca</u> <u>John Hale</u>	Date Started: <u>1/14/87</u>	Date Finished: <u>1/14/87</u>
Drilling Equipment: <u>B-53</u>		Completion: <u>60</u>	Rock Depth: <u></u>
Method of Drilling: <u>Hollow Stem Auger - 6 Inch Dia.</u>		Number of Samples: <u>5</u>	Dist.: <u></u> Undist.: <u>5</u> Core: <u></u>
Borehole Size: <u>8 Inch</u>		Water Depth (ft): <u>30</u>	First: <u></u> Compl.: <u>24 hrs.</u>
Type of Perforation Backfill: <u>None</u>		Logged By: <u></u> Checked by: <u></u>	
Type of Seal: <u>5% Bentonite Cement Grout</u>		Sharon Lagas Barbara Fontes	

Depth (feet)	Description	Graphic Log		Samples				Remarks
		Lithology	OVA (ppm)	Number	Type	Blow Count	Drilling Rate/Time	
								Slant Drilling Angle = 20°
	Dry, brown, silty fine to medium size sand - at 6" hit old brick and large boulder	SM					10:00	OVA not working
5'	Same as above with gravel and cobble - no sample collected	FILL		-	Note			No sample collected, augers grinding on gravel and cobble
7'	Broke through gravel	---						Black brown color soil
10-11.5'	Dry, black-brown, fine to medium sand and silt with small wood fragments	SM		1	15/19, 26		10:51	Soil becomes brown in color and fluffy in texture
15-16.5'	Dry, brown, medium to coarse grained sand with gravel	SP		2	10/10, 8		11:00	
20'	No recovery			-	Note			Hammer sticking so drilling another 5 feet
25-25.5'	Dry, light brown, medium to coarse grained sand with gravel	SP		3	Note		11:21	Only 6" of sample due to sampler falling at an angle. Sampler hitting against the auger
	Groundwater encountered at approx. 30 feet							

BOREHOLE LOG

Project name: METRO RAIL TRANSIT

Project Number: 87-600-0033 Field Log of Borehole Number: BH-203 Sheet 2 of 2

Depth (feet)	Description	Graphic Log		Samples			Remarks	
		Lithology	GVA (ppm)	Number	Type	Blow Count		Drilling Rate/Time
	30-30.5' Wet, brown, coarse grained sand and gravel	SP		4	N	50/6"	11:30	
	32.5' Small Cobble, large gravel	GP						
35	35-35.7' Wet, gray, medium to coarse grained sand	SP		5	Z	9/50 for 2"	11:43	Slight oily odor, only 8-10" of sample, rest was slough
	39' Small Cobble, large gravel (about 2 in.)	GP						
40	40' No recovery - Possibly cobble and gravel*			-		Note	12:00	Hammer sticking
45	45' No recovery - Possibly cobble and gravel*			-		Note	1:11	Hammer sticking- cannot sample without hammer getting stuck so continuing on to 60 feet
50	50' No recovery - Possibly cobble and gravel*			-		Note	12:17	
55	55' No recovery			-		Note		Hitting cobbles
	Wet, gray, medium to coarse grained sand with slight hydrocarbon odor coming up from augers							Appears to be predominantly slough
60	60' End hole						12:33	Collected water samples

BOREHOLE LOG

METRO RAIL TRANSIT

Project Name: _____

Project Number: 87-600-0033

Field Log of Borehole Number: BH-204

Sheet 1 of 2

Borehole Location: <u>Old Center St. (b/t Aliso & Comm.)</u>			Elevation and Datum: <u>275.4 ft</u>		
Drilling Agency: <u>DRILL LINE</u>		Driller: <u>Gregg DeLuca</u> <u>John Hale</u>		Date Started: <u>1/12/87</u>	Date Finished: <u>1/12/87</u>
Drilling Equipment: <u>B-53</u>			Completion: <u>61.5</u> Depth (feet)		Rock Depth: <u> </u> (feet)
Method of Drilling: <u>Hollow Stem Auger - 6 Inch Dia.</u>			Number of Samples: <u>6</u>	Dist.: <u> </u>	Undist.: <u>6</u> Core: <u> </u>
Borehole Size: <u>8 Inch</u>			Water Depth (ft): <u>30</u>	First: <u> </u>	Compl.: <u> </u> 24 hrs. <u> </u>
Type of Perforation Backfill: <u>None</u>			Logged By: <u>Barbara Fontes</u>		Checked by: <u>Sharon Lagas</u>
Type of Seal: <u>5% Bentonite Cement Grout</u>					

Depth (feet)	Description	Graphic Log		Samples				Remarks
		Lithology	OVA (ppm)	Number	Type	Blow Count	Drilling Rate/Time	
	Asphalt, concrete debris						7:30	Baseline OVA Reading at 4 ppm
	Dry, dark brown, silty fine to medium size sand	SM						
5'	Same as above	SM		-				
8-9'	Moist clayey sand	SC						
10-11.5'	Dry, brown, silty, fine to medium size sand	SM	2	1	8/15/11	8:00		OVA Readings @ base-line
15-15.5'	Same as above	SM	4	2	18/6"	8:10		Collected only OVA sample. Hit large object-refusal. Sampler is not penetrating
20-21.5'	Dry, brown, medium to coarse grained sand with fragmented gravel and small cobbles	SP	4	3	39/50/49	8:17		OVA readings @ base-line
25-25.5'	Same as above	SP	160	4	25/6"	8:25		Soil has hydro-carbon odor. OVA values recorded at 160 ppm
	Groundwater encountered at approx. 30 feet							

BOREHOLE LOG

METRO RAIL TRANSIT

Project name: _____
 Project Number: 87-600-0033 Field Log of Borehole Number: BH-204 Sheet 2 of 2

Depth (feet)	Description	Graphic Log		Samples				Remarks
		Lithology	OVA (ppm)	Number	Type	Blow Count	Drilling Rate/Time	
30-31.0'	Wet, gray, coarse grained sand	SP	-	5	20/50			No OVA recovery
35-36.5'	Same as above	SP		6	Note			
38.5'	Cobble, gravel							
40'	No recovery - cobble, gravel			-	Note	8:59		OVA reading 2 ppm Hole has slight creosote odor (40 to 60 feet)
45'	No recovery - cobble, gravel			-	Note			
50'	No recovery - slough			-	Note			Augers contained approx. 4 feet of slough
55'	No recovery			-	Note			
60'	Wet, gray, coarse grained sand End Hole	SP	>1000	-	8/11/16	9:44 10:01		Collected water samples, not enough recovery for soil samples

BOREHOLE LOG

METRO RAIL TRANSIT

Project Name: _____

Project Number: 87-600-0033 Field Log of Borehole Number: BH-205 Sheet 1 of 2

Borehole Location: Commercial and Center St., West		Elevation and Datum: 274.7 ft	
Drilling Agency: DRILL LINE	Driller: Gregg Deluca John Hale	Date Started: 1/13/87	Date Finished: 1/13/87
Drilling Equipment: B-53		Completion: Depth (feet) 61.5	Rock Depth: (feet)
Method of Drilling: Hollow Stem Auger - 6 Inch Dia.		Number of Samples: 7	Dist.: Undist.: 7 Core:
Borehole Size: 8 Inch		Water Depth (ft): 30	First: Compl.: 24 hrs.
Type of Perforation Backfill: None		Logged By: Barbara Fontes	
Type of Seal: 5% Bentonite Cement Grout		Checked by: Sharon Lagas	

Depth (feet)	Description	Graphic Log		Samples				Remarks
		Lithology	OVA (ppm)	Number	Type	Blow Count	Drilling Rate/Time	
	Dry, brown, silty, fine to medium size sand with brick chips, possibly fill material	SM Fill					9:00	Baseline OVA reading @ 2ppm Surface soil contains shells and broken pottery. Soil type not evident in other areas
5'	No sample collected	----	-	-	Note			
10-11.5'	Dry, light brown, medium to coarse sand with gravel	SP	4	1	26/22/23	9:05		
15-16.0'	Same as above	SP	-	2	48/50	9:10		
20-21.0'	Dry, brown, coarse grained sand and small gravel	SP	-	3	49/50	9:20		
25-26.0'	Same as above	SP	-	4	33/56	9:36		Decomposed granite cobble in auger (cobble > 3 in.)

BOREHOLE LOG

Project name: METRO RAIL TRANSIT
 Project Number: 87-600-0033 Field Log of Borehole Number: BH-205 Sheet 2 of 2

Depth (feet)	Description	Graphic Log		Samples				Remarks
		Lithology	OVA (ppm)	Number	Type	Blow Count	Drilling Rate/Time	
30-31.0'	Wet, grey, medium to coarse grained sand Groundwater encountered at approximately 30 feet	SP	30	5	✓	28/50	9:48	OVA and 1 brass recovery
35-36.5'	Same as above	SP	4	6	✓	14/37/48	9:54	
40-41.5'	Same as above	SP		7	✓	Note	10:00	1 brass recovery, no OVA sample OVA reading @ base-line
43'	Cobble, gravel	GP						
45'	No recovery - cobble, gravel			-		Note	10:27	
50'	Wet, dark gray, fine to medium size sand, oily film and odor	SP	100	-		10/26/50	10:37	Only OVA sample recovery OVA reading @ base-line
55-56.5'	Same as above	SP	100	-		3/13/50	10:48	
60'	No recovery-sampler and "A" rods stuck in augers End Hole			-		Note	10:59	Water samples collected

BOREHOLE LOG

METRO RAIL TRANSIT

Project Name: _____
 Project Number: 87-600-003 Field Log of Borehole Number: BH-206A Sheet 1 of 2

Borehole Location: Vignes St. (C.C. Meyer's yard)		Elevation and Datum: 276.5 ft	
Drilling Agency: DRILL LINE	Driller: Gregg Deluca John Hale	Date Started: 1-9-87	Date Finished: 1-9-87
Drilling Equipment: B-53		Completion: Depth (feet) 41.5	Rock Depth (feet)
Method of Drilling: Hollow Stem Auger - 6 Inch Dia.		Number of Samples: 6	Dist.: 6 Core:
Borehole Size: 8 Inch		Water Depth (ft): 29.5	First: 24 hrs.
Type of Perforation Backfill: None		Logged By: Sharon Lagas	
Type of Seal: 5% Bentonite Cement Grout		Checked by: Barbara Fontes	

Depth (feet)	Description	Graphic Log		Samples				Remarks
		Lithology	OVA (ppm)	Number	Type	Blow Count	Drilling Rate/Time	
	Dry, dark brown, sand and gravel with some silt	SP					10:00	Baseline OVA reading @ 2 to 5ppm
5	5-6' Dry, medium to coarse sand with some gravel	SP	3	1		10/10	10:10	OVA reading @ baseline
	6-6.5' Dry, medium grained sand with silt and some clay	SC						
10	10' No recovery (probably fill)			-		10/15	10:13	OVA reading @ baseline
15	15-15.5' Dry, light brown, medium to coarse sand with gravel	SP	14	2		50/6"	10:23	OVA reading @ baseline
20	20' Dry, gravel with coarse grained sand	GP		-		23/6"	10:30	No recovery, cobble stuck in sampler
	23' Gravel and cobble	GP						
25	25-26.5' Moist, medium to coarse grained sand with gravel	SP	12	3		10/43	10:38	OVA reading @ baseline
	Groundwater encountered at approx. 29.5 feet					50		
30								

BOREHOLE LOG

Project name: METRO RAIL TRANSIT

Project Number: 87-600-0033 Field Log of Borehole Number: BH-206A Sheet 2 of 2

Depth (feet)	Description	Graphic Log		Samples				Remarks
		Lithology	OVA (ppm)	Number	Type	Blow Count	Drilling Rate/Time	
30-31.5'	Wet, gray, medium to coarse grained sand	SP	8	4	/	3/6/10	11:20	OVA reading @ baseline
35-36.5'	Wet, gray, fine to medium size sand	SP	10	5	/	6/10/13	11:26	OVA reading @ baseline
40-41.5'	Same as above End Hole	SP	6	6	/	23/49/48	11:36	OVA reading at baseline, 10 feet of slough in hole Collected water samples
45								
50								
55								
60								
65								
70								

BOREHOLE LOG

Project Name: METRO RAIL TRANSIT

Project Number: 87-600-0033 Field Log of Borehole Number: BH-207 Sheet 1 of 2

Borehole Location: 101 FWY South from Vignes		Elevation and Datum: 276.9 ft	
Drilling Agency: DRILL LINE	Driller: Gregg Deluca John Hale	Date Started: 1/12/87	Date Finished: 1/12/87
Drilling Equipment: B-53		Completion: Depth (feet) 60	Rock Depth: (feet)
Method of Drilling: Hollow Stem Auger - 6 Inch Dia.		Number of Samples: 4	Dist.: Undist.: 4 Core:
Borehole Size: 8 Inch		Water Depth (ft): 30	First: Compl.: 24 hrs.
Type of Perforation Backfill: None		Logged By: Barbara Fontes	
Type of Seal: 5% Bentonite Cement Grout		Checked by: Sharon Lagas	

Depth (feet)	Description	Graphic Log		Samples				Remarks
		Lithology	OVA (ppm)	Number	Type	Blow Count	Drilling Rate/Time	
5	Dry, dark brown, silty, fine to medium size sand with gravel and rock/garbage debris	Fill					12:10	Baseline OVA reading @ 2 ppm
5-6.5'	Same as above	Fill				Note		Very little pressure on augers
10	10-11.5' Moist, black-brown, silty sand, medium plasticity clay with oxidation staining	SC	2	1	Z	3/5/8	12:28	
12.5'	Hit debris-augers crunching							
15	15-16.5' Moist to dry, medium to coarse sand	SP	4	2	Z	31/36/33	12:35	OVA reading @ baseline
19'	Gravel and cobbles	GP						
20'	Dry, coarse grained sand with gravel and cobbles	SP	6	-		50/6"	12:56	OVA reading @ baseline, cobble stuck in sampler
25'	Same as above	SP	6	-		50/6"	1:01	No recovery for lab samples

BOREHOLE LOG

Project name: METRO RAIL TRANSIT

Project Number: 87-600-0033 Field Log of Borehole Number: BH-207 Sheet 2 of 2

Depth (feet)	Description	Graphic Log		Samples			Remarks	
		Lithology	GVA (ppm)	Number	Type	Blow Count		Drilling Rate/Time
	30-31.5' Wet, gray, coarse sand with some silt Groundwater encountered at approximately 30 feet	SP	12	3		4/4/24	1:07	Augers vibrating
35	35-36.0' Same as above	SP	4	4		20/50	1:14	
	38' Gravel and cobble	GP						
40	40' Wet, gray, medium to coarse grained sand	SP	12	-		50/6"	1:27	No recovery for lab samples
45	45' No recovery - Possibly medium to coarse grained sand			-		Note	1:30	Having problem with sand heaves going to 60'-sand locking around drill
50	50' No recovery - Possibly medium to coarse grained sand			-		Note		
55	55' No recovery - Possibly medium to coarse grained sand			-		Note		
60	60' End Hole						2:15	Collected water Samples
65								
70								

BOREHOLE LOG

METRO RAIL TRANSIT

Project Name: _____
 Project Number: 87-600-0033 Field Log of Borehole Number: BH-208 Sheet 1 of 2

Borehole Location: NE of BH-205/Adjacent to Center St.		Elevation and Datum: 270.6 ft	
Drilling Agency: DRILL LINE	Driller: Gregg Deluca John Hale	Date Started: 1/13/87	Date Finished: 1/13/87
Drilling Equipment: B-53		Completion: 60 Depth (feet)	Risk Depth: (feet)
Method of Drilling: Hollow Stem Auger - 6 Inch Dia.		Number of Samples: 6	Dist.: 6 Core:
Borehole Size: 8 Inch		Water Depth (ft): 25	First: 24 hrs.
Type of Perforation Backfill: None		Logged By: Barbara Fontes Checked by: Sharon Lagas	
Type of Seal: 5% Bentonite Cement Grout			

Depth (feet)	Description	Graphic Log		Samples				Remarks
		Lithology	OVA (ppm)	Number	Type	Blow Count	Drilling Rate/Time	
	Dry, dark brown, silty fine to medium size sand	SM					12:42	Baseline OVA reading @ 2 ppm
5'	No sample collected					Note	12:45	OVA reading @ base-line
10-11.5'	Dry, brown, medium to coarse grained sand with gravel	SP	2	1	Z	33/45/45	12:48	OVA reading @ base-line, large cobble in sampler
15-16.0'	Dry, brown, fine to medium grained sand	SP	2	2	Z	34/50	12:58	OVA reading @ base-line
20-21.0'	Dry, brown, medium to coarse sand with gravel and broken cobble	SP	4	3	Z	40/50	1:05	Bouncing off large cobble
25-26.5'	Wet, gray, medium to coarse grained sand with occasional gravel Groundwater encountered at approx. 25 feet	SP	100	4	Z	16/19/15	1:12	Slight oily odor

BOREHOLE LOG

METRO RAIL TRANSIT

Project name: _____
 Project Number: 87-600-0033 Field Log of Borehole Number: BH-208 Sheet 2 of 2

Depth (feet)	Description	Graphic Log		Samples				Remarks
		Lithology	OVA (ppm)	Number	Type	Blow Count	Drilling Rate/Time	
30-31.5'	Same as above-not as coarse	SP	40	5	/	7/7/13	1:19	Drilling very difficult
34'	Gravel and cobble	GP						
35'	No recovery-gravel and cobble	GP		-		Note	1:28	
40-41.5'	Wet, gray, medium grained sand	SP	2	6	/	7/9/34	1:43	OVA reading @ baseline, slight creosote odor
45'	No recovery - Possibly sand			-		Note		
50'	No recovery-6 feet of slough in augers - Possibly sand			-		Note		
55'	No recovery - Possibly sand			-		Note		Upon removal of augers, strong creosote odor. No water samples collected due to sampler being stuck
60'	Abandoned hole due to sampler being stuck in augers. Could not advance hole any further						2:44	

BOREHOLE LOG

Project Name: METRO RAIL TRANSIT

Project Number: 87-600-0033 Field Log of Borehole Number: BH-200 Sheet 1 of 2

Borehole Location: <u>East Corner Center & Commercial St.</u>		Elevation and Datum: <u>273.6 ft</u>	
Drilling Agency: <u>DRILL LINE</u>	Driller: <u>Greg Deluca</u> <u>John Hale</u>	Date Started: <u>1/21/87</u>	Date Finished: <u>1/21/87</u>
Drilling Equipment: <u>B-53</u>		Completion: Depth (feet) <u>50</u>	Rock Depth: (feet)
Method of Drilling: <u>Hollow Stem Auger - 6 Inch Dia.</u>		Number of Samples: <u>8</u>	Dist.: <u>8</u> Undist.: <u>8</u> Core:
Borehole Size: <u>8 Inch</u>		Water Depth (ft): <u>30</u>	First: <u>24 hrs.</u> Compl.: <u>24 hrs.</u>
Type of Perforation Backfill: <u>None</u>		Logged By: <u>Sharon Lagas</u> Checked by: <u>Barbara Fontes</u>	
Type of Seal: <u>5% Bentonite Cement Grout</u>			

Depth (feet)	Description	Graphic Log		Samples				Remarks
		Lithology	OVA (ppm)	Number	Type	Blow Count	Drilling Rate/Time	
0-6"	Asphalt						9:18	Baseline OVA reading @ 6 ppm
6"-1.2'	Brick Road							
1.2'-1.6'	Concrete	F118						
	Dry, dark brown, silty, fine to medium size sand with some gravel							
5-6.5'	Dry, brown-black, silty, fine to medium size sand with some gravel	SM	6	1	5/4/4	9:54		OVA reading @ baseline, only OVA sample recovery
10.7-11.7'	Moist, black-brown, silty, fine to medium size sand with some gravel	SM	6	2	16/17	10:00		At 10' sampler hit pocket and dropped approx. 8"
15-16.5'	Dry, brown, fine to medium sand with pea size gravel. Upper 8" stained black. Gravel increasing in size with depth. Entire sample saturated with gasoline	SP	33	3	14/41/37	10:05		OVA reading @ baseline Large cobble in bottom of sampler Oily film on sampler
20-20.5'	Dry, brown, silty sand	SM	6	4	20/37/43	10:20		OVA reading @ baseline
20.5-21.5'	Moist, gray, medium to coarse sand with pea size gravel	SP						Strong oily odor
25-26.0'	Dry, brown, silty, medium to coarse sand with gravel.	SM	6	5	27/50	10:27		OVA reading @ baseline Strong oily odor
27.5'	Hit cobble and gravel Groundwater encountered at approx. 30 feet	GP						

BOREHOLE LOG

Project name: METRO RAIL TRANSIT

Project Number: 87-600-0033 Field Log of Borehole Number: BH-209 Sheet 2 of 2

Depth (feet)	Description	Graphic Log		Samples			Remarks
		Lithology	OVA (ppm)	Number	Type	Blow Count	
30-31.0'	Wet, green-gray, medium to coarse sand with some gravel	SP	24	6		36/50	10:35 OVA reading at base-line Hit void Soil has H ₂ S odor Oily film on sampler
35'	35'-35.5' Wet, gray, medium to coarse grained sand	SP	46	7		50/6"	10:44 OVA reading @ base-line
37'	Hit cobble and gravel	GP					Strong H ₂ S odor
39'	Broke through cobble						Slight creosote odor on sampler
40-41.5'	Wet, gray, medium to coarse grained sand with gravel	SP	12	8		6/8/16	10:59 OVA reading @ base-line Oily film on sampler
45'	No recovery - 4' slough in augers			-		Note	
50'	End hole - no recovery due to sampler sticking in augers						11:21 Water samples collected OVA reading 14 ppm at top of hole

Existing Geotechnical Boring Logs

GeoBase & GPI, 1993

UNIFIED SOIL CLASSIFICATION SYSTEM (ASTM D-2487)

PRIMARY DIVISIONS			GROUP SYMBOL	SECONDARY DIVISIONS
COARSE GRAINED SOILS MORE THAN HALF OF MATERIALS IS LARGER THAN #200 SIEVE SIZE	GRAVELS MORE THAN HALF OF COARSE FRACTION IS LARGER THAN #4 SIEVE	CLEAN GRAVELS (LESS THAN 5% FINES)	GW	WELL GRADED GRAVELS, GRAVEL-SAND MIXTURES, LITTLE OR NO FINES.
			GP	POORLY GRADED GRAVELS OR GRAVEL-SAND MIXTURES, LITTLE OR NO FINES
		GRAVEL WITH FINES	GM	SILTY GRAVELS, GRAVEL-SAND-SILT MIXTURE, NON PLASTIC FINES
			GC	CLAYEY GRAVELS, GRAVEL-SAND-CLAY MIXTURES, PLASTIC FINES.
	SANDS MORE THAN HALF OF COARSE FRACTION IS SMALLER THAN #4 SIEVE	CLEAN SANDS (LESS THAN 5% FINES)	SW	WELL GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES.
			SP	POORLY GRADED SANDS OR GRAVELLY SANDS, LITTLE OR NO FINES.
		SANDS WITH FINES	SM	SILTY SANDS, SAND-SILT MIXTURES, NON-PLASTIC FINES.
			SC	CLAYEY SANDS, SAND-CLAY MIXTURES, PLASTIC FINES.
FINE GRAINED SOILS MORE THAN HALF OF MATERIAL IS SMALLER THAN #200 SIEVE SIZE	SILTS AND CLAYS LIQUID LIMIT IS LESS THAN 50	ML	INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS OR CLAYEY SILTS WITH SLIGHT PLASTICITY.	
		CL	INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS.	
		OL	ORGANIC SILTS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY.	
	SILTS AND CLAYS LIQUID LIMIT GREATER THAN 50	MH	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SANDY OR SILTY SOILS, ELASTIC SILTS.	
		CH	INORGANIC CLAYS OF HIGH PLASTICITY, FAT CLAYS.	
		OH	ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS.	
	HIGHLY ORGANIC SOILS	PT	PEAT AND OTHER HIGHLY ORGANIC SOILS.	

CLASSIFICATION CRITERIA BASED ON FIELD TESTS


PENETRATION RESISTANCE (PR)	
SANDS AND GRAVELS	
RELATIVE DENSITY	BLOWS/FOOT*
VERY LOOSE	0 - 4
LOOSE	4 - 10
MEDIUM DENSE	10 - 30
DENSE	30 - 50
VERY DENSE	OVER 50

CLAYS AND SILTS		
CONSISTENCY	BLOWS/FOOT*	STRENGTH**
VERY SOFT	0 - 2	0 - 1/4
SOFT	2 - 4	1/4 - 1/2
FIRM	4 - 8	1/2 - 1
STIFF	8 - 15	1 - 2
VERY STIFF	15 - 30	2 - 4
HARD	OVER 30	OVER 4

* NUMBER OF BLOWS OF 140 POUND HAMMER FALLING 30 INCHES TO DRIVE A 2 INCH O.D. (1 1/4 INCH I.D.) SPLIT BARREL SAMPLER (ASTM-1586 STANDARD PENETRATION TEST)

** UNCONFINED COMPRESSIVE STRENGTH IN TONS/SQ. FT. READ FROM POCKET PENETROMETER

CLASSIFICATION CRITERIA BASED ON LAB TESTS



GW AND SW - $C_u = \frac{D_{60}}{D_{10}}$ GREATER THAN 4 FOR GW AND 7 FOR SW; $C_c = \frac{(D_{30})^2}{D_{10} \times D_{60}}$ BETWEEN 1 AND 3

GP AND SP - CLEAN GRAVEL OR SAND NOT MEETING REQUIREMENT FOR GW AND SW

GW AND SM - ATTERBERG LIMIT BELOW 'A' LINE OR P.I. LESS THAN 4

GC AND SC - ATTERBERG LIMIT ABOVE 'A' LINE P.I. GREATER THAN 7

FINES (SILT OR CLAY)	FINE SAND	MEDIUM SAND	COARSE SAND	FINE GRAVEL	COARSE GRAVEL	COBBLES	BOULDERS
SIEVE SIZES	200	40	10	4	3/4"	3"	10"


CLASSIFICATION OF EARTH MATERIALS IS BASED ON FIELD INSPECTION AND SHOULD NOT BE CONSTRUED TO IMPLY LABORATORY ANALYSIS UNLESS SO STATED.

GEOBASE/GPI

KEY FOR SOIL EXPLORATION LOGS

FIGURE A-1

1010408200516088

	MOISTURE (%)	DRY DENSITY (PCF)	PENETRATION RESISTANCE (BLOWS/FOOT)	SAMPLE TYPE	DEPTH (FEET)	DESCRIPTION OF SUBSURFACE MATERIALS		ELEVATION (FEET)
						This summary applies only at the location of this boring and at the time of drilling. Subsurface conditions may differ at other locations and may change at this location with the passage of time. The data presented is a simplification of actual conditions encountered.		
	2.4	95			0		FILL: MISC. CRUSHED BASE COARSE, brown, slightly moist, medium dense to dense	-290-
			B	CRUSHED ROCK MIXED WITH SILTY SAND (SM), brown, slightly moist, dense to very dense, 1 to 1.5 inch gravels				
	24.1		B	SILTY CLAY to CLAYEY SILT (CL-ML), mottled grey green, moist to very moist, stiff to very stiff				
	23.2		B					
					5	Refusal at 5 feet.		

SAMPLE TYPES

- ☐ Rock Core
☐ Standard Split Spoon
☐ Drive Sample
☐ Bulk Sample
☐ Tube Sample

DATE DRILLED: 9-10-93

 EQUIPMENT USED:
 HAND

 GROUNDWATER LEVEL:
 NOT ENCOUNTERED




GEOBASE/GPI

 PROJECT NO.: 1133.21
 METROLINK

LOG OF BORING NO. B-1

FIGURE A-2

1010408200516008

	MOISTURE (%)	DRY DENSITY (PCF)	PENETRATION RESISTANCE (BLOWS/FOOT)	SAMPLE TYPE	DEPTH (FEET)	DESCRIPTION OF SUBSURFACE MATERIALS		ELEVATION (FEET)
						This summary applies only at the location of this boring and at the time of drilling. Subsurface conditions may differ at other locations and may change at this location with the passage of time. The data presented is a simplification of actual conditions encountered.		
					0		FILL: SILTY GRAVEL (GM), grey, dry, loose, 3/4 to 1.5 inch gravels, trace sand	-290-
	28.2	90		B			SILTY CLAY to CLAYEY SILT (CL-ML), mottled brown green, moist, very stiff	
		29.5		B				
	13.0			B	5		@ 5.5', black ash SILTY SAND (SM), grey, moist, medium dense to dense	-285-
							Refusal on rock at 7.5 feet.	

SAMPLE TYPES <input type="checkbox"/> Rock Core <input type="checkbox"/> Standard Split Spoon <input type="checkbox"/> Drive Sample <input type="checkbox"/> Bulk Sample <input type="checkbox"/> Tube Sample	DATE DRILLED: 9-10-93 EQUIPMENT USED: HAND GROUNDWATER LEVEL: NOT ENCOUNTERED	GEOBASE/GPI LOG OF BORING NO. B-2	PROJECT NO.: 1133.21 METROLINK
---	---	--	-----------------------------------



FIGURE A-3

1010409200516068

	MOISTURE (%)	DRY DENSITY (PCF)	PENETRATION RESISTANCE (BLOWS/FOOT)	SAMPLE TYPE	DEPTH (FEET)	DESCRIPTION OF SUBSURFACE MATERIALS		ELEVATION (FEET)
						This summary applies only at the location of this boring and at the time of drilling. Subsurface conditions may differ at other locations and may change at this location with the passage of time. The data presented is a simplification of actual conditions encountered.		
	3.2	144		B	0		FILL: SILTY GRAVEL (GM), brown, slightly moist, very dense, 1" to 3" crushed rock, trace sand SILTY CLAY to CLAYEY SILT (CL-ML), light brown, stiff to very stiff, moist, trace sand SILTY SAND (SM), brown, moist, medium dense, bricks, concrete, clay chunks	294.6
	18.6	100		B				
	9.1			B				
						Refusal on concrete at 3.5 feet.		

SAMPLE TYPES <input type="checkbox"/> Rock Core <input type="checkbox"/> Standard Split Spoon <input type="checkbox"/> Drive Sample <input checked="" type="checkbox"/> Bulk Sample <input type="checkbox"/> Tube Sample		DATE DRILLED: 9-2-93 EQUIPMENT USED: HAND GROUNDWATER LEVEL: NOT ENCOUNTERED		GEOBASE/GPI	PROJECT NO.: 1133.21 METROLINK
				LOG OF BORING NO. B-3	
FIGURE A-4					



1010409200316000

	MOISTURE (%)	DRY DENSITY (PCF)	PENETRATION RESISTANCE (BLOWS/FOOT)	SAMPLE TYPE	DEPTH (FEET)	DESCRIPTION OF SUBSURFACE MATERIALS		ELEVATION (FEET)
						This summary applies only at the location of this boring and at the time of drilling. Subsurface conditions may differ at other locations and may change at this location with the passage of time. The data presented is a simplification of actual conditions encountered.		
	2.7	140		B	0		FILL: SILTY GRAVEL (GM), brown, slightly moist, very dense, crushed gravels to 3", trace sand	-295-
	29.1			B			SILTY CLAY to CLAYEY SILT (CL-ML), mottled dark brown, brown, grey, stiff to very stiff, siltstone fragments	
	16.8			B				
						Refusal at 4.5 feet.		

SAMPLE TYPES <input type="checkbox"/> Rock Core <input type="checkbox"/> Standard Split Spoon <input type="checkbox"/> Drive Sample <input type="checkbox"/> Bulk Sample <input type="checkbox"/> Tube Sample	DATE DRILLED: 9-2-93 EQUIPMENT USED: HAND GROUNDWATER LEVEL: NOT ENCOUNTERED	GEOBASE/GPI	PROJECT NO.: 1133.21 METROLINK
LOG OF BORING NO. B-4			FIGURE A-5

1010406200516038



11300300272

	MOISTURE (%)	DRY DENSITY (PCF)	PENETRATION RESISTANCE (BLOWS/FOOT)	SAMPLE TYPE	DEPTH (FEET)	DESCRIPTION OF SUBSURFACE MATERIALS		ELEVATION (FEET)
						This summary applies only at the location of this boring and at the time of drilling. Subsurface conditions may differ at other locations and may change at this location with the passage of time. The data presented is a simplification of actual conditions encountered.		
					0		FILL: SANDY GRAVEL (GW), brown, dry, loose, glass, trash	298
							SANDY GRAVEL (GP), grey, dry, loose, 3/8" round gravels	
							Refusal at 20 inches on asphalt concrete.	

SAMPLE TYPES <input type="checkbox"/> Rock Core <input type="checkbox"/> Standard Split Spoon <input type="checkbox"/> Drive Sample <input type="checkbox"/> Bulk Sample <input type="checkbox"/> Tube Sample	DATE DRILLED: 9-2-93 EQUIPMENT USED: HAND GROUNDWATER LEVEL: NOT ENCOUNTERED	GEOBASE/GPI LOG OF BORING NO. B-5	PROJECT NO.: 1133.21 METROLINK
---	--	--	-----------------------------------

FIGURE A-9

1010409200516068

	MOISTURE (%)	DRY DENSITY (PCF)	PENETRATION RESISTANCE (BLOWS/FOOT)	SAMPLE TYPE	DEPTH (FEET)	DESCRIPTION OF SUBSURFACE MATERIALS		ELEVATION (FEET)		
						This summary applies only at the location of this boring and at the time of drilling. Subsurface conditions may differ at other locations and may change at this location with the passage of time. The data presented is a simplification of actual conditions encountered.				
	10.7	113	1	B	0		FILL: SILTY SAND to SAND (SM-SP), brown, slightly moist to moist, medium dense, gravels to 3 inches, concrete fragments, bricks	-295-		
	3.4	99		D						
	7.7	99	3	D	5				@ 7.5' - 9.0', bricks, ash	-290-
	10.6	97	6	D						
	12.7	96	PUSH	D	10		SILTY SAND (SM), brown, moist, loose, slight petroleum odor	-285-		
	22.9	96	3	D						
					15	Terminated at 15 feet. No caving.				

SAMPLE TYPES

- ☐ Rock Core
☐ Standard Split Spoon
☐ Drive Sample
☐ Bulk Sample
☐ Tube Sample

DATE DRILLED: 9-7-93

 EQUIPMENT USED:
18" BUCKET AUGER

 GROUNDWATER LEVEL:
NOT ENCOUNTERED

GEOBASE/GPI

 PROJECT NO.: 1133.21
METROLINK

LOG OF BORING NO. B-6

FIGURE A-7

1010400200510000

	MOISTURE (%)	DRY DENSITY (PCF)	PENETRATION RESISTANCE (BLOWS/FOOT)	SAMPLE TYPE	DEPTH (FEET)	DESCRIPTION OF SUBSURFACE MATERIALS		ELEVATION (FEET)
						This summary applies only at the location of this boring and at the time of drilling. Subsurface conditions may differ at other locations and may change at this location with the passage of time. The data presented is a simplification of actual conditions encountered.		
	4.1	111	1	B	0		FILL: SILTY SAND (SM), brown, slightly moist to moist, loose to medium dense, glass, bricks, gravels, concrete, chunks of clay, @ 5', brick @ 7', refusal on concrete, moved boring 5 feet. SAND (SP), grey, slightly moist, dense SANDY CLAY (CL), brown, moist, stiff, bricks NATIVE: SAND (SW), grey, moist, dense, gravels to 3"	-295-
	6.6	91		D				
	12.5	99	PUSH	D	5			-290-
	3.1		3	D				
	5.8	97	6	D	10			-285-
	3.2		5	D	15			
						Terminated at 16 feet. Slight caving and ravelling.		

SAMPLE TYPES

- ☒ Rock Core
- ☐ Standard Split Spoon
- ☐ Drive Sample
- ☐ Bulk Sample
- ☐ Tube Sample

DATE DRILLED: 9-7-93

EQUIPMENT USED:
18" BUCKET AUGER

GROUNDWATER LEVEL:
NOT ENCOUNTERED

GEOBASE/GPI

PROJECT NO.: 1133.21
METROLINK

LOG OF BORING NO. B-7

FIGURE A-8

1010409200516068

	MOISTURE (%)	DRY DENSITY (PCF)	PENETRATION RESISTANCE (BLOWS/FOOT)	SAMPLE TYPE	DEPTH (FEET)	DESCRIPTION OF SUBSURFACE MATERIALS		ELEVATION (FEET)
						This summary applies only at the location of this boring and at the time of drilling. Subsurface conditions may differ at other locations and may change at this location with the passage of time. The data presented is a simplification of actual conditions encountered.		
	4.1	117		B	0		FILL: SILTY SAND (SM), brown, loose, moist, gravels to 2"	-285-
	3.4	92	1	D			NATIVE: SAND (SW), grey, moist, very dense, gravels to 3"	
	2.6	119	6	D	5			-280-
	6.2	102	10	D	10			
							Terminated at 11 feet. No caving.	

SAMPLE TYPES <input checked="" type="checkbox"/> Rock Core <input checked="" type="checkbox"/> Standard Split Spoon <input checked="" type="checkbox"/> Drive Sample <input checked="" type="checkbox"/> Bulk Sample <input checked="" type="checkbox"/> Tube Sample	DATE DRILLED: 9-7-93 EQUIPMENT USED: 18" BUCKET AUGER GROUNDWATER LEVEL: NOT ENCOUNTERED	GEOBASE/GPI LOG OF BORING NO. B-8	PROJECT NO.: 1133.21 METROLINK
--	---	--	--

FIGURE A-9

1010409200516038

Existing Geotechnical Boring Logs Geotechnical Soilutions, 2005

Geotechnical Soilutions, Inc.				Project No: GS5101	Client: Tetra Tech Location: Aliso Sector D/MTA
501 S. Fairfax Avenue, Suite 101 Los Angeles, California 90036 Tel: (323) 937-1097 Fax: (323) 937-1099				Drilling Contractor: C&C Drilling	
				Equipment: 8" Hollow Stem Auger	Boring 1
				Driving Weight: 140 lbs	
				Surface Elevation:	Sheet 1
Logged by: SMD		Date: 5/9/2005		Reference:	of 1

Depth in Feet	Drive Sample	Sample Type	Bag Sample	Blows Per 6 inches	Visual Description	Moisture Content %	Dry Unit Weight (Pcf)
0					About 4 inches asphalt, about 4 inches base. Fill: Dark gray brown fine sand and gravel, pieces of concrete and brick, dry, moderately loose.		
5					Fine black sand, brick pieces, slightly moist, moderately loose.		
12	CA				Discarded sample, abundant brick pieces.		
17							
30							
10							
	CA				6 Possible Native: Brown medium grained sand, moist, moderately dense.		
					7		
					10		
	CA				4 Brown medium grained sand, moist, moderately dense.		
15					6 End of boring 14 feet.		
					12 Fill to about 10 feet.		
					No groundwater.		

PLATE XVIII

1010212200744793

Geotechnical Soilutions, Inc.				Project No: GS5101	Client: Tetra Tech		
501 S. Fairfax Avenue, Suite 101 Los Angeles, California 90036 Tel: (323) 937-1097 Fax: (323) 937-1099				Location: Aliso Sector D/MTA			
				Drilling Contractor: C&C Drilling			
				Equipment: 8" Hollow Stem Auger	Boring 2		
				Driving Weight: 140 lbs			
				Surface Elevation:	Sheet 1		
Logged by: SMD				Date: 5/9/2005	of 1		
				Reference:			
Depth in Feet	Drive Sample	Sample Type	Bag Sample	Blows Per 6 inches	Visual Description	Moisture Content %	Dry Unit Weight (Pcf)
0					About 6 inches asphalt, about 5 inches base.		
					<u>Fill:</u> Dark gray medium grained sand, lumps of brown clay, pieces of concrete, brick and asphalt, slightly moist, moderateley loose.		
					Black sand, pieces of brick and concrete, slightly moist, moderately loose.		
5				6			
		SPT		6			
				6			
				6			
10							
		CA		11	<u>Possible Native:</u> Brown sand, medium grained, scattered gravel, slightly moist,		
				13	moderately loose.		
				17	End of boring 11 feet.		
					Fill to about 10 feet		
15					No groundwater.		

PLATE XIX

1010212200744793

Geotechnical Soilutions, Inc.				Project No: GS5101	Client: Tetra Tech
501 S. Fairfax Avenue, Suite 101 Los Angeles, California 90036 Tel: (323) 937-1097 Fax: (323) 937-1099				Location: Aliso Sector D/MTA	
				Drilling Contractor: C&C Drilling	
				Equipment: 8" Hollow Stem Auger	Boring 3
				Driving Weight: 140 lbs	
				Surface Elevation:	Sheet 1
Logged by: SMD		Date: 5/9/2005		Reference:	of 1

Depth in Feet	Drive Sample	Sample Type	Bag Sample	Blows Per 6 inches	Visual Description	Moisture Content %	Dry Unit Weight (Pcf)
0					About 6 inches asphalt, about 5 inches base. Fill: Gray-brown sand, pieces of brick and asphalt, slightly moist, moderately loose. Black sand, pieces of brick and concrete, slightly moist, moderately loose.		
5							
10							
		SPT		11	Black sand and clayey sand, slight odor, scattered pieces of brick, gravel, slightly moist, moderately loose.		
				15			
				26			
15							
		CA		26	Possible Native: Light gray coarse sand with abundant gravel, odor, slightly moist, moderately dense.		
				50			
				6"			
20							
		CA		100	Light gray coarse sand and gravel, odor, slightly moist, moderately dense.		
				6"	Layers of coarse gravel/boulders.		
25							
		CA		20	Gray clayey silt and coarse sand, odor, moist to wet, moderately dense.		
				32	End of boring at 26 feet.		
				33	Water at 26 feet, possibly perched. Fill to about 15 feet.		

PLATE XX

10102122007 447 93

Geotechnical Soilutions, Inc.				Project No: GS5101	Client: Tetra Tech		
501 S. Fairfax Avenue, Suite 101 Los Angeles, California 90036 Tel: (323) 937-1097 Fax: (323) 937-1099				Location: Aliso Sector D/MTA			
Logged by: SMD				Drilling Contractor: C&C Drilling			
Date: 5/9/2005				Equipment: 8" Hollow Stem Auger			
				Driving Weight: 140 lbs			
				Surface Elevation:			
				Reference:			
				Boring 4			
				Sheet 1 of 2			
Depth in Feet	Drive Sample No.	Sample Type	Blows Per 6 inches	Visual Description		Moisture Content %	Dry Unit Weight (Pcf)
0				About 8 inches asphalt, about 5 inches base. <u>Fill:</u> Medium grained brown sand and gravel, pieces of brick and wood, slightly moist, moderately loose. Mottled dark gray and light brown silty clay, slightly moist, moderately stiff.			
5							
10	CA		6	Black silty clay, scattered brick fragments, odor, moist, moderately stiff.			
			7				
			25				
15	CA		10	<u>Possible Native:</u> Dark gray fine sand, slightly moist, moderately dense.			
			15				
			28				
20	CA		27	Dark gray coarse sand and gravel, strong odor, moist, moderately dense.			
			50				
			2"				
25	SPT		25	Dark gray coarse sand and abundant gravel, strong odor, moist, moderately dense.			
			35				
			50				
			5"				
30			28				
			50	Dark gray medium grained sand, strong odor, moist, moderately dense.			

PLATE XXI

10102122007 447 93

Geotechnical Soilutions, Inc.					Project No: GS5101	Client: Tetra Tech	
501 S. Fairfax Avenue, Suite 101 Los Angeles, California 90036 Tel: (323) 937-1097 Fax: (323) 937-1099					Location: Aliso Sector D/MTA		
					Drilling Contractor: C&C Drilling		
					Equipment: 8" Hollow Stem Auger		Boring 4
					Driving Weight: 140 lbs		Sheet 2 of 2
					Surface Elevation:		
Logged by: SMD					Date: 5/9/2005		Reference:
Depth in Feet	Drive Sample	Sample Type	Bag Sample	Blows Per 6 inches	Visual Description		Moisture Content %
30					End of boring at 31 feet. Fill to about 15 feet. No groundwater.		Dry Unit Weight (Pcf)
35							

PLATE XXII

1010212200744793

Geotechnical Soilutions, Inc.				Project No: GS5101	Client: Tetra Tech
501 S. Fairfax Avenue, Suite 101 Los Angeles, California 90036 Tel: (323) 937-1097 Fax: (323) 937-1099				Location: Aliso Sector D/MTA	
				Drilling Contractor: C&C Drilling	
				Equipment: 8" Hollow Stem Auger	Boring 5
				Driving Weight: 140 lbs	
				Surface Elevation:	Sheet 1
Logged by: SMD		Date: 5/9/2005		Reference:	of 1

Depth in Feet	Drive Sample	Sample Type	Bag Sample	Blows Per 6 inches	Visual Description	Moisture Content %	Dry Unit Weight (Pcf)
0					About 4 inches asphalt, about 8 inches base.		
5					Fill: Brown medium grained sand, abundant gravel, brick pieces, slightly moist, moderately loose.		
10		CA		10	Gray and brown silty clay, moist, moderately stiff.		
				10	Gray-brown silty fine sand, moist, moderately dense, slight odor.		
				15			
15		CA		18	Possible Native: Light brown coarse sand and gravel, moist, moderately dense.		
				38			
				50			
20		SPT		50	Light brown silty fine sand with occasional gravel, slightly moist, dense.		
				5"			
25		CA		40	Gray fine to coarse sand and gravel, slight odor, slightly moist, dense.		
				50	End of boring at 26 feet.		
				5"	Fill to about 15 feet.		
30					No groundwater.		

PLATE XXIII



1010212200744793

Existing Geotechnical Boring Logs





Kleinfelder, 2003

Date Drilled:
 Drilled By:
 Drilling Method:
 Logged By:

Water Depth:
 Date Measured:
 Reference Elevation:
 Datum:

Elevation (feet) Depth	Sample	Sample No.	Blow Count (Blows/ft.)	Graphic Log	GEOTECHNICAL DESCRIPTION AND CLASSIFICATION	Dry Density (pcf)	Moisture Content (%)	Additional Tests
		1	6			108	10	DS, SE
		2	12					GS
5	(1)	(2)	(3)	(4)	(5)	(6)	(6)	(7)
10								

NOTES ON FIELD INVESTIGATION

- SAMPLE** - Graphical representation of sample type as shown below.
 - Split Spoon - Standard Penetration Test Sample (SPT) 
 - Drive Sample - California Sample (Cal) 
 - Bulk Sample - Obtained by collecting cuttings in a plastic bag 
 - Tube Sample - Shelby/Pitcher Tube Sample 
- SAMPLE NO.** - Sample Number
- BLOWS/FT** - Number of blows required to advance sampler 1 foot (unless a lesser distance is specified).
 Samplers in general were driven into the soil at the bottom of the hole with a standard (140 lb) hammer dropping a standard 30 inches.
 Drive samples collected in bucket auger borings may be obtained by dropping non-standard weight from variable heights.
 When a SPT sampler is used the blow count conforms to ASTM D-1586.

SCR/ROD - Sample Core Recovery (SCR) in percent (%) and Rock Quality Designation (ROD) in percent (%). ROD is defined as the percentage of core in each run which the spacing between natural fractures is greater than 4 inches. Mechanical breaks of the core are not considered.
- GRAPHIC LOG** - Standard symbols for soil and rock types, as shown on plate B-1b.
- GEOTECHNICAL DESCRIPTION**
Soil - Soil classifications are based on the Unified Soil Classification System per ASTM D-2487, and designations include consistency, moisture, color and other modifiers. Field descriptions have been modified to reflect results of laboratory analyses where deemed appropriate.
Rock - Rock classifications generally include a rock type, color, moisture, mineral constituents, degree of weathering, alteration, and the mechanical properties of the rock. Fabric, lineations, bedding spacing, foliations, and degree of cementation are also presented where appropriate.
 Description of soil origin or rock formation is placed in brackets at the beginning of the description where applicable, for example, Residual Soil.
- DRY DENSITY, MOISTURE CONTENT:** As estimated by laboratory or field testing.
- ADDITIONAL TESTS** - (Indicates sample tested for properties other than the above):

MAX - Maximum Dry Density	SG - Specific Gravity	PP - Pocket Penetrometer
GS - Grain Size Distribution	HA - Hydrometer Analysis	WA - Wash Analysis
SE - Sand Equivalent	AL - Atterberg Limits	DS - Direct Shear
EI - Expansion Index	RV - R-Value	CP - Collapse Potential
CHEM - Sulfate and Chloride Content, pH, Resistivity	CN - Consolidation	UC - Unconfined Compression
PM - Permeability	CU - Consolidation Undrained Triaxial	1 - Torvane
UU - Unconsolidated Undrained Triaxial	CD - Consolidated Drained Triaxial	
- ATTITUDES** - Orientation of rock discontinuity observed in bucket auger boring or rock core, expressed in strike/dip and dip angle, respectively, preceded by a one-letter symbol denoting nature of discontinuity as shown below.
 B: Bedding Plane J: Jointing C: Contact F: Fault S: Shear



KLEINFELDER

EXPLANATION OF LOGS

PLATE

A-1a

1010210200513241

UNIFIED SOIL CLASSIFICATION SYSTEM (ASTM D-2487)

PRIMARY DIVISIONS			GROUP SYMBOLS		SECONDARY DIVISIONS
COARSE-GRAINED SOILS MORE THAN HALF OF MATERIALS IS LARGER THAN #200 SIEVE SIZE	GRAVELS MORE THAN HALF OF COARSE FRACTION IS LARGER THAN #4 SIEVE	CLEAN GRAVELS (LESS THAN 5% FINES)	GW		WELL GRADED GRAVELS, GRAVEL-SAND MIXTURES, LITTLE OR NO FINES
			GP		POORLY GRADED GRAVELS OR GRAVEL-SAND MIXTURES, LITTLE OR NO FINES
		GRAVEL WITH FINES	GM		SILTY GRAVELS, GRAVEL-SAND-SILT MIXTURES
			GC		CLAYEY GRAVELS, GRAVEL-SAND-CLAY MIXTURES
	SANDS MORE THAN HALF OF COARSE FRACTION IS SMALLER THAN #4 SIEVE	CLEAN SANDS (LESS THAN 5% FINES)	SW		WELL GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES
			SP		POORLY GRADED SANDS OR GRAVELLY SANDS, LITTLE OR NO FINES
		SANDS WITH FINES	SM		SILTY SANDS, SAND-SILT MIXTURES
			SC		CLAYEY SANDS, SAND-CLAY MIXTURES
FINE-GRAINED SOILS MORE THAN HALF OF MATERIALS IS SMALLER THAN #200 SIEVE SIZE	SILTS AND CLAYS LIQUID LIMIT IS LESS THAN 50		ML		INORGANIC SILTS, VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS
			CL		INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS
			OL		ORGANIC SILTS AND ORGANIC SILT-CLAYS OF LOW PLASTICITY
	SILTS AND CLAYS LIQUID LIMIT IS GREATER THAN 50		MH		INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SANDS OR SILTS, ELASTIC SILTS
			CH		INORGANIC CLAYS OF HIGH PLASTICITY, FAT CLAYS
			OH		ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS
	HIGHLY ORGANIC SOILS		PT		PEAT, MUCK AND OTHER HIGHLY ORGANIC SOILS
TYPICAL FORMATIONAL MATERIALS	SANDSTONES		SS		
	SILTSTONES		SH		
	CLAYSTONES		CS		
	LIMESTONES		LS		
	SHALES		SL		

CONSISTENCY CRITERIA BASED ON FIELD TESTS

RELATIVE DENSITY: COARSE-GRAINED SOIL			CONSISTENCY: FINE-GRAINED SOIL		TORVANE	POCKET ** PENETROMETER
RELATIVE DENSITY	SPT * (# blows/ft)	RELATIVE DENSITY (%)	CONSISTENCY	SPT (# blows/ft)	UNDRAINED SHEAR STRENGTH (tsf)	UNCONFINED COMPRESSIVE STRENGTH (tsf)
Very Loose	<4	0 - 15	Very Soft	<2	<0.13	<0.25
Loose	4 - 10	15 - 35	Soft	2 - 4	0.13 - 0.25	0.25 - 0.5
Medium Dense	10 - 30	35 - 65	Medium Stiff	4 - 8	0.25 - 0.5	0.5 - 1.0
Dense	30 - 50	65 - 85	Stiff	8 - 15	0.5 - 1.0	1.0 - 2.0
Very Dense	>50	85 - 100	Very Stiff	15 - 30	1.0 - 2.0	2.0 - 4.0
			Hard	>30	>2.0	>4.0

* NUMBER OF BLOWS OF 140 POUND HAMMER FALLING 30 INCHES TO DRIVE A 2 INCH O.D. (1 3/8 INCH I.D.) SPLIT BARREL SAMPLER (ASTM-1586 STANDARD PENETRATION TEST)

** UNCONFINED COMPRESSIVE STRENGTH IN TONS/SQ.FT. READ FROM POCKET PENETROMETER

MOISTURE CONTENT

DESCRIPTION	FIELD TEST
Dry	Absence of moisture, dusty, dry to the touch
Moist	Damp but no visible water
Wet	Visible free water, usually soil is below water table

CEMENTATION

DESCRIPTION	FIELD TEST
Weakly	Crumbles or breaks with handling or slight finger pressure
Moderately	Crumbles or breaks with considerable finger pressure
Strongly	Will not crumble or break with finger pressure



KLEINFELDER

EXPLANATION OF LOGS

PLATE

A-1b

1010210200513241

Date Drilled:	4/24/03	Water Depth:	>30.5 feet
Drilled By:	West Hazmat	Date Measured:	4/24/03
Drilling Method:	Hollow Stem Auger 6"	Elevation:	~280 feet
Logged By:	Ed Che	Reference Datum:	MSL

Elevation (feet) Depth	Sample Type	Sample Number	Blow Counts (blows/foot)	Graphic Log	SOIL DESCRIPTION AND CLASSIFICATION	Dry Unit Weight (pcf)	Moisture Content (%)	Additional Tests PID (ppm)
280					Asphaltic Concrete (AC): approximately 3 inches thick over 1 foot base approximatley			
					Artificial Fill (Af): Sandy Clay (CL): olive gray, moist, fine to coarse sand, brick fragments found, no odor			
275	5	1	35		Sandy Silt (ML): olive brown, moist, very stiff, iron oxide stains, mottled with pockets of clay, no odor	90	20.9	DS
270	10	2	32		Native: Sand (SP): yellow brown, slightly moist, medium dense, fine grained, no odor			WA
265	15	3	45			110	6.8	
260		4	81		-- moist, dense, fine to coarse grained, some fine gravel, 2 inch layer of gray clay, highly moist, no odor			




PROJECT NO. 29712

Proposed Shored Excavation Project
710 N. Keller Street
Los Angeles, California
LOG OF BORING B-1

PLATE
A-2a

Explanation To Logs On Plate A-1

1010210200513241

Elevation (feet) Depth	Sample Type	Sample Number	Blow Counts (blows/foot)	Graphic Log	SOIL DESCRIPTION AND CLASSIFICATION <i>(Continued From Previous Page)</i>	Dry Unit Weight (pcf)	Moisture Content (%)	Additional Tests	PID (ppm)
260					-- very dense				
255 25		5	26 50/6"						
250 30		6	19 50/6"		Gravelly Sand with Silt (SP-SM): gray, moist, very dense, fine to medium grained, fine and coarse gravel, no odor Total depth of boring: 30.5 feet No groundwater encountered Boring backfilled with bentonite grout and topped with rapid set concrete				
 KLEINFELDER PROJECT NO. 29712					Proposed Shored Excavation Project 710 N. Keller Street Los Angeles, California LOG OF BORING B-1				PLATE A-2b

Explanation To Logs On Plate A-1

1010210200513241

Date Drilled:	4/24/03	Water Depth:	>31 feet
Drilled By:	West Hazmat	Date Measured:	4/24/03
Drilling Method:	Hollow Stem Auger 6"	Elevation:	~280 feet
Logged By:	Ed Che	Reference Datum:	MSL

Elevation (feet) Depth	Sample Type	Sample Number	Blow Counts (blows/foot)	Graphic Log	SOIL DESCRIPTION AND CLASSIFICATION	Dry Unit Weight (pcf)	Moisture Content (%)	Additional Tests	PID (ppm)
280					Asphaltic Concrete (AC): approximately 3.5 inches thick without base				
					Artificial Fill (Af):				
					Clayey Sand (SC): dark olive gray, moist, fine to medium sand, brick fragments, trace fine gravel, some staining, no odor, trace coarse gravel and cobbles, concrete debris				
275	5	1	16		-- olive brown, trace wood debris and fragments of ceramics	94	22.7	CHEM, WA	
					Native:				
					Sand (SP): yellow brown, moist, dense, fine to medium grained, some coarse gravel, no odor				
270	10	2	39			105	6.0	GS	
					Silty Sand (SM): olive brown, moist, very dense, fine grained, no odor				
265	15	3	28 50/6"			87	7.4		
					Gravelly Sand with Silt (SP-SM): gray, moist to very moist, dense, fine to coarse grained, fine and coarse gravel, occasional layers of sandy gravel, no odor				
260		4	59						



PROJECT NO. 29712

Proposed Shored Excavation Project
710 N. Keller Street
Los Angeles, California
LOG OF BORING B-2

PLATE

A-3a

Explanation To Logs On Plate A-1

1010210200513241

Existing Geotechnical Boring Logs
Lowney Associates, 2003

EXPLORATORY BORING: LB-01

Sheet 1 of 1

DRILL RIG: AL-ROY DRILLING CO.

BORING TYPE: BUCKET AUGER

LOGGED BY: TKK

START DATE: 7-30-03

FINISH DATE: 7-30-03

PROJECT NO: 1651-15A

PROJECT: TOSCO CENTER STREET REMEDIATION

LOCATION: LOS ANGELES, CALIFORNIA

COMPLETION DEPTH: 17.5 FT.

This log is a part of a report by Lowney Associates, and should not be used as a stand-alone document. This description applies only to the location of the exploration at the time of drilling. Subsurface conditions may differ at other locations and may change at this location with time. The description presented is a simplification of actual conditions encountered. Transitions between soil types may be gradual.

ELEVATION (FT)	DEPTH (FT)	SOIL LEGEND	MATERIAL DESCRIPTION AND REMARKS	SOIL TYPE	PENETRATION RESISTANCE (BLOWS/FT.)	SAMPLER	MOISTURE CONTENT (%)	DRY DENSITY (PCF)	PERCENT PASSING NO. 200 SIEVE	Undrained Shear Strength (ksf)			
274.0	0		SURFACE ELEVATION: 274 FT. (+/-)										
			5-INCHES OF ASPHALT	GW									
			2-INCHES OF CRUSHED AGGREGATED BASE										
			(GW), greenish brown										
			FILL: SILTY SAND (SM), trace of fine gravel and asphalt, moist, dark brown to black										
	5		- loose, no odor	SM	1	X	12	102	33				
			AUGER REFUSAL DUE TO STEEL PIPE MOVED TO 3-FEET SOUTH OF ORIGINAL LOCATION										
			- weak petroleum odor										
	10		- weak petroleum odor, cohesive		6	X	11	122					
			NATIVE: SAND (SP), fine to coarse, trace of fine gravel, dense, moist, light brown, no odor	SP									
	15				14	X	4	127					
			AUGER REFUSAL DUE TO BOULDER (greater than 18-inches in diameter)										
			BOTTOM OF BORING AT 17½ FEET										
			NO FREE GROUNDWATER ENCOUNTERED										
			BORING WAS BACKFILLED WITH CUTTINGS										
			WEIGHT OF KELLY:										
			0 TO 24-FEET: 2,150 POUNDS										
			25 TO 44-FEET: 1,350 POUNDS										
			45 TO 65-FEET: 650 POUNDS										
	25												
	30												

GROUND WATER OBSERVATIONS:

NO FREE GROUNDWATER ENCOUNTERED

LA CORP.GDT. 08/15/03 Fullerton JSR

EXPLORATORY BORING: LB-02

Sheet 1 of 2

DRILL RIG: AL-ROY DRILLING CO.

BORING TYPE: BUCKET AUGER

LOGGED BY: TTK

START DATE: 7-30-03

FINISH DATE: 7-30-03

PROJECT NO: 1651-15A

PROJECT: TOSCO CENTER STREET REMEDIATION

LOCATION: LOS ANGELES, CALIFORNIA

COMPLETION DEPTH: 32.0 FT.

This log is a part of a report by Lowney Associates, and should not be used as a stand-alone document. This description applies only to the location of the exploration at the time of drilling. Subsurface conditions may differ at other locations and may change at this location with time. The description presented is a simplification of actual conditions encountered. Transitions between soil types may be gradual.

ELEVATION (FT)	DEPTH (FT)	SOIL LEGEND	MATERIAL DESCRIPTION AND REMARKS	SOIL TYPE	PENETRATION RESISTANCE (BLOWS/FT.)	SAMPLER	MOISTURE CONTENT (%)	DRY DENSITY (PCF)	PERCENT PASSING NO. 200 SIEVE	Undrained Shear Strength (ksf)
272.0	0		SURFACE ELEVATION: 272 FT. (+/-)							○ Pocket Penetrometer △ Torvane ● Unconfined Compression ▲ U-U Triaxial Compression
			FILL: SILTY SAND (SM), trace of fine gravel, slightly moist to moist, brick rubble, brown	SM						1.0 2.0 3.0 4.0
	5		FILL: SILT (ML), trace of sand and fine gravel, medium stiff, moist, brown, no odor	ML						
			FILL: SAND (SP), fine to coarse, with fine to coarse gravel and cobbles less than 12-inches in diameter, moist, light brown	SP	3	×	10	104		
			- concrete rubble greater than 24-inches in diameter							
	10		REFUSAL DUE TO SAND CAVING, MOVED TO 5-FEET NORTH, 4-FEET WEST OF ORIGINAL LOCATION		6	×	4	110		
			SAND (SP), with fine to coarse gravel and cobbles less than 12-inches in diameter, medium dense, orange brown	SP						
	15		- brown	SP	18	×	3	130		
	20									
			GRAVELLY SAND (SW), fine to coarse gravel and cobbles less than 12-inches in diameter, dense, moist, orange brown with white mottling, no odor	SW	19	×	7	114		
	25		SAND (SP), medium to coarse, trace of gravel and cobbles less than 12-inches in diameter, dense to very dense, olive green, no odor	SP	30/10"	×	6	115		
	30		- fine to medium, moist to very moist							
				SP	30/10"	×	19	105		

Continued Next Page

GROUND WATER OBSERVATIONS:

▽: FREE GROUND WATER MEASURED DURING DRILLING AT 32.0 FEET

LA CORP.GDT 08/15/03 Fullerton JSR

Sheet 2 of 2

DRILL RIG: AL-ROY DRILLING CO.

BORING TYPE: BUCKET AUGER

LOGGED BY: TKK

START DATE: 7-30-03

FINISH DATE: 7-30-03

PROJECT NO: 1651-15A

PROJECT: TOSCO CENTER STREET REMEDIATION

LOCATION: LOS ANGELES, CALIFORNIA

COMPLETION DEPTH: 32.0 FT.

[illegible]

GROUND WATER OBSERVATIONS:

▽: FREE GROUND WATER MEASURED DURING DRILLING AT 32.0 FEET

EXPLORATORY BORING: LB-03

Sheet 1 of 1

DRILL RIG: AL-ROY DRILLING CO.

BORING TYPE: BUCKET AUGER

LOGGED BY: TKK

START DATE: 7-30-03

FINISH DATE: 7-30-03

PROJECT NO: 1651-15A

PROJECT: TOSCO CENTER STREET REMEDIATION

LOCATION: LOS ANGELES, CALIFORNIA

COMPLETION DEPTH: 24.0 FT.

ELEVATION (FT)	DEPTH (FT)	SOIL LEGEND	MATERIAL DESCRIPTION AND REMARKS	SOIL TYPE	PENETRATION RESISTANCE (BLOWS/FT.)	SAMPLER	MOISTURE CONTENT (%)	DRY DENSITY (PCF)	PERCENT PASSING NO. 200 SIEVE	Undrained Shear Strength (ksf)			
										○ Pocket Penetrometer	△ Torvane	● Unconfined Compression	▲ U-U Triaxial Compression
272.0	0		SURFACE ELEVATION: 272 FT. (+/-)							1.0	2.0	3.0	4.0
			FILL: SILT (ML), trace of fine sand and gravel, slightly moist to moist, brick rubble, brown	ML									
			FILL: CLAYEY SAND (SC), with fine gravel, trace of asphalt, low to medium plasticity, moist, brown	SC					45				
	5		FILL: SAND (SP), medium to coarse, trace of gravel and cobbles less than 12-inches in diameter, medium dense to dense, moist, light brown to brown		8	×	5	110					
	10		- light brown	SP	10	×	3	114					
			- with gravel and cobbles less than 12-inches in diameter										
	15		SILT (ML), trace of fine sand, soft to medium stiff, moist, brown with iron oxide stains, no odor	ML	4	×	12	107					
	20		SILTY SAND (SM), with gravel and cobbles less than 12-inches in diameter, fine to coarse, moist, brown	SM									
			SAND (SP), fine to coarse with gravel and cobbles less than 12-inches in diameter, medium dense to dense, moist, orange brown, no odor		13	×	6	115					
			- olive green	SP									
	25		BOTTOM OF BORING AT 24 FEET NO FREE GROUNDWATER ENCOUNTERED BORING HOLE WAS BACKFILLED WITH CUTTINGS BORING STOPPED AT 34 FEET DUE TO REFUSAL, BOULDER GREATER THAN 18-INCHES IN DIAMETER										
	30		WEIGHT OF KELLY: 0 TO 24-FEET: 2,150 POUNDS 25 TO 44-FEET: 1,350 POUNDS 45 TO 65-FEET: 650 POUNDS										

GROUND WATER OBSERVATIONS:

NO FREE GROUNDWATER ENCOUNTERED

LA CORP.GDT 08/15/03 Fullerton* JSR

EXPLORATORY BORING: LB-04

Sheet 1 of 1

DRILL RIG: AL-ROY DRILLING CO.

BORING TYPE: BUCKET AUGER

LOGGED BY: TKK

START DATE: 7-30-03














FINISH DATE: 7-30-03

PROJECT NO: 1651-15A

PROJECT: TOSCO CENTER STREET REMEDIATION

LOCATION: LOS ANGELES, CALIFORNIA

COMPLETION DEPTH: 24.0 FT.

This log is a part of a report by Lowney Associates, and should not be used as a stand-alone document. This description applies only to the location of the exploration at the time of drilling. Subsurface conditions may differ at other locations and may change at this location with time. The description presented is a simplification of actual conditions encountered. Transitions between soil types may be gradual.													
ELEVATION (FT)	DEPTH (FT)	SOIL LEGEND	MATERIAL DESCRIPTION AND REMARKS	SOIL TYPE	PENETRATION RESISTANCE (BLOWS/FT.)	SAMPLER	MOISTURE CONTENT (%)	DRY DENSITY (PCF)	PERCENT PASSING NO. 200 SIEVE	Undrained Shear Strength (ksf)			
													
										1.0	2.0	3.0	4.0
272.0	0		SURFACE ELEVATION: 272 FT. (+/-)										
			FILL: SILT (ML), with sand, trace of gravel, slightly moist to moist, brown										
			- trace of sand, moist, gray brown	ML									
	5		- trace of fine sand, soft, brown										
			FILL: SILTY SAND (SM), fine to coarse, moist, dark brown	SM	3		10	105					
			NATIVE: SAND (SP), medium to coarse, with gravel, medium dense, moist, light brown										
	10			SP	9		2	128					
			- disturbed soil sample was retrieved in sampler tip, only, due to gravel		9		3						
			SILT (ML), trace of fine sand and gravel, moist, gray brown	ML									
	20		SAND (SP), fine to coarse, with gravel and cobbles less than 12-inches in diameter, moist, light brown										
			- medium to coarse, medium dense	SP	9		3	125					
			- required 30 minutes to drill from 22-feet to 24-feet due to gravel and cobbles less than 12-inches in diameter										
	25		BOTTOM OF THE BORING AT 24 FEET NO GROUNDWATER ENCOUNTERED BORING WAS BACKFILLED WITH CUTTINGS BORING STOPPED AT 24-FEET DUE TO REFUSAL										
	30		WEIGHT OF KELLY: 0 TO 24-FEET: 2,150 POUNDS 25 TO 44-FEET: 1,350 POUNDS 45 TO 65-FEET: 650 POUNDS										

GROUND WATER OBSERVATIONS:

NO FREE GROUNDWATER ENCOUNTERED

LA CORP.GDT 08/15/03 Fullerton* JSR

PRIMARY DIVISIONS			SOIL TYPE	LEGEND	SECONDARY DIVISIONS
COARSE GRAINED SOILS MORE THAN HALF OF MATERIAL IS LARGER THAN NO. 200 SIEVE SIZE	GRAVELS MORE THAN HALF OF COARSE FRACTION IS LARGER THAN NO. 4 SIEVE	CLEAN GRAVELS (Less than 5% Fines)	GW		Well graded gravels, gravel-sand mixtures, little or no fines
			GP		Poorly graded gravels or gravel-sand mixtures, little or no fines
		GRAVEL WITH FINES	GM		Silty gravels, gravel-sand-silt mixtures, plastic fines
			GC		Clayey gravels, gravel-sand-clay mixtures, plastic fines
	SANDS MORE THAN HALF OF COARSE FRACTION IS SMALLER THAN NO. 4 SIEVE	CLEAN SANDS (Less than 5% Fines)	SW		Well graded sands, gravelly sands, little or no fines
			SP		Poorly graded sands or gravelly sands, little or no fines
		SANDS WITH FINES	SM		Silty sands, sand-silt-mixtures, non-plastic fines
			SC		Clayey sands, sand-clay mixtures, plastic fines
FINE GRAINED SOILS MORE THAN HALF OF MATERIAL IS SMALLER THAN NO. 200 SIEVE SIZE	SILTS AND CLAYS LIQUID LIMIT IS LESS THAN 50 %		ML		Inorganic silts and very fine sands, rock flour, silty or clayey fine sands or clayey silts with slight plasticity
			CL		Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays
			OL		Organic silts and organic silty clays of low plasticity
	SILTS AND CLAYS LIQUID LIMIT IS GREATER THAN 50 %		MH		Inorganic silts, micaceous or diatomaceous fine sandy or silty soils, elastic silts
			CH		Inorganic clays of high plasticity, fat clays
			OH		Organic clays of medium to high plasticity, organic silts
HIGHLY ORGANIC SOILS			PT		Peat and other highly organic soils

DEFINITION OF TERMS

U.S. STANDARD SIEVE SIZE			CLEAR SQUARE SIEVE OPENINGS		
200	40	10	4	3/4"	3" 12"
SILTS AND CLAY	SAND			GRAVEL	
	FINE	MEDIUM	COARSE	FINE	COARSE
				COBBLES	BOULDERS

GRAIN SIZES

TERZAGHI (N-values)
SPLIT SPOON, STANDARD
PENETRATION TEST (SPT)

MODIFIED CALIFORNIA
SAMPLER (brass ring lined)

D & M
UNDERWATER
SAMPLER

PISTON SAMPLER

SAMPLERS

AT TIME OF DRILLING

MEASURED FOLLOWING DRILLING

GROUND WATER

SAND AND GRAVEL	BLOWS/FOOT*
VERY LOOSE	0-4
LOOSE	4-10
MEDIUM DENSE	10-30
DENSE	30-50
VERY DENSE	OVER 50

SILTS AND CLAYS	STRENGTH+	BLOWS/FOOT*
VERY SOFT	0-1/4	0-2
SOFT	1/4-1/2	2-4
MEDIUM STIFF	1/2-1	4-8
STIFF	1-2	8-16
VERY STIFF	2-4	16-32
HARD	OVER 4	OVER 32

RELATIVE DENSITY

CONSISTENCY

*Applicable only for Standard Penetration Tests (ASTM D-1586).

+Unconfined compressive strength in tons/sq.ft. as determined by laboratory testing or approximated by the standard penetration test (ASTM D-1586), pocket penetrometer, torvane, or visual observation.

KEY TO EXPLORATORY BORING LOGS

Unified Soil Classification System (ASTM D 2487)

Existing Geotechnical Boring Logs
Sladden Engineering, 2004











Dynamic Builders
718 & 728 East Commercial, L.A.

Date: 2/14/2004

Boring No. 1

Job Number:

444-4041

Depth, ft	Symbol	Core	Blows/6"	Description	Soil type	Unit Wt, pcf	Moisture, %	% Minus #200	Remarks
0			---	Silty Sand with Gravel: Brown	SM	---	---	---	Artificial Fill 4'
5			10/24/28	No Recovery	---	---	---	---	Native Soils
10			11/42/50	Silty Sand: Grey Brown	SM	107	3	4	
15			50-5"	Gravelly Sand: Brown	SM		2		
20			34/50-3"	Sand: Grey Brown	SM	103	3	2	
25			50-5"	Silty Sand: Grey Brown	SM		4		
30			50-4"	Gravelly Sand: Grey	SM		11		Petroleum Odor Groundwater @ 29'
35			50-5"	Gravelly Sand: Grey	SM		10		
40			40/50-3"	Sand: Grey	SM		11		Note: The stratification lines represent the approximate boundaries between the soil types; the transition may be gradual.
45			50-3"	Sand: Grey	SM		15		Total Depth = 50.5' No Bedrock
50			50-4"	Sand: Grey	SM		10		

Dynamic Builders
718 & 728 East Commercial, L.A.

Date: 2/14/2004

Boring No. 2

Job Number:

444-4041

Depth, ft	Symbol	Core	Blows/6"	Description	Soil type	Unit Wt, pcf	Moisture, %	% Minus #200	Remarks
0			---	Silty Sand: Brown	SM	---	---	---	Artificial Fill 5'
5			18/20/22	Silty Sand: Grey	SM	99	3	8	Native Soils Disturbed Sample
10			18/22/26	Silty Sand: Brown	SM	---	2	---	
15			50-5"	Gravelly Silty Sand: Brown	SM	101	3	5	
20			50-3"	Gravelly Sand: Brown	SM	102	2	6	
25									Total Depth = 20.5' No Bedrock No Groundwater
30				Recovered Sample					
				Unrecovered Sample					
				Standard Penetration Sample					
35									
40									
45									
50									

Note: The stratification lines represent the approximate boundaries between the soil types; the transition may be gradual.

Dynamic Builders
718 & 728 East Commercial, L.A.

Date: 2/14/2004

Boring No. 3

Job Number:

444-4041

Depth, ft	Symbol	Core	Blows/6"	Description	Soil type	Unit Wt, pcf	Moisture, %	% Minus #200	Remarks
0			..	Silty Sand: Brown	SM	Artificial Fill 5'
6			36/50-5"	8" to 12" Thick Concrete @ 5' Gravelly Silty Sand: Grey Brown	SM	104	3	6	Native Soils
10			10/16/23	Silty Sand: Brown	SM	98	7	5	
15			27/40/50	Gravelly Sand: Brown	SM	123	4	4	
20			39/50-3"	Gravelly Sand: Brown	SM	104	3	6	
25									Total Depth = 20.5' No Bedrock No Groundwater
30				Recovered Sample					
				Unrecovered Sample					
				Standard Penetration Sample					
35									
40				Note: The stratification lines represent the approximate boundaries between the soil types; the transition may be gradual.					
45									
50									

Dynamic Builders
718 & 728 East Commercial, L.A.

Date: 2/14/2004

Boring No. 4

Job Number:

444-4041

Depth, ft	Symbol	Core	Blows/6"	Description	Soil type	Unit Wt, pcf	Moisture, %	% Minus #200	Remarks
0			..	Silty Sand: Brown	SM	Artificial Fill 19'
5			18/40/50	Gravelly Silty Sand: Dark Brown	SM	119	12	45	
10			20/31/42	Silty Sand with Gravel: Dark Grey Brown	SM	119	10	30	
15			50-3"	No Recovery	---	---	---	---	
20			42/50-3"	Gravelly Silty Sand: Brown	SM	107	3	6	Native Soils
25									Total Depth = 20.5'
30									No Bedrock
35									No Groundwater
40									
45									
50									

Note: The stratification lines represent the approximate boundaries between the soil types; the transition may be gradual.

Dynamic Builders
718 & 728 East Commercial, L.A.

Date: 2/14/2004

Boring No. 5

Job Number:
















444-4041

Depth, ft	Symbol	Core	Blows/6"	Description	Soil type	Unit Wt, pcf	Moisture, %	% Minus #200	Remarks
0			---	Silty Sand with Gravel: Grey Brown	SM	---	---	---	Artificial Fill 9'
5			7/7/7	Silty Sand with Gravel: Grey Brown	SM	96	9	31	
10			35/50-2"	Silty Sand: Grey Brown	SM	106	3	6	Native Soils
15			36/50-2"	Gravelly Sand: Brown	SM	113	2	7	
20			28/30/50	No Recovery	---	---	---	---	
25									Total Depth = 20.5'
30									No Bedrock
35									No Groundwater
40									
45									
50									

Note: The stratification lines represent the approximate boundaries between the soil types; the transition may be gradual.

Existing Geotechnical Boring Logs

Smith-Emery GeoServices, 2003

MAJOR SUBDIVISIONS			GROUP SYMBOL	MAJOR SUBDIVISIONS	
COARSE GRAINED SOILS	GRAVEL AND GRAVELLY SOILS MORE THAN 50% OF COARSE FRACTION <u>RETAINED</u> FRACTION ON A NO. 4 SIEVE	CLEAN GRAVELS (LITTLE OR NO FINES)		GW	WELL GRADED GRAVELS, GRAVEL-SAND MIXTURES, LITTLE OR NO FINES.
				GP	POORLY GRADED GRAVELS, OR GRAVEL-SAND MIXTURES, LITTLE OR NO FINES.
		GRAVELS WITH FINES (APPRECIABLE AMOUNT OF FINES)		GM	SILTY GRAVELS, GRAVEL-SAND-SILT MIXTURES.
				GC	CLAYEY GRAVELS, GRAVEL-SAND-CLAY MIXTURES.
	SAND AND SANDY SOILS	CLEAN SANDS (LITTLE OR NO FINES)		SW	WELL GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES.
				SP	POORLY GRADED SANDS OR GRAVELLY SANDS, LITTLE OR NO FINES.
		SANDS WITH FINES (APPRECIABLE AMOUNT OF FINES)		SM	SILTY SANDS, SAND-SILT MIXTURES.
				SC	CLAYEY SANDS, SAND-CLAY MIXTURES.
FINE GRAINED SOILS	SILTS AND CLAYS LIQUID LIMIT <u>LESS</u> THAN 50.		ML	INORGANIC SILTS, SANDY SILTS, AND CLAYEY SILTS OF LOW PLASTICITY.	
			CL	INORGANIC CLAYS OF LOW TO MED. PLASTICITY; GRAVELLY, SANDY OR SILTY CLAYS, LEAN CLAYS.	
			OL	ORGANIC SILTS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY.	
	SILTS AND CLAYS LIQUID LIMIT <u>GREATER</u> THAN 50.		MH	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SANDY OR SILTY SOILS. PLASTIC SILTS.	
			CH	INORGANIC CLAYS OF HIGH PLASTICITY, FAT CLAYS.	
			OH	ORGANIC CLAYS AND SILTY CLAYS OF MEDIUM TO HIGH PLASTICITY.	
HIGHLY ORGANIC SOILS				PT	PEAT AND OTHER HIGHLY ORGANIC SOILS.

NOTE: DUAL SYMBOLS ARE USED TO INDICATE BORDERLINE CLASSIFICATIONS

SOIL CLASSIFICATION CHART






KEY TO LOG OF BORINGS

SYMBOL

TYPE OF TEST

KEY TO SAMPLES

COMP	COMPACTION CHARACTERISTICS
TX	TRIAxIAL COMPRESSION TEST
DS	DIRECT SHEAR TEST
UC	UNCONFINED COMPRESSION TEST
C	CONSOLIDATION TEST
COLL	COLLAPSE TEST
EXP	PERCENT EXPANSION
EI	EXPANSION INDEX
SA	SIEVE ANALYSIS (+ #200 ONLY)
-200	% PASSING #200 SIEVE
HA	HYDROMETER ANALYSIS (- #200 ONLY)
AL	ATTERBERG LIMITS
SE	SAND EQUIVALENT
P	PERMEABILITY
R	R-VALUE
Gs	SPECIFIC GRAVITY
S	SOLUBLE SULFATES
CH	HYDROGEN ION CONTENT
RE	RESISTIVITY
CL	CHLORIDE
PTV	POCKET TORQUE VANE
PP	POCKET PENETROMETER

	INDICATES DEPTH OF UNDISTURBED SAMPLE
	INDICATES DEPTH OF BULK SAMPLE
	INDICATES DEPTH OF SAMPLING ATTEMPT WITH NO RECOVERY
	INDICATES DEPTH OF STANDARD PENETRATION TEST (SPT)
	INDICATES DEPTH OF DISTURBED SAMPLE

NOTE ON SAMPLERS:

Undisturbed samples were obtained with a "California" sampler having an O.D. of 3.0 inches and an I.D. of 2.4 inches. The SPT sampler is 2 inches O.D.; the bit has an I.D. of 1.4 inches and the split barrel has an I.D. of 1.5 inches. Unless practical refusal was encountered, the samplers were driven 18 inches into the soil using a 140 pound weight falling 30 inches. The blow count for the final 12 inches is recorded on the boring logs.

NOTES:

The descriptions on the boring logs apply only at the specific boring locations and at the time the borings were made. They are not warranted to be representative of subsurface conditions. Soil and rock descriptions are based on commonly accepted geotechnical methods of identification and classification and are based on our professional judgment and experience. Field descriptions have been modified where appropriate to reflect laboratory test results. The stratification of soil layers is represented with approximate boundaries and the transition between soil types may be gradual.

Groundwater depths indicated on boring logs are specific to the time of drilling. The term "encountered" refers to the level at which free water was first noticed in the boring. The term "stabilized" refers to the level of the water after a lapse of at least one hour.

Smith-Emery GeoServices

PLATE NO.: A-1B

1010330200515544

SMITH-EMERY GEOSERVICES

PROJECT: Proposed Two Elevators
 LOCATION: 801 E. Commercial Street, Los Angeles, California
 SURFACE ELEVATION: (Not surveyed)
 GROUNDWATER LEVEL: Not encountered
 DATUM

FILE NO.: 33182-1
 REPORT NO. G-03-5577
 DATE DRILLED: 9-11-03
 CORRECTED LOG BY: ABC
 SHEET 1 OF 1

LOG OF BORING NO. 1

PLATE NO. A-2A

SP-SM: MDD = 121.2 pcf

D (FT.)	ST	MATERIAL DESCRIPTION	USC	SYM	N'	G _d (pcf)	W %	S %	LL %	PL %	% -200	RC %	G _m (pcf)
0		5" thick reinforced concrete floor slab											
		Fill: SILTY SAND- brown, some gravel, brick frag- ments, loose, damp	SM		31	98.9	6.6	26.0				81.6	105.4
		(moist)			27	111.5	10.6	58.2				92.0	123.3
5		FINE SANDY SILT - olive brown, very loose, moist	ML		22	87.8	19.8	59.4			63.5	76.3	105.2
		(wet)			29	85.2	33.0	92.9				74.1	113.3
10		Bottom at 10 feet											

LOG OF BORING NO. 2

0		3" thick concrete floor slab											
		SILTY SAND- olive brown, w/ gravel, loose to medium dense, humid	SP		28	104.0	1.7	7.6				85.8	105.8
					42	108.0	2.2	11.0			4.0	89.1	110.4
5					38	106.0	3.2	15.1				87.5	109.4
					45	109.0	3.3	16.9				89.9	112.6
10		Bottom at 9 feet											

ML: MDD* = 115.0 pcf

*Estimated

LEGEND:

B - Bedding
 J - Joint
 C - Contact
 F - Fault
 RS - Rupture Surface

N' - Blows per Foot (35-lb. weight)
 G_d - Dry Unit Weight
 W - Water Content
 S - Saturation
 LL - Liquid Limit
 MDD - Maximum Dry Density
















PL - Plastic Limit
 RC - Relative Compaction
 ST - Sample Type
 USC - Unified Classification System
 D - Depth
 G_m - Moist Density (pcf)

1010330200515544

Existing Geotechnical Boring Logs

URS, 2003

SOIL CLASSIFICATION CHART

MAJOR DIVISIONS			SYMBOLS		TYPICAL DESCRIPTIONS
COARSE GRAINED SOILS MORE THAN 50% OF MATERIAL IS LARGER THAN NO. 200 SIEVE SIZE	GRAVEL AND GRAVELLY SOILS MORE THAN 50% OF COARSE FRACTION RETAINED ON NO. 4 SIEVE	CLEAN GRAVELS (LITTLE OR NO FINES)		GW	WELL-GRADED GRAVELS, GRAVEL - SAND MIXTURES, LITTLE OR NO FINES
				GP	POORLY GRADED GRAVELS, GRAVEL - SAND MIXTURES, LITTLE OR NO FINES
		GRAVELS WITH FINES (APPRECIABLE AMOUNT OF FINES)		GM	SILTY GRAVELS, GRAVEL - SAND - SILT MIXTURES
			GC	CLAYEY GRAVELS, GRAVEL - SAND - CLAY MIXTURES	
	SAND AND SANDY SOILS MORE THAN 50% OF COARSE FRACTION PASSING NO. 4 SIEVE	CLEAN SANDS (LITTLE OR NO FINES)		SW	WELL-GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES
				SP	POORLY GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES
		SANDS WITH FINES (APPRECIABLE AMOUNT OF FINES)		SM	SILTY SANDS, SAND - SILT MIXTURES
				SC	CLAYEY SANDS, SAND - CLAY MIXTURES
FINE GRAINED SOILS MORE THAN 50% OF MATERIAL IS SMALLER THAN NO. 200 SIEVE SIZE	SILTS AND CLAYS LIQUID LIMIT LESS THAN 50			ML	INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS OR CLAYEY SILTS WITH SLIGHT PLASTICITY
				CL	INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS
				OL	ORGANIC SILTS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY
	SILTS AND CLAYS LIQUID LIMIT GREATER THAN 50			MH	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SANDY OR SILTY SOILS, ELASTIC SILTS
				CH	INORGANIC CLAYS OF HIGH PLASTICITY
				OH	ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS
		HIGHLY ORGANIC SOILS			PT

NOTE: Dual symbols are used to indicate gravels or sand with 5-12% fines and soils with fines classifying as CL-ML. Symbols separated by a slash indicate borderline soil classifications.

Sampler and Symbol Descriptions

- ☒ Dames & Moore Type-U sample
- ☒ Standard Penetration Test
- ☐ No Recovery
- Bk ☒ Bulk sample
- ☒ Disturbed Type-U Sample
- ☐ Shelby Tube Sample
- ☐ Rock Core Sample
- ☒ Approximate depth of perched water or groundwater

Note: Number of blows required to advance driven sample 12" (or length noted) is recorded.

Laboratory and Field Test Abbreviations

CBR	California Bearing Ratio test
COL	Collapse Potential test (test result in parentheses)
COMP	Compaction test
CON	Consolidation test
CORR	Corrosivity test
DSCD	Consolidated drained direct shear test (normal pressure and shear strength results shown)
EI	Expansion Index test (test result in parentheses)
LL=29	Liquid limit (Atterberg limits test)
PI=11	Plasticity Index (Atterberg limits test)
PP	Pocket Penetrometer test (test result in parentheses, tsf)
R-Value	Resistance Value test
SA	Sieve Analysis (-200 result in parentheses)
SE	Sand Equivalent test (test result in parentheses)
SWELL	Swell Load test (test result in parentheses)
TV	Torvane test (test result in parentheses, tsf)
-200	Percent passing #200 sieve (test result in parentheses)

KEY TO LOG OF BORING
 PROPOSED WEST CAMPUS INFRASTRUCTURE PROJECT
 UNION STATION
 LOS ANGELES, CALIFORNIA

Date(s) Drilled	10-14-02	Logged By	Jeff Pyska	Boring B-1 Sheet 1 of 1	
Drilling Method	Hollow Stem Auger	Drill Bit Size/Type	8-inch O.D.		
Drill Rig Type	B61	Hammer Data	140 lbs, 30-inch drop		
Sampling Method(s)	Dames & Moore Type-U, SPT, Bulk			Job Number	29401632.00001
Approximate Groundwater Depth and Date Measured	Groundwater encountered at 24 feet below ground surface on 10/14/2002			Total Depth Drilled (ft)	40.0
Comments	None			Approximate Ground Surface Elevation(ft)	278 feet MSL

Elevation (ft)	Depth (ft)	SAMPLES			USCS	MATERIAL DESCRIPTION	Moisture Content (%)	Dry Density (pcf)	OTHER TESTS and REMARKS
		Type	Number	Blows per 6-inch					
	0	☒ Bk-1			SM	About 2.5-inch thick Asphaltic Concrete			
	1	■	1	35		FILL Silty SAND mottled brown, loose to medium dense, moist, fine to coarse, with fine gravel Pieces of bricks in cuttings Grades dark gray, with trace asphalt	12	101	-200(26); +4(27)
	5	□		11			11		
	270	■	2	4					
		■	3	35/1*					
	10	☒	4	28	SM	ALLUVIUM Silty SAND brown, medium dense, slightly moist, fine to coarse, with fine to coarse gravel Gravel/rock powder in shoe	2		
	15	■	5	91/11*	SP-SM	SAND with silt brown, very dense, slightly moist, fine to coarse, with fine to coarse gravel	3	124	
	260								
	20	☒	6	50/5*					
	25	■	7	56		Grades wet	13	111	
	250								
	30	☒	8	56	SM	Silty SAND gray, very dense, wet, fine to coarse, with fine to coarse gravel			
	35	■	9	50/0*		Grades with coarse gravel and cobble			
	240								
	40	☒	10	50/2*					

This log is part of the report prepared by URS for this project and should be read together with the report. This summary applies only at the location of the exploration and at the time of drilling or excavation. Subsurface conditions may differ at other locations and may change at this location with time. Data presented are a simplification of actual conditions encountered.

LOG OF BORING
PROPOSED WEST CAMPUS INFRASTRUCTURE PROJECT
UNION STATION
LOS ANGELES, CALIFORNIA

FIGURE A-2

URS

1020312200514722

Date(s) Drilled	10-14-02	Logged By	Jeff Pyska	Boring B-2 Sheet 1 of 2	
Drilling Method	Hollow Stem Auger	Drill Bit Size/Type	8-inch O.D.		
Drill Rig Type	B61	Hammer Data	140 lbs, 30-inch drop		
Sampling Method(s)	Dames & Moore Type-U, SPT, Bulk			Job Number	29401632.00001
Approximate Groundwater Depth and Date Measured	Groundwater encountered at 40 feet below ground surface on 10/14/2002			Total Depth Drilled (ft)	51.5
Comments	None			Approximate Ground Surface Elevation(ft)	293 feet MSL

Elevation (ft)	Depth (ft)	SAMPLES			USCS	MATERIAL DESCRIPTION	Moisture Content (%)	Dry Density (pcf)	OTHER TESTS and REMARKS
		Type	Number	Blows per 6-inch					
0		☒ BK-1			SM	About 2.5-inch thick Asphaltic Concrete			
290						FILL Silty SAND brown, loose to medium dense, moist, fine to coarse, with fine gravel and pieces of brick			COMP DSCD
	5	☐ 1	14		ML	Sandy SILT olive-brown, medium dense, moist, fine to coarse, with trace fine gravel and pieces of siltstone	20		-200(57); +4(7)
	10	☐ 2	42			Grades mottled brown and gray, with fine to coarse gravel			
280		☐ 3	50/6*			Grades very dense	10		
	15	☐ 4	28		SM	ALLUVIUM Silty SAND gray, loose to medium dense, moist, fine to coarse, with trace fine gravel			
		☐ 5	8		ML	Grades with less silt and gravel Sandy SILT gray, medium dense, moist, fine			DSCD
270		☐ 6	35			White with black crystals rock in shoe			
	25	☐ 7	27		SM	Silty SAND light greenish-gray, medium dense, slightly moist, fine to coarse, with some fine to coarse gravel	4		
		☐ 8	79			Grades with some brown layers, dense			
		☐ 9	38		SP-SM	SAND with silt gray, dense, slightly moist, fine			
	30	☐ 10	36		SM	Silty SAND greenish-gray to gray, medium dense, slightly moist, fine to coarse, with some fine to coarse gravel	25	96	CON
260									
	35	☐ 11	50/5*			Grades greenish-gray to brown, very dense, with more sand	3		
40									

This log is part of the report prepared by URS for this project and should be read together with the report. This summary applies only at the location of the exploration and at the time of drilling or excavation. Subsurface conditions may differ at other locations and may change at this location with time. Data presented are a simplification of actual conditions encountered.

LOG OF BORING
PROPOSED WEST CAMPUS INFRASTRUCTURE PROJECT
UNION STATION
LOS ANGELES, CALIFORNIA

FIGURE A-3



1020312200514722

Elevation (ft)	Depth (ft)	SAMPLES			USCS	MATERIAL DESCRIPTION	Moisture Content (%)	Dry Density (pcf)	OTHER TESTS and REMARKS
		Type	Number	Blows per 6-inch					
40		■	12	64					
250					SM	Silty SAND greenish-gray to brown, dense, wet, fine to coarse, with fine to coarse gravel			
45		■	13	28	SP-SM	SAND with silt gray, medium dense, moist, fine to coarse, with trace fine gravel	12	112	-200(8); +4(7)
50		■	14	45			9		
240									
55									
60									
230									
65									
70									
220									
75									
80									
210									
85									
90									

Date(s) Drilled	10-16-02	Logged By	Jeff Pyska	Boring B-3 Sheet 1 of 2	
Drilling Method	Hollow Stem Auger	Drill Bit Size/Type	8-inch O.D.		
Drill Rig Type	B61	Hammer Data	140 lbs, 30-inch drop		
Sampling Method(s)	Dames & Moore Type-U, SPT, Bulk			Job Number	29401632.00001
Approximate Groundwater Depth and Date Measured	Groundwater encountered at 38 feet below ground surface on 10/16/2002			Total Depth Drilled (ft)	51.5
Comments	None			Approximate Ground Surface Elevation(ft)	293 feet MSL

Elevation (ft)	Depth (ft)	SAMPLES		Graphic Log	USCS	MATERIAL DESCRIPTION	Moisture Content (%)	Dry Density (pcf)	OTHER TESTS and REMARKS
		Type	Number						
0		☒ Bk-1			SM	About 2.5-inch thick Asphaltic Concrete			
						FILL Silty SAND brown, loose to medium dense, moist, fine to coarse, with fine to coarse gravel			CORR
290	5	☐ 1	11		CL	Sandy CLAY mottled brown and gray, stiff, moist, fine to coarse, with trace fine gravel and some organics	19		-200(61); +4(2)
	10	☐ 2	37			Grades very stiff, with some silty sand layers, some siltstone fragments, and no organics	23	103	-200(76); +4(2)
280		☐ 3	26				26		
	15					Grades with pieces of wood and brick in cuttings			
		☐ 5	22			Grades stiff, with large gravel particle in bottom ring and nothing in shoe	26	98	
	20	☐ 6	7		SM	ALLUVIUM Silty SAND dark gray, loose, moist, fine, with organics			
270									
	25	☐ 8	39			Grades gray, dense, fine to coarse, with fine to coarse gravel			
		☐ 9	50/4"			Grades gray to brown, very dense, slightly moist, coarse gravel in shoe	4	120	
	30	☐ 10	50/6"						
260									
	35	☐ 11	50/4"		SP-SM	SAND with silt gray, very dense, moist, fine to coarse, with fine to coarse gravel			
40									

This log is part of the report prepared by URS for this project and should be read together with the report. This summary applies only at the location of the exploration and at the time of drilling or excavation. Subsurface conditions may differ at other locations and may change at this location with time. Data presented are a simplification of actual conditions encountered.

LOG OF BORING
PROPOSED WEST CAMPUS INFRASTRUCTURE PROJECT
UNION STATION
LOS ANGELES, CALIFORNIA

FIGURE A-4



1020312200514722

Elevation (ft)	Depth (ft)	SAMPLES			USCS	MATERIAL DESCRIPTION	Moisture Content (%)	Dry Density (pcf)	OTHER TESTS and REMARKS
		Type	Number	Blows per 6-inch					
40		■	12	79/11*	SP-SM	SAND with silt gray, very dense, moist, fine to coarse, with fine to coarse gravel	8	128	
250									
45		■	13	50/6*					
50		■	14	69/11*					
240									
55									
60									
230									
65									
70									
220									
75									
80									
210									
85									
90									

Date(s) Drilled	10-16-02	Logged By	Jeff Pyska	Boring B-4 Sheet 1 of 2	
Drilling Method	Hollow Stem Auger	Drill Bit Size/Type	8-inch O.D.		
Drill Rig Type	B61	Hammer Data	140 lbs, 30-inch drop		
Sampling Method(s)	Dames & Moore Type-U, SPT, Bulk			Job Number	29401632.00001
Approximate Groundwater Depth and Date Measured	Groundwater encountered at 39 feet below ground surface on 10/16/2002			Total Depth Drilled (ft)	51.5
Comments	None			Approximate Ground Surface Elevation(ft)	293 feet MSL

Elevation (ft)	Depth (ft)	SAMPLES			USCS	MATERIAL DESCRIPTION	Moisture Content (%)	Dry Density (pcf)	OTHER TESTS and REMARKS
		Type	Number	Blows per 6-inch					
0		<input checked="" type="checkbox"/> Bk-1			SM	About 2.5-inch thick Asphaltic Concrete			
290						FILL Silty SAND brown to reddish-brown, loose to medium dense, moist, fine to coarse, with trace fine gravel			
	5	<input checked="" type="checkbox"/> 1	36				16	112	
	10	<input checked="" type="checkbox"/> 2	50/6*			Grades gray, moist, very dense, with asphalt and grass	11		
280						Pieces of brick and wood in cuttings			
	15	<input checked="" type="checkbox"/> 4	24		ML	SILT gray, black, and brown mottled, very stiff, moist, with fine to coarse sand and pieces of wood	16		
	20	<input checked="" type="checkbox"/> 6	21			Grades with pieces of wood and concrete			
270		<input type="checkbox"/> 7	50/6*		SM	ALLUVIUM Silty SAND grayish-brown, very dense, slightly moist, fine to coarse, with trace fine gravel			
	25	<input checked="" type="checkbox"/> 8	50/4*				4		
		<input type="checkbox"/> 9	82						
	30	<input checked="" type="checkbox"/> 10	50/6*						
260									
	35	<input checked="" type="checkbox"/> 11	89/11*			Grades gray, with fine to coarse gravel			
40									

This log is part of the report prepared by URS for this project and should be read together with the report. This summary applies only at the location of the exploration and at the time of drilling or excavation. Subsurface conditions may differ at other locations and may change at this location with time. Data presented are a simplification of actual conditions encountered.

LOG OF BORING
PROPOSED WEST CAMPUS INFRASTRUCTURE PROJECT
UNION STATION
LOS ANGELES, CALIFORNIA



FIGURE A-5

1020312200514722

Elevation (ft)	Depth (ft)	SAMPLES		Graphic Log	USCS	MATERIAL DESCRIPTION	Moisture Content (%)	Dry Density (pcf)	OTHER TESTS and REMARKS
		Type	Number	Blows per 6-inch					
40		■	12	53	SM	Silty SAND gray, very dense, moist, fine to coarse, with fine to coarse gravel			
250									
45		■	13	50/5*	SP-SM	SAND with silt gray, very dense, wet, fine to coarse, with fine gravel			
50		■	14						Sample may contain slough
240									
55									
60									
230									
65									
70									
220									
75									
80									
210									
85									
90									

Date(s) Drilled	10-14-02	Logged By	Jeff Pyska	Boring B-6 Sheet 1 of 2	
Drilling Method	Hollow Stem Auger	Drill Bit Size/Type	8-inch O.D.		
Drill Rig Type	B61	Hammer Data	140 lbs, 30-inch drop		
Sampling Method(s)	Dames & Moore Type-U, SPT, Bulk			Job Number	29401632.00001
Approximate Groundwater Depth and Date Measured	Groundwater encountered at 24 feet below ground surface on 10/14/2002			Total Depth Drilled (ft)	51.0
Comments	None			Approximate Ground Surface Elevation(ft)	278 feet MSL

Elevation (ft)	Depth (ft)	SAMPLES		Graphic Log	USCS	MATERIAL DESCRIPTION	Moisture Content (%)	Dry Density (pcf)	OTHER TESTS and REMARKS
		Type	Number						
	0	☒ Bk-1			SM	About 2.5-inch thick Asphaltic Concrete			
		█ 1	9		ML	FILL Silty SAND brown, moist, fine to coarse, with fine gravel	25		-200(76); +4(0) CORR
	5	☒ 2	26		SM	Sandy SILT grayish-brown, loose, moist, fine to coarse, with trace fine to coarse gravel and some clay	3	92	
270		█ 3	35			ALLUVIUM Silty SAND brown, medium dense to dense, moist, fine to coarse, with some fine to coarse gravel and trace clay	2		
	10	█ 4	63			Grades with iron-oxide staining and trace gray clay/silt chunks			
	15	█ 5	50/6"			Grades very dense, without clay/silt chunks	4		-200(9); +4(39)
260		█ 6	50/6"			Grades gray	3	115	
	25	█ 7	37			Grades dense, wet	12		
250		█ 8	31		ML	Sandy SILT greenish-gray, medium dense, wet, fine to coarse, with fine to coarse gravel and some clay			CON, DSCD
	35	█ 9	5			Grades loose	45		-200(92); +4(0)
240					SP	SAND			
40									

This log is part of the report prepared by URS for this project and should be read together with the report. This summary applies only at the location of the exploration and at the time of drilling or excavation. Subsurface conditions may differ at other locations and may change at this location with time. Data presented are a simplification of actual conditions encountered.

LOG OF BORING
PROPOSED WEST CAMPUS INFRASTRUCTURE PROJECT
UNION STATION
LOS ANGELES, CALIFORNIA

FIGURE A-7

Elevation (ft)	Depth (ft)	SAMPLES		Graphic Log	USCS	MATERIAL DESCRIPTION	Moisture Content (%)	Dry Density (pcf)	OTHER TESTS and REMARKS
		Type	Number	Blows per 6-inch					
	40	■	10	36	SP	SAND gray, medium dense, wet, fine to coarse			
	45	▣	11	56	SM	Silty SAND gray to greenish-gray, very dense, wet, fine to coarse, with some fine gravel			
230									
	50	⊗	12	50/6*			12		
	55								
220									
	60								
	65								
210									
	70								
	75								
200									
	80								
	85								
190									
	90								

Date(s) Drilled	10-16-02	Logged By	Jeff Pyska	Boring B-7 Sheet 1 of 1	
Drilling Method	Hollow Stem Auger	Drill Bit Size/Type	8-inch O.D.		
Drill Rig Type	B61	Hammer Data	140 lbs, 30-inch drop		
Sampling Method(s)	Dames & Moore Type-U, SPT, Bulk			Job Number	29401632.00001
Approximate Groundwater Depth and Date Measured	No groundwater encountered			Total Depth Drilled (ft)	16.0
Comments	None			Approximate Ground Surface Elevation(ft)	278 feet MSL

Elevation (ft)	Depth (ft)	SAMPLES		Graphic Log	USCS	MATERIAL DESCRIPTION	Moisture Content (%)	Dry Density (pcf)	OTHER TESTS and REMARKS
		Type	Number						
	0	☒ Bk-1			SM	About 4-inch thick Asphaltic Concrete over 2-inch thick Base			
	1	☑ 1	4		ML	<u>FILL</u> Silty SAND reddish-brown, moist, fine to coarse, with trace fine to coarse gravel and brick fragments	13		-200(37); +4(18)
	5	☑ 2	35		SP-SM	Sandy SILT dark brown, loose, moist, fine to coarse	8	115	
270	10	☑ 3	34			<u>ALLUVIUM</u> SAND with silt yellowish-brown, medium dense to dense, moist, fine to coarse, with some fine to coarse gravel			
	15	☑ 4	50/5*			Grades very dense			
	20	☑ 5	50/5*				5		
260	25								
250	30								
	35								
240	40								

This log is part of the report prepared by URS for this project and should be read together with the report. This summary applies only at the location of the exploration and at the time of drilling or excavation. Subsurface conditions may differ at other locations and may change at this location with time. Data presented are a simplification of actual conditions encountered.

LOG OF BORING
PROPOSED WEST CAMPUS INFRASTRUCTURE PROJECT
UNION STATION
LOS ANGELES, CALIFORNIA



FIGURE A-8

1020312200514/22

Date(s) Drilled	10-16-02	Logged By	Jeff Pyska	Boring B-8 Sheet 1 of 1	
Drilling Method	Hollow Stem Auger	Drill Bit Size/Type	8-inch O.D.		
Drill Rig Type	B61	Hammer Data	140 lbs, 30-inch drop		
Sampling Method(s)	Dames & Moore Type-U, SPT, Bulk			Job Number	29401632.00001
Approximate Groundwater Depth and Date Measured	No groundwater encountered			Total Depth Drilled (ft)	16.5
Comments	None			Approximate Ground Surface Elevation(ft)	278 feet MSL

Elevation (ft)	Depth (ft)	SAMPLES		Graphic Log	USCS	MATERIAL DESCRIPTION	Moisture Content (%)	Dry Density (pcf)	OTHER TESTS and REMARKS
		Type	Number	Blows per 6-inch					
	0	☑ Bk-1			SM	About 4-inch thick Asphaltic Concrete			
	1	■	1	19		<u>FILL</u> Silty SAND brown to dark brown, loose, moist, fine to coarse, with fine to coarse gravel and concrete debris			
	5	☑	2	25	SM	<u>ALLUVIUM</u> Silty SAND brown to yellowish-brown, medium dense, slightly moist, fine to coarse, with fine to coarse gravel	2		
270	3	■	3	26	SP-SM	SAND with silt brown, medium dense, slightly moist, fine to coarse, with trace fine gravel	4	96	
10	4	☑	4	10					
15	5	■	5	24		Grades yellowish-brown, moist, with some silt lenses, and iron-oxide staining	8	100	
260									
20									
25									
250									
30									
35									
240									
40									

This log is part of the report prepared by URS for this project and should be read together with the report. This summary applies only at the location of the exploration and at the time of drilling or excavation. Subsurface conditions may differ at other locations and may change at this location with time. Data presented are a simplification of actual conditions encountered.














LOG OF BORING
PROPOSED WEST CAMPUS INFRASTRUCTURE PROJECT
UNION STATION
LOS ANGELES, CALIFORNIA

FIGURE A-9

URS

1020312200514722

SOIL CLASSIFICATION CHART

MAJOR DIVISIONS			SYMBOLS		TYPICAL DESCRIPTIONS
COARSE GRAINED SOILS MORE THAN 50% OF MATERIAL IS LARGER THAN NO. 200 SIEVE SIZE	GRAVEL AND GRAVELLY SOILS MORE THAN 50% OF COARSE FRACTION RETAINED ON NO. 4 SIEVE	CLEAN GRAVELS (LITTLE OR NO FINES)		GW	WELL-GRADED GRAVELS, GRAVEL - SAND MIXTURES, LITTLE OR NO FINES
		GRAVELS WITH FINES (APPRECIABLE AMOUNT OF FINES)		GP	POORLY GRADED GRAVELS, GRAVEL - SAND MIXTURES, LITTLE OR NO FINES
				GM	SILTY GRAVELS, GRAVEL - SAND - SILT MIXTURES
	SAND AND SANDY SOILS MORE THAN 50% OF COARSE FRACTION PASSING NO. 4 SIEVE	CLEAN SANDS (LITTLE OR NO FINES)			SW
		SANDS WITH FINES (APPRECIABLE AMOUNT OF FINES)		SP	POORLY GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES
				SM	SILTY SANDS, SAND - SILT MIXTURES
FINE GRAINED SOILS MORE THAN 50% OF MATERIAL IS SMALLER THAN NO. 200 SIEVE SIZE	SILTS AND CLAYS LIQUID LIMIT LESS THAN 50			ML	INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS OR CLAYEY SILTS WITH SLIGHT PLASTICITY
				CL	INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS
				OL	ORGANIC SILTS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY
	SILTS AND CLAYS LIQUID LIMIT GREATER THAN 50			MH	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SANDY OR SILTY SOILS, ELASTIC SILTS
				CH	INORGANIC CLAYS OF HIGH PLASTICITY
				OH	ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS
HIGHLY ORGANIC SOILS				PT	PEAT, HUMUS, SWAMP SOILS WITH HIGH ORGANIC CONTENTS

NOTE: Dual symbols are used to indicate gravels or sand with 5-12% fines and soils with fines classifying as CL-ML. Symbols separated by a slash indicate borderline soil classifications.

Sampler and Symbol Descriptions

- ☒ Dames & Moore Type-U sample
- ☒ Standard Penetration Test
- ☐ No Recovery
- Bk ☒ Bulk sample
- ☒ Disturbed Type-U Sample
- ☐ Pitcher Tube Sample
- ☐ Shelby Tube Sample
- ☐ Rock Core Sample
- ☒ Approximate depth of perched water or groundwater

Note: Number of blows required to advance driven sample 12" (or length noted) is recorded.

Laboratory and Field Test Abbreviations

CBR	California Bearing Ratio Test
COL	Collapse Potential test (test result in parentheses)
COMP	Compaction test
CON	Consolidation test
CORR	Corrosivity test
DSCD	Consolidated drained direct shear test (normal pressure and shear strength results shown)
EI	Expansion Index test (test result in parentheses)
LL=29	Liquid limit (Atterberg limits test)
PI=11	Plasticity Index (Atterberg limits test)
PP	Pocket Penetrometer test (test result in parentheses, tsf)
R-Value	Resistance Value test
SA	Sieve Analysis (-200 result in parentheses)
SE	Sand Equivalent test (test result in parentheses)
SWELL	Swell Load test (test result in parentheses)
TV	Torvane test (test result in parentheses, tsf)
-200	Percent passing #200 sieve (test result in parentheses)

KEY TO LOG OF BORING
 PROPOSED 3-STORY OFFICE BUILDING
 LOS ANGELES, CALIFORNIA
 FOR: CATELLUS DEVELOPMENT CORPORATION

Date(s) Drilled	9/11/01	Logged By	TO	Boring BH-1 Sheet 1 of 2	
Drilling Method	Hollow-Stem Auger	Drill Bit Size/Type	Drag		
Drill Rig Type	Mobile Drill B-61	Hammer Data	140-lbs Hammer / 30-inch drop		
Sampling Method(s)	Dames & Moore Type U, SPT, Bulk			Job Number	59-00112046.01
Approximate Groundwater Depth and Date Measured	Not encountered			Total Depth Drilled (ft)	51.5
Comments	None			Approximate Ground Surface Elevation(ft)	278

Elevation (ft)	Depth (ft)	SAMPLES		Graphic Log	USCS	MATERIAL DESCRIPTION	Moisture Content (%)	Dry Density (pcf)	OTHER TESTS and REMARKS
		Type	Number						
0						4-inch Asphalt over 6-inch base material			
		☒ Bk-1			SM	ARTIFICIAL FILL (Af): Dark brown silty fine to medium SAND, moist (loose)			
5		■ 1	23				7	107	
270					SP	ALLUVIUM (Qal): Dark gray fine to coarse SAND with fine gravel, moist (medium dense)			
10		□ 2	23						
15		■ 3	100/8"			Grades medium to coarse sand with fine gravel (very dense)	3		DSCD -200(5)
260									
20		▣ 4	52			PUENTE FORMATION (Tp): Dark olive-gray SILTSTONE and CLAYSTONE, moist (weathered)			
25		■ 5	50/2"						
250									
30		▣ 6	50/6"			Grades with clasts			
35		■ 7	50/5"						
240									
40									

This log is part of the report prepared by URS for this project and should be read together with the report. This summary applies only at the location of the exploration and at the time of drilling or excavation. Subsurface conditions may differ at other locations and may change at this location with time. Data presented are a simplification of actual conditions encountered.

LOG OF BORING
PROPOSED 3-STORY OFFICE BUILDING
LOS ANGELES, CALIFORNIA
FOR: CATELLUS DEVELOPMENT CORPORATION

URS

Figure A-1

1020312200514722

Elevation (ft)	Depth (ft)	SAMPLES		Graphic Log	USCS	MATERIAL DESCRIPTION	Moisture Content (%)	Dry Density (pcf)	OTHER TESTS and REMARKS
		Type	Number	Blows per foot					
40		8	80						
45		9	32			Grades olive-brown			
230									
50		10	70/10*			Becomes interbedded with SANDSTONE, thinly bedded, bedding inclined about 40 degrees from horizontal			
						Boring completed to a depth of 51.5 feet below the existing ground surface. Borehole backfilled with soil cuttings on 9/11/01.			
55									
220									
60									
65									
210									
70									
75									
200									
80									
85									
190									
90									

Date(s) Drilled	9/11/01	Logged By	TO	Boring BH-2 Sheet 1 of 2	
Drilling Method	Hollow-Stem Auger	Drill Bit Size/Type	Drag		
Drill Rig Type	Mobile Drill B-61	Hammer Data	140-lbs Hammer / 30-inch drop		
Sampling Method(s)	Dames & Moore Type U, SPT			Job Number	59-00112046.01
Approximate Groundwater Depth and Date Measured	24.5 feet			Total Depth Drilled (ft)	50.9
Comments	None			Approximate Ground Surface Elevation(ft)	278

Elevation (ft)	Depth (ft)	SAMPLES		Graphic Log	USCS	MATERIAL DESCRIPTION	Moisture Content (%)	Dry Density (pcf)	OTHER TESTS and REMARKS
		Type	Number	Blows per foot					
0					SM	4-inch of asphalt over 6-inch of base material ARTIFICIAL FILL (Af): Dark brown moist silty fine to medium SAND with gravel to 0.5 inches, moist (medium dense)			
5		□	1	29	CL	Dark brown silty CLAY with coarse sand, moist (stiff)			
270		■	2	42	SP	ALLUVIUM (Ga): Yellowish-brown fine to medium SAND with trace coarse sand, moist (medium dense)	3	108	DSCD
10		▣	3	11	ML	Dark brown fine to medium sandy SILT, wet (medium dense)	12		
15		■	4	50/6"	SP	Yellowish-brown fine to medium SAND with trace gravel up to 2-inch, moist (very dense)	3	97	
260		▣	5	50/6"					
25					CL	Light brown silty CLAY, wet (hard)			
250		■	6			Grades bluish-gray			
30		▣	7	79		PUENTE FORMATION (Tp): Dark olive-gray interbedded CLAYSTONE and SANDSTONE, wet (weathered)			
35		■	8	50/4"					
240									
40									

This log is part of the report prepared by URS for this project and should be read together with the report. This summary applies only at the location of the exploration and at the time of drilling or excavation. Subsurface conditions may differ at other locations and may change at this location with time. Data presented are a simplification of actual conditions encountered.

LOG OF BORING

PROPOSED 3-STORY OFFICE BUILDING
LOS ANGELES, CALIFORNIA

FOR: CATELLUS DEVELOPMENT CORPORATION

URS

Figure A-2

1020312200514722

LOS ANGELES, CALIFORNIA
FOR: CATELLUS DEVELOPMENT CORPORATION

Boring BH-2
Sheet 2 of 2

Elevation (ft)	Depth (ft)	SAMPLES		Graphic Log	USCS	MATERIAL DESCRIPTION	Moisture Content (%)	Dry Density (pcf)	OTHER TESTS and REMARKS
		Type	Number						
	40	■	9	50/6"					
	45	■	10	100/10"		Grades black SILTSTONE with fine sand			
230	50	■	11	50/5"		Grades dark gray			
	55					Boring completed to a depth of 51 feet below the existing ground surface. Borehole backfilled with soil cuttings 9/11/01.			
220	60								
	65								
210	70								
	75								
200	80								
	85								
190	90								

Report: DMG4; Project File: G:\GINT\PROJECTS\UNION2.GPJ; Data Template: DMLA.GDT Printed: 10/30/02

Date(s) Drilled	9/11/01	Logged By	TO	Boring BH-3 Sheet 1 of 2	
Drilling Method	Hollow-Stem Auger	Drill Bit Size/Type	Drag		
Drill Rig Type	Mobile Drill B-61	Hammer Data	140-lbs Hammer / 30-inch drop		
Sampling Method(s)	Dames & Moore Type U, SPT			Job Number	59-00112046.01
Approximate Groundwater Depth and Date Measured	20 feet			Total Depth Drilled (ft)	51.0
Comments	None			Approximate Ground Surface Elevation(ft)	278

Elevation (ft)	Depth (ft)	SAMPLES		Graphic Log	USCS	MATERIAL DESCRIPTION	Moisture Content (%)	Dry Density (pcf)	OTHER TESTS and REMARKS
		Type	Number	Blows per foot					
0						4-inch of Asphalt over 6-inch of base material			
					SM	ARTIFICIAL FILL (Af): Dark brown silty fine to medium SAND with gravel up to 0.5-inch, moist (loose to medium dense)			
5		■	1	27					
					SP	ALLUVIUM (Qal): Yellowish-brown fine to medium SAND, slightly moist (loose)			DSCD CORR
					SP-SC	Dark brown fine to medium SAND with clay, moist (medium dense)			
270									
		▣	2	45		SP	Yellowish-brown fine to coarse SAND with fine to coarse gravel, slightly moist (dense)	3	SA(3) CORR
15		■	3	50/5*			3	93	CON
260									
		▣	4	50		PUENTE FORMATION (Tp): Yellowish-brown SANDSTONE and bluish-gray SILTSTONE, thinly bedded, moist (weathered)			
25		■	5	50/5*		Becomes wet, less weathered	27	95	CON
250									
		▣	6	50					
35		■	7	100/8*					
240									
40									

This log is part of the report prepared by URS for this project and should be read together with the report. This summary applies only at the location of the exploration and at the time of drilling or excavation. Subsurface conditions may differ at other locations and may change at this location with time. Data presented are a simplification of actual conditions encountered.

LOG OF BORING

PROPOSED 3-STORY OFFICE BUILDING
LOS ANGELES, CALIFORNIA

FOR: CATELLUS DEVELOPMENT CORPORATION

URS

Figure A-3

1020312200514722

LOS ANGELES, CALIFORNIA
FOR: CATELLUS DEVELOPMENT CORPORATION

Boring BH-3
Sheet 2 of 2

Elevation (ft)	Depth (ft)	SAMPLES		Graphic Log	USCS	MATERIAL DESCRIPTION	Moisture Content (%)	Dry Density (pct)	OTHER TESTS and REMARKS
		Type	Number	Blows per foot					
40		■	8	85					Bedding inclined at about 30 to 35 degrees from horizontal
45		■	9	50/6"					Bedding inclined at about 65 to 70 degrees from horizontal
230									
50		■	10	50					
						Boring completed to a depth of 51 feet below the existing ground surface. Borehole backfilled with soil cuttings 9/11/01.			
55									
220									
60									
65									
210									
70									
75									
200									
80									
85									
190									
90									

Report: DMG4; Project File: G:\GINT\PROJECTS\UNION2.GPJ; Data Template: DMLA.GDT Printed: 10/30/02

Date(s) Drilled	9/11/01	Logged By	TO	Boring BH-4 Sheet 1 of 2	
Drilling Method	Hollow-Stem Auger	Drill Bit Size/Type	Drag		
Drill Rig Type	Mobile Drill B-61	Hammer Data	140-lbs Hammer / 30-inch drop		
Sampling Method(s)	Dames & Moore Type U, SPT			Job Number	59-00112046.01
Approximate Groundwater Depth and Date Measured	19.5 feet			Total Depth Drilled (ft)	50.9
Comments	None			Approximate Ground Surface Elevation(ft)	278

Elevation (ft)	Depth (ft)	SAMPLES		Graphic Log	USCS	MATERIAL DESCRIPTION	Moisture Content (%)	Dry Density (pcf)	OTHER TESTS and REMARKS
		Type	Number	Blows per foot					
0						4-inch of Asphalt over 6-inch of base material			
					SM	ARTIFICIAL FILL (Af): Dark brown silty fine to medium SAND with gravel up to 2.5-inch, moist (loose)			
	5	■	1	20		Grades brown	12	116	-200(30)
270					SP	ALLUVIUM (Qal): Yellowish-brown fine SAND with trace coarse sand and fine to coarse gravel, moist (dense)			
	10	▣	2	40			3		
	15	■	3	50/4*			5	116	
260									
	20	▣	4	38		PUENTE FORMATION (Tp): Gray CLAYSTONE and yellowish-brown SANDSTONE, thinly bedded, wet (weathered)			Bedding inclined at about 50 to 60 degrees from horizontal
	25	■	5	50/5*					
250									
	30	▣	6	65		Grades light bluish-gray and dark gray			
	35	■	7	50/4*					
240									
40									

This log is part of the report prepared by URS for this project and should be read together with the report. This summary applies only at the location of the exploration and at the time of drilling or excavation. Subsurface conditions may differ at other locations and may change at this location with time. Data presented are a simplification of actual conditions encountered.

LOG OF BORING

PROPOSED 3-STORY OFFICE BUILDING
LOS ANGELES, CALIFORNIA

FOR: CATELLUS DEVELOPMENT CORPORATION

URS

Figure A-4

1020312200514722

LOS ANGELES, CALIFORNIA
FOR: CATELLUS DEVELOPMENT CORPORATION

Boring BH-4
Sheet 2 of 2

Elevation (ft)	Depth (ft)	SAMPLES		Graphic Log	USCS	MATERIAL DESCRIPTION	Moisture Content (%)	Dry Density (pcf)	OTHER TESTS and REMARKS
		Type	Number	Blows per foot					
40		■	8	50/5					
45		■	9	50/4*					
230									
50		■	10	50/5*					
						Boring completed to a depth of 51 feet below the existing ground surface. Borehole backfilled with soil cuttings 9/11/01.			
55									
220									
60									
65									
210									
70									
75									
200									
80									
85									
190									
90									

Report: DMG4; Project File: G:\GINTWP\PROJECTS\UNION2.GPJ; Data Template: DMLA.GDT Printed: 10/30/02

Date(s) Drilled	5/22/01	Logged By	KK - AP Engineering	Boring BH-1 Sheet 1 of 2	
Drilling Method	Hollow-Stem Auger	Drill Bit Size/Type	8-inch O.D.		
Drill Rig Type	Mobile Drill B-61	Hammer Data	140 lbs, 30-inch drop		
Sampling Method(s)	Dames & Moore Type U, SPT, Bulk			Job Number	59-00112046.01
Approximate Groundwater Depth and Date Measured	Encountered at 24.0 feet, 5/22/01			Total Depth Drilled (ft)	50.5
None				Approximate Ground Surface Elevation(ft)	278.0

Elevation (ft)	Depth (ft)	SAMPLES		Graphic Log	USCS	MATERIAL DESCRIPTION	Moisture Content (%)	Dry Density (pcf)	OTHER TESTS and REMARKS
		Type	Number						
0					SM	5-inches Asphalt Grayish-brown, silty fine SAND with gravel, dry (medium dense)			
	22	☒							SA(13)
5	41	■			SP-SM	Brown, fine SAND with silt and gravel to 3/4-inch, medium to coarse, dry (medium dense)	2	119	
270									
10	46	☒				Becomes yellowish-brown to grayish-brown (dense)	3		SA(5)
15	50/4"	■			SP	Yellowish-brown, poorly graded SAND with gravel to 3/8-inch, medium to coarse, moist (very dense)	8	104	-200(4), DS
260									
20	50/4"	□							No recovery @ 20'
25	60	■			ML	Gray, sandy SILT, moist (dense) Becomes wet	29	96	-200(78), DS, CON
250									
30	70	☒			SP	Gray, poorly graded SAND, medium, trace gravel, wet (very dense)	13		-200(2)
35	100/5"	■				Becomes coarse with more gravel	14	119	
240									
40									

This log is part of the report prepared by Dames & Moore for this project and should be read together with the report. This summary applies only at the location of the exploration and at the time of drilling or excavation. Subsurface conditions may differ at other locations and may change at this location with time. Data presented are a simplification of actual conditions encountered.

LOG OF BORING
ONE UNION STATION PLAZA
LOS ANGELES, CALIFORNIA
FOR: CATELLUS DEVELOPMENT CORPORATION

LOS ANGELES, CALIFORNIA
FOR: CATELLUS DEVELOPMENT CORPORATION

Boring BH-1
Sheet 2 of 2

Elevation (ft)	Depth (ft)	SAMPLES			USCS	MATERIAL DESCRIPTION	Moisture Content (%)	Dry Density (pcf)	OTHER TESTS and REMARKS
		Type	Number	Blows per foot					
	40	■		50/5"			17		
	45	■		50/1"	SM	Gray, silty fine to medium SAND, wet (very dense)	19	108	DS, CON
230					SP-SM	Gray, fine to medium SAND with silt, wet (very dense)			
	50	■		50/6"		Borehole completed to a depth of 50 1/2 feet below the ground surface on 05/22/01. Borehole backfilled with soil cuttings.	24		
	55								
220									
	60								
	65								
210									
	70								
	75								
200									
	80								
	85								
190									
	90								

DMG4 UNION_-1.GPJ DMLA.GDT 7/23/01

Date(s) Drilled	5/22/01	Logged By	KK - AP Engineering	Boring BH-2 Sheet 1 of 2	
Drilling Method	Hollow-Stem Auger	Drill Bit Size/Type	8-inch O.D.		
Drill Rig Type	Mobile Drill B-61	Hammer Data	140 lbs, 30-inch drop		
Sampling Method(s)	Dames & Moore Type U, SPT, Bulk			Job Number	59-00112046.01
Approximate Groundwater Depth and Date Measured	Encountered at 30.0 feet, 5/22/01			Total Depth Drilled (ft)	50.8
None				Approximate Ground Surface Elevation(ft)	278.0

Elevation (ft)	SAMPLES			USCS	MATERIAL DESCRIPTION	Moisture Content (%)	Dry Density (pcf)	OTHER TESTS and REMARKS
	Type	Number	Blows per foot					
0					4-inches Asphalt over 3-inches of Base			
2	☒		24	SM	Dark grayish-brown, silty fine to medium SAND with fine gravel, moist (medium dense)	14	117	
5	☑		53	SP-SM	Grayish-brown, medium SAND with silt and gravel to 3/8-inch, moist (medium dense)		118	
10	■		62	SM	Grayish-brown, silty medium to coarse SAND, moist (dense)	8		-200(17)
15	☑		50	SP-SM	Olive-brown, medium SAND with silt and fine gravel, moist (very dense)	4		CORR
20	■		50/2"		Becomes yellowish-brown, gravel to 3/4-inch	6		-200(7)
25	☑		30			22		
30	■		36	ML	Gray, sandy SILT, moist (medium dense)			
32					Becomes wet	38	79	LL=44, PI=15 -200(88), DS, CON
35	☑		70	SP	Gray, poorly graded SAND with gravel, medium, wet (very dense)	9		-200(4)

This log is part of the report prepared by Dames & Moore for this project and should be read together with the report. This summary applies only at the location of the exploration and at the time of drilling or excavation. Subsurface conditions may differ at other locations and may change at this location with time. Data presented are a simplification of actual conditions encountered.

LOG OF BORING
ONE UNION STATION PLAZA
LOS ANGELES, CALIFORNIA
FOR: CATELLUS DEVELOPMENT CORPORATION

URS

1020312200514722

LOS ANGELES, CALIFORNIA
FOR: CATELLUS DEVELOPMENT CORPORATION

Boring BH-2
Sheet 2 of 2

Elevation (ft)	Depth (ft)	SAMPLES			USCS	MATERIAL DESCRIPTION	Moisture Content (%)	Dry Density (pcf)	OTHER TESTS and REMARKS
		Type	Number	Blows per foot					
40		■		50/2"		Becomes fine to medium	17	117	
45		■		40	SP-SM	Gray, medium SAND with silt, trace gravel, wet (dense)	18		-200(7)
230									
50		■		50/3"		Becomes very dense	18	112	DS
						Borehole completed to a depth of 50 3/4 feet below the ground surface on 05/22/01. Borehole backfilled with soil cuttings.			
55									
220									
60									
65									
210									
70									
75									
200									
80									
85									
190									
90									

DMG4 UNION -1.GPJ DMLA GDT 7/23/01

URS

1020312200514722

Date(s) Drilled	5/22/01	Logged By	KK - AP Engineering	Boring BH-3 Sheet 1 of 1	
Drilling Method	Hollow-Stem Auger	Drill Bit Size/Type	8-inch O.D.		
Drill Rig Type	Mobile Drill B-61	Hammer Data	140 lbs, 30-inch drop		
Sampling Method(s)	Dames & Moore Type U, SPT, Bulk			Job Number	59-00112046.01
Approximate Groundwater Depth and Date Measured	Encountered at 24.0 feet, 5/22/01			Total Depth Drilled (ft)	36.0
None				Approximate Ground Surface Elevation(ft)	278.0

Elevation (ft)	Depth (ft)	SAMPLES		Graphic Log	USCS	MATERIAL DESCRIPTION	Moisture Content (%)	Dry Density (pcf)	OTHER TESTS and REMARKS
		Type	Number						
	0				SM	4-inches Asphalt Dark brown, silty fine to medium SAND, moist (medium dense)			
	17								
	5		32		SP	Yellowish-brown, poorly graded SAND with gravel to 3/4-inch, medium, dry (medium dense)	2	115	-200(2)
270	10		57			Gravel to 3/8-inch (very dense)	2		
	15		50/1"		SP-SM	Brown, medium to coarse SAND with silt and gravel to 3/8-inch, dry (very dense)	3	112	-200(6)
260	20		50/6"			Becomes grayish-brown, medium	3		
	25		50/5"			Becomes wet	20	100	DS
250	30		50/6"			Becomes gray	11		-200(7)
	35		50/2"				16	108	Drill chatter @ 35' DS
240	40					Borehole terminated due to refusal at a depth of 36 feet below the ground surface on 05/22/01. Borehole backfilled with soil cuttings.			

This log is part of the report prepared by Dames & Moore for this project and should be read together with the report. This summary applies only at the location of the exploration and at the time of drilling or excavation. Subsurface conditions may differ at other locations and may change at this location with time. Data presented are a simplification of actual conditions encountered.

LOG OF BORING
ONE UNION STATION PLAZA
LOS ANGELES, CALIFORNIA
FOR: CATELLUS DEVELOPMENT CORPORATION

URS

1020312200514722

Date(s) Drilled	5/22/01	Logged By	KK - AP Engineering	Boring BH-4 Sheet 1 of 2	
Drilling Method	Hollow-Stem Auger	Drill Bit Size/Type	8-inch O.D.		
Drill Rig Type	Mobile Drill B-61	Hammer Data	140 lbs, 30-inch drop		
Sampling Method(s)	Dames & Moore Type U, SPT, Bulk			Job Number	59-00112046.01
Approximate Groundwater Depth and Date Measured	Encountered at 29.0 feet, 5/22/01			Total Depth Drilled (ft)	50.9
None				Approximate Ground Surface Elevation(ft)	278.0

Elevation (ft)	SAMPLES			USCS	MATERIAL DESCRIPTION	Moisture Content (%)	Dry Density (pcf)	OTHER TESTS and REMARKS
	Type	Number	Blows per foot					
0					5-inches Asphalt over 5-inches Base			
	☒		15	SP-SM	Grayish-brown, fine SAND with silt, dry (loose)	6	115	
5	☑		24		Becomes medium with gravel to 3/8-inch (medium dense)	2		
270				SM	Brown, silty medium SAND with gravel to 3/8-inch, moist (dense)			
10	■		67			16	106	-200(34)
				SP-SM	Grayish-brown, medium SAND with silt and gravel to 3/8-inch, dry (very dense)			
15	☑		50/6"			3		CORR
260				SM	Gray, silty fine SAND, moist (medium dense)			
20	■		45			27	98	-200(45), DS, CON
				SP-SM	Gray, medium SAND with silt, moist (dense)			
25	☑		31			11		
250				ML	Gray, sandy SILT, very moist (medium dense)			
30	☑		19		Becomes wet	34		-200(84)
				SP-SM	Gray, medium SAND with silt and gravel, wet (very dense)			
35	☑		55			10		-200(7)
240								
40								

This log is part of the report prepared by Dames & Moore for this project and should be read together with the report. This summary applies only at the location of the exploration and at the time of drilling or excavation. Subsurface conditions may differ at other locations and may change at this location with time. Data presented are a simplification of actual conditions encountered.

LOG OF BORING
ONE UNION STATION PLAZA
LOS ANGELES, CALIFORNIA
FOR: CATELLUS DEVELOPMENT CORPORATION

URS

1020312200514722

Elevation (ft)	Depth (ft)	SAMPLES		Graphic Log	USCS	MATERIAL DESCRIPTION	Moisture Content (%)	Dry Density (pcf)	OTHER TESTS and REMARKS
		Type	Number						
	40	■	49				18		-200(7)
	45	■	50/5"		ML	Gray, sandy SILT, wet (very dense)	12		
230	50	■	50/5"						
						Borehole completed to a depth of 51 feet below the ground surface on 05/22/01. Borehole backfilled with soil cuttings.			
	55								
220	60								
	65								
210	70								
	75								
200	80								
	85								
190									
	90								

DMG4 UNION_-1.GPJ DMLA.GDT 7/23/01

Existing Geotechnical Boring Logs

Law Crandall, 1997

ELEVATION (ft.)	DEPTH (ft.)	MOISTURE (% of dry wt.)	DRY DENSITY (lbs./cu. ft.)	O.V.A.*** (ppm)	"N" VALUE STD.PEN.TEST	BLOW COUNT* (blows/ft.)	SAMPLE LOC.
270	5	23.2	89	0		23	ML
		19.5	104	0		14	ML
265	10	--	--	0		16	SP
260	15	1.7	106	0		41	
255	20	9.9	105	0		105	
250	25	--	--			100	
		--	--			75 for 4"	
245	30	27.0	93	> 1000		76	
240	35	30.3	90	> 1000		79	
235	40	33.6	84	> 1000		55	

BORING 1

DATE DRILLED: August 19, 1997
EQUIPMENT USED: 8" - Diameter Hollow Stem Auger

ELEVATION: 275**

3" Asphalt Paving
ARTIFICIAL FILL (af)
CLAYEY SILT - some bedrock fragments, some roots,
light brown

SANDY SILT - brown

ALLUVIUM (Qal)
SAND - fine to coarse, some Gravel, few Cobbles (to
6" in size), brown
Sample not recovered

Some Silt

SAN PEDRO FORMATION (Qsp)
SILT - bedded, lenses of fine Sand, dark grey

Sample not recovered

Sample not recovered
Some Clay
Some sulfur odor

* Number of blows required to drive the Standard
sampler 12 inches using a 140 pound hammer
falling 30 inches.

** See Plot Plan for location of bench mark

*** OVA Gastechtor Model No. 1238 used

NOTE: Water not encountered.

END OF BORING AT 40'.

LOG OF BORING

LAW/CRANDALL



ELEVATION (ft.)	DEPTH (ft.)	MOISTURE (% of dry wt.)	DRY DENSITY (lbs./cu. ft.)	O.V.A.*** (ppm)	"N" VALUE STD.PEN.TEST	BLOW COUNT* (blows/ft.)	SAMPLE LOC.
		12.1	114	0		1	SM
		4.8	119	0		1	
270	5	2.3	111	0		4	SW
		2.1	122	20		6	
265	10						
		2.9	128	30		5	
260	15	8.1	133	0		12	
255	20			0	100		SP-SM
		16.4	116	0		68+	SW
250	25			0	90		
		24.1	98	0		47	
245	30			0	100 for 8"		
240	35	25.6	100	0		65	
235	40			0	50		

BORING 2

DATE DRILLED: August 19 and 21, 1997
 EQUIPMENT USED: 24"-Diameter Bucket to 16 1/2'
 10"-Dia. Hollow Stem Auger to 40 1/2'
 ELEVATION: 275

4" Asphalt Paving
ARTIFICIAL FILL (af)
 SILTY SAND - fine to coarse, about 40% Gravel,
 few Cobbles (to 5" in size), some pieces of
 brick, brown

ALLUVIUM (Qal)
 SAND - well graded, about 10% Gravel and Cobbles,
 light brownish grey

About 30% Gravel and Cobbles (to 6" in size)

Grey

SAND and SILTY SAND - fine to coarse, about 20%
 Gravel, light greyish brown

SAN PEDRO FORMATION (Qsp)
 SAND - well graded, thin layers of Clayey Silt, some
 Gravel, grey to dark grey

Some fine Sand

SILT - bedded, lenses of fine Sand, dark grey

* Number of blows required to drive the Crandall
 sampler 12 inches using a 1600 pound hammer
 falling 12 inches.

+ Number of blows required to drive the Crandall
 sampler 12 inches using a 140 pound hammer
 falling 30 inches.

(CONTINUED ON FOLLOWING FIGURE)

LOG OF BORING

LAW/CRANDALL



[illegible]

DATE DRILLED: August 19 and 21, 1997
EQUIPMENT USED: 24"-Diameter Bucket to 16½'
10"-Dia. Hollow Stem Auger to 40½'
ELEVATION: 275

NOTE: BUCKET BORING: Water seepage encountered during drilling at a depth of 14 1/2'. Bucket boring terminated at a depth of 16 1/2' due to caving and sloughing below water seepage.

HOLLOW STEM AUGER BORING: To obtain future water level measurement and sampling installed 4-inch-diameter PVC pipe to 40'. Pipe perforated between depths of 10' and 40'. Backfilled with sand to within 8' of ground surface and filled with concrete above 3'. A bentonite plug placed between depths of 3' and 8' of ground surface. Water level measured in the monitoring well at a depth of 14' on 8/26/97.

LAW/CRANDALL



BORING 3

DATE DRILLED: August 14, 1997
EQUIPMENT USED: 24"-Diameter Bucket to 17 1/2'
10"-Dia. Hollow Stem Auger to 42'
ELEVATION: 277

ELEVATION (ft.)	DEPTH (ft.)	MOISTURE (% of dry wt.)	DRY DENSITY (lbs./cu. ft.)	O.V.A.*** (ppm)	"N" VALUE STD.PEN.TEST	BLOW COUNT* (blows/ft.)	SAMPLE LOC.	
275		6.9	114	30		1		SM
		18.6	105	0		< 1		ML
5		8.0	100	20		1		SM
270		2.6	122	50		5		SW
10		3.7	113	80		6		
265		11.4	116	0		2		
15		11.5	120	50		135		
260		33.0	90	60		75 for 10"		ML
25		27.1	96	200		70		
245		35.1	89	0		47		SM
35		15.0	111	0		65		SW
240								
40								

7" Asphalt Paving
ARTIFICIAL FILL (af)
SILTY SAND - fine to coarse, some Clay, some
Gravel, dark grey
SANDY SILT - grey

ALLUVIUM (Qa)
SILTY SAND - fine, some pieces of wood, light brown
SAND - well graded, some Gravel and Cobbles (to 8"
in size), light brownish grey

About 30% Gravel

Grey

CLAYEY SILT - grey to dark grey

SAN PEDRO FORMATION (Qsp)
SILT - massive, dark grey

SILTY SAND - fine, thin layers of Silty Clay, bluish
grey to dark grey

SAND - well graded, some lenses of Clayey Silt, dark
grey

(CONTINUED ON FOLLOWING FIGURE)

LOG OF BORING

LAW/CRANDALL



DATE DRILLED: August 14, 1997
EQUIPMENT USED: 24"-Diameter Bucket to 17½'
10"-Dia. Hollow Stem Auger to 42'
ELEVATION: 277

[illegible]

NOTE: BUCKET BORING: Water seepage encountered during drilling at a depth of 15'. Water level measured after completion of drilling. Raveling from 6' to 15'. Bucket boring terminated at a depth of 17½' due to caving and sloughing below water.

HOLLOW STEM AUGER BORING: To obtain future water level measurement and sampling installed 4-inch-diameter PVC pipe to 42'. Pipe perforated between depths of 10' and 40'. Backfilled with sand to within 8' of ground surface and filled with concrete above 4'. A bentonite plug placed between depths of 4' and 8' of ground surface. Water level measured in the monitoring well at a depth of 15' on 8/26/97.

LAW/CRANDALL



FIGURE A-1.3b

1020312290514722

It is not warranted to be representative of subsurface conditions at other locations and times.

ELEVATION (ft.)	DEPTH (ft.)	MOISTURE (% of dry wt.)	DRY DENSITY (lbs./cu. ft.)	O.V.A. *** (ppm)	"N" VALUE STD.PEN.TEST	BLOW COUNT* (blows/ft.)	SAMPLE LOC.
275		9.7	103	0		17	SM
	5			0		35	SW
270		2.8	107	0		36	
	10						
265		42.8	79	0		10	
	15						
260		6.2	124	5		57	
	20						
255		8.5	126	10		60	
	25						
		29.9	91	10		34	
250		25.8	98	300		80	
	30						
		25.4	100	190		80	
245							
	35						
		26.0	100	250		75 for 4"	
240							
	40						
		25.9	97	200		80	

BORING 4

DATE DRILLED: August 20, 1997
EQUIPMENT USED: 8" - Diameter Hollow Stem Auger
ELEVATION: 276

3' Asphalt Paving
ARTIFICIAL FILL (af)
SILTY SAND - fine, some Gravel, brownish grey

ALLUVIUM (Qal)
SAND - well graded, about 30% Gravel, light grey

* Number of blows required to drive the Crandall sampler 12 inches using a 140 pound hammer falling 30 inches.

Layer of Silty Clay

Some fine Sand

About 40% Gravel

SAN PEDRO FORMATION (Qsp)
SILT - bedded, lenses of fine Sand, dark grey

NOTE: Water seepage encountered during drilling at depths of 18' to 20', and 30'. Water level measured at a depth of 18' at completion of drilling.

END OF BORING AT 40'.

LOG OF BORING

LAW/CRANDALL



FIGURE A-1.4

1020312200514722

BORING 5

DATE DRILLED: August 13, 1997
EQUIPMENT USED: 24" - Diameter Bucket

ELEVATION: 278

ELEVATION (ft.)	DEPTH (ft.)	MOISTURE (% of dry wt.)	DRY DENSITY (lbs./cu. ft.)	O.V.A.*** (ppm)	"N" VALUE STD.PEN.TEST	BLOW COUNT* (blows/ft.)	SAMPLE LOC.
275		-	-	0		4	SM
		1.4	121	0		3	SW
270	5	1.9	128	0		7	
		3.3	103	0		2	
265		6.3	114	0		4	
	15						
260		29.5	97	0		1	ML
	20	37.4	85	0		<1	
255		35.1	87	0		<1	
	25						
250		14.0	109	10		9	SW
	30	25.7	100	100		11	
245		23.0	104	175		19	

3 1/2" Asphalt Paving
ARTIFICIAL FILL (af) - SILTY SAND - fine, light grey -
ALLUVIUM (Qal)
SAND - well graded, about 40% Gravel, few Cobbles
(to 5" in size), light grey

* Number of blows required to drive the Crandall
sampler 12 inches using a 140 pound hammer
falling 30 inches.

CLAYEY SILT - dark grey

SAN PEDRO FORMATION (Qsp)
SAND - well graded, lenses of Silty Sand and Clayey
Silt, dark grey

SILT - bedded, lenses of fine Sand, dark grey

(BORING TERMINATED AT A DEPTH OF 33' DUE TO
DIFFICULT DRILLING BELOW WATER).

NOTE: Water seepage encountered during drilling at a
depth of 22'. Water level measured at a
depth of 22' 30 minutes after completion of
drilling. Raveling from 2' to 8' (to 3 1/2' in
diameter) and from 8' to 17' (to 2 1/2' in
diameter).

LOG OF BORING

LAW/CRANDALL



1020312200514722

FIGURE A-1.5

ELEVATION (ft.)	DEPTH (ft.)	MOISTURE (% of dry wt.)	DRY DENSITY (lbs./cu. ft.)	O.V.A.*** (ppm)	"N" VALUE STD.PEN.TEST	BLOW COUNT* (blows/ft.)	SAMPLE LOC.
275	5	1.4	116	50		2	SM
		1.7	103	75		1	SW
270	10	1.6	117	10		5	
		1.8	115	0		6	
265	15	2.7	99	0		5	
		4.1	114	0		8	
260	20	30.3	94	0		4	
		22.1	104	0		6	
255	25	7.8	118	0		1	SM
		18.3	114	0		2	
250	30	10.7	117	0		145 +	SW
245	35						
240	40	8.6	136	0		70	

BORING 6

DATE DRILLED: August 19, 1997
 EQUIPMENT USED: 24"-Diameter Bucket to 30'
 10"-Dia. Hollow Stem Auger to 42'
 ELEVATION: 278

4" Asphalt Paving - 6" Brick floor
 ARTIFICIAL FILL (af)
 SILTY SAND - fine to coarse, brown
 ALLUVIUM (Qal)
 SAND - well graded, about 40% Gravel, and
 Cobbles (to 5" in size), light brownish grey

Thin layers of Sandy Silt

SILTY SAND - fine, lenses of Sandy Silt, few Gravel,
 grey

SAND - well graded, about 15% Gravel and Cobbles,
 grey

* Number of blows required to drive the Crandall
 sampler 12 inches using a 1600 pound hammer
 falling 12 inches.

+ Number of blows required to drive the Crandall
 sampler 12 inches using a 140 pound hammer
 falling 30 inches.

Note: The log of subsurface conditions shown herein applies only at the specific boring location and at the time and times.
 It is not warranted to be representative of subsurface conditions at other locations and times.

(CONTINUED ON FOLLOWING FIGURE)

LOG OF BORING

LAW/CRANDALL



DATE DRILLED: August 19, 1997
EQUIPMENT USED: 24"-Diameter Bucket to 30'
10"-Dia. Hollow Stem Auger to 42'
ELEVATION: 278

[illegible]

NOTE: BUCKET BORING: Water seepage encountered during drilling at a depth of 24'. Water level measured at a depth of 24' 15 minutes after completion of drilling. Bucket boring terminated at a depth of 30' due to caving and sloughing.

HOLLOW STEM AUGER BORING: To obtain future water level measurement and sampling installed 4-inch-diameter PVC pipe to 42'. Pipe perforated between depths of 15' and 40'. Backfilled with sand to within 11' of ground surface and filled with concrete above 3'. A bentonite plug placed between depths of 3' and 11' of ground surface. Water level measured in the monitoring well at a depth of 22' on 8/26/97.

LAW/CRANDALL



Note: The log of subsurface conditions shown herein applies only at the specific boring location and at the time of drilling. It is not warranted to be representative of subsurface conditions at other locations and times.

BORING 7							
ELEVATION (ft.)		DEPTH (ft.)	MOISTURE (% of dry wt.)	DRY DENSITY (lbs./cu. ft.)	O.V.A. *** (ppm)	"N" VALUE STD. PEN. TEST	BLOW COUNT* (blows/ft.)
275			13.4	109	0		13 for 6"
		5	--	--	0		50 for 6"
270							
		10	2.9	105	0		73 for 11"
265							
		15	3.5	110	0		75 for 11"
260							
		20	1.9	98	0		50 for 4"
255							
		25	37.4	82	0		26
250							
		30	30.1	92	0		62
245							
		35	24.3	97	0		69
240							
		40	26.8	97	0		73
			29.7	94	0		75
			21.7	99	0		32

BORING 7

DATE DRILLED: August 18, 1997
EQUIPMENT USED: 8" - Diameter Hollow Stem Auger
ELEVATION: 278

5" Asphalt Paving
ARTIFICIAL FILL (af)
SANDY SILT - some Clay, some pieces of brick, brown

Pieces of concrete
Sample not recovered

ALLUVIUM (Qal)
SAND - well graded, about 30% Gravel and Cobbles (to 6" size), light brown

* Number of blows required to drive the Crandall sampler 12 inches using a 140 pound hammer falling 30 inches.

SAN PEDRO FORMATION (Qsp)
SILT - bedded, lenses of Sand, dark grey

More Clay

NOTE: Water seepage encountered during drilling at a depth of 20'. Water level measured at a depth of 36' 5 minutes after completion of drilling.

END OF BORING AT 40'.

LOG OF BORING

LAW/CRANDALL



FIGURE A-1.7

1020312200514722

ELEVATION (ft.)	DEPTH (ft.)	MOISTURE (% of dry wt.)	DRY DENSITY (lbs./cu. ft.)	O.V.A.*** (ppm)	"N" VALUE STD.PEN.TEST	BLOW COUNT* (blows/ft.)	SAMPLE LOC.
275		8.2	108	0		51	SM
	5	--	--	0		39	SP
270		1.6	108	0		58	
	10	4.4	92	0		50 for 9"	
265				0	64 for 9"		
	15						
260		1.7	115	0		50 for 6"	SW
	20			0	73 for 9"		
255		8.7	123	0		50 for 9"	
	25			0	50 for 4"		
250							
	30	13.3	117	0		57	
245				0	85 for 10"		ML
	35	--	--			48	
240				0		32	
40							

BORING 8

DATE DRILLED: August 18, 1997
EQUIPMENT USED: 8" - Diameter Hollow Stem Auger

ELEVATION: 278

3" Asphalt Paving

ARTIFICIAL FILL (af)

SILTY SAND - fine to medium, some Gravel, few
Cobbles (to 6" in size), brown

ALLUVIUM (Qal)

SAND - fine to medium, some coarse, about 30%
Gravel and Cobbles (to 6" in size), light brownish
grey
Sample not recovered

Fine Sand, less Gravel

SAND - well graded, about 30% Gravel and Cobbles
(to 6" in size), light brownish grey

SANDY SILT - some Clay, light greyish green

Sample not recovered

SAN PEDRO FORMATION (Qsp)

SILT - bedded, lenses of fine Sand, dark grey

Note: The log of subsurface conditions shown herein applies only at the boring location and times.
It is not warranted to be representative of subsurface conditions at other locations and times.

(CONTINUED ON FOLLOWING FIGURE)

LOG OF BORING

LAW/CRANDALL



FIGURE A-1.8a

1020312200514722

DATE DRILLED: August 18, 1997
EQUIPMENT USED: 8" - Diameter Hollow Stem Auger
ELEVATION: 278

ELEVATION (ft.)	DEPTH (ft.)	MOISTURE (% of dry wt.)	DRY DENSITY (lbs./cu. ft.)	O. V. A. *** (ppm)	"N" VALUE STD. PEN. TEST	BLOW COUNT * (blows/ft.)	SAMPLE LOC.	B D E L
235		26.3	99	0		72	■	
	45			0	54		▲	
230		--	--	0		64	□	
	50							
225				0	75		▲	
	55							
220		26.1	95	0		69	■	
	60			0	50 for 6"		▲	

Note: The log of subsurface conditions shown is based on the data furnished by the contractor. It is not warranted to be representative of subsurface conditions at other locations and times.

END OF BORING AT 61'.

NOTE: Water seepage encountered during drilling at a depth of 23'. Water level measured at a depth of 38' 5 minutes after completion of drilling.

It is not warranted to be representative of subsurface conditions at other locations and times.


LAW/CRANDALL



FIGURE 1.8b

1020312200514722

Note: The log of subsurface conditions shown herein is only at the boring locations and times.
 It is not warranted to be representative of subsurface conditions at other locations and times.



(CONTINUED ON FOLLOWING FIGURE)

LOG OF BORING

LAW/CRANDALL



FIGURE A-1.9a

1020312200514722

DATE DRILLED: August 18, 1997
EQUIPMENT USED: 8" - Diameter Hollow Stem Auger
ELEVATION: 278

DATE DRILLED: August 18, 1997

DATE DRILLED: August 18, 1997
EQUIPMENT USED: 8" - Diameter Hollow Stem Auger

ELEVATION: 278

[illegible]

NOTE: Water seepage encountered during drilling at a depth of 26'. Water level measured at a depth of 31' 10 minutes after completion of drilling.

LAW/CRANDALL



BORING 10

DATE DRILLED: August 19, 1997
EQUIPMENT USED: 8" - Diameter Hollow Stem Auger

ELEVATION: 279

ELEVATION (ft.)	DEPTH (ft.)	MOISTURE (% of dry wt.)	DRY DENSITY (lbs./cu. ft.)	O.V.A.*** (ppm)	"N" VALUE STD.PEN.TEST	BLOW COUNT* (blows/ft.)	SAMPLE LOC.
275	5	8.9	110	50		32	SM
		2.0	86	10		16	SP
270	10	3.2	103	10		19	
				0	55		SW
265	15	4.8	121	0		55	
				0	60		
260	20	2.3	110	0		55	
				0	50		
255	25	13.4	117	0		49	
				0	95		
250	30	--	--			37	
245	35	10.7	128	0		55	
				0	70		SP-SM
240	40						

3" Asphalt Paving
ARTIFICIAL FILL (af)
SILTY SAND - fine to coarse, some Gravel, some pieces of brick, brown

ALLUVIUM (Qa)
SAND - fine to medium, about 15% Gravel, light brown

SAND - well graded, about 20% Gravel and Cobbles, grey

About 40% Gravel and Cobbles (to 6" in size)

Sample not recovered

SAND and SILTY SAND - fine to coarse, about 10% Gravel, grey

(CONTINUED ON FOLLOWING FIGURE)

LOG OF BORING

LAW/CRANDALL



DATE DRILLED: August 19, 1997
EQUIPMENT USED: 8" - Diameter Hollow Stem Auger
ELEVATION: 279

ELEVATION (ft.)	DEPTH (ft.)	MOISTURE (% of dry wt.)	DRY DENSITY (lbs./cu. ft.)	O.V.A.*** (ppm)	"N" VALUE STD.PEN.TEST	BLOW COUNT* (blows/ft.)	SAMPLE LOC.
235	45	18.5	110	0		75	☑
230	50	--	--	50	100 for 9"		☑
225	55			0	54		☑
220	60			0	97		☑

Sample not recovered

END OF BORING AT 60 1/2'.

NOTE: Water seepage encountered during drilling at a depth of 23'. Water level measured at a depth of 35 1/2' 5 minutes after completion of drilling.

It is not warranted to be representative of subsurface conditions at other locations and times.

LOG OF BORING

LAW/CRANDALL



Existing Geotechnical Boring Logs

J Byer, 1998

LOG OF BORING 1					
PROJECT: JB:17776-B CATELLUS					
DATE LOGGED: 6/4/98 BY: JWB					
BORING TYPE: 8 Inch Hollow-Stem					
SURFACE: 5 Inch AC Pavement					
REPORT DATE: 7/9/98 ELEVATION: 276.4					
0					4 Inches Asphalt
26.0	96.9	15*	R	SC	FILL: Clayey Sand, dark brown, moist, dense, some debris, asphalt, concrete, brick
				SC	ALLUVIUM: Clayey Sand, dark brown, moist, medium dense, porous, grades to sand, light brown, moist, dense
6.2	119.5	43	R	SM	Silty Sand, light and dark brown, moist, medium dense with round granite cobbles
3.1	—	43	R		Silty Sand, light brown, moist, dense
33.6	80.9	9	R		Gravelly layers with coarse sand
4.6	112.3	40	R	SG	Sandy Silt, gray green, moist, firm, some peat
36.7	83.5	25	R		Gravelly Sand, light brown, moist, dense
				ML	Water at 16 Feet
				SG	Clayey Silt, light bluish gray, saturated, soft
9.8	118.4	50	R		Gravelly Sand, gray, saturated, dense
10.6	114.7	43	R	GW	Sandy Gravel, gray, saturated, dense, rounded granite clasts
12.0	125.9	45	R		

*140 Pound hammer, 30 Inch drop

LOG OF BORING 1 (Continued)

PROJECT: JB:17776-B CATELLUS

DATE LOGGED: 6/4/98 BY: JWB

BORING TYPE: 8 Inch Hollow-Stem

SURFACE: Asphalt Parking Lot

REPORT DATE: 7/9/98

ELEVATION: 276.4

Depth (feet)	Moisture Content %	Dry Density (pcf)	Blow Count	Sample Type	Symbol USCS	
26	31.2	93.0	50	R		BEDROCK: Siltstone, blue gray, saturated, bedded, with layers of fine grained sandstone, soft to very firm
	28.2	96.4	50/9	R		Hydrogen Sulfide odor
30						
	29.9	94.3	50/11	R		Siltstone with sandstone interbeds, firmer
35						
						slow drilling
	34.6	87.1	50/9	R		Siltstone continues
40						
45						
50						End at 50 Feet; Water at 16 Feet. Boring developed as 2 inch diameter monitoring well, sand to 15 feet, bentonite plug to top.

LOG OF BORING 2

PROJECT: JB:17776-B CATELLUS

DATE LOGGED: 6/4/98 BY: JWB

BORING TYPE: 8 Inch Hollow-Stem

SURFACE: 5 Inch AC Pavement

REPORT DATE: 7/9/98

ELEVATION: 276.4

Depth (feet)	Moisture Content %	Dry Density (pcf)	Blow Count	Sample Type	Symbol USCS	
0					SM	FILL: Silty Sand, dark brown, moist, dense, with rock fragments and brick
5					SG	ALLUVIUM: Gravelly Sand, light brown, moist, dense
10					SW	grades to fine grained sand with gravel
12					GW	Gravel and Cobble layer, 4 feet thick, hard drilling
15					SW	
20						
23						Water at 23 Feet
25						

LOG OF BORING 2 (Continued)

PROJECT: JB17776-B CATELLUS

DATE LOGGED: 6/4/98 BY: JWB

BORING TYPE: 8 Inch Hollow-Stem

SURFACE: 5 Inch AC Pavement

REPORT DATE: 7/9/98 ELEVATION: 276.4

Depth (feet)	Moisture Content %	Dry Density (pcf)	Blow Count	Sample Type	Symbol USCS	
26						
30						
32					ML	WEATHERED BEDROCK: Clayey Silt, greenish gray, saturated, soft to firm
35						
36						BEDROCK: Siltstone, blue gray, very moist, bedded, fine sandstone layers
38						End at 38 Feet; Water at 23 Feet; Fill to 6 Feet.