Appendix D

DRAFT ARBORIST REPORT

Arborist Draft Report

for Silicon Valley Power – 115 kV T-line NRS-KRS Project Santa Clara, California

> Prepared for: Aspen Environmental Group 235 Montgomery Street, Suite 935 San Francisco, CA 94104

> > Prepared by: Kramer Botanical PO Box 1582 El Granada, CA 94018

Revised July 8, 2024

Draft Arborist Report -

Silicon Valley Power – NRS to KRS 115 kV Transmission Line Project

Table of Contents

Arborist Draft Report)
Project Overview	L
Scope of Report1	L
City of Santa Clara Tree Policies1	L
Figure 1. Project Overview Map	<u>)</u>
Survey Methods	3
Survey Results	ł
Tree Health/Condition	ł
Protected Trees	ł
Assessment of Project Impacts on Trees	5
Tree Protection for Retained Trees	7
Attachment A: Tree Survey Results – March 2024 Survey)
Attachment B: Tree Location Maps)
Attachment C: Tree Protection "City of Santa Clara Arborist Notes"	L

This page intentionally left blank

Project Overview

Silicon Valley Power (SVP) is proposing to construct approximately 2.24 miles of a new 115 kV transmission line (Project) within the City of Santa Clara (City) limits in Santa Clara County, California. Based on a Project Description provided by Aspen Environmental Group (AEG) on April 5, 2024, the proposed transmission line will begin at the SVP Northern Receiving Station (NRS), approximately 0.2 miles southeast of Levi's Stadium, and would travel south down Lafayette Street, Bassett Street and Duane Avenue to end at the SVP Kifer Receiving Station (KRS), approximately 0.1 miles northwest of the intersection of Lafayette Street and Central Expressway.

Two different Options have been proposed for the Project. Under Option 1, the entire Project would be overhead, with transmission lines on new poles. Under Option 2, the Project would be underground from the median of Lafayette Street near NRS to approximately 300 feet south of the intersection of Lafayette Street and Agnew Road, then overhead south of Agnew Road to KRS.

<u>Figure 1</u> provides an overview of the proposed SVP – NRS-KRS 115kV Transmission-line (T-line) Project route and shows proposed alignments for both Option 1 and Option 2.

Scope of Report

This preliminary arborist report provides the following:

- An inventory of trees within and immediately adjacent to proposed SVP 115 kV T-Line NRS-KRS Project boundaries. Project boundaries extend 20 feet on either side of the Project centerline. Boundaries are shown on tree location Maps 1-9, provided with this report as Attachment B.
- A general assessment of health/condition for each tree surveyed.
- An assessment of anticipated project impacts to trees within the Project area.
- A Tree Protection Plan for trees to be retained.


City of Santa Clara Tree Policies

City of Santa Clara General Plan policies which may apply to trees documented by this report for the SVP NRS-KRS 115kV T-line Project include the following:

5.10.1-P4 Protect all cedars, redwoods, oaks, olives, bay laurel and pepper trees of any size, and all other trees over 36 inches in circumference (approximately 11.5 inches in diameter) measured at 48 inches above-grade on private and public property as well as in the public right-of-way.

5.10.1-P3 Require preservation of all City-designated heritage trees listed in the Heritage Tree Appendix 8.10 of the General Plan





Survey Methods

A tree survey for the SVP NRS-KRS 115 kV T-line Project was conducted by Kramer Botanical certified arborist Neal Kramer, with Project site visits on March 7, 13, 14, 16 and 20, 2024. All trees within Project boundaries, or immediately adjacent with canopy overhanging a Project boundary, having at least one woody trunk with a diameter of 3 inches or greater at 48 inches above the ground were surveyed for this report. Newly planted trees with trunk diameters of less than 3 inches were also included in the survey.

Each surveyed tree has been marked with a numbered round aluminum tag, tags 101 – 177 and tags 189 - 262, with 101 starting at the north end of the project alignment. Tree tag 178 – 188 represent trees that were a part of the March 2024 survey but are no longer a part of the alignments proposed for this report revision. GPS coordinates for each tree were documented using ArcGIS Field Maps paired with a Bad Elf Flex, Mini GNSS Receiver to enhance accuracy. The approximate location of each tree was also noted on an aerial field map, and information regarding the species, trunk diameter at 48 inches above the ground, and the approximate canopy spread, and height was collected for each tree.

Health and structure were evaluated for each tree using a basic ground-based inspection, and a general condition rating was assigned using the categories shown below. Individual tree ratings consider a variety of factors, including overall tree vigor, evidence of decay, insects or diseases, and/or any other structural defects observed.

Good: 80-100% healthy foliage and no significant defects.

Fair: 50-79% healthy foliage and/or minor defects.

Poor: 5-49% healthy foliage and/or other significant defects.

Based on maps provided by AEG, which show the proposed transmission alignment and transmission pole positions for both overhead alignment Option 1, and underground alignment Option 2, and considering a 20-foot buffer on either side of the transmission centerline, an assessment of project impacts to trees was made. Each tree was assigned a project impact code using one of the following three categories:

(R) Tree may need to be removed for underground trenching, overhead pole placement, or for transmission line clearance.

- (CP) Clearance pruning may be required, but trees can likely be retained.
- (-) No impact expected.

In general, tree branches that are closer than 5 feet vertically or 10 feet horizontally to any conductor or wire (with or without wind) would be trimmed to meet these minimum clearance standards. According to the Project Description, maximum allowable tree height under transmission lines will vary from 27 to 35 feet depending on location.

Survey Results

A total of 151 trees along the Project Alignment were documented for this report. A summary of all 151 trees is provided with this report as <u>Attachment A</u>. Attachment A lists each surveyed tree sequentially by tag number, and includes information regarding the common and scientific name, trunk diameter at 48 inches above the ground, approximate canopy spread and height, City protected status, and a general tree condition rating at the time of the March 2024 survey. Preliminary Project impact assessments for each tree are indicated in Attachment A for both Project Option 1 (overhead) and Project Option 2 (underground and overhead). Specific notes regarding individual trees are included where relevant.

Approximate tree locations along the transmission alignment are shown on aerial maps 1-9 provided with this report as <u>Attachment B</u>.

Trees documented for this report include 29 different species. <u>Table 1</u> below lists each species by common and scientific name in descending order of abundance and includes the total number of each species documented.

Tree Health/Condition

Of the 151 trees documented for this report, 88 trees (58%) are rated in <u>good</u> condition, 51 trees (34%) are in <u>fair</u> condition and 12 trees (8%) are in <u>poor</u> condition. The condition ratings for individual trees are included in <u>Attachment A</u>.

Thirty trees were still "dormant" during March 2024 surveys conducted for this report, making true condition assessment difficult. Dormant tree species included American elm, Crape myrtle, Linden, Horse chestnut, Liquidambar and Tree of heaven. The condition of these dormant trees should be reviewed again later in the season, once the trees have leafed out, to confirm condition ratings assigned for this report and update them if necessary.

Unless expressed otherwise, tree condition assessments for this report were limited to visual examination of accessible tree parts without dissection, excavation, probing, or coring. There is no warranty or guarantee, expressed or implied, that problems or deficiencies regarding the trees discussed in this report may not arise in the future.

Protected Trees

The City of Santa Clara General Plan (5.10.1-P4) defines "protected trees" as "all healthy cedars, redwoods, oaks, olives, bay laurel and pepper trees of any size and all other trees over 36 inches in circumference (approximately 11.5 inches in diameter) measured at 48 inches above-grade".

Seventy-seven (77) of the 151 trees surveyed for this report qualify as "protected trees" under the City of Santa Clara General Plan. Each protected tree is indicated as such in <u>Attachment A</u> under the "Santa Clara Protected Tree" column.

No "Heritage trees" are present within or immediately adjacent to the proposed SVP NRS-KRS 115 kV Tline Project boundaries.

descending order of abundance (March 2024)								
	Trees	Native/ Non-						
Common Name	Scientific Name	Documented	native					
Olive	Olea europea	28	Non-					
Shamel ash	Fraxanus uhdei	17	Non-					
Chinese Elm	Ulmus parvifolia	14	Non-					
Glossy privet	Ligustrum lucidum	13	Non-					
Ginkgo	Ginkgo biloba	13	Non-					
American elm	Ulmus americana	12	Non-					
Jacaranda	Jacaranda mimosifolia	11	Non-					
Crape myrtle	Lagerstroemia indica	11	Non-					
Canary Island Pine	Pinus canariensis	5	Non-					
Deodar cedar	Cedrus deodara	3	Non-					
Bradford pear	Pyrus calleryana	3	Non-					
Blackwood acacia	Acacia melanoxylon	2	Non-					
Red ironbark	Eucalyptus sideroxylon	2	Non-					
Purple-leaf plum	Prunus cerasifera 'Atropurpurea'	2	Non-					
Evergreen pear	Pyrus kawakamii	2	Non-					
Linden	<i>Tillia</i> sp.	2	Non-					
Horse chestnut	Aesculus sp.	1	Non-					
Tree of heaven	Ailanthus altissima	1	Non-					
Nichol's willow-leafed peppermint	Eucalyptus nicholii	1	Non-					
Eucalyptus	<i>Eucalyptus</i> sp.	1	Non-					
Liquidambar	Liquidambar styraciflua	1	Non-					
Magnolia	Magnolia sp.	1	Non-					
Italian stone pine	Pinus pinea	1	Non-					
Fremont cottonwood	Populus fremontii	1	Native					
Holly oak	Quercus ilex	1	Non-					
Southern live oak	Quercus virginiana	1	Non-					
Water gum	Tristaniopsis laurina	1	Non-					

Table 1: Tree species documented along the Project alignments, by	
descending order of abundance (March 2024)	

Assessment of Project Impacts on Trees

Some trees along the Project alignment may need to be removed for the placement of new transmission line structures, or for installation of underground lines.

Furthermore, some trees along the new alignment will need to be pruned to create minimum clearance distances around new structures and transmission lines. Based on clearance guidelines provided by project engineers, tree branches that are closer than 5 feet vertically or 10 feet horizontally to any conductor or wire will be trimmed to meet these minimum clearance standards. Maximum allowable tree height within 25 feet of the transmission centerline is expected to vary between 27 feet to 35 feet above the ground.

The Project Impact Code column in Attachment A of this report designates likely impacts to individual trees using one of the following impact codes:

(R) Tree may need to be removed for structure placement, line clearance, or underground installation.

(CP) Clearance pruning may be required for pole installation, line clearance or equipment access, but tree to be retained.

No impact expected. (-)

Table 2 below summarizes projected impacts to all surveyed trees by impact code as described above for Project Option 1 (all overhead). Table 3 summarizes projected impacts to all surveyed trees by impact code for the Project Option 2 (underground and overhead).

Table 2: Impacts to Trees - Option 1 (All Overhead)											
	To be Removed	May Require Clearance Pruning	No Impact Expected	Total							
All trees	3	33	115	151							
"Protected" trees											

Table 3: Impacts to Trees - Option 2 (Underground and Overhead)										
	To be Removed	May Require Clearance Pruning	No Impact Expected	Total						
All trees	2	32	117	151						
"Protected" trees	1	22	54	77						

The above assessment of project impacts on individual trees is preliminary, based on information provided July 5, 2024. During Project final development processes, in consultation with the City arborist or City designated arborist, it may be determined that additional trees will need to be removed for the Project. Or it may also be determined that with special protection measures, or by adjusting a pole location, a tree listed to be removed can be retained.

Table 4 below shows trees with survey tree tag number, that are projected to be removed for Project Alignment Option 1 vs. Alignment Option 2.

	Table 4: Trees Projected for RemovalAlignment Option 1 vs. Option 2									
(City Pro	tected trees shown in b	oold font)								
	Option 1 Option 2									
Olive	tree #132									
Deodar Cedar	tree #177	tree #177								
Ginkgo	Ginkgo tree #236 tree #236									
Total	Total 3 trees 2 trees									

Once final Project plans are in place, the Project arborist will review the plans and update this report to reflect changes made during final design processes. After the Project is completed, a post construction tree inventory can be conducted to confirm the actual number of trees removed for the Project.

Tree Protection for Retained Trees.

Development activities along the Project alignment have the potential to cause damaging impacts to trees to be retained. Tree root systems can be functionally compromised by soil compaction resulting from heavy equipment operating within tree root zones, and roots can be damaged or lost during excavation activities related to undergrounding, or installation of foundations for new transmission line poles. Furthermore, if not properly managed construction equipment operating in the vicinity of retained trees can cause significant and irreversible damage to tree trunks and canopies.

To minimize potential damage and ensure the long-term health, stability and survival of retained trees, measures outlined in the Tree Protection Plan below shall be implemented.

TREE PROTECTION PLAN

Tree Protection Zone

A Tree Protection Zone (TPZ) shall be defined by the City arborist or City designated arborist for all trees that could be impacted by project activities and are intended for preservation. A TPZ will typically include all area within the dripline of trees to be retained.

The TPZ will be protected by a fenced enclosure to prevent unauthorized access during project activities. At minimum, TPZ fencing will be constructed of 4-foot-tall high-visibility orange ESA fencing hung from a heavy wire attached to firmly anchored T-posts at no more than 8 foot spacing. Warning signs (e.g. "WARNING - Tree Protection Zone – This fence shall not be moved without approval by the City Arborist or a City designated arborist") shall be prominently displayed and visible from all sides of the TPZ fencing.

TPZ fencing shall be installed prior to any demolition, grading, staging, stockpiling, or any other construction activities within 50 feet of the TPZ, and unless otherwise approved by the City Arborist or a City designated arborist, shall remain in place until all construction activities are complete on the affected construction segment.

- No construction, staging, or storage of materials, equipment or vehicles shall occur within a TPZ without advanced approval and oversite by the City arborist or a City designated arborist.
- No excess soil, excess concrete or concrete wash, chemicals, refuse or other waste shall be placed within the TPZ.

The primary contractor shall be responsible for maintaining TPZ fencing and enforcing all TPZ guidelines outlined above throughout the course of the Project.

Site Grading and Excavation and Trenching

• Soil disturbance or grade changes within a TPZ are not permitted unless approved by the City arborist or a City designated arborist. Any approved grading, excavation or trench work within a TPZ will be field staked and inspected by the City arborist or a City designated arborist prior to implementation.

• All approved grading, excavation and trenching work within a TPZ shall be performed under the observation of a City designated Arborist.

• All grading shall be designed to provide positive drainage away from the base of trees to be preserved and shall not create ponding within a TPZ.

• Grade changes in the vicinity of trees to be preserved should remain as close to natural grade as possible.

Canopy Pruning

• To the extent possible, any necessary canopy pruning shall be completed prior to the commencement of construction activities.

• Pruning shall be performed by a qualified tree service worker under the direction of a certified arborist following International Society of Arboriculture tree pruning best management practices. Pruning shall not be performed by construction personnel.

Root Pruning

• Any roots one inch and larger requiring removal shall be cut cleanly in sound tissue. No pruning seals or paint shall be used on wounds.

• Roots two inches and greater shall remain in place and undamaged to the extent practicable. If removal is required, cuts shall be made with the approval and under the direction of a certified arborist.

Communication for Tree Protection Compliance

• A preconstruction meeting shall be arranged for the City arborist or City designated arborist to meet with the Project Engineer, Project Contractors, Onsite Project Supervisors, Tree Pruning and Removal Contractor, and/or other appropriate Project Leads to review and secure a commitment to compliance with all tree protection measures.

The City of Sana Clara provides additional guidelines for tree protection. These are outlined in "City of Santa Clara Arborist notes", a copy of which is included with this report as <u>Attachment C.</u>

Attachment A: Tree Survey Results – March 2024 Survey

Appendix A: Tree Survey Results March 2024 - Silicon Valley Power NRS-KRS Transmission Line Alignment, Santa Clara, Ca

rev. nk7/8/24

Tree	Common Name	Scientific Name	Diameter (inches) at 48" above grade ¹	Canopy Spread (feet)		Santa Clara Protected Tree (P)	Project Impact Code (Op1) ²	Project Impact Code (Op2) ²	General Condition ³	Commonts
101	Crape myrtle	Lagerstroemia indica	5	15	15	1100 (1)	(001)	(0p2)	Fair	Dormant. Canopy buried under trumpet vine
101	Crape myrtle	Lagerstroemia indica	5	13	13				Fair	Dormant. Canopy buried under trumpet vine
102	Jacaranda	Jacaranda mimosifolia	10	24	20		-	-	Good	Dormant. Canopy ouried under trumpet vine
103	Jacaranda	Jacaranda mimosifolia	9	24	18				Fair	thin canopy
104	Jacaranda	Jacaranda mimosifolia	8	18	16				Fair	thin canopy
105	Jacaranda	Jacaranda mimosifolia	6	15	10				Fair	thin canopy
100	Jacaranda	Jacaranda mimosifolia	10	24	12					thin canopy
107	Jacaranda	Jacaranda mimosifolia	7	16	16			-		thin canopy
100	Jacaranda	Jacaranda mimosifolia	9	22	18			_	Good	
110	Jacaranda	Jacaranda mimosifolia	8	15	15			_		thin canopy
111	Jacaranda	Jacaranda mimosifolia	9	20	13		_	_	Good	
112	Jacaranda	Jacaranda mimosifolia	5	14	15		_	_		thin canopy
112	Jacaranda	Jacaranda mimosifolia	6	12	13		_	_	Good	
113	Olive	Olea europaea	5+5+7	12	18	Р	_	-	Good	
	Olive	Olea europaea	7+6+7	20	20	P	-	-	Good	
116	Olive	Olea europaea	5+3+3	11	12	P	-	-	Fair	
117	Olive	Olea europaea	5+3+3+4	15	12	P	-	-	Good	
118	Olive	Olea europaea	5+4+4+2	16	14	Р	-	-	Good	
119	Olive	Olea europaea	4+3+3	13	12	Р	-	-	Good	
120	Olive	Olea europaea	3+5+5	16	14	Р	СР	-	Good	Pole #12
121	Olive	Olea europaea	4+3+5	13	14	Р	-	-	Fair	
122	Olive	Olea europaea	4+7+6	17	16	Р	-	-	Good	
123	Olive	Olea europaea	5+4	12	12	Р	-	-	Good	
124	Olive	Olea europaea	3+5	11	11	Р	-	-	Good	
125	Olive	Olea europaea	5+5+3	14	14	Р	-	-	Good	
126	Olive	Olea europaea	5+5+5	14	14	Р	-	-	Good	
127	Olive	Olea europaea	5+6	13	13	Р	-	-	Good	
128	Olive	Olea europaea	6+4	15	15	Р	-	-	Good	
129	Olive	Olea europaea	4+3+4	12	12	Р	-	-	Good	
130	Olive	Olea europaea	4	9	9	Р	-	-	Good	
131	Olive	Olea europaea	4+3+3	16	16	Р	-	-	Good	
132	Olive	Olea europaea	4+6	12	12	Р	R	-	Good	Pole #13
133	Olive	Olea europaea	7	10	10	Р	-	-	Good	
134	Olive	Olea europaea	4+5+3	12	12	Р	-	-	Good	

¹More than one diameter in the trunk diameter column represent multiple stems arising below 48 inches above the ground.

² Project Impact code: **R** = Remove for underground line, pole placement or line clearance, **CP** = May require pruning for line clearance, **(-)** = No impacts expected. **Op1** = Overhead Option 1, **Op2** = Underground and Overhead Option 2.

³ Condition: Good = 80-100% healthy foliage and no significant defects; Fair = 50-79% healthy foliage and/or minor defects; Poor = 5-49% healthy foliage and/or other significant defects; Dead = less than 5% healthy foliage.

			Diameter (inches)			Santa Clara	Impact	Project Impact		
Tree	C N		at 48" above	-	Height		Code	Code	General 3	
#	Common Name	Scientific Name	grade ¹	(feet)	(feet)	Tree (P)	(Op1) ²	$(Op2)^2$	Condition ³	
		Eucalyptus sideroxylon	21	28	32	P	CP	CP	Fair	History of branch removals, water sprouts
-	7	Pinus canariensis	12	16	34	P	CP	CP	Good	
	7	Pinus canariensis	16	24	30	P	СР	СР	Good	
138		Pinus canariensis	13	24	36	P	-	-	Good	
		Eucalyptus sp.	18	36	40	Р	-	-	Good	30° lean SW
140	Horse chestnut	Aesculus sp.	4	8	11		-	-	Fair	Dormant, cracked bark at base
		Ulmus parvifolia	7	28	25		-	-	Fair	40° lean SE, soil lifted on NW side
	Nichol's willow-leafe		30	40	35	Р	СР	СР	Fair	Thin canopy, previous topped for utility lines
	J 1	Ligustrum lucidum	14	18	24	Р	-	-	Good	
		Ulmus parvifolia	5	18	20		-	-	Good	
		Ulmus parvifolia	6	25	22		-	-	Good	
	Magnolia	Magnolia sp.	8	16	24		-	-	Good	
	¥ 1	Ligustrum lucidum	15	25	26	Р	-	-	Good	
148	Chinese elm	Ulmus parvifolia	7	28	25		-	-	Fair	Thin canopy
149	Glossy privet	Ligustrum lucidum	14	30	25	Р	-	-	Good	
150	Chinese elm	Ulmus parvifolia	6	22	18		-	-	Fair	Thin canopy
151	Chinese elm	Ulmus parvifolia	see comment	16	17		-	-	Fair	Numerous small stems from base, 1-3" dia.
152	Chinese elm	Ulmus parvifolia	8	28	28		-	-	Fair	Late leaf break
153	Chinese elm	Ulmus parvifolia	7	24	26		-	-	Good	Late leaf break
154	Chinese elm	Ulmus parvifolia	6	25	25		-	-	Good	
155	Glossy privet	Ligustrum lucidum	13	25	24	Р	-	-	Good	
156	Glossy privet	Ligustrum lucidum	15	30	27	Р	СР	СР	Good	
157	Chinese elm	Ulmus parvifolia	13	35	32	Р	СР	СР	Good	
158	Glossy privet	Ligustrum lucidum	13	25	24	Р	-	-	Good	
159	Glossy privet	Ligustrum lucidum	7+8+8+13	26	30	Р	СР	СР	Good	
160	Glossy privet	Ligustrum lucidum	17	27	25	Р	-	-	Good	
161	Glossy privet	Ligustrum lucidum	15	25	25	Р	-	-	Fair	Thin canopy, cracked bark SW side. Root damage from recent concrete work?
1.60										Dormant. Significant basal decay cavity, poor response growth. Hard prune, epicormic
	Linden	<i>Tilia</i> sp.	33	25	35	Р	-	-	Poor	sprouts
		<i>Tilia</i> sp.	24	32	44	Р	-	-	Fair	Dormant
	Liquidambar	Liquidambar styraciflua	10	20	30		-	-	Good	Dormant
		Ulmus parvifolia	20	43	30	Р	-	-	Good	
		Ligustrum lucidum	15	21	28	Р	СР	СР	Good	Canopy unbalances to NW
-		Cedrus deodara	25	42	60	Р	-	-	Good	
		Ulmus parvifolia	13	35	35	Р	-	-	Good	
	Chinese elm	Ulmus parvifolia	13	28	30	Р	СР	СР	Good	
170	Chinese elm	Ulmus parvifolia	17	44	36	Р	-	-	Good	

² Project Impact code: **R** = Remove for underground line, pole placement or line clearance, **CP** = May require pruning for line clearance, **(-)** = No impacts expected. **Op1** = Overhead Option 1, **Op2** = Underground and Overhead Option 2.

³ Condition: Good = 80-100% healthy foliage and no significant defects; Fair = 50-79% healthy foliage and/or minor defects; Poor = 5-49% healthy foliage and/or other significant defects; Dead = less than 5% healthy foliage.

Tree #	Common Name	Scientific Name	Diameter (inches) at 48" above grade ¹			Santa Clara Protected Tree (P)	Project Impact Code (Op1) ²	Project Impact Code (Op2) ²	General Condition ³	Comments
171	Deodar cedar	Cedrus deodara	18	28	30	Р	CP	CP	Good	Previously topped for utility line
172	Glossy privet	Ligustrum lucidum	13	18	28	Р	СР	СР	Good	
173	Glossy privet	Ligustrum lucidum	14	25	30	Р	СР	СР	Good	
174	Glossy privet	Ligustrum lucidum	13	20	24	Р	-	-	Good	
175	Southern live oak	Quercus virginiana	19	42	26	Р	-	-	Good	
176	Fremont cottonwood	Populus fremontii ssp. fremontii	43	60	65	Р	-	-	Good	
177	Deodar cedar	Cedrus deodara	21	30	30	Р	R	R	Poor	Pole #20. Hard pruned for utility lines, 20% dead branches
178	Coast live oak	Quercus agrifolia	24	46	34	Р	-	-	Good	
179	Cork oak	Quercus suber	11	15	12	Р	-	-	Fair	50° lean to W
180	Glossy privet	Ligustrum lucidum	12	24	24	Р	-	-	Good	
181	Deodar cedar	Cedrus deodara	19	22	28	Р	СР	СР	Poor	Hard prune for utility lines
182	American elm	Ulmus americana	9+12	24	25	Р	-	-	Fair	Dormant, canopy unbalanced to NW, pruned for utility lines, epicormic sprouting at cuts
183 184	American elm American elm	Ulmus americana Ulmus americana	12 15+11+10+14	27 45	35 32	P P	CP CP	CP CP	Fair Fair	Dormant, canopy unbalanced to SE, pruned for utility lines, epicormic sprouting at cuts Dormant
184	American elm	Ulmus americana	9	23	25	P	Cr		Poor	Dormant, trunk bowed 90° to NE
185	American elm	Ulmus americana	18	23	14	Р	-	-	Fair	Dormant, trunk bowed 90 to NE
187	Glossy privet	Ligustrum lucidum	10	16	16	1	-	-	Poor	Trunk diameter measured @ 3', 14 codominants stems above, some dead
188	Glossy privet	Ligustrum lucidum	5+9+3+4	18	14		-	-	Fair	Multi-stemmed from base
189	Blackwood acacia	Acacia melanoxylon	5+6+3	15	28		-	-	Good	
190	Blackwood acacia	Acacia melanoxylon	6+7+4	18	25		-	-	Good	
191	Shamel ash	Fraxinus uhdei	10	30	32		СР	СР	Fair	Codominant with included bark at 8'
192	Shamel ash	Fraxinus uhdei	16	30	36		СР	СР	Fair	Pole #23. Thin canopy south side
193	Shamel ash	Fraxinus uhdei	4+7+4	12	18		-	-	Poor	Pole #23. Dead top removed
194	Shamel ash	Fraxinus uhdei	16	30	34	P	CP	CP	Good	
195	Shamel ash	Fraxinus uhdei	15	25	35	Р	CP	CP	Good	
196	Shamel ash	Fraxinus uhdei	10	18	30		СР	СР	Fair	Bark seam, flush cuts
197	Shamel ash	Fraxinus uhdei	13+5	18	28	Р	СР	СР	Fair	Main stem removed @ 5', codominants weak attachments
	Shamel ash	Fraxinus uhdei	10	10	27		СР	СР	Poor	Main stem removed @ 5', 1 codominant dead
199	Shamel ash	Fraxinus uhdei	11	11	20		-	-	Fair	
200	Shamel ash	Fraxinus uhdei	8	8	18		-	-	Fair	
201	Shamel ash	Fraxinus uhdei	12	12	22	Р	-	-	Good	
202	Shamel ash	Fraxinus uhdei	10	10	24		CP	СР	Poor	Pole #24. 50% deadwood

¹ Project Impact code: **R** = Remove for underground line, pole placement or line clearance, **CP** = May require pruning for line clearance, **(-)** = No impacts expected. **Op1** = Overhead Option 1, **Op2** = Underground and Overhead Option 2.

² Condition: Good = 80-100% healthy foliage and no significant defects; Fair = 50-79% healthy foliage and/or minor defects; Poor = 5-49% healthy foliage and/or other significant defects; Dead = less than 5% healthy foliage.

Tree #	Common Name	Scientific Name	Diameter (inches) at 48" above grade ¹	Canopy Spread (feet)		Santa Clara Protected Tree (P)	Project Impact Code (Op1) ²	Project Impact Code (Op2) ²	General Condition ³	Comments
203	Shamel ash	Fraxinus uhdei	12	12	24	Р	-	-	Fair	20% deadwood
204	Shamel ash	Fraxinus uhdei	6	8	18		-	-	Poor	Main stem dead @ 6'
205	Shamel ash	Fraxinus uhdei	9	9	26		СР	СР	Poor	50% deadwood, weak new growth
206	Shamel ash	Fraxinus uhdei	4+4+3+5	15	20		-	-	Fair	
207	Shamel ash	Fraxinus uhdei	10	16	22		-	-	Good	
208	Italian stone pine	Pinus pinea	14	24	24	Р	-	-	Fair	Significant needle drop 30% of W side
209	Red ironbark	Eucalyptus sideroxylon	29	38	42	Р	-	-	Good	
210	Olive	Olea europaea	10+7+9	26	22	Р	-	-	Good	
211	Olive	Olea europaea	13+12+13+14	34	32	Р	СР	СР	Fair	Thin canopy and dead branches on SW side
212	Olive	Olea europaea	6+7+8+8+11	28	24	Р	-	-	Fair	30% dead canopy
213	Olive	Olea europaea	7+9+10+7	24	24	Р	-	-	Good	
214	Olive	Olea europaea	8+8+12+8+11	30	34	Р	СР	СР	Good	
215	Olive	Olea europaea	11+8+7	24	22	Р	-	-	Good	
216	Olive	Olea europaea	13+10+13+11	24	30	Р	СР	СР	Fair	Thin canopy SE side
217	Evergreen pear	Pyrus kawakamii	17	30	30	Р	СР	СР	Good	
218	Evergreen pear	Pyrus kawakamii	10	30	24		-	-	Fair	Thin canopy
										Dormant, codominant with included bark from
219	American elm	Ulmus americana	18+15	40	45	Р	СР	CP	Fair	base
220	American elm	Ulmus americana	11	20	42		СР	СР	Fair	Dormant
221	American elm	Ulmus americana	10+5+8+11+11+12	35	45	Р	СР	СР	Fair	Dormant, 6 stems from base
222	American elm	Ulmus americana	8+11	28	36		СР	СР	Fair	Dormant, codominant, included bark from base
223	American elm	Ulmus americana	9	25	42		СР	СР	Fair	Dormant, canopy unbalanced NE
224	American elm	Ulmus americana	8	22	36		СР	СР	Fair	Dormant, canopy unbalanced W
225	American elm	Ulmus americana	16+10	32	42	Р	-	-	Fair	Dormant, included bark, canopy unbalanced SE Dormant, included bark, canopy unbalanced
_	American elm	Ulmus americana	4+4	28	22		-	-	Poor	SW
227	American elm	Ulmus americana	8	22	45		-	-	Poor	Dormant, trunk imbedded in chain link fence
228	American elm	Ulmus americana	8+8	40	42		-	-	Fair	Dormant
	American elm	Ulmus americana	8	25	42		-	-	Fair	Dormant, canopy unbalanced E
	American elm	Ulmus americana	11	40	45		-	-	Fair	Dormant, canopy unbalanced W
	Ginkgo	Ginkgo biloba	12	15	24	Р	-	-	Good	
	Ginkgo	Ginkgo biloba	8	14	18		-	-	Good	
	Ginkgo	Ginkgo biloba	13	16	25	Р	-	-	Good	
	Ginkgo	Ginkgo biloba	8	13	20		-	-	Good	
	Ginkgo	Ginkgo biloba	8	11	20		-	-	Good	
	Ginkgo	Ginkgo biloba	8	14	18		R	R	Good	Pole #36
	Ginkgo	Ginkgo biloba	6	10	16		-	-	Good	
238	Ginkgo	Ginkgo biloba	3	8	12		-	-	Good	

¹ Project Impact code: **R** = Remove for underground line, pole placement or line clearance, **CP** = May require pruning for line clearance, **(-)** = No impacts expected. **Op1** = Overhead Option 1, **Op2** = Underground and Overhead Option 2.

² Condition: Good = 80-100% healthy foliage and no significant defects; Fair = 50-79% healthy foliage and/or minor defects; Poor = 5-49% healthy foliage and/or other significant defects; Dead = less than 5% healthy foliage.


			Diameter (inches)	Canony	Tree	Santa Clara	Project Impact	Project Impact		
Tree			at 48" above	Spread			Code	Code	General	
#	Common Name	Scientific Name	grade ¹	(feet)	(feet)	Tree (P)	$(Op1)^2$	$(Op2)^2$	Condition ³	Comments
239	Ginkgo	Ginkgo biloba	6	10	16		-	-	Good	
240	Water gum	Tristaniopsis laurina	8	15	16		-	-	Good	
241	Ginkgo	Ginkgo biloba	6	9	14		-	-	Good	
242	Ginkgo	Ginkgo biloba	8	12	18		-	-	Good	
243	Purple-leaf plum	Prunus cerasifera 'Atropurpurea'	8	8	14		-	-	Good	
244	Purple-leaf plum	Prunus cerasifera 'Atropurpurea'	7+8	8	14		-	-	Good	
245	Crape myrtle	Lagerstroemia indica	9	18	18		-	-	Poor	No live 2024 buds apparent
246	Crape myrtle	Lagerstroemia indica	8	18	18		-	-	Poor	No live 2024 buds apparent
247	Crape myrtle	Lagerstroemia indica	2	6	12		-	-	Fair	Recent planting, waersprouts from base
248	Ginkgo	Ginkgo biloba	3	8	10		-	-	Good	
249	Ginkgo	Ginkgo biloba	5	8	16		-	-	Good	
250	Tree of heaven	Ailanthus altissima	4+3+3	10	16		-	-	Poor	Dormant, root sprouts, topped @ 16'
251	Holly oak	Quercus ilex	3+9+6+8	18	10	Р	-	-	Good	Topped @10" but full green canopy
252	Bradford pear	Pyrus calleryana 'Bradford'*	13	24	30	Р	-	-	Good	
253	Canary Island pine	Pinus canariensis	14	16	40	Р	-	-	Good	
254	Bradford pear	Pyrus calleryana 'Bradford'*	14	28	30	Р	-	-	Good	
255	Canary Island pine	Pinus canariensis	8	14	22		-	-	Good	
256	Bradford pear	Pyrus calleryana 'Bradford'*	30	30	25	Р	СР	СР	Good	
257	Crape myrtle	Lagerstroemia indica	7	14	24		-	-	Fair	Dormant
258	Crape myrtle	Lagerstroemia indica	6	15	16		-	-	Fair	Dormant
259	Crape myrtle	Lagerstroemia indica	6	14	16		-	-	Fair	Dormant
260	Crape myrtle	Lagerstroemia indica	6	14	16		-	-	Fair	Dormant
261	Crape myrtle	Lagerstroemia indica	6	18	16		-	-	Fair	Dormant
262	Crape myrtle	Lagerstroemia indica	6	12	16		-	-	Fair	Dormant

¹ Project Impact code: **R** = Remove for underground line, pole placement or line clearance, **CP** = May require pruning for line clearance, **(-)** = No impacts expected. **Op1** = Overhead Option 1, **Op2** = Underground and Overhead Option 2.


² Condition: Good = 80-100% healthy foliage and no significant defects; Fair = 50-79% healthy foliage and/or minor defects; Poor = 5-49% healthy foliage and/or other significant defects; Dead = less than 5% healthy foliage.


Attachment B: Tree Location Maps






















Attachment C: Tree Protection "City of Santa Clara Arborist Notes"



I. <u>GENERAL</u>

- 1. No cutting of any part of city trees, including roots, shall be done without securing approval and direct supervision from the city arborist or arborist employed by city (408-615-3080).
- 2. No cutting of any part of private trees, including roots, shall be done without direct supervision of an international society of arboriculture (ISA) certified arborist.
- 3. When construction occurs within the drip line of existing trees, contractor shall pile the soil on the side away from the tree. When this is not possible, place soil on plywood, tarp, or 4"-5" thick bed of mulch. This is to help prevent cutting into the soil surface when the backhoe or tractor blade refills the trench.
- 4. Refill open trenches quickly within hours of excavation when they occur within the drip line of existing trees. If this is not possible and the weather is hot, dry, or windy, contractor must keep root ends moist by covering them with wet burlap. If the temperature is 80°f or greater, the burlap must be inspected every hour and re-wet as necessary to maintain a constant cool moist condition. If the temperature is below 80°, the burlap must be inspected every four hours and re-wet as necessary to maintain a constant cool moist condition. Small roots can dry out and die in 10-15 minutes. Larger roots can succumb in an hour or less under unfavorable weather conditions.
- 5. When roots 2" or larger are required to be cut, shovel by hand near the roots and prune the roots with an industry-approved pruning tool. Roots that are accidentally broken should be pruned two inches from the damaged end. Crushed or torn roots are more likely to allow decay to begin. Sharply cut roots produce a flush of new roots helping the tree to recover from its injury.
- 6. Contractor shall notify the city arborist or arborist employed by city 72 hours in advance of any work requiring digging around or within the drip line of existing trees.
- 7. A clear system of flagging must be provided around trees within 20' of the proposed grading. Contractor shall secure approval of such system from the city arborist or arborist employed by city.
- 8. Materials, equipment, temporary buildings, fuels, paints and other construction items shall not be placed within the drip line of existing trees.



9. Fence all trees to be retained to completely enclose the <u>tree protection zone</u> prior to demolition, grubbing or grading. Fencing shall be placed at the drip line of existing trees or, if possible, 1.5 times the radius of the drip line out from the trunk of the tree. A warning sign shall be prominently displayed on each fence. The sign shall be a minimum of 8.5"x11" and clearly state "warning – <u>tree protection zone</u> this fence shall not be removed without approval from the city arborist/project arborist". Fences shall be 6-foot tall chain link or

equivalent, as approved by the city arborist or arborist employed by city. Fences shall remain until all grading and construction work is completed. In addition, wrap all trees with straw waddle up to the first main branch, and then wrap snow fencing around the waddle on all trees in the construction zone to protect them from bark damage caused by the work.

- 10. No trenching shall be done within the drip line of existing trees without the approval of the city arborist or arborist employed by city. Open trenching in the root zone of a public tree is prohibited except in cases where the trenching falls outside the drip line of the tree involved. Exceptions may be allowed if, in the opinion of the city arborist or arborist employed by city, the impact of trenching on the tree will be negligible.
- 11. Any cutting of existing roots of city trees shall be done with approved light equipment under the direct supervision of the city arborist or arborist employed by city. Any cutting of existing roots of private trees shall be done with approved equipment under the direct supervision of an ISA certified arborist.
- 12. Grading should not create drainage problems for trees by channeling water into them, or creating sunken areas.
- 13. All grading within the drip line of city trees shall be done with approved light equipment under the direct supervision of the city arborist or arborist employed by city. All grading within the drip line of private trees shall be done with approved equipment under the direct supervision of an ISA certified arborist. The original grade at the base of existing trees shall not be modified. If a grade increase is necessary, dry wells should be used.
- 14. When trenching is allowed, the contractor must first cut roots with a vermeer root cutter prior to any trenching to avoid tugging or pulling of roots.
- 15. Trees that are determined to be removed by the city arborist or arborist employed by city due to an unforeseen circumstance during construction shall be replaced by the



contractor. The city arborist or arborist employed by city shall determine the replacement specie, size, quantity, and spacing.

- 16. Place 4"-5" thick mulch around all existing trees (out to their drip line) that are to be retained prior to any construction. This will help maintain moisture under the tree within the fencing area.
- 17. Bore pits are not allowed within the drip line of any tree.

II. <u>BORING</u>

Where there is insufficient space to bypass the drip line by trenching adjacent to all existing trees in excess of 5" DBH, the installation must be made by boring. The beginning and ending distance of the bore from the face of the tree in any direction is determined by the diameter of the tree as specified by the accompanying table:

When the tree dia	meter at 4½ feet is:	this minimum dist	replaced by boring at tance from the face of any direction:
0-2	inches	1	foot
3-4	inches	2	feet
6-9	inches	5	feet
10-14	inches	10	feet
15-19	inches	12	feet
over 19	inches	15	feet

Tree diameter	(minimum) depth of bore
9 inches or less	2.5 feet
10-14 inches	3.0 feet
15-19 inches	3.5 feet
20 inches or more	4.0 feet

III. TREE PROTECTION

1. Contractor shall tag and identify existing trees which are to remain within the project limits and on the public right-of-way prior to start of work. Protect all tagged trees at all times from damage by the work. Treatment of all minor damage to tagged trees shall be performed by an ISA certified arborist or other personnel approved by the city arborist or arborist employed by city. If a tagged tree is permanently



disfigured or killed as a result of the work, contractor shall remove the tree, including its roots, from the site and replace each removed tree with an equal-sized tree. If such replacement is not possible, the contractor shall reimburse to the tree owner the amount listed in the table below. The city arborist or arborist employed by city shall be the sole judge of the condition of any tree. Contractor shall provide regular watering of existing landscaping within the construction area through the construction period.

2. Contractor shall pay the tree owner the value of existing trees to remain that died or were damaged because of the contractor's failure to provide adequate protection and maintenance. The payment amount shall be in accordance with the following schedule of values, using "tree caliper" method established in the most recent issue of the "guide for establishing values of trees and other plants", prepared by the council of tree and landscape architects.

7	inches	\$ 2,400
8	inches	\$ 3,400
9	inches	\$ 4,400
10	inches	\$ 5,200
11	inches	\$ 6,200
12	inches	\$ 7,200
13	inches	\$ 8,200
14	inches	\$ 9,200
15	inches	\$ 10,000
16	inches	\$ 11,000
17	inches	\$ 12,000
18 inc	ehes and over:	
Add for each caliper inch		\$ 1,200