







SOUTH YALE CORRIDOR IMPROVEMENTS PROJECT

Project Report

April 2024
CIP No. 312204

prepared for:







Table of Contents

I.	Int	roduction	1
II.	Ва	ckground	2
Α		Project History	2
В		Previous Community Interaction	2
III.	Exi	isting Facility	2
E	xisti	ing Adjoining Land Uses and Facilities	3
	1.	Land Uses	3
	2.	Facilities	4
IV.	Tra	affic Data	7
Α		Existing Traffic Conditions	7
В	•	Buildout Conditions	10
C	ollis	sion Data	12
V.	De	ficiencies and Justifications	14
VI.	Pro	oject Description	15
Α		Proposal and Alternatives	15
	1.	Preferred Project	16
	2.	Alternatives Withdrawn from Consideration	19
	3.	No Project Alternative	20
	4.	Project Phasing	20
В	•	Material Alternatives and Restrictions	20
C		Non-Standard Design Features / Variances	20
D		Utilities	21
	1.	Determination of Prior Rights	22
	2.	Required Relocations	22
E.	,	Drainage	22
F.		Landscaping & Irrigation	22
G	•	Traffic Signal Improvements	23
Н		Conformance with General Plan and Zoning Code Standards	23



I.	Inter-Agency Considerations	23
J.	Project Schedule	24
K.	Project Costs	24
VII. A	greements/Permits	25
A.	Utilities	25
В.	Inter-Agency	25
C.	Intra-Agency	25
VIII. R	ight-of-Way	25
A.	Existing ROW	25
В.	Constraints	26
C.	Proposed ROW	26
IX. E	nvironmental Clearance	26
X. P	ublic Involvement/Hearing Process	28
XI. O	ther Considerations	29
A.	Impacts on Non-Motorized Transportation and Pedestrian Modes	29
В.	Prolonged Temporary Road and/or Ramp Closure	30
C.	Hazardous Waste or Material	30
D.	Wetland and Floodplain	30
E.	Roadway Reconstruction, Restoration, Pavement Rehabilitation	31
F.	Bus and Emergency Lanes	31
G.	Interim Features	31
H.	Traffic Management Plan	31
I.	Biological Requirements	32
XII. R	ecommendations	32



Attachment A – Engineering Concepts

Attachment B – Cross-Section Alternatives

Attachment C – Utility Maps

Attachment D – Engineering Cost Estimate

Attachment E – Traffic Analysis

Attachment F – Yale Avenue and University Drive Bike and Pedestrian Traffic Analysis



I. Introduction

The South Yale Corridor Improvements Project (Project) is located in the City of Irvine (City) along Yale Avenue between Interstate 405 (I-405) and University Drive. Originally identified in the City's 2020 Strategic Active Transportation Plan, the Project recommends improvements to multi-modal mobility and access along Yale Avenue to address City goals of reducing greenhouse gas emissions, diversifying mobility options, and improving safety. The Project study corridor is within the University Park community, adjacent to Rancho San Joaquin Middle School (RSJMS), and connects to the University Trail off-street multi-use path within the OC Parks managed William R. Mason Regional Park.

The Project boundaries are approximately 350-feet north of Michelson Drive to the north and University Drive to the south, which covers a distance of 2,700-feet. The segment of Yale Avenue that's located in the study area currently includes landscaped parkways, sidewalks, onstreet bike lanes (Class II bikeways), and two travel lanes. Marked crosswalks exist at the Yale Avenue and University Drive intersection and the Yale Avenue and Michelson Drive intersection. The 64-feet wide roadway is considered for redesign to improve current mobility and traffic operation. Potential Project benefits include but are not limited to:

- Improved safety for all roadway users;
- Diversified travel options; enhanced connections to the City's off-street trail network;
- Reduced air, noise, and stormwater pollution; and
- Community-building and increased quality of life with recreational opportunities.

Through agency review and significant community engagement activities, a roadway cross-section concept was approved and advanced to conceptual engineering design and environmental review. The Project improvements include modifications at three (3) intersections and a designated pedestrian crossing located approximately 715-feet south of Michelson Drive.

The proposed roadway cross-section recommends the following:

- One-way cycletracks (Class IV bikeway) in each direction,
- raised buffer,
- · some on-street motor vehicle parking, and
- one motor vehicle travel lane in each direction.

Time restricted parking will be allowed north and south of Michelson for approximately 700 feet, then a wider raised landscaped buffer will be provided. The Project modifications are planned to occur within the existing curb-to-curb width. The Project recommends signage,



pavement markings, and intersection modifications at the Yale Avenue/Michelson Drive intersection and signage, pavement markings, and traffic signal modifications at the Yale Avenue/University Drive intersection. Additional recommendations include pedestrian crossing enhancements such as improved signing and striping, and reduced crossing distance as a result of the cycletracks' raised buffers.

Construction is anticipated to have a duration of approximately one (1) year.

II. Background

A. Project History

The South Yale Avenue corridor was originally identified in the City's 2020 Strategic Active Transportation Plan (SATP) as an opportunity to implement enhanced bicycle facilities, with the SATP recommending buffered Class II bicycle lanes or a Class IV separated cycletrack. In the recently adopted 2024 Sustainable Mobility Plan (SMP), Class IV separated bikeway (cycletrack) is also proposed along Yale Avenue south of I-405. Yale Avenue currently is striped for two (2) travel lanes while the roadway width can accommodate four (4) travel lanes. In the adopted General Plan Circulation Element, Yale Avenue is classified as a secondary highway between University Drive and Michelson Drive. North of Michelson Drive, Yale Avenue is classified as a commuter highway with a planned vehicular overcrossing over I-405.

B. Previous Community Interaction

The Project was a recommendation of the City's SATP and SMP, both of which incorporated robust community engagement in their development. Engagement methods included social media posts (i.e. Facebook, Twitter, Nextdoor), email communication, online mapping, surveys, and other in person events. The online mapper and online survey allowed community members to provide anecdotal feedback on a geo-coded map that highlighted the community's areas of interest.

III. Existing Facility

As shown in Figure 1, the Project is located along Yale Avenue and entirely within the Cityowned ROW. The curb-to-curb width for the entire Project limit is 64-feet. The Project distance measures at approximately 2,700 feet in length, with the north extent starting 300 feet north of Michelson Drive and extending south to University Drive. The posted speed limit along Yale Avenue is 40 miles per hour between University Drive and Royce Road and is 45 miles per hour between Royce Road and Michelson Drive.

The Project connects to existing bicycle and pedestrian facilities on both ends. To the north, the Project connects to a Class I path that provides connectivity to the pedestrian and bicycle



bridge over I-405. To the south, the Project provides access to the University Trail off-street multi-use path via the Yale Avenue and University Drive intersection crosswalk's western leg. Sidewalks exist on both sides of Yale Avenue. The east side of the roadway provides a wider 9-foot width whereas the west sidewalk is 5-feet wide. Marked crosswalks exist at the Yale Avenue intersections with University Drive and Michelson Drive. The intersection at University Drive provides crosswalks on the west and north intersection legs only. A community paseo connects to the sidewalks on both the east and west sides of Yale Avenue approximately 700-feet south of Michelson Drive. The mid-block paseo south of Michelson Drive does not include a marked crosswalk, pedestrian curb ramp, or other pedestrian crossing features.

Existing Adjoining Land Uses and Facilities

1. Land Uses

The Project is adjacent to several land use types that impact its functionality, including low and medium density residential, the RSJMS educational facility, and the William M. Mason Park recreational area. On the west side of Yale Avenue between Royce Road and University Drive and Michelson Drive and the I-405, there is zoning for low-density residential (0-5 units per acre). On the east side of the Project area and west side between Royce Road and Michelson Drive, the land is zoned for medium-density residential (0-10 units per acre). The only non-residential land use within the Project area is at RSJMS. Nearby land uses include parks and medium high density residential (0-25 units per acre). Figure 2 identifies land uses and key destinations within the study area.

The Project is primarily surrounded by residential land uses to the east and west, with no residential units fronting Yale Avenue. Permanent on-street parking within the project limit is currently prohibited. Temporary parking occurs on special occasions through special permits during RSJMS school events. As seen in Section IV. Traffic Data, the majority of average daily traffic along the corridor occurs in the morning peak period reflecting an overlap in morning commutes and school drop-off times.

RSJMS is located adjacent to the northern study limits and directly influences Yale Avenue traffic, especially during the school year from August to June. Traffic and parking are particularly affected during morning drop-off, afternoon pick-up, and school special events. Although the school driveway along Michelson Drive is the designated drop-off location, a considerable number of students are dropped off along Yale Avenue. Additionally, many students walk and bicycle to school along the existing sidewalks along Yale Avenue.

William R. Mason Park is located at the southern end of the study area and provides bicycle and pedestrian connectivity to land uses adjacent to the Project location. Adjacent to the



intersection of Yale Avenue and University Drive in William R. Mason Park is environmentally sensitive OC Parks land that limits development.

Yale Avenue is located within 2-miles of various pedestrian generators including parks, multiuse paths, trails, schools, hospitals and health care facilities, senior centers, recreation centers, libraries, transit stations, retail, places of worship, office facilities, and bus stops. The closest destinations and trip generators near the Project area include University Community Park and the Adventure Playground, University Elementary School, OC Library- University Park, Parkview Shopping Center, and University Park Shopping Center, which can be accessed via Michelson Drive and University Drive. Other nearby destinations include the University of California Irvine, Concordia University Irvine, South Lake Middle School, Rancho Senior Center, Woodbridge Community Park, Hoag Hospital, and Kaiser Permanente Medical Center.

2. Facilities


The Project intersects or connects to several facilities including I-405 pedestrian and bicycle bridge, Michelson Drive, Royce Road, University Drive and University Trail. The I-405 pedestrian and bicycle bridge is located north of the study area and provides a connection between the Project area and the Class II bike lanes on Yale Avenue and Yale Loop north of the freeway.

Michelson Drive is an east-west commuter roadway that intersects Yale Avenue south of the Project's northern terminus and the I-405 pedestrian and bicycle bridge. The two-lane Michelson Drive features Class II bike lanes on both sides and includes a landscaped center median. The posted speed limit along Michelson Drive is 35 MPH. The stop-controlled intersection with Yale Avenue provides high-visibility crosswalks, curb ramps, and tactile bumps at each leg of the intersection.

Royce Road is an east-west residential street that intersects with Yale Avenue south of the Michelson Drive intersection. The Yale Avenue and Royce Road intersection does not feature marked crossings but does provide curb ramps with tactile bumps at each leg of the intersection.

Located at the southern Project limits, University Drive is a four-lane Primary roadway with Class II bike lanes on both sides. The posted speed limit on University Drive is 50 MPH east of Yale Avenue and 55 MPH west of Yale Avenue. The signalized intersection at University Drive and Yale Avenue features crosswalks on the west and north legs along with curb ramps and tactile bumps. Pedestrian crossing is prohibited on the east leg. The University Trail multi-use path is located south of the Project limits and can be accessed via the western leg crosswalk of the Yale Avenue and University Drive intersection. University Trail connects to several trails that provide access to destinations including William R. Mason Park, University High School and Concordia University.







IV. Traffic Data

A. Existing Traffic Conditions

Traffic counts were performed on Tuesday 15th and Wednesday 16th of November 2022. Morning peak period (AM) and afternoon peak period (PM) traffic counts were collected between 7:00 AM to 9:00 AM and 2:30 PM to 6:00 PM, respectively, along with roadway average daily traffic (ADT) counts. Table 1 summarizes the motor vehicle traffic count data. Generally, the highest traffic volumes were observed during the morning peak period, aligning with morning commutes and the RSJMS drop-off time. Almost half of the observed daily traffic along Yale Avenue north of Michelson Drive occurred during the morning peak period. Yale Avenue south of Royce Road had higher traffic volumes than north of Royce Road.

Table 1 - Daily and Peak Period Traffic Summary

		any ana re			y		
Location	ADT	AM Peak	PM School Peak	PM Evening	AM Peak %	PM School Peak%	PM Evening%
Yale Avenue north of Michelson Drive	540	250	135	8	46%	25%	1%
Yale Avenue north of Royce Road	1,230	253	188	89	21%	15%	7%
Yale Avenue south of Royce Road	1,770	295	217	133	17%	12%	8%

The Yale Avenue intersection movement counts are shown in Table 2 for the two days of collected counts. Traffic volumes at the three intersections show higher volumes at the Yale Avenue and University Drive intersection reflecting the higher volumes along University Drive.



Table 2 - Yale Avenue Intersection Movement Counts by Period

Intersection	Date	Peak	Hour Starting	TOTAL
		AM	7:45 AM	710
	Tue, Nov 15, 2022	PM	2:30 PM	581
		PM	4:45 PM	597
		AM	7:45 AM	753
Yale/Michelson	Wed, Nov 16, 2022	PM	2:30 PM	604
		PM	4:45 PM	575
		AM	7:45 AM	732
	Average	PM	2:30 PM	593
		PM	4:45 PM	586
		AM	7:45 AM	380
	Tue, Nov 15, 2022	PM	2:15 PM	285
		PM	4:45 PM	214
		AM	7:45 AM	385
Yale/Royce	Wed, Nov 16, 2022	PM	2:15 PM	291
		PM	4:45 PM	177
		AM	7:45 AM	383
	Average	PM	2:15 PM	288
		PM	4:45 PM	196
		AM	7:45 AM	2,393
	Tue, Nov 15, 2022	PM	2:30 PM	1,578
		PM	4:45 PM	2,556
		AM	8:00 AM	2,373
Yale/University	Wed, Nov 16, 2022	PM	2:30 PM	1,651
		PM	4:45 PM	2,544
		AM	8:00 AM	2,383
	Average	PM	2:30 PM	1,615
		PM	4:45 PM	2,550



Intersection Level of Service (LOS) analysis was prepared during the AM, PM, and school peak hours for Existing conditions and results are shown in Table 3. Under Existing conditions, the study intersections are operating at acceptable LOS (LOS C or better) during both AM and PM peak periods.

Table 3 - Existing Conditions Intersection Peak Hour LOS

					Existing						
#	Intersection	Methodology	Al	М	Evenir	ng PM	Schoo	I PM			
			V/C	LOS	V/C	LOS	V/C	LOS			
			Delay		Delay		Delay				
1	Yale Ave and Michelson Dr	HCM ¹ 4-WSC ²	17.7	С	14.0	В	13.3	В			
2	Yale Ave and Royce Rd	HCM 2-WSC ³	17.9	С	10.6	В	10.6	В			
3	Yale Ave and University Dr	ICU⁴	0.53	Α	0.48	Α	0.32	Α			

As shown in Table 4, the roadway segment analysis illustrates Yale Avenue operations at LOS A for Existing conditions.

Table 4 - Existing Conditions Roadway Study Segment LOS

#	Sagment	Existing					
#	Segment	Туре	Total Capacity	ADT	V/C	LOS	
Α	Yale Ave North of Michelson Dr	Commuter	13,000	540	0.04	Α	
В	Yale Avenue between Michelson Drive and Royce Road	Commuter	13,000	1,230	0.09	А	
С	Yale Avenue between Royce Road and University Drive	Commuter	13,000	1,770	0.14	А	

Table 5 and Figure 3 show the total active transportation movement counts during AM (7AM-9AM) and PM (2PM-6PM) periods (six hours) at the study intersections and at I-405 overcrossing by mode. The highest pedestrian movement is at Yale Avenue and Michelson Drive directly adjacent RSJMS. Bicycle counts show more even distribution throughout the study area, suggesting bicyclists traverse the entire study corridor while pedestrians are either walking to nearby homes or loading by automobile along adjacent streets. This observation was supported by field observations. Scooters and skateboards were observed as a less common travel mode, with a total of 53 and 10 observed respectively.

¹ Highway Capacity Manual 6th Edition

² Four-way stop controlled

³ Two-way stop controlled

⁴ Intersection Capacity Utilization



Table 5 - November 2022 AM and PM Periods Active Transportation Counts

Mode	I-405 Overcrossing	Yale/Michelson	Yale/Royce	Yale/University	Total by Mode
Pedestrians	107	397	150	82	735
Bicyclists	88	194	160	192	634
Scooter	6	20	10	18	53
Skateboard	1	5	2	2	10
Total by Segment	201	616	321	294	1431

Total Active Transportation Counts 6 Hour (7-9 AM + 2-6 PM)

Peds Bikes Scooter Skateboard

I-405 Michelson Royce University

B. Buildout Conditions

In the adopted General Plan Circulation Element, Yale Avenue is classified as a secondary highway between University Drive and Michelson Drive. North of Michelson Drive, Yale Avenue is classified as a commuter highway with a planned vehicular overcrossing over I-405. The City has coordinated with OCTA regarding implementation of the Project and the Project does not intend to formally change the OCTA managed Master Plan of Arterial Highways (MPAH) classification of Yale Avenue.

Since the City General Plan identifies the potential future construction of Yale Avenue over I-405 to serve car traffic, additional traffic scenarios were analysis with and without the roadway crossing. Therefore, the following four (4) buildout conditions are evaluated for traffic analysis considering the possibility of a vehicular overcrossing and the number of vehicle travel lanes on Yale Avenue:



- I-405 Vehicular Overcrossing (OC) with Four-Lane Yale Avenue
- I-405 Vehicular OC with Two-Lane Yale Avenue
- No I-405 Vehicular OC with Four-Lane Yale Avenue
- No I-405 Vehicular OC With Two-lane Yale Avenue

The study intersection forecast LOS analysis was prepared during the AM and PM peak periods as shown in Table 6.

Table 6 - Forecast Buildout Conditions Study Intersection Peak Hour LOS

			Buildout Year I-405 Vehicular OC With Four-Lane Yale Ave		Buildout Year I-405 Vehicular OC With Two-Lane Yale Ave		Buildout Year No I-405 Vehicular OC With Four-Lane Yale Ave		Buildout Year No I-405 Vehicular OC With Two-Lane Yale Ave	
#	Intersection	Methodology	AM	PM	AM	PM	AM	PM	AM	PM
			LOS	LOS	LOS	LOS	LOS	LOS	LOS	LOS
1	Yale Avenue and Michelson Drive	HCM ⁵ 4-WSC ⁶	F	F	F	F	С	С	С	С
2	Yale Avenue and Royce Road	HCM 2-WSC ⁷	E	С	E	С	С	В	С	В
3	Yale Avenue and University Drive	ICU ⁸	В	Α	В	Α	В	Α	В	Α

N/A = Not Applicable

The following intersections under buildout year I-405 vehicular OC with four-lane Yale Avenue are expected to operate at LOS E or worse during either AM or PM peak hours:

- Yale Avenue and Michelson Drive (AM LOS F | PM LOS F for four-way stop-controlled operation)
- Yale Avenue and Royce Road (AM LOS E for two-way stop-controlled operation)

The following intersections under buildout year I-405 vehicular OC with two-lane Yale Avenue are expected to operate at LOS E or worse during either AM or PM peak hours:

- Yale Avenue and Michelson Drive (AM LOS F | PM LOS F for four-way stop-controlled operation)
- Yale Avenue and Royce Road (AM LOS E for two two-way stop-controlled operation)

Signalization is identified as a potential improvement to provide acceptable LOS at Yale Avenue and Michelson Drive as it meets signal warrants. A four-way stop controlled

⁵ Highway Capacity Manual 6th Edition

⁶ Four-way stop controlled

⁷ Two-way stop controlled

⁸ Intersection Capacity Utilization



intersection at Yale Avenue and Royce Road is identified as a potential improvement to reduce delay.

The study roadway segment forecast LOS analysis was prepared for daily traffic as shown in Table 7.

Table 7 - Buildout Conditions Roadway Study Segment LOS

#	Sagment	Buildout Year I-405 Vehicular OC with Four-Lane Yale Ave	Buildout Year I-405 Vehicular OC with Two-Lane Yale Ave	Buildout Year No I-405 Vehicular OC with Four-Lane Yale Ave	Buildout Year No I-405 Vehicular OC with Two-Lane Yale Ave
"	Segment	LOS	LOS	LOS	LOS
Α	Yale Avenue North of Michelson Drive	D	D	А	А
В	Yale Avenue between Michelson Drive and Royce Road	А	А	А	А
С	Yale Avenue between Royce Road and University Drive	А	А	А	А

As shown in Table 7, the study segments are forecast to operate at acceptable LOS (LOS D or better) operations under all four buildout conditions scenarios.

Collision Data

Within the study area, a total of six collisions were recorded between March 2016 and March 2018 and are identified in Figure 4. Of the six collisions, four property damage only collisions were reported at the intersection of Yale Avenue and University Drive. At the intersection of Yale Avenue and Michelson Drive two collisions with bicyclists are recorded near the south leg crosswalk.





V. Deficiencies and Justifications

The City of Irvine General Plan Circulation Element designates Yale Avenue as a secondary highway, where secondary highways provide for the movement of traffic between planning areas and/or the movement of traffic to and from activity centers within planning areas. North of Michelson Drive and over I-405, Yale Avenue is designated as a commuter highway. A commuter highway functions primarily as a collector facility which has the ability to handle through traffic movements between arterials. However, the commuter highway segment over I-405 remains undeveloped, resulting in Yale Avenue being built for more vehicular travel lanes than needed for traffic demands.

In addition to an excess roadway ROW for current traffic demand, the existing bicycle facilities along Yale Avenue are not separated from motor vehicles. The feedback from the Project's community engagement largely supported a separated cycletrack along Yale Avenue to lower the bicyclist level of stress which in turn can improve multi-modal conditions and encourage more bicycle trips. As shown by the 2023 United States Federal Highway Administration (FHWA) study titled "Developing Crash Modification Factors for Separated Bicycle Lanes", converting a Class II bike lane to a Class IV separated bikeway yields a 50% or more reduction in crashes. Implementation of lower stress bicycle facilities may encourage additional pedestrian trips through increased separation from moving car traffic and with less cyclists use of the sidewalk.

The community also noted an absence of pedestrian crossings, particularly at the community paseos south of Michelson Drive. The FHWA utilizes a chart for pedestrian crash countermeasures by roadway features, included in the "Guide for Improving Safety at Uncontrolled Crossing Locations". The City also considers factors such as posted speed limits, number of vehicle lanes, and vehicle and pedestrians volumes for installation of countermeasures at uncontrolled crossing. A Rectangular Rapid Flashing Beacon (RRFB) is proposed in conjunction with the proposed pedestrian crosswalk under the Project location conditions.

Other identified Project corridor challenges include:

- The lack of a crosswalk on the east leg of the Yale Avenue and University Drive intersection.
- Bicycle riding behavior observed along sidewalks introduces potential conflicts with pedestrians.
- Bicyclists counter-flow riding observed within the roadway introduces potential conflicts with other bicyclists and vehicles.



 An unmarked crossing at Royce Road intersection where there are sight distance concerns.

The Project will address existing challenges and reconfigure underutilized roadway space to provide improved bicycle facilities with a higher level of comfort and enhance pedestrian facilities for those who walk and bicycle and roll (skateboard, scooter, etc.) along Yale Avenue.

VI. Project Description

A. Proposal and Alternatives

Criteria was developed to support an evaluation of potential bicycle facility and roadway elements in December 2022. The criteria sought to identify positive outcomes or avoidance of issues of potential roadway concepts. The criteria included the following:

- Explores a new bikeway concept;
- Offers low stress bicycle facilities;
- Offers low stress pedestrian facilities;
- Provides direct access to University Trail and William R. Mason Regional Park;
- Provides direct access to RSJMS;
- Avoids conflicts with RSJMS parking and circulation;
- Matches drivers expectations;
- Avoids tree impacts;
- Impose minor impact on traffic operations;
- Allows for center medians or raised buffers;
- Avoids utility impacts;
- Avoids requiring new maintenance equipment; and
- Avoids complex reconfiguration of University Drive signal operations.

Potential roadway concepts evaluated through the criteria included the following:

- Two-way Class IV (cycletrack) on east side;
- Two-way Class IV (cycletrack) on west side;
- Class I (multi-use path) on east side;
- Class I (multi-use path) on west side;
- One-way Class IV (cycletrack) on both sides; and
- Class II (on-street bike lanes) with median (similar to Michelson Drive).



Utilizing the criteria, the concepts were narrowed to four (4) cross-section alternatives for subsequent public review and are shown in Attachment B – Cross Section Alternatives. The four alternatives included:

- 1. Alternative 1: 2-Way Class IV (Cycletrack) -West Side
 - a. Provides a 12' wide two-way cycletrack with a 4' landscaped median on the west side of the roadway. Provides one 11' vehicle travel lane and parking is available on both sides of the roadway. Includes a 10' middle two-way turn lane.
- 2. Alternative 2: 2-Way Class IV (Cycletrack) -West Side Hybrid
 - a. Provides a 12' wide two-way cycletrack with a 4' landscaped median on the west side of the roadway. Provides one 12' vehicle travel lane and 6' buffered Class II bike lane in each direction. Parking is available only on the east side of the roadway.
- 3. Alternative 3: 1-Way Class IV (Cycletrack)
 - a. Provides a 7' one-way cycletrack, 5' landscaped median, and one 12' vehicle travel lane in both directions. Parking is available on both sides of the roadway.
- 4. Alternative 4: Class II Buffered Bike Lanes and Widened Shared Use Path
 - a. A 6' Class II bike lane, 3' buffer, and 12' vehicle travel lane is provided in each direction. A 14' median runs along the center of the roadway.

1. Preferred Project

Based on public feedback, Alternative 3, a one-way Class IV (cycletrack), was identified as the most desired Project cross-section. The public's support for the one-way Class IV (cycletrack) concept was documented during the second community workshop, where potential cross-sections were presented, and during the second public survey, where participants were asked to identify and rank the Project alternatives. The public's endorsement of Alternative 3 was further demonstrated through a Southern California Association of Governments (SCAG) *Go Human* demonstration event. One-way Class IV (cycletracks) were temporarily installed between Michelson Drive and Royce Road with materials from the SCAG *Go Human* Kit of Parts. This event provided an opportunity for the public to experience the Alternative 3 concept firsthand and provide immediate feedback. Alternative 3 was further refined with more design features in the finalized concept.



The preferred Project concept includes:

- One-way Class IV (cycletracks) on each side of the roadway that are 6 to 7-feet wide with raised landscaped/concrete buffers.
- New and modified pavement delineation (striping) and signage.
- Parking and passenger loading/unloading zones adjacent to the landscaped/concrete buffers between north end of Yale Avenue and the community paseo approximately 700 feet south of Michelson Drive. Approximately 46 vehicles could park south of Michelson Drive and 19 could park north of Michelson Drive after implementation of the Project.
- Reduced crossing distances for pedestrians at all intersections and the paseo (via the Class IV cycletrack buffers).
- High-visibility crosswalk markings, advanced yield lines, pedestrian refuge islands (via the Class IV cycletrack buffers), and installation of a Rectangular Rapid Flashing Beacons (RRFB) traffic control device at the paseo approximately 700 feet south of Michelson Drive.
- Traffic signal modifications for bicycle operations and green crossbike paint at the Yale
 Avenue and University Drive intersection. Additional improvements at the Yale Avenue
 and University Drive intersection include modification to the southwest corner guard rail
 for a widened and upgraded ADA curb ramp within City ROW.
- Additional streetlights throughout the Project area.
- New sidewalk, curb, and gutter at north end of Yale Avenue to connect to the pedestrian and bicycle I-405 overcrossing.

The proposed Project recommends modification to the traffic signal operations to provide a dedicated phase to allow bicyclists and pedestrians to cross University and for northbound cyclists to access the cycletrack. The traffic signal modifications are included in the cost estimates for the project and the operations have been reviewed assuming the signal phasing operations which is not forecast to cause deficient level of service operations.

The preferred Project improvements are located within the existing City owned ROW and will have minimal impacts on existing landscaping and sidewalks. Project benefits include but are not limited to a reduction in roadway collisions; diversified travel options; enhanced connections to the City's off-street trail network; reduced air, noise, and stormwater pollution; reduced motorist speeding behavior, and community-building and increased quality of life with recreational facilities.





Figure 5 —Bicyclists riding in the temporary Class IV cycletrack on Yale Avenue during the SCAG Go Human Demonstration Event on August 26th, 2023



2. Alternatives Withdrawn from Consideration

The first online public survey was open from October 4th, 2022 to November 4th, 2022 which identified the following improvements as most effective in encouraging walking and biking along the Project Corridor:

- 1. Enhanced bicycle/pedestrian separation from moving cars
- 2. Improved crossings at existing intersections
- 3. Wider bike lanes
- 4. Slower vehicle speeds

On October 22nd, 2022, a Project workshop was held in-person at the University Community Center in Irvine. Approximately 50 attendees attended. From the engagement at the public workshop, the Project Team identified the following considerations for the corridor;

- Enhanced bicycle/pedestrian separation from moving cars
- Support improved crossings at existing intersections
- Slower motor vehicle speeds
- Suggestions for a center median
- Additional pedestrian crossings
 - Particularly at Yale Avenue and Royce Road intersection and at paseo north of Tamarack Way where there is no marked crossing or pedestrian curb ramps

In December 2022, the following concepts were evaluated for consideration in the development of Project alternatives:

- Two-way Class IV (cycletrack) on east side;
- Two-way Class IV (cycletrack) on west side;
- Class I (multi-use path) on east side;
- Class I (multi-use path) on west side;
- One-way Class IV (cycletrack) on both sides; and
- Class II (on-street bike lanes) with median (similar to Michelson Drive).

The initial scoring identified the top three concepts as the two-way cycletrack on the west side, two-way cycletrack on the east side, and the one-way cycletrack on both sides of Yale Avenue. Four cross-section alternatives were developed based on this initial evaluation of concepts. Feedback was sought on the cross-section alternatives in the second public survey that was open from March 8th, 2023 to April 7th, 2023. Table 8 below details the results of the survey when respondents were asked for their first and second choice cross-section alternative:



Table 8 - Survey Results for Preferred Cross-Section Alternatives

Cross-Section Alternative	1 st Choice for % of Respondents	2 nd Choice for % of Respondents
Alternative 3 (One-Way Cycletrack)	30%	33%
Alternative 4 (Buffered Bike Lanes and Widened Shared Use Path)	28%	17%
Alternative 1 (Two-Way Cycletrack-West Side)	23%	29%
Existing Conditions	13%	9%
Alternative 2 (Two-Way Cycletrack- West Side Hybrid)	6%	13%

Alternatives 1, 2, and 4 were removed from consideration following strong support for Alternative 3 from the public and City staff.

3. No Project Alternative

In the No Project alternative, no improvements are proposed along the Yale Avenue corridor. Consequently, the Yale Avenue corridor would remain a wide roadway without the benefit of enhancing bicyclist and pedestrian mobility and safety that support the City's goal of GHG reductions and potential management of travel speeds.

4. Project Phasing

Implementation of the Project would be carried out in a single project phase.

B. Material Alternatives and Restrictions

The Project implementation will include construction of two one-way Class IV cycletracks and two raised buffers. Cycletrack construction would consist of concrete, asphalt concrete, and aggregates for base materials as available to the City.

The Project team has also identified and analyzed landscaped and hardscaped options for the proposed raised buffers. Selected materials will be identified during the Plan, Specification, and Estimate (PS&E) phase and will be indicated on the Project construction plans.

C. Non-Standard Design Features / Variances

The Project concept includes variances from the City Standard Plans with vehicle travel lane widths and parking lane widths.

The Class IV separated cycletrack may be the first facility of its kind within the City, subject to other parallel City efforts, that requires a deviation from the current City standards or minimum requirements. Standard Plan 104 note 9 from the City Standard Plans states each parallel parking space shall have a minimum dimension of 8 feet wide by 22 feet long and shall be in accordance with the zoning ordinance section 4-4-1 A.5. The Project concept proposes 7-foot



wide parking along a landscaped buffer, consistent with the National City Transportation Officials (NACTO) Urban Street Design Guide which recommends parking stalls be 7-9 feet wide. The City Signing and Striping Guidelines also call for 13-foot travel lanes next to raised medians, while the project proposes 11-foot-wide travel lanes. Caltrans Design Information Bulletin 94 (DIB 94) provides justification for the concept travel lane widths in *Table 5.3 Suggested Minimum Lane Widths by Place Type and Proposed Operating Speed.* As the Project is in a suburban area and has posted speed limits of 40-45 miles per hour, DIB 94 recommends 11 to 12-foot vehicle travel lane widths.

D. Utilities

Table 9 identifies the companies and agencies who own utilities within or near the study limits.

Table 9—Yale Avenue Utility Inventory

Company	Utility Equipment	Required Relocations
AT&T Distribution	 Buried, conduit, building, and underground substructures 	No
COX Communications	 Underground 2" Conduit 	No
Irvine Ranch Water District	 12" RCP Sewer 8" Water Line 6" ACP RW 4" Service Line RW 	Potential
Municipal Water District of Orange County	 12" ACP water main 54" inside-diameter welded-steel East Orange County Feeder No. 2 and accompanying manhole structures, air-release-vacuum-valve structure 40' wide permanent easement right-of-way 	Potential
Southern California Edison	UG Conductor 0-750V	No
Southern California Gas Company	8" HSL 35-20-43" PA	No



1. Determination of Prior Rights

Prior rights have yet to be confirmed but will be identified in the Caltrans B-letters process via coordination with the identified utility companies in the Project area. Through this process the utilities companies will provide their rights within the roadway.

From a review of received As-Builts and GIS maps, it can be assumed that AT&T Distribution, COX Communications, Irvine Ranch Water District, Southern California Edison, and Southern California Gas Company have a franchise agreement with the City as they all have infrastructure within the roadway and/or sidewalk of Yale Avenue. Metropolitan Water District (MWD) is assumed to pre-exist the roadway and appears to have permanent right-of-way 20 feet to either side of the 55-inch pipeline. It is assumed at this point that they have prior rights and would likely be the City's liability for any potential cost for adjustments.

2. Required Relocations

The Project utility mapping analysis revealed challenges in accurately determining the locations of various utilities but relocations of all utilities were determined to be unlikely. Continued utility coordination will be necessary during the Project's preliminary engineering phase. The telecommunications GIS maps did not provide accurate alignments for manholes or pull boxes so aerial imagery and site visit review was utilized to identify their locations. Additionally, most utilities lack elevation details, except for the water lines. The available information suggests that the water lines were placed approximately 10 feet below elevation.

Anticipated conflicts which are likely to require relocations within the study area include water valve covers in the proposed landscaped/concrete buffers and Class IV cycletracks. The water lines located 10 feet under the surface and running parallel to the buffers are unlikely to require relocation and instead may constrain the types and placements of plants within the proposed landscaped/concrete buffers.

E. Drainage

The Project proposes two total Filterra treatments at the storm drain inlets on the west and east sides of Yale Avenue near the University Drive intersection.

F. Landscaping & Irrigation

The Project will incorporate plant selections harmonizing with the surrounding landscape areas and adhere to the guidelines outlined in the City Landscape Manual and Standard Plans. The Project irrigation strategy will prioritize water efficiency, employing techniques such as bubblers and drip irrigation systems detailed in the City Landscape Manual and Standard Plans.



G. Traffic Signal Improvements

The proposed Project recommends modification to the traffic signal operations to provide a dedicated phase to stop motor vehicle traffic and allow bicyclists and pedestrians to cross University and for northbound cyclists to access the cycletrack. The traffic signal modifications are included in the cost estimates for the project and the operations have been reviewed assuming the signal phasing operations which is not forecast to cause deficient level of service operations.

H. Conformance with General Plan and Zoning Code Standards

The Project is in conformance with the following objectives from the City's General Plan:

Element B Circulation

Objective B-3 addresses multi-modal goals by finding policies that support a pedestrian circulation system to support and encourage walking as a mode of transportation.

Element K Parks and Recreation

Objective K-3 aims to establish parks and recreation facilities with safe and easy access via policy (c), which uses the adopted 2017 Parks Master Plan to locate parks adjacent to public shared-use paths in an effort to connect parks to nearby paths for enhanced connectivity.

In addition to conformance with the City's General Plan, the Project was identified in the City's SATP as a potential opportunity to support mobility for bicyclists by implementing a Class IV cycletrack.

The Project also supports regional bicycle planning efforts which include OC Active, Orange County Transportation Agency's (OCTA) 2022 Long-Range Transportation Plan, and the 2016 OC Foothills Bikeways Strategy. The Project will connect to the existing bikeways on University Drive that are part of Corridor J, the Jeffrey Corridor of the OC Foothills Bikeways Strategy. When completed, Corridor J will provide over nine (9) miles of connected Class I and Class II bikeways.

I. Inter-Agency Considerations

The City is the lead agency for the Project. Inter-agency coordination has been ongoing throughout the Project planning process with OC Parks, Orange County Fire Authority (OCFA), and Irvine Police Department. OC Parks manages William R. Mason Regional Park which is adjacent to the Project area and located south of University Drive. The Project team has consulted with OCFA on allowable roadway design and with OC Parks related to potential habitat impacts in the regional park.



The following utility companies have infrastructure within the Project area where continued coordination will be needed; AT&T Distribution, Cox Communications, Irvine Ranch Water District, Municipal Water District of Orange County, Southern California Edison, and Southern California Gas Company.

J. Project Schedule

The Project's planning phase concluded in Summer 2024. The Project engineering phase is expected to begin in Fall 2024 and be completed within one (1) to two (2) years and one (1) additional year for Project construction.

K. Project Costs

The estimate cost of construction of the Project, based on 30% concept plans, is \$7,865,000. Components of the Project cost include the construction of curb ramps, sidewalk, bike paths, landscaping, drainage, RRFB, traffic signal modification, and street lighting. A detailed construction cost estimate is provided in Attachment D- Engineering Cost Estimate. The total project cost is estimated to be \$9,440,000, which includes the following project phases - preliminary engineering, final design, construction, construction engineering and other supporting costs, as detailed in Table 10.

Table 10 - Summary of Project Costs

Phase	Assumptions	Amount
Preliminary Engineering and	Completed	\$325,000
Environmental Document		
Final Design and Right of Way	Includes contingency and	\$500,000
Engineering and Administration	management estimate	
Construction	Includes 25% contingency	\$7,865,000
Construction Engineering and	Includes contingency and	\$573,000
Administration	management estimate	
Other Costs	Administration Costs	\$177,000
	Total - All Phases	\$9,440,000



VII. Agreements/Permits

The following coordination, agreements, and permit approvals will be required prior to commencement of project construction:

A. Utilities

Utility notification letters were sent to utility companies identified by the Dig Alert website for the study area. Continued coordination with the following companies will be required to confirm the locations, extents, and costs of necessary relocations:

- AT&T Distribution
- COX Communications
- Irvine Ranch Water District
- Municipal Water District of Orange County
- Southern California Gas Company
- Southern California Edison

B. Inter-Agency

OC Parks; Review of proposed improvements within City ROW along Yale Avenue and at the Yale Avenue and University Drive intersection.

OCTA; Review of proposed improvements within City ROW along Yale Avenue as it relates to the MPAH.

C. Intra-Agency

City of Irvine – California Environmental Quality Act Clearance documents; Approval of construction bid documents.

VIII. Right-of-Way

A. Existing ROW

The existing ROW is 91-feet wide along Yale Avenue within the project limit. The proposed Project improvements are to be implemented within the existing 64-foot curb-to-curb width within the existing City owned ROW. The improvements will have minimal changes to existing landscaping and sidewalks. Yale Avenue's existing roadway configuration is as follows:

- 5-foot sidewalk on the west side of the roadway.
- 4-foot landscaped area on the west side of the roadway.
- One 8-foot Class II bike lane.
- Two 24-foot motor vehicle travel lanes.
- One 8-foot Class II bike lane.



- 11-foot landscaped area on the east side of the roadway.
- 9-foot sidewalk on the east side of the roadway.

B. Constraints

William R. Mason Park

William R. Mason Park, located south of the University Drive and Yale Avenue intersection, is maintained by OC Parks and is an environmentally sensitive area. As an environmentally sensitive area, there are constraints on allowable development at the Yale Avenue and University Drive intersection. While an additional crossing on the east leg would benefit bicycle and pedestrian access to and from the University Trail, the nearby environmentally sensitive OC Parks land limits the development of a direct north-south crosswalk. Modification of the OC Parks managed area would impact protected habitat and require notable landform modifications that could also affect the creek flowlines. The existing University Drive and Yale Avenue intersection only provides crosswalks on the north and west legs of the intersection and therefore does not provide direct pedestrian and bicycle connectivity to the east side of Yale Avenue.

To address this constraint, the Project proposes providing a diagonal crossbike through the intersection. The Project improvements will accomplish greater bicycle access to and from the University trail and William R. Mason Park and support the implementation of one-way Class IV cycletracks.

<u>University Park Homeowner's Association (HOA)</u>

The University Park HOA owns the ROW adjacent to the roadway between University Drive and Michelson Drive as well as the community paseos. The Project's enhancements will not encroach on the HOA's ROW.

C. Proposed ROW

The Project improvements are planned within the existing City owned ROW. No additional ROW is proposed.

IX. Environmental Clearance

The proposed improvements will not create additional travel lanes and instead will include one-way Class IV bicycle facilities and pedestrian crossings that qualify for both a California Environmental Quality Act (CEQA) Class 1 Categorical Exemption (per Section 15301 of the CEQA Guidelines), the California Public Resources Code (PRC) 21080.25, as well as a Statutory Exemption under Senate Bill (SB) 922. The City is preparing a Notice of Exemption per the statutory exemption identified in PRC 21080.25.



The Project is statutorily exempt from a Water Quality Management Plan (WQMP) as the Project would reduce overall impervious areas in the study area. Despite this, a WQMP was prepared before the notice of the statutory exemption. The WQMP found that the post-Project conditions will increase the pervious roadway area to a total of 0.79 acres.

A biological study for the Project area was conducted which resulted in the following findings and recommendations:

- Due to the nature of the Project activities, no impacts are anticipated on special-status species, and existing landscaped and ornamental habitat on-site will be protected to the greatest extent possible through implementation of measure BIO 1.
- Project activities should be conducted outside of the nesting bird season if feasibly possible as per measure BIO 2.
- If the Project must occur during the nesting season (February 1–September 15), then preconstruction nesting bird surveys should be conducted by a qualified biologist as described in measure BIO 3.
- In order to prevent the proliferation and spread of noxious, invasive weed species, all construction equipment, associated tools, and personnel footwear should be thoroughly washed before arriving on-site, as stated in measure BIO 4.

A cultural study was conducted for the Project area. No archaeological resources were identified in the Project area and the potential for the Project to encounter or affect subsurface cultural materials during construction and its excavations is low. Additionally, no historic resources exist within or directly adjacent to the Project limits. The University Park neighborhood is not locally designated or identified as a potential historic district in the City of Irvine's General Plan. Therefore, the Project area contains no historical resources under CEQA. The Project does not have the potential to cause significant adverse impacts on historical resources under CEQA.

An Initial Site Assessment (ISA) was performed with the purpose to review, evaluate, and document present and past land uses and practices, and visually examine Project area conditions to identify recognized environmental conditions (RECs). A REC is defined as the presence or likely presence of any hazardous substances or petroleum hydrocarbons on a property under conditions that indicate an existing release, a past release, or a material threat of a release of any hazardous substances or petroleum hydrocarbons into structures or into the ground, groundwater, or surface water of the Project area. The REC term does not include de minimis conditions that generally do not present a threat to human health or the environment, and that generally would not be the subject of an enforcement action if brought to the attention of appropriate governmental agencies. The ISA assessment did not reveal any RECs in connection with the proposed Project area.



X. Public Involvement/Hearing Process

The Project engagement, which included Phase I, Phase II, and the *Go Human* demonstration event, identified a variety of challenges and concerns as well as improvements.

Phase I included the following activities:

- Three (3) meetings at Rancho San Joaquin Middle School
 - School District meeting August 26th, 2022
 - Executive Board Parent Teacher's Association October 4th, 2022
 - Associated Study Body meeting October 4th, 2022
- One (1) stakeholder meeting
 - In-Person Meeting October 12th, 2022
- Five (5) Community Homeowner Association (HOA) meetings
 - Parkcrest HOA October 6th, 2022
 - Parkside HOA October 11th, 2022
 - University HOA October 12th, 2022
 - o The Terrace HOA October 25th, 2022
 - Village Park November 2nd, 2022
- One (1) in-person public workshop
 - o October 22nd, 2022
- One (1) online survey
 - o Via Mentimeter October 4th, 2022 to November 4th, 2022
- Digital and print promotion of the Project

Phase II included the following activities:

- One (1) stakeholder meeting
 - Virtual Meeting March 7th 2023
- One (1) virtual public workshop
 - Zoom Workshop March 8th, 2023
- One (1) presentation at Rancho San Joaquin Middle School
 - o Parent Teacher Association Presentation March 16th, 2023
- Two (2) Community Homeowner Association (HOA) meetings
 - Parkside HOA February 28th, 2023
 - Village Park HOA March 30th, 2023
- One (1) online survey
 - o Via Mentimeter March 8th, 2023 to April 7th, 2023
- Digital and print promotion of the Project



- One (1) SCAG Go Human Demonstration event on August 26, 2023, which included the following:
 - Demonstration of separated one-way Class IV cycletrack
 - Community engagement hubs at Royce Road and University Drive
 - o Digital and print promotion of the Go Human Demonstration event

Tribal consultation pursuant to Assembly Bill 52 is not required for the Project because the project is statutorily exempt from the requirement to comply with CEQA. The construction will be minor and will occur within the confines of the existing roadway.

The Project engagement was critical for guiding the vision for Yale Avenue and advancing the Project from its initial identification in the City's 2020 SATP. The engagement feedback will continue to be instrumental in the development of the Project through engineering and design. From Phase I, Phase II, and the *Go Human* demonstration event, the following Project priorities were identified:

- Incorporate physical separation between transportation modes, most especially between vehicles and bicyclists and bicyclists and pedestrians, through the construction of one-way Class IV cycletracks.
- Promote traffic calming through travel lane narrowing and other engineering and signage measures.
- Install crosswalks and other pedestrian crossing enhancements at the community paseos and at Royce Road.
- Install crossing enhancements at the existing crosswalks at Michelson Drive and University Drive.
- Consider parking and/or loading spaces near RSJMS that support student pick-up and drop-off as well as parking lot overflow during special events.
- Balance muti-modal travel needs and the community desire to maintain limited parking on Yale Avenue.

XI. Other Considerations

A. Impacts on Non-Motorized Transportation and Pedestrian Modes

During construction, modifications between existing curbs along Yale Avenue between the I-405 bridge and University Drive may require temporary impacts to bicycle and pedestrian routes within the study area. Detour routes will be accessible and clearly signed to direct bicyclists and pedestrians around the construction areas. The Project's one-way Class IV facilities will ultimately improve active transportation roadway user mobility and safety due to the physical separation between vehicles.



B. Prolonged Temporary Road and/or Ramp Closure

Construction of the proposed improvements will not require prolonged temporary road closures. To minimize construction impacts to local circulation, measures will be taken to minimize street/lane closures and detours, particularly during weekday rush hours and RSJMS related loading activity. Traffic control/detour plans will be prepared for necessary closures using approved City of Irvine traffic control guidelines.

C. Hazardous Waste or Material

Within the Project area, there is record of one site with recognized environmental conditions (REC). In May 1997, the Irvine Ranch Water District reported a release of 9,000 gallons of reclaimed water to the Orange County Emergency Management Division. Reportedly, a line broke on the customers side of a meter due to new installation of a gate valve. The reclaimed water flowed down the road into San Diego Creek down to Newport Back Bay. Based on this information, this listing does not represent a recognized environmental condition to the Project.

The following precautionary recommendation is provided in the event of unknown or suspect materials are encountered during construction:

General Site Disturbance Activities

If unknown wastes or suspect materials are discovered during construction by the contractor, which they believe may involve hazardous waste/materials, the contractor shall:

- Immediately stop work in the vicinity of the suspected contaminant, removing workers and the public from the area;
- Notify the City of Irvine Director of Public Works;
- Secure the areas as directed by the City;
- Notify the implementing agency's Hazardous Waste/Materials Coordinator; and
- Perform remedial activities as required under existing regulatory agency standards.

D. Wetland and Floodplain

The Project area lies on the Orange County Coastal Plain approximately 114 feet above mean sea level. The Orange County Basin is bounded to the north by the Puente and Chino Hills, to the east by the Santa Ana Mountains, to the south by the San Joaquin Hills, and to the southwest by the Pacific Ocean (DWR, 2003).

The Orange County basin underlies the lower Santa Ana River watershed and is characterized by a deep structural alluvial basin containing a thick accumulation of interbedded sand, silt and clay. The Irvine subbasin, bounded by the Santa Ana Mountains and the San Joaquin Hills, forms the southern-most portion of the basin. Irvine area aquifers are thinner and contain



greater percentages of clay and silt deposits than aquifers in the main portion of the basin (DWR, 2003).

The nearest groundwater monitoring well is located approximately 1,800 feet southeast of the Project area and the average depth-to-groundwater during the June 2023 groundwater event was approximately 48 feet below the top of well casing, with general groundwater flow direction to the northwest (Geotracker Global ID T0605900193).

According to the 2004 Preliminary Digital Geologic Map of the Santa Ana 30' x 50' Quadrangle, Southern California, version 2.0 compiled by Douglas M. Morton, subsurface materials at the Project area are primarily Marine deposits which in part are overlain by local, mostly alluvial fan, deposits. A concealed fault is depicted in the northern portion of the Project area.

As presented in the Environmental Data Resources (EDR) Radius map report, the Project area surface soil (to a depth of 22 inches) is a sandy loam, with very slow infiltration rates, which is underlain by a sandy clay/sandy clay loam. The soil has a high corrosion potential for uncoated steel.

E. Roadway Reconstruction, Restoration, Pavement Rehabilitation

The existing pavement along Yale Avenue is in very good condition and shows minimal signs of wear throughout the study limits. The City of Irvine prepared a Pavement Management Plan in 2023 which identified Yale Avenue with a Pavement Condition Index (PCI) ranging from 85 to 100 within the Project limits. The construction of the proposed roadway improvements will also be with materials consistent with the standard City requirements and shall be identified during the PS&E phase of the Project.

F. Bus and Emergency Lanes

The Project will not include bus or emergency lanes but through coordination with the OCFA, the Project design will provide facilities that accommodate emergency vehicles.

G. Interim Features

No interim improvements are proposed.

H. Traffic Management Plan

A Traffic Management Plan (TMP) will be prepared for approval by the City of Irvine prior to the commencement of construction activities. The TMP will describe necessary detours, emergency routes, and other measures to provide congestion relief and safety during short-term construction activities. Construction staging should be developed to minimize traffic impacts with considerations for phased implementation. Local residents and RSJMS stakeholders will be consulted in the development of construction staging and the TMP to best reflect school-



related traffic and activities and to maintain access to the residential communities directly adjacent to Yale Avenue. Detour routes for pass through traffic shall be identified where appropriate. The TMP will meet City of Irvine traffic control guidelines.

I. Biological Requirements

No materials or equipment shall be placed on the dirt or vegetation adjacent to the developed portions of the Project area (i.e., outside of the existing concrete footprint). Work should occur outside of nesting bird season which occurs annually between February 15th and September 15th. Should work be required during nesting bird season, pre-disturbance avian nesting surveys must be conducted by a qualified biologist. Survey reports shall be furnished to OC Parks upon request. If nests or nesting behaviors are identified, the biologist shall notify the OC Parks Natural Resources Program Coordinator within 24 hours with a report summarizing survey findings. The biologist shall establish appropriate no-work buffers, and the City shall be solely responsible for complying with all federal, state, and local laws.

To prevent invasive weed seed spread, vehicles, equipment, tools, and personnel footwear shall be cleaned before each entrance onto the Project site.

XII. Recommendations

After extensive community and stakeholder engagement and close collaboration between City and Mark Thomas staff, the Project team recommends Alternative 3 (Class IV Separated Bikeway/Cycletrack) with the following improvements be advanced for final design and implementation:

Bicycle Enhancements

- Separated, one-way Class IV cycletracks along both sides of Yale Avenue from the southern boundary at University Drive to the north terminus that connects to the I-405 pedestrian and bicycle bridge.
- Intersection improvements at Yale Avenue and University Drive which include a diagonal bicycle crossing with green markings.
- Intersection improvements at Yale Avenue and Royce Road which include green conflict paint





Pedestrian Enhancements

- Crossing enhancements at the community paseos.
- High-visibility crosswalk markings, advanced yield lines, pedestrian refuges (via the Class IV cycletrack buffers), and installation of an RRFB are likely to be recommended by the City at the paseos.
- Crossing enhancements including an upgraded ADA ramp at the southwest corner of Yale Avenue and University Drive intersection.



RECOMMENDED BY:

Melisse By

Melissa Dugan

Project Development Administrator

City of Irvine

Paul Martin, PE, TE Project Manager

RANN

Mark Thomas



Attachment A – Engineering Concepts


CONSTRUCTION PLANS FOR THE IMPROVEMENT OF

SOUTH YALE CORRIDOR IMPROVEMENTS

CIP# 312204

INDEX OF DRAWINGS

SHEET No.	DESCRIPTION
1	TITLE SHEET
2-3	TYPICAL SECTIONS
4-5	LAYOUT



VICINITY MAP NOT TO SCALE



					PLAN PREPARED BY: MARK THOMAS MARK THOMAS & COMPANY 2121 ALTON PARKWAY, SUITE 210 IRVINE, CA 92606
TE	REVISIONS	ENGR.	APPROV.	DATE	DESIGN ENGINEER R.C.E. No.

PROFESSIONAL ** ** ** ** ** ** ** ** **		
	DATE	APPROVED BY: CITY ENGINEER
T. MIYATA	2/20/2024	CITENGINEER
	DATE	
r: T. MIYATA	2/20/2024	
	DATE	

A. SILVA

CHECKED BY:

RECOMMENDED BY:

CITY APPROVAL:

DATE	APPROVED BY:
0/2024	CITY ENGINEER
DATE	
0/2024	
DATE	
0/2024	
DATE	STEVEN CARRILLO R.C.E. NO. 73170

	IRVINE RANCH WATER DISTRICT APPROVED OF DOMESTIC WATER, SANITARY SEWER & RECYCLED WATER FACILITIES IRWD CODE 7969, PROJECT NUMBER 311611	
	APPROVED BY: DATE	
-	SUPERVISED BY: DATE	

REVIEWED BY:


30% CONCEPT PLANS	CIP NO 31220
SOUTH YALE CORRIDOR IMPROVMENTS	PROJECT X
TITLE SHEET	SHEET
CITY OF IRVINE	


PUBLIC WORKS DEPARTMENT

PLAN CHECK NO.

of **5**

SHEET REVISED: 8/15/07





30% CONCEPT PLANS

 7
 6
 DATE

 5
 DRAWN BY: T. MIYATA
 DATE 2/20/2024

 DESIGNED BY: T. MIYATA
 DATE 2/20/2024

 DATE 2/20/2024
 DATE 2/20/2024

 1
 DATE 2/20/2024

 NO. DATE
 REVISIONS
 ENGR. APPROV. DATE CHECKED BY: A. SILVA 2/20/2024



REPARED BY:
4 MARK
■ THOMAS
K THOMAS & COMPANY
ALTON PARKWAY, SUITE 210
NE, CA 92606

R.C.E. No.

SOUTH YALE
CORRIDOR IMPROVEMENTS
TYPICAL SECTIONS

PUBLIC WORKS DEPARTMENT

312204
SHEET

OF 5

CIP NO.

SHEET REVISED: 8/15/07

J:\Irvine-ZZ-000/8-South Yale Corridor Imp\CADD\Sheets\Yale



EXPOSED AGGREGATE CONCRETE

NEW SIDEWALK


e⇒ EXISTING STREET LIGHT


LANDSCAPE

NEW ASPHALT

◆ PROPOSED STREET LIGHT

LIMITED USE AREA





30% CONCEPT PLANS

7										
6										
5										ĺ,
4									DATE	1 //
3						DRAWN BY:	<u>T.</u>	MIYATA	2/20/2024] [
2						DESIGNED BY:	Τ.	MIYATA	DATE 2/20/2024	
1									DATE	
NO.	DATE	REVISIONS	FNGR.	APPROV.	DATE	CHECKED BY:	Λ	SII \/A	l	İ





PLAN PREPARED BY:		
MARI	K	
MARK THOMAS & 2121 ALTON PARKWAIRVINE, CA 92606	MAS & COMPANY	
DESIGN ENGINEER	R.C.E. No.	DAT

SOUTH YALE CORRIDOR IMPROVEMENTS LAYOUT


CIP NO. 312204 SHEET

PUBLIC WORKS DEPARTMENT 0F 5





PLANTER MEDIAN CURB CUT AND
COBBLESTONE DETAIL
NO SCALE



MAINTENANCE VEHICLE PULLOUT

NO SCALE

30% CONCEPT PLANS

CIP NO.

312204

SHEET

of **5**

7									
6									
5									
4									DATE
3						DRAWN BY:	Τ.	MIYATA	DATE 2/20/2024
2						DESIGNED BY:	Τ.	MIYATA	DATE 2/20/2024
1									DATE
۱0.	DATE	REVISIONS	ENGR.	APPROV.	DATE	CHECKED BY:	А	SILVA	2/20/2024



PREPARED BY:
⊿ MARK
■ THOMAS
ARK THOMAS & COMPANY
21 ALTON PARKWAY, SUITE 210
/INE, CA 92606

R.C.E. No.

DESIGN ENGINEER

SOUTH YALE CORRIDOR IMPROVEMENTS LAYOUT

LAYOUT


CITY OF IRVINE

PUBLIC WORKS DEPARTMENT


SHEET REVISED: 8/15/07




Attachment B – Cross-Section Alternatives




YALE AVENUE EXISTING




ALTERNATIVE 1: 2-WAY CYCLETRACK - WEST SIDE



ALTERNATIVE 2: 2-WAY CYCLETRACK - WEST SIDE HYBRID




ALTERNATIVE 3: 1-WAY CYCLETRACK



ALTERNATIVE 4: BUFFERED BIKE LANES AND WIDENED SHARED USE PATH



Attachment C – Utility Maps



30% CONCEPT PLANS

7									
6									
5									
4									DATE
3						DRAWN BY:	S.	STRAUB	DATE 12/26/2023
2						DESIGNED BY:	S.	STRAUB	DATE 12/26/2023
1									DATE
NO	DATE	DEMICIONIC	ENICD	VDDDU/	DATE	CHECKED BY	٨	\bigcirc II \ / \	40 /00 /0007



PLAN PREPARED BY:		
► MAR	K	
THO		
MARK THOMAS		
2121 ALTON PARKW. IRVINE, CA 92606	AT, SULLE ZIU	
DESIGN ENGINEER	R.C.E. No.	DATE

SOUTH YALE CORRIDOR IMPROVEMENTS LAYOUT

PUBLIC WORKS DEPARTMENT

312204 SHEET

of **5**

CIP NO.

30% CONCEPT PLANS

7							
6							
5							
4							DATE
3						DRAWN BY: S. STRAUB	12/26/2023
2						DESIGNED BY: S. STRAUB	DATE 12/26/2023
1						3. 3117700	DATE
NO.	DATE	RFVISIONS	FNGR.	APPROV.	DATF	TO CHECKED BY: A SILVA	





SOUTH YALE CORRIDOR IMPROVEMENTS LAYOUT

PUBLIC WORKS DEPARTMENT

312204 SHEET of **5**

CIP NO.

SHEET REVISED: 8/15/07



Attachment D – Engineering Cost Estimates

South Yale Corridor Improvements Yale Avenue (University Drive to I-405)



(30% Concept Plans)

	(2010 001100)	,				
ITEM No.	ITEM DESCRIPTION	UNIT	QUANTITY	ι	JNIT PRICE	TOTAL
ROADW	YAY					
1	Install Concrete - Curb Ramp	EA	3	\$	8,000	\$24,000
2	Install Concrete - Curb	LF	9590	\$	30	\$287,700
3	Install Concrete - Maintenance	SF	1570	\$	15	\$23,550
4	Install Concrete - Sidewalk	SF	1480	\$	15	\$22,200
5	Install Concrete - Textured Pavment	SF	6510	\$	25	\$162,750
6	Install Concrete - Bike Path	SF	22860	\$	15	\$342,900
7	Roadway Excavation	CY	31900	\$	65	\$2,073,500
8	Remove Concrete	SF	1200	\$	2	\$2,400
9	Hot Mix Asphalt	TON	360	\$	260	\$93,600
10	Slurry Seal	SF	104000	\$	0.33	\$34,320
11	CL2 Aggregate Base	CY	16000	\$	45	\$720,000
12	Signing and Striping	LS	1	\$	33,000	\$33,000
13	Landscape, Irrigation, Green Infrastructure	SF	34420	\$	35	\$1,204,700
					SUBTOTAL	\$5,024,620
DRAINA	AGE					
14	Minor Drainage	EA	2	\$	15,000	\$30,000
					SUBTOTAL	\$30,000
ELECTR	ICAL				<u> </u>	
15	Rapid Rectangular Flashing Beacon System	EA	1	\$	45,000	\$45,000
16	Traffic Signal Modification	EA	1	\$	100,000	\$100,000
17	Street Lighting	EA	14	\$	20,000	\$280,000
18	Cycle Track Lighting	LS	1	\$	240,000	\$240,000
					SUBTOTAL	\$665,000
19	Mobilization (10% of Items 1-18)	LS	1	\$	572,000	\$572,000
	•	•	CON	TINGI	ENCY (25%) *	\$1,573,000
			CONSTRU	JCTIC	N SUBTOTAL	\$5,719,620
GRAND	TOTAL					
1			CONST	RUCT	ION TOTAL=	\$7,864,620

^{*} This concept level estimate includes a 25% contingency intended to compensate for the use of preliminary and limited information.

General Note: Where applicable, only minor drainage improvements for transportation projects to address safety are included.

Utility improvements such as water, communication, gas, etc. are not included in these estimates.

South Yale Corridor Improvements Estimate



Attachment E – Traffic Analysis

iteris

City of IrvineSouth Yale Corridor Improvements Traffic Analysis





April 12, 2024

Submitted to:



11797.23 | Prepared by Iteris, Inc.

DOCUMENT VERSION CONTROL

DOCUMENT NAME	SUBMITTAL DATE	VERSION NO.
Draft 1	May 10, 2023	1.0
Final Draft	February 28, 2024	2.0
Final	April 12, 2024	3.0

TABLE OF CONTENTS

DOCU	MENT	VERSION CONTROL	ii
TABLE	OF CO	DNTENTS	3
	List	of Tables	3
	List	of Figures	4
	Арр	endices	4
1	Exec	utive Summary	5
2	Intro	oduction	6
	2.1	Project Description	6
	2.2	Project Site	6
3	Inte	rsection Analysis Methodology	9
4	Exist	ing Conditions	11
	4.1	Existing Corridor Land Uses	11
	4.2	Existing Roadways and Intersections	11
	4.3	Transit Services	11
	4.4	Existing Traffic Counts	15
	4.5	Existing Conditions Traffic Analysis	20
5	Deve	elopment of Future Forecast Traffic Volumes And Methodology	22
6	Build	dout Year Traffic Operations	27
	6.1	Buildout Year I-405 Vehicular OC with Four-Lane Yale Avenue	27
	6.2	Buildout Year I-405 Vehicular OC with Two-Lane Yale Avenue	28
	6.3	Buildout Year No I-405 Vehicular OC with Four-Lane Yale Avenue	29
	6.4	Buildout Year No I-405 Vehicular OC with Two-Lane Yale Avenue	30
7	Sign	al Warrants	32
8	Find	ings and Recommendations	34
List	of T	ables	
Table	3-1: IC	CU Level of Service Definitions	9
Table	3-2: H	CM Level of Service Definitions	9
Table	3-3: R	oadway Classification and Daily Capacities	10
Table	4-1: In	tersection Turning Movement Count Comparison	16
Table	4-2: A	rterial Daily Flow Comparison	17
Table	4-3: N	ovember 2022 AM and PM Periods Non-Motorized Counts	20
Table	4-4: E	xisting Conditions Intersection Peak Hour LOS	21
Table	4-5: E	xisting Conditions Roadway Segment LOS	21
Table	5-1: Fo	precast Buildout Year Arterial Segment Volumes	25
Table	6-1: B	suildout Year I-405 Vehicular OC with Four-Lane Yale Avenue Intersection LOS	27
Table	6-2: B	uildout Year I-405 Vehicular OC with Four-Lane Yale Avenue Roadway Segment LOS	28

Table 6-3: Buildout Year I-405 Vehicular OC with Two-Lane Yale Avenue Intersection LOS	29
Table 6-4: Buildout Year I-405 Vehicular OC with Two-Lane Yale Avenue Roadway Segment LOS	29
Table 6-5: Buildout Year No I-405 Vehicular OC with Four-Lane Yale Avenue Intersection LOS	30
Table 6-6: Buildout Year No I-405 Vehicular OC Four-Lane Yale Avenue Roadway Segment LOS	30
Table 6-7: Buildout Year No I-405 Vehicular OC with Two-Lane Yale Avenue Intersection LOS	31
Table 6-8: Buildout Year No I-405 Vehicular OC with Two-Lane Yale Avenue Roadway Segment LOS	31
List of Figures	
Figure 2-1: Study Area within the City of Irvine	7
Figure 2-2: South Yale Corridor Project Site	8
Figure 4-1: South Yale Corridor Land Use	12
Figure 4-2: Existing Lane Configurations	13
Figure 4-3: South Yale Corridor Commuter Route 167 Bus Stops	14
Figure 4-4: Existing Vehicle Traffic Counts	17
Figure 4-5: Existing Pedestrian and Bike Counts AM and Evening PM Peak Hours (1Hr)	18
Figure 4-6: Existing Pedestrian and Bike Counts School Peak Hour (1Hr)	19
Figure 4-7: Non-motorized movements by Location and Mode	20
Figure 5-1: Buildout Year I-405 Vehicular OC with Four-Lane Yale Avenue Traffic Volumes	22
Figure 5-2: Buildout Year I-405 Vehicular OC with Two-Lane Yale Avenue Traffic Volumes	23
Figure 5-3: Buildout Year No I-405 Vehicular OC with Four-Lane Yale Avenue Traffic Volumes	24
Figure 5-4: Buildout Year No I-405 Vehicular OC with Two-Lane Yale Avenue Traffic Volumes	25
Figure 7-1: Buildout Year I-405 Vehicular OC with Four-Lane Yale Avenue – MUTCD Traffic Signal Warrant (Yale Avenue and Michelson Drive)	32
Figure 7-2: Buildout Year I-405 Vehicular OC with Two-Lane Yale Avenue – MUTCD Traffic Signal Warrant (Yale Avenue and Michelson Drive)	33

Appendices

Appendix A – 2022 Traffic Counts

Appendix B – ICU Calculation Sheets

Appendix C – HCM Synchro Worksheets

Appendix D – Traffic Signal Warrants

1 EXECUTIVE SUMMARY

The purpose of this report is to study the traffic impacts of the potential elimination of a future street upgrade of Yale Avenue from an existing two-lane commuter street to a four-lane secondary arterial between Michelson Drive and University Drive. This future reclassification is currently assumed in the City of Irvine's General Plan and OCTA's Master Plan of Arterial Highways (MPAH).

The Irvine Strategic Active Transportation Plan (ISATP) includes analysis of existing conditions and potential barriers to active transportation within the City. The plan identified the South Yale Corridor as a potential active transportation project. Therefore, instead of a street upgrade for vehicular traffic, bicycle and pedestrian friendly street design solutions are under consideration for this roadway segment which would be incompatible with upgrading the street classification.

Traffic counts were collected along Yale Avenue and at the intersections of Yale Avenue and Michelson Drive, Yale Avenue and Royce Road, and Yale Avenue and University Drive in November 2022. In existing conditions all three study area intersections and roadway segments operate at satisfactory levels of service. There are two pairs of Buildout Scenarios with and without the widening to four lanes.

- 1. **No Future Vehicular crossing of Yale Avenue over I-405** In this scenario pair the elimination of the future widening Yale Avenue from two-lanes to four-lanes will not result in any deficient level of service at any of the three study intersections or roadway segments. All intersections and arterial segments will continue to operate at satisfactory levels of service.
- 2. Future Vehicular crossing of Yale Avenue over I-405 This is the current General Plan and MPAH scenario. In this scenario pair, in both the four-lane and two-lane scenarios the intersection of Yale Avenue and Michelson Drive would operate and unsatisfactory levels of service with the existing four-way stop control. However, this intersection meets signal warrants based on future peak hour volumes. Based on the assumption that the intersection would be signalized should a vehicular overcrossing of I-405 be implemented, then the intersection would operate at satisfactory levels of service using the ICU methodology.

The intersection of Yale Avenue and Royce Avenue would operate at unsatisfactory levels of service using the existing two-way stop control configuration. The future volumes at the intersection do not warrant a traffic signal. A four-lane stop controlled analysis was therefore performed as a sensitivity test. Although the overall intersection delay increases with a four-way control the intersection level of service as defined by the approach with maximum delay would improve in both two-lane and four-lane Yale Avenue scenarios. In the case of the four-lane Yale Avenue scenario, the intersection would operate at a satisfactory level of service but with the two-lane stop control (the existing configuration) the level of service would remain unsatisfactory.

• Since the purpose of the study is for the potential removal of the street widening of Yale Avenue, there is no VMT impact under CEQA.

2 INTRODUCTION

The purpose of this report is to study the traffic impacts of the potential elimination of a future street upgrade of Yale Avenue from an existing two-lane commuter street to a four-lane secondary arterial between Michelson Drive and University Drive. This future reclassification is currently assumed in the City of Irvine's General Plan and OCTA's Master Plan of Arterial Highways (MPAH).

The Irvine Strategic Active Transportation Plan (ISATP) includes analysis of existing conditions and potential barriers to active transportation within the City. The plan identified the South Yale Corridor as a potential active transportation project. Therefore, instead of a street upgrade for vehicular traffic, bicycle and pedestrian friendly street design solutions are under consideration for this roadway segment, which would be incompatible with upgrading the street classification.

2.1 Project Description

The study analyses existing traffic conditions and operations as well as four future scenarios as described below. The current Yale Avenue overcrossing of I-405 is for non-vehicular traffic only. As part of the City of Irvine's General Plan and OCTA's MPAH Buildout conditions, a two-lane vehicular overcrossing (OC) of I-405 is assumed to be built. However, since there are currently no plans to build a vehicular OC, traffic analysis was performed with and without the vehicular OC. Future year No Project and With Project scenarios were analyzed using the Irvine Transportation Analysis Model (ITAM). The four future scenarios are:

- 1. Buildout Year I-405 Vehicular OC with Four-lane Yale Avenue Analyzes the widening of Yale Avenue from a two-lane to a four-lane Secondary arterial between University Drive and Michelson Drive. The I-405 OC along Yale Avenue was modeled as a two-lane Commuter consistent with the current Master Plan of Arterial Highways (MPAH).
- **2. Buildout Year I-405 Vehicular OC with Two-lane Yale Avenue** Analyzes the removal of future street widening of Yale Avenue, keeping Yale Avenue as a two-lane Commuter Street between University Drive and Michelson Drive. The I-405 vehicular OC along Yale Avenue was modeled as a Commuter Street.
- 3. Buildout Year No I-405 Vehicular OC with Four-lane Yale Avenue Analyzes the widening of Yale Avenue from a two-lane to a four-lane Secondary arterial between University Drive and Michelson Drive consistent with the current Master Plan of Arterial Highway (MPAH). I-405 OC along Yale Avenue will remain as pedestrians and bicycles only.
- **4. Buildout Year No I-405 Vehicular OC with Two-lane Yale Avenue** Analyzes the removal of street widening of Yale Avenue, keeping Yale Avenue two-lane Commuter Street between University Drive and Michelson Drive. I-405 OC along Yale Avenue will remain as pedestrians and bicycles only.

2.2 Project Site

The project study area is Yale Avenue bounded by University Drive (to the south) and the pedestrian and bicycle crossing over Interstate 405 (to the north). Along the roadway, three segments and three intersections were analyzed. The three segments are:

- 1. Yale Avenue north of Michelson Drive;
- 2. Yale Avenue between Michelson Drive and Royce Road; and
- 3. Yale Avenue between Royce Road and University Drive.

The three intersections are:

- A. Yale Avenue and Michelson Drive;
- B. Yale Avenue and Royce Road; and
- C. Yale Avenue and University Drive.

Figure 2-1 illustrates the study area within the City of Irvine boundary and **Figure 2-2** illustrates the project site and the study intersections.




Figure 2-1: Study Area within the City of Irvine




Figure 2-2: South Yale Corridor Project Site

3 INTERSECTION ANALYSIS METHODOLOGY

The City of Irvine uses the Intersection Capacity Utilization (ICU) methodology for the calculation of signalized intersection Level of Service (LOS). The ICU methodology compares the volume-to-capacity (V/C) ratios of conflicting turn movements at an intersection, sums these critical conflicting V/C ratios for each intersection approach, and determines the overall ICU. The resulting ICU is expressed in terms of level of service (LOS), where LOS A represents free-flow activity and LOS F represents overcapacity operation. Parameters set by the City for ICU calculations, including lane capacity, right-turn treatment, and clearance interval are included in the analysis.

LOS definitions for signalized intersections and roadways are provided in **Table 3-1.** LOS E or worse is considered deficient at these locations by the City of Irvine.

LOS ICU Description At this LOS, traffic volumes are low and speed is not restricted by other vehicles. All Α ≤ 0.60 signal cycles clear with no vehicles waiting through more than one original cycle. At this LOS, traffic volumes begin to be affected by other traffic. Between one and R ten percent of the signal cycles have one or more vehicles which wait through more 0.61 - 0.70than one signal cycle during peak traffic periods. At this LOS, operating speeds and maneuverability are closely controlled by other C traffic. Between 11 and 30 percent of the signal cycles have one or more vehicles 0.71 - 0.80which wait through more than one signal cycle during peak traffic periods. At this LOS, traffic will operate at tolerable operating speeds, although with D 0.81 - 0.90restricted maneuverability. Traffic will experience restricted speeds, vehicles will frequently have to wait Ε through two or more cycles at signalized intersections, and any additional traffic will 0.91 - 1.00result in breakdown of the traffic carrying ability of the system. Long queues of traffic, unstable flow, stoppages of long duration with traffic F volumes and traffic, speed can drop to zero. Traffic volumes will be less than the >1.00 volume which occurs at LOS E.

Table 3-1: ICU Level of Service Definitions

The City of Irvine does not have any criteria for HCM analysis for unsignalized intersections. The unsignalized intersection will be evaluated using the latest Highway Capacity Manual 6th Edition (HCM 6) methodology. The HCM 6 methodology defines LOS by the average vehicle delay experienced by all vehicles traveling through the intersection. Traffic operations analysis for HCM methodologies will be completed using Synchro software.

Table 3-2 presents the average delay associated with each LOS grade as well as a qualitative description of intersection operations at that grade.

LOS	Description	Unsignalized Intersection Delay (Seconds)
А	Free flowing, virtually no delay.Minimal traffic.	≤ 10.0
В	 Free flow and choice of lanes. Delays are minimal. All cars clear intersection easily. 	>10.0 – 15.0
С	 Good operation. Delays starting to become a factor but still within acceptable limits. 	>15.0 – 25.0

Table 3-2: HCM Level of Service Definitions

D	 Approaching unstable flow. Queues at intersection are quite long but most cars clear intersection on their green signal. Occasionally, several vehicles must wait for a second green signal. 	>25.0 – 35.0		
E	 Congestion is moderate. Severe congestion and delay. Most of the available capacity is used. Many cars must wait through a complete signal cycle to clear the 			
F	 intersection. Excessive delay and congestion. Most cars must wait through more than one on one signal cycle. 	>50.0		
	 Queues are very long, and drivers are obviously irritated. 			

Source: Highway Capacity Manual 6th Edition

The arterial roadway analysis involved the calculation of average daily traffic (ADT) volume-to-capacity (V/C) ratios on study roadway segments. **Table 3-3** summarizes the roadway capacities per the City of Irvine Traffic Study Guidelines 2023 within the study area.

Table 3-3: Roadway Classification and Daily Capacities

Roadway Classification	Number of Lanes	Daily Capacity			
Expressway	6 Lanes	135,000			
Major Artorial	8 Lanes Divided	72,000			
Major Arterial	6 Lanes Divided	54,000			
Primary Arterial	4 Lanes Divided	32,000			
Secondary Arterial	4 Lanes Undivided	28,000			
Commuter	2 Lanes Undivided	13,000			

4 EXISTING CONDITIONS

4.1 Existing Corridor Land Uses

The adjacent land use along the South Yale Corridor is primarily residential with Rancho San Joaquin Middle School located in the northeast quadrant of the intersection of Michelson Drive and Yale Avenue.

4.2 Existing Roadways and Intersections

The speed limit on Yale Avenue between Michelson Drive and Royce Road is currently 45 miles per hour (mph) and between Royce Road and University Drive the speed limit is 40 mph. Yale Avenue is a two-lane roadway (one-lane in each direction) with Class II bike lane in each direction. The intersections of Yale Avenue and Michelson Drive (four-way stop-controlled) and Yale Avenue and Royce Road (two-way stop-controlled) are unsignalized. Yale Avenue and University Drive is a signalized intersection.

Figure 4-1 illustrates the land uses within the study area and **Figure 4-2** illustrates the lane configurations for each study intersection.

4.3 Transit Services

The study area is currently served by one bus transit service operated by OCTA, which is Community Route 167 as shown in **Figure 4-3**. This service operates between the Village in the City of Orange and University Center Area in UCI. The route traverses Michelson Drive between University Drive and Culver Drive within the study area. The service operates an hourly service on weekdays only, with 18 buses per day in each direction.




Figure 4-1: South Yale Corridor Land Use

University Drive 3. Yale Ave & University Dr 1. Yale Ave & 2. Yale Ave & Royce Rd Michelson Dr Legend ہا لہ X Study Intersections Defacto

Figure 4-2: Existing Lane Configurations




Figure 4-3: South Yale Corridor Commuter Route 167 Bus Stops

4.4 Existing Traffic Counts

Traffic counts were performed on Tuesday 15th and Wednesday 16th of November 2022. AM and PM peak hour counts were collected between 7:00 AM to 9:00 AM and 2:30 PM to 6:00 PM, respectively, along with arterial average daily traffic (ADT) counts which are provided in **Appendix A**. The two-day weekday counts were averaged as is per City standard practice. PM traffic counts were extended beyond the traditional 4:00 PM to 6:00 PM time period to include the school peak hour at Rancho San Joaquin Middle School.

The Covid-19 pandemic along with the associated lockdowns and remote work requirements has affected traffic patterns and volumes, including shifting traffic to different times of the day. While traffic volumes recovered during 2022 a comparison with available pre-Covid counts was performed to determine the most existing traffic counts to use for the analysis. Year 2018/2019 intersection turning movement counts for two of the three intersection turning movements were available from the ITAM post-processor. **Table 4-1** shows the intersection turning movement count comparison between 2022 and 2018/2019 for the traditional AM and PM peak periods.

In November 2022, the AM peak hour traffic volumes at the intersection of Yale Avenue and Michelson Drive were around 67% higher than pre-Covid conditions, while the evening PM peak hour traffic volumes were around 32% lower than pre-Covid conditions. At the intersection of Yale Avenue and University Drive, the AM peak hour traffic volumes were approximately 32% lower than pre-Covid conditions and 30% lower in the evening PM peak hour.

While the volumes along University Drive are higher in 2018 compared to 2022 this mainly relates to the east-west through movements. At the time of the 2022 count, there was construction on eastbound University Drive near I-405 but since volumes were lower in both eastbound and westbound directions it seems more likely that this is due to a secular reduction in weekday peak hour traffic due to increased working from home. The volumes on Yale Avenue itself are actually higher in 2022 compared to 2018 so it was determined that the year 2022 counts would better reflect current conditions.

Table 4-1: Intersection Turning Movement Count Comparison

tota mente e	Peak V		Northbound			S	Southbound Eastbound				Westbound			Int. LT	LT	THRU	RT	
Intersection	Hour	Year	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Total	Total	Total	Total
		2022	13	56	33	21	37	52	65	135	21	88	193	20	732	186	420	126
	A.D.4	2018/2019	10	4	14	5	1	4	7	173	25	16	177	1	437	38	355	44
	AM	Diff	3	52	19	16	36	48	58	-39	-5	72	16	19	295	148	65	82
Yale Avenue and		% Diff	30%	>100%	>100%	>100%	>100%	>100%	>100%	-22%	-18%	>100%	9%	>100%	67%	>100%	18%	>100%
Michelson		2022	14	1	57	2	0	3	2	284	7	13	204	1	586	30	489	68
Drive	PM (4:45 PM)	2018/2019	11	1	58	1	2	2	2	505	15	19	241	2	859	33	749	77
		Diff	3	-1	-1	1	-2	1	-1	-221	-8	-6	-37	-1	-273	-4	-261	-9
		% Diff	23%	-50%	-2%	50%	-100%	50%	-25%	-44%	-53%	-32%	-15%	-50%	-32%	-11%	-35%	-12%
		2022	0	0	0	76	0	104	81	769	0	0	1,319	35	2,382	156	2,088	139
		2018/2019	0	0	0	67	0	119	67	1,278	0	0	1,930	33	3,494	134	3,208	152
	AM	Diff	0	0	0	9	0	-15	14	-509	0	0	-612	2	-1,112	22	-1,121	-14
Yale Avenue and		% Diff				13%		-13%	20%	-40%			-32%	5%	-32%	16%	-35%	-9%
University		2022	0	0	0	13	0	21	68	1,416	0	0	1,001	32	2,550	81	2,417	53
Drive	PM	2018/2019	0	0	0	27	0	30	64	2,071	0	0	1,406	37	3,635	91	3,477	67
	(4:45 PM)	Diff	0	0	0	-14	0	-9	4	-656	0	0	-405	-6	-1,086	-11	-1,061	-15
		% Diff				-52%		-30%	5%	-32%			-29%	-15%	-30%	-12%	-31%	-22%


The 2022 ADT counts on the arterial roadways shown in **Table 4-2** indicate that traffic volume on Yale Avenue was higher than pre-Covid volumes.

Table 4-2: Arterial Daily Flow Comparison

#	Segment	Year 2022	Year 2018	% Difference
А	Yale Avenue north of Michelson Drive	540	Not Available	Not Available
В	Yale Avenue between Michelson Drive and Royce Road	1,230	1,130	9%
С	Yale Avenue between Royce Road and University Drive	1,770	1,160	53%

Figure 4-4 illustrates the existing vehicle traffic counts.

Figure 4-4: Existing Vehicle Traffic Counts



Legend



Study Intersections

XX/XX AM/PM Peak Hour Volume XXXX ADT Volumes

Figure 4-5 illustrates the existing conditions bicycle and pedestrian counts during the AM and PM peak hours (1hr).

1. Yole Ave & Royce Rd University Dr I 11/2 1 12/10

Figure 4-5: Existing Pedestrian and Bike Counts AM and Evening PM Peak Hours (1Hr)




Figure 4-6 illustrates the existing conditions bicycle and pedestrian counts during school peak hour (1hr).

3 3. Yale Ave & University Dr 2. Yale Ave & 1. Yale Ave & Michelson Dr Royce Rd 13 Legend 66 3 Study Intersections \$ 33 6 16 Private Sidewalk 26 School Peak Hour Pedestrian Counts XX School Peak Hour Bike Counts 10 **I-405 Overcrossing *Private Sidewalk


Figure 4-6: Existing Pedestrian and Bike Counts School Peak Hour (1Hr)

Table 4-3 and Figure 4-7 shows the total non-motorized movements during AM (7AM-9AM) and PM (2:30 PM-6PM) periods (six hours) at the study intersections and at I-405 overcrossing by mode. The main pedestrian movement is at Yale Avenue and Michelson Drive around the Rancho San Joaquin Middle School. Bicycles are more evenly spread throughout the study area. This suggests bikes traversing the whole corridor while pedestrians are either walking to nearby homes or being picked up by parents from school who are waiting on adjacent streets. This observation was supported by field observations. Only a small number of scooters and skateboards were observed.

Mode	I-405 Overcrossing	Yale Avenue and Michelson Drive	Yale Avenue and Royce Road	Yale Avenue and University Drive
Pedestrian	107	397	150	82
Bicycle	88	194	160	192
Scooter	6	20	10	18
Skateboard	1	5	2	2
Total	201	616	321	294

Table 4-3: November 2022 AM and PM Periods Non-Motorized Counts





4.5 Existing Conditions Traffic Analysis

The intersection LOS results were calculated during the AM, PM, and school peak hours for Existing conditions and the results are shown in **Table 4-4**. The ICU worksheets are provided in **Appendix B**. The synchro worksheets are provided in **Appendix C**. Under Existing conditions, the study intersections are operating at LOS C or better during both AM and PM peak hours.

Table 4-4: Existing Conditions Intersection Peak Hour LOS

			Existing									
#	Intersection	Methodology	AM		Evening F	M	School PM					
			V/C Delay	LOS	V/C Delay	LOS	V/C Delay	LOS				
1	Yale Avenue and Michelson Drive ¹	HCM 6th 4-WSC	17.7	С	14.0	В	13.3	В				
2	Yale Avenue and Royce Road ¹	HCM 6 th 2-WSC	17.9	С	10.6	В	10.6	В				
3	Yale Avenue and University Drive	ICU	0.53	А	0.48	А	0.32	А				

Note:

¹ Unsignalized intersection

2-WSC: 2-way stop control

4-WSC: 4-way stop control

The roadway segment LOS results during existing conditions are shown in **Table 4-5**. The study roadway segments operate at LOS A under Existing conditions.

Table 4-5: Existing Conditions Roadway Segment LOS

#	Someont	Existing								
#	Segment	Туре	Total Capacity	ADT	V/C	LOS				
А	Yale Avenue north of Michelson Drive	Commuter	13,000	540	0.04	А				
В	Yale Avenue between Michelson Drive and Royce Road	Commuter	13,000	1,230	0.09	А				
С	Yale Avenue between Royce Road and University Drive	Commuter	13,000	1,770	0.14	А				


5 DEVELOPMENT OF FUTURE FORECAST TRAFFIC VOLUMES AND METHODOLOGY

Future traffic volumes were extracted from the City's traffic model ITAM. Prior to running ITAM, the highway networks were reviewed to ensure that they adequately represented the roadway system in the study area.

ITAM uses future model forecasts along with existing model volumes and existing traffic counts to generate post-processed forecast model volumes for the four Buildout year scenarios. **Figure 5-1** through **Figure 5-4** illustrates the buildout year turning movement volumes from ITAM while **Table 5-1** summarizes the buildout year daily volumes on the arterial segments.



Figure 5-1: Buildout Year I-405 Vehicular OC with Four-Lane Yale Avenue Traffic Volumes



Legend


Study Intersections

XX/XX AM/PM Peak Hour Volume

XXXX ADT Volumes



Figure 5-2: Buildout Year I-405 Vehicular OC with Two-Lane Yale Avenue Traffic Volumes



Legend



X Study Intersections

XX/XX AM/PM Peak Hour Volume XXXX ADT Volumes





Figure 5-3: Buildout Year No I-405 Vehicular OC with Four-Lane Yale Avenue Traffic Volumes



Legend



X Study Intersections

XX/XX AM/PM Peak Hour Volume XXXX ADT Volumes

Figure 5-4: Buildout Year No I-405 Vehicular OC with Two-Lane Yale Avenue Traffic Volumes




Table 5-1: Forecast Buildout Year Arterial Segment Volumes

				Buildout Year Po	st-Processed ADT	
#	Segment	Existing	I-405 Vehicular OC with 4-Lane Yale Avenue	I-405 Vehicular OC with 2-Lane Yale Avenue	No I-405 Vehicular OC with 4-Lane Yale Avenue	No I-405 Vehicular OC with 2-Lane Yale Avenue
А	Yale Avenue north of Michelson Drive	540	11,700	11,400	570	570
В	Yale Avenue between Michelson Drive and Royce Road	1,230	6,800	6,300	2,600	2,400
С	Yale Avenue between Royce Road and University Drive	1,770	7,200	6,800	3,200	3,000

Two different Buildout networks were used, one with an I-405 vehicular OC along Yale Avenue and the other with an I-405 pedestrians and bicyclists-only OC along Yale Avenue. Using traffic forecasts based on the City of Irvine's traffic model ITAM, Yale Avenue volumes from both Buildout scenarios with 2 lanes are lower than with 4 lanes. Also, the Buildout scenario with I-405 vehicular OC are higher than the scenarios with No I-405 vehicular OC, likely due to the network using Yale Avenue as an alternative route for some origin-destination pairs which could potentially increase traffic along Yale Avenue.

6 BUILDOUT YEAR TRAFFIC OPERATIONS

LOS analysis was conducted to evaluate the future scenarios:

- Buildout Year I-405 Vehicular OC with Four-lane Yale Avenue,
- Buildout Year I-405 Vehicular OC with Two-lane Yale Avenue,
- Buildout Year No I-405 Vehicular OC with Four-lane Yale Avenue, and
- Buildout Year No I-405 Vehicular OC with Two-lane Yale Avenue during AM and PM peak hours.

The signalized intersections were analyzed using the ICU methodology, and additional HCM analyses were completed at the unsignalized intersections.

6.1 Buildout Year I-405 Vehicular OC with Four-Lane Yale Avenue

The intersection LOS results were calculated during the AM and PM peak hours are shown in **Table 6-1**. The ICU worksheets are provided in **Appendix B**. The synchro worksheets are provided in **Appendix C**. Two (2) intersections are expected to operate at LOS E or worse during either AM or PM peak hours:

- Yale Avenue and Michelson Drive (AM LOS F | PM LOS F for 4-way stop-controlled operation)
- Yale Avenue and Royce Road (AM LOS E for 2-way stop-controlled operation)

LOS is also shown for informational purposes using the ICU methodology at Yale Avenue and Michelson Drive and using a four-way stop-controlled methodology at Yale Avenue and Royce Road, which both operate at satisfactory levels of service. Unlike ICU analysis, for HCM analysis typically the delay for the most restrictive approach is reported rather than the delay for the intersection. Therefore, in the case of Royce Road, the delay in the eastbound and westbound direction is reduced significantly. Although there is an increase in delay for the northbound and southbound movements compared to 2-way stop-controlled operation, overall delay for the intersection increases, but with an improvement in reported LOS (since stop-controlled intersections are reported by worst approach).

Table 6-1: Buildout Year I-405 Vehicular OC with Four-Lane Yale Avenue Intersection LOS

				Exis	sting		Buildout Year I-405 Vehicular OC with Four-Lane Yale Avenue				
#	Intersection	Methodology	logy AM		PM		AM		PM		
			V/C Delay	LOS	V/C Delay	LOS	V/C Delay	LOS	V/C Delay	LOS	
1	Yale Avenue and Michelson Drive	HCM 6th 4-WSC	17.7	С	14.0	В	388.4	F	341.5	F	
1	raie Avenue and Michelson Drive	ICU					0.43	Α	0.46	Α	
		HCM 6 th 2-WSC	17.9	С	10.6	В	41.5	E	19.5	С	
2	Yale Avenue and Royce Road ¹	HCM 6 th 4-WSC					16.0	С	11.2	В	
3	Yale Avenue and University Drive	ICU	0.53	А	0.48	А	0.68	В	0.56	А	

Note: Bolded cell denotes deficient LOS ($V/C \ge 0.91$)

¹ Unsignalized intersection

2-WSC: 2-way stop control

4-WSC: 4-way stop control

A traffic signal warrant study per Manual on Uniform Traffic Control Devices (MUTCD) was performed for both intersections. The unsignalized intersection of Yale Avenue and Royce Road does not meet the peak hour volume warrant, while the unsignalized intersection of Yale Avenue and Michelson Drive does meet the peak hour volume warrant, meaning that signal installation may be recommended. The peak hour volume warrant is provided in

Appendix D.

The roadway segment LOS results during Buildout Year I-405 Vehicular OC with four-lane Yale Avenue are shown in **Table 6-2**. The study roadway segments are expected to operate at LOS D or better under Buildout Year I-405 Vehicular OC with Four-Lane Yale Avenue scenario conditions.

Table 6-2: Buildout Year I-405 Vehicular OC with Four-Lane Yale Avenue Roadway Segment LOS

#	Secure		Existing					Buildout Year I-405 Vehicular OC with Four-Lane Yale Avenue					
#	Segment	Туре	Total Capacity	ADT	v/c	LOS	Туре	Total Capacity	ADT	V/C	LOS		
А	Yale Avenue north of Michelson Drive	Commuter	13,000	540	0.04	А	Commuter	13,000	11,700	0.90	D		
В	Yale Avenue between Michelson Drive and Royce Road	Commuter	13,000	1,230	0.09	А	Secondary	28,000	6,800	0.24	А		
С	Yale Avenue between Royce Road and University Drive	Commuter	13,000	1,770	0.14	А	Secondary	28,000	7,200	0.26	А		

6.2 Buildout Year I-405 Vehicular OC with Two-Lane Yale Avenue

The intersection LOS results were calculated during the AM and PM peak hours for as shown in **Table 6-3**. The ICU worksheets are provided in **Appendix B**. The synchro worksheets are provided in **Appendix C**.

As shown in **Table 6-3**, the following two (2) intersections are expected to operate at LOS E or worse during AM or PM peak hours:

- Yale Avenue and Michelson Drive (AM LOS F | PM LOS F for 4-way stop-controlled operation)
- Yale Avenue and Royce Road (AM LOS E for 2-way stop-controlled operation)

LOS is also shown <u>for informational purposes</u> using the ICU methodology at Yale Avenue and Michelson Drive and using a four-way stop-controlled methodology for Yale Avenue and Royce Road. Unlike the four-lane Yale Avenue conditions (summarized in *Section 6.1*), the two-way stop-control would not result in a satisfactory level of service in the AM peak.

Table 6-3: Buildout Year I-405 Vehicular OC with Two-Lane Yale Avenue Intersection LOS

				Exis	ting		Buildout Year I-405 Vehicular OC with Two-Lane Yale Avenue				
#	Intersection	Methodology	AM		PM		AM		PM		
			V/C Delay	LOS	V/C Delay	LOS	V/C Delay	LOS	V/C Delay	LOS	
1	Yale Avenue and Michelson Drive	HCM 6th 4-WSC	17.7	С	14.0	В	903.6	F	456.8	F	
1	raie Avenue and Michelson Drive	ICU					0.51	Α	0.54	Α	
2	Yale Avenue and Royce Road ¹	HCM 6 th 2-WSC	17.9	С	10.6	В	46.3	Е	19.1	С	
	Tale Avenue and Royce Road	HCM 6 th 4-WSC					38.8	E	16.1	С	
3	Yale Avenue and University Drive	ICU	0.53	А	0.48	А	0.68	В	0.56	А	

Note: Bolded cell denotes deficient LOS ($V/C \ge 0.91$)

A traffic signal warrant study per Manual on Uniform Traffic Control Devices (MUTCD) was performed for both intersections. The unsignalized intersection of Yale Avenue and Royce Road does not meet the peak hour volume warrant, while the unsignalized intersection of Yale Avenue and Michelson Drive does meet the peak hour volume warrant and signal installation should be considered. The peak hour volume warrant is provided in **Appendix D.**

The roadway segment LOS results during Buildout Year I-405 Vehicular OC with Two-Lane Yale Avenue are summarized in **Table 6-4**. The study roadway segments are expected to operate at LOS D or better under Buildout Year I-405 Vehicular OC with Two-Lane Yale Avenue scenario conditions.

Table 6-4: Buildout Year I-405 Vehicular OC with Two-Lane Yale Avenue Roadway Segment LOS

#	Segment	Existing					Buildout Year I-405 Vehicular OC with Two-Lane Yale Avenue						
#	Segment	Туре	Total Capacity	ADT	v/c	LOS	Туре	Total Capacity	ADT	V/C	LOS		
А	Yale Avenue north of Michelson Drive	Commuter	13,000	540	0.04	А	Commuter	13,000	11,400	0.88	D		
В	Yale Avenue between Michelson Drive and Royce Road	Commuter	13,000	1,230	0.09	А	Secondary	28,000	6,300	0.23	А		
С	Yale Avenue between Royce Road and University Drive	Commuter	13,000	1,770	0.14	А	Secondary	28,000	6,800	0.24	А		

6.3 Buildout Year No I-405 Vehicular OC with Four-Lane Yale Avenue

The intersection LOS results were calculated during the AM and PM peak hours for Buildout Year No I-405 Vehicular OC with Four-Lane Yale Avenue scenario, and the results are summarized in **Table 6-5**. The ICU worksheets are provided in **Appendix B**. The synchro worksheets are provided in **Appendix C**. The study intersections are expected to operate at LOS C or better during both AM and PM peak hours under the Buildout Year No I-405 Vehicular OC with Four-Lane Yale Avenue scenario conditions.

¹ Unsignalized intersection 2-WSC: 2-way stop control 4-WSC: 4-way stop control

Table 6-5: Buildout Year No I-405 Vehicular OC with Four-Lane Yale Avenue Intersection LOS

				Exi	sting		Buildout OC with		I-405 Ve ne Yale A	
#	Intersection	Methodology Al		AM		М	AM		PM	
			V/C Delay	LOS	V/C Delay	LOS	V/C Delay	LOS	V/C Delay	LOS
1	Yale Avenue and Michelson Drive ¹	HCM 6 th 4-WSC	17.7	С	14.0	В	24.2	С	18.1	С
2	Yale Avenue and Royce Road ¹	HCM 6 th 2-WSC	17.9	С	10.6	В	22.9	С	12.0	В
3	Yale Avenue and University Drive	ICU	0.53	А	0.48	А	0.61	В	0.55	А

Note:

The roadway segment LOS results during Buildout Year No I-405 Vehicular OC with Four-Lane Yale Avenue are summarized in **Table 6-6**. The study roadway segments are expected to operate at LOS A under Buildout Year No I-405 Vehicular OC Four-Lane Yale Avenue scenario conditions.

Table 6-6: Buildout Year No I-405 Vehicular OC Four-Lane Yale Avenue Roadway Segment LOS

#	Segment		Existin	g			Buildout Year No I-405 Vehicular OC with Four-Lane Yale Avenue					
#	Segment	Туре	Total Capacity	ADT	v/c	LOS	Туре	Total Capacity	ADT	v/c	LO S	
А	Yale Avenue north of Michelson Drive	Commuter	13,000	540	0.04	А	Commuter	13,000	570	0.04	А	
В	Yale Avenue between Michelson Drive and Royce Road	Commuter	13,000	1,230	0.09	А	Secondary	28,000	2,600	0.09	А	
С	Yale Avenue between Royce Road and University Drive	Commuter	13,000	1,770	0.14	А	Secondary	28,000	3,200	0.11	А	

6.4 Buildout Year No I-405 Vehicular OC with Two-Lane Yale Avenue

The intersection LOS results were calculated during the AM and PM peak hours for Buildout Year No I-405 Vehicular OC with Two-Lane Yale Avenue conditions, and the results are summarized in **Table 6-7**. The ICU worksheets are provided in **Appendix B**. The synchro worksheets are provided in **Appendix C**. The study intersections are expected to operate at LOS C or better during both AM and PM peak hours under Buildout Year No I-405 Vehicular OC with Two-Lane Yale Avenue scenarios conditions.

¹ Unsignalized intersection

²⁻WSC: 2-way stop control

⁴⁻WSC: 4-way stop control

Table 6-7: Buildout Year No I-405 Vehicular OC with Two-Lane Yale Avenue Intersection LOS

			Existing					Buildout Year No I-405 Vehicular OC with Two-Lane Yale Avenue				
#	# Intersection	section Methodology		AM		PM		AM		PM		
			V/C Delay	LOS	V/C Delay	LOS	V/C Delay	LOS	V/C Delay	LOS		
1	Yale Avenue and Michelson Drive ¹	HCM 6 th 4-WSC	17.7	С	14.0	В	20.4	С	18.4	С		
2	Yale Avenue and Royce Road ¹	HCM 6 th 2-WSC	17.9	С	10.6	В	24.7	С	11.9	В		
3	Yale Avenue and University Drive	ICU	0.53	А	0.48	А	0.61	В	0.55	А		

Note:

¹ Unsignalized intersection

2-WSC: 2 ways stop control

4-WSC: 4 ways stop control

The roadway segments LOS results during Buildout Year No I-405 Vehicular OC with Two-Lane Yale Avenue conditions are summarized in **Table 6-8**. The study roadway segments are expected to operate at LOS A under Buildout Year No I-405 Vehicular OC Two-Lane Yale Avenue scenario conditions.

Table 6-8: Buildout Year No I-405 Vehicular OC with Two-Lane Yale Avenue Roadway Segment LOS

#	Segment		Existing					Buildout Year No I-405 Vehicular OC with Two-Lane Yale Avenue					
#	Segment	Туре	Total Capacity	ADT	v/c	LOS	Туре	Total Capacity	ADT	v/c	LOS		
А	Yale Avenue north of Michelson Drive	Commuter	13,000	540	0.04	А	Commuter	13,000	570	0.04	А		
В	Yale Avenue between Michelson Drive and Royce Road	Commuter	13,000	1,230	0.09	А	Secondary	28,000	2,400	0.09	А		
С	Yale Avenue between Royce Road and University Drive	Commuter	13,000	1,770	0.14	А	Secondary	28,000	3,000	0.11	А		


7 SIGNAL WARRANTS

The following unsignalized intersections are expected to operate deficiently under Buildout Year I-405 vehicular overcrossing under both four-lane Yale Avenue and two-lane Yale Avenue scenarios:

- Yale Avenue and Michelson Drive
- Yale Avenue and Royce Road

Traffic signal warrant studies per Manual on Uniform Control Devices (MUTCD) was performed for both intersections. The intersection of Yale Avenue and Michelson Drive met the conditions for Warrant 3 (Peak Hour) with AM and PM peak hour volumes as shown in **Figure 7-1** and **Figure 7-2**, while the intersection of Yale Avenue and Royce Road did not meet the conditions for Warrant 3 (Peak Hour) for either AM or PM peak hour volumes.

Figure 7-1: Buildout Year I-405 Vehicular OC with Four-Lane Yale Avenue – MUTCD Traffic Signal Warrant (Yale Avenue and Michelson Drive)



MAJOR STREET—TOTAL OF BOTH APPROACHES— VEHICLES PER HOUR (VPH)

*Note: 150 vph applies as the lower threshold volume for a minor-street approach with two or more lanes and 100 vph applies as the lower threshold volume for a minor-street approach with one lane.

600 500 2 OR MORE LANES & 2 OR MORE LANES MINOR AM (1040,342) 400 STREET 2 OR MORE LANES & 1 LANE HIGHER-300 VOLUME 1 LANE & 1 LANE PM (968,323) APPROACH -VPH 200 150* 100* 100 800 1000 1100 1200 1300 1400 1500 1600 1700 1800 400 500 700 900 600 MAJOR STREET-TOTAL OF BOTH APPROACHES-VEHICLES PER HOUR (VPH)

Figure 7-2: Buildout Year I-405 Vehicular OC with Two-Lane Yale Avenue – MUTCD Traffic Signal Warrant (Yale Avenue and Michelson Drive)

*Note: 150 vph applies as the lower threshold volume for a minor-street approach with two or more lanes and 100 vph applies as the lower threshold volume for a minor-street approach with one lane.

8 FINDINGS AND RECOMMENDATIONS

In existing conditions all three study area intersections and roadway segments operate at satisfactory levels of service. There are two pairs of Buildout Scenarios with and without the widening to four lanes.

- 1. **No Future Vehicular crossing of Yale Avenue over I-405** In this scenario pair, the elimination of the future widening Yale Avenue from two-lanes to four-lanes will not result in any deficient level of service at any of the three study intersections or roadway segments. All intersections and arterial segments will continue to operate at satisfactory levels of service.
- 2. Future Vehicular crossing of Yale Avenue over I-405 This is the current General Plan and MPAH scenario. In this scenario pair, in both the four-lane and two-lane scenarios the intersection of Yale Avenue and Michelson Drive would operate and unsatisfactory levels of service with the existing four-way stop control. However, this intersection meets signal warrants based on future peak hour volumes. Based on the assumption that the intersection would be signalized should a vehicular overcrossing of I-405 be implemented, then the intersection would operate at satisfactory levels of service using the ICU methodology.

The intersection of Yale Avenue and Royce Avenue would operate at unsatisfactory levels of service using the existing two-way stop control configuration. The future volumes at the intersection do not warrant a traffic signal. A four-lane stop controlled analysis was therefore performed as a sensitivity test. Although the overall intersection delay increases with a four-way control the intersection level of service as defined by the approach with maximum delay would improve in both two -lane and four lane Yale Avenue scenarios. In the case of the four-lane Yale Avenue configuration, the intersection would operate at a satisfactory level of service, but with the two-lane stop control (the existing configuration), the level of service would remain unsatisfactory.


Since the purpose of the study is for the potential removal of the street widening of Yale Avenue, there is no VMT impact under CEQA.




© 2023 Iteris, Inc. All rights reserved.

iteris

City of Irvine
South Yale Avenue Traffic Study
Technical Appendix





APPENDIX A- 2022 TRAFFIC COUNTS

South Yale Corridor Study -Average Daily Traffic Summary

ID	Location	ADT	AM Peak	PM School Peak	PM Evening	AM Peak %	PM School Peak%	PM Evening%
1	Yale Ave north of Michelson Dr	540	250	135	8	46%	25%	1%
2	Yale Ave north of Royce Rd	1,230	253	188	89	21%	15%	7%
3	Yale Ave south of Royce Rd	1,770	295	217	133	17%	12%	8%

			Tuesday			Wednesda	av.			
			11/15/202	2		11/16/202	,		Average	
ID	Location	NB	SB	Combined	NB	SB	Combined	NB	SB	Combined
1	Yale Ave north of Michelson Dr	259	253	512	280	288	568	270	270	540
2	Yale Ave north of Royce Rd	722	563	1,285	646	522	1,168	680	540	1,230
3	Yale Ave south of Royce Rd	978	821	1,799	926	811	1,737	950	820	1,770

Volumes	for:	Tuesday, Nove	ember 15, 2022		CITY:					PROJECT: SC3579	
Locatio	n:	ADT1 Yale n	orth of Michelson	Prepared by	y: Field Data Ser	vices c	f Arizo	ona, Ind	5 .	Suhsduhg#e #DlpW	G#00F##who1#:47
					AY 1						
M Period NB	3	SB			PM Period	NB		SB			
0:00		0			12:00	0		1			
0:15 0 0:30 0		0			12:15 12:30	1 1		0			
0:45 0		0 0		0	12:45	0	2	0	1		3
1:00 0	כ	0			13:00	1		0			
1:15 0		0			13:15	0		0			
1:30 0		0 0		0	13:30	0	1	1 0	1		2
1:45 0 2:00 0		0		U	13:45 14:00	1	1	1	1		2
2:00 0 2:15 0		0			14:15	4		2			
2:30 0		0			14:30	14		0			
2:45 0	0 0	0 0		0	14:45	22	41	4	7		48
3:00 0		0			15:00	19		45			
3:15 0		0			15:15	7		16			
3:30 0 3:45 0		0 0 0		0	15:30 15:45	1 5	32	3 2	66		98
4:00 0		0		<u> </u>	16:00	7	J-	21			50
4:15		0			16:15	1		3			
4:30 0		0			16:30	1		2			
	0 0	0 0		0	16:45	0	9	0	26		35
5:00 1		1			17:00	1		0			
5:15 1 5:30 0		0			17:15 17:30	0		1 1			
5:45		0 1		3	17:45	0	1	1	3		4
6:00 1		1			18:00	0		2			
6:15 1		0			18:15	0		0			
6:30 0		2			18:30	1		1			
6:45 0		0 3		5	18:45	2	3	3	6		9
7:00 3		0			19:00	2		3 0			
7:15 11 7:30 10		6 11			19:15 19:30	0		0			
7:45 15		5 22		61	19:45	0	2	0	3		5
8:00 47	7	29			20:00	0		0			
8:15 64		61			20:15	0		0			
8:30 3		5		215	20:30	0	•	0	0		0
	114	6 101		215	20:45	0	0	0	0		0
9:00 1 9:15 2		2 2			21:00 21:15	0		0			
9:30 1		0			21:30	0		1			
9:45 1		2 6		11	21:45	0	0	0	1		1
10:00 0		1			22:00	0		0			
10:15 2		1			22:15	0		0			
10:30 1 10:45 1		0 0 2		6	22:30 22:45	0	0	0	0		0
11:00 0		0 2		U	23:00	0	U	0	U		U
11:15 1		0			23:15	0		0			
11:30 0		1			23:30	0		1			
11:45 1	1 2	2 3		5	23:45	0	0	0	1		1
otal Vol.	168	138		306			91		115		206
							NB		SB	Daily Totals	Combined
						_	259		253		512
			AM				2 33		233	РМ	312
Split %	54.9%	45.1%	Al·i	59.8%	*****************	4	4.2%		55.8%	1 1/1	40.2%
	7:30	7:30		7:30			14:30		14:45		14:30
eak Hour											
eak Hour Volume	136	106		242			62		68		127

cs@aimtd.com

Tell. 714 253 7888

Volum Loca			*****	le north of Michelson	Prepared by:	Field Data Service				Juquii	n PROJECT: SC3579 Suhsduhg#e #DlpWG#00F##who1#:47#586#:
LUCA	uon		ADIITA	ie norm of wichelson		AY 2		· nonenenenene		en nen en	Sunsdung#e #DIpwG#OOF##WNOI#:4/#586#:
AM Period	ND		SB		υ,	PM Period	NB		SB		
0:00	0		0			12:00	0		2		
0:15 0:30	0		0			12:15 12:30	1		0 1		
0:45	0	0	0 0	1	0	12:45	0	1	1	4	5
	0	-	0			13:00	0		0		
1:00 1:15	0		0			13:15	2		0		
1:30	0		0			13:30	0		1		
1:45	0	0	0 0)	0	13:45	0	2	0	1	3
2:00	0		0		-	14:00	7		4		
2:15	0		0			14:15	6		1		
2:30	0		0			14:30	9		3		
2:45	0	0	0 0)	0	14:45	22	44	4	12	56
3:00	0		0			15:00	25		58		
3:15	0		0			15:15	6		16		
3:30	0		0			15:30	2		3		
3:45	0	0	0 0)	0	15:45	5	38	4	81	119
4:00	0		0			16:00	7		19		
4:15	0		0			16:15	0		1		
4:30	0		0			16:30	0		0		
4:45	0	0	0 0)	0	16:45	2	9	0	20	29
5:00	0		0			17:00	1		5		
5:15	0		0			17:15	0		0		
5:30	0		0			17:30	1		2		
5:45	1	1	1 1	<u> </u>	2	17:45	0	2	0	7	9
6:00	0		0			18:00	0		1		
6:15	0		0			18:15	0		0		
6:30	0		0			18:30	0		1		
6:45	1	1	0 0)	1	18:45	0	0	0	2	2
7:00	1		3			19:00	0		0		
7:15	7		0			19:15	0		0		
7:30	4		1			19:30	0		1		
7:45		35	8 17	2	47	19:45	0	0	0	1	1
8:00	57		34			20:00	0		1		
8:15	68		71			20:15	0		0		
8:30	3		6	_		20:30	0		0		
8:45		135	6 11	.7	252	20:45	0	0	0	1	1
9:00	0		2			21:00	1		2		
9:15	2		2			21:15	1		0		
9:30	1		1		42	21:30	0	_	2		
9:45	1	4	3 8	5	12	21:45	0	2	0	4	6
10:00	1		3			22:00	0		0		
10:15	2		0			22:15	0		0		
10:30	1	4	1	1	0	22:30	0	0	0	0	0
10:45	0	4	0 4		8	22:45	0	0	0	0	0
11:00	1		1			23:00	0		2		
11:15	0		5			23:15	0		0		
11:30 11:45	0 1	2	3 1 10	0	12	23:30 23:45	0	0	1 0	3	3
11.40		۷	1 10	<u> </u>	14	43.43	U	U	U	J	<u> </u>

334

58.8%

7:45

270 0.49

AM

cs@aimtd.com

Tell. 714 253 7888

136

SB

288

58.1%

14:30

81 0.35

Daily Totals

PΜ

98

NB

280

41.9%

14:15

62 0.67

234

568

41.2%

14:30

143 0.43

Combined

152

7:45

119 0.42

Total Vol.

Split %

Peak Hour

Volume P.H.F.

182

54.5%

7:30

152 0.56

Volume	es for	: '	Tuesday, Nov	ember 15, 2022		CITY:	Irvine	Ranch	o San I	loaquin	PROJECT: SC3579	
Locat	tion:	,	ADT2 Yale	north of Royce	Prepared	d by: Field Dat	a Serv	rices o	of Arizo	na, Inc.	Suhsduhg#e #DlpW	G#00F##who1#:47#58
					D	AY 1						
AM Period	NB		SB			PM Period	NB		SB			
0:00	1		0			12:00	21		13			
0:15 0:30	0		0			12:15 12:30	12 9		6 8			
0:45	0 :	1	0 0		1	12:45	18	60	7	34		94
1:00	1		0			13:00	12		6			
1:15	0		0			13:15	8		3			
1:30 1:45	0	1	0 0		1	13:30 13:45	12 7	39	9 6	24		63
2:00	0		0		-	14:00	27	- 55	7			
2:15	0		0			14:15	25		7			
2:30	0		0			14:30	18		5			
2:45	0 ()	0 0		0	14:45	43	113	4	23		136
3:00 3:15	0		0 0			15:00 15:15	27 6		61 19			
3:15	0		0			15:15	10		7			
3:45	0 ()	0 0		0	15:45	16	59	7	94		153
4:00	0		0			16:00	21		25			
4:15	0		0			16:15	20		8			
4:30 4:45	0 0)	0 1 1		1	16:30 16:45	6 13	60	9 2	44		104
5:00	0		0		-	17:00	19		4			
5:15	0		0			17:15	18		4			
5:30	1		1		_	17:30	30		7			
5:45	0 :	1	0 1		2	17:45	13	80	5	20		100
6:00 6:15	1 2		1 2			18:00 18:15	9		6 3			
6:30	2		0			18:30	4		1			
6:45	4 9)	3 6		15	18:45	6	27	2	12		39
7:00	3		1			19:00	8		4			
7:15	6		6			19:15	4		5			
7:30 7:45	6 11 2	6	10 13 30		56	19:30 19:45	4	19	3 2	14		33
8:00	36		40		50	20:00	4	-15	0			33
8:15	46		82			20:15	6		1			
8:30	10		9			20:30	3		0			
8:45	8 10	00	9 140		240	20:45	1	14	1	2		16
9:00 9:15	12 5		5 4			21:00 21:15	2		2 1			
9:30	15		6			21:30	0		1			
9:45	7 3	9	10 25		64	21:45	4	7	0	4		11
10:00	7		17			22:00	2		0			
10:15	8		12			22:15	1		0			
10:30 10:45	9 7 3	1	5 3 37		68	22:30 22:45	0	5	0 1	1		6
11:00	5		15			23:00	1	<u> </u>	0			
11:15	9		14			23:15	1		0			
11:30	6	_	9			23:30	0	_	1			
11:45	9 2		11 49		78	23:45	0	2	11	2		4 750
otal Vol.	23	5/	289		526			485		274	Daily Totals	759
							_	NB		SB		Combined
								722		563		1285
Split 0/-		10/	E4.00/	AM	40.00%	******************		62.00/		26 10/	PM	EQ 10/-
Split %		.1%	54.9%		40.9%			63.9%	1	36.1%		59.1%
eak Hour		:45	7:30		7:45			14:00		15:00		14:15
Volume P.H.F.		03 .56	145 0.44		247 0.48			113 0.81		94 0.39		190 0.54
				cs@aimtd.com		714 253 7888						

cs@aimtd.com Tell. 714 253 7888

Volumes for: Location:	r:	#######	#########		CITY:				aquin	PROJECT: SC3579		
Locati	ion:		ADT2 Yale r	orth of Royce	Prepared b	y: Field Data Servic	es of A	Arizona	a, Inc.		Suhsduhg#e #DlpW	G#00F##who1#:47#58
						DAY 2						
M Period 1	NB		SB			PM Period	NB		SB			
0:00	0		0			12:00	11		6			
0:15	1		0			12:15	9		4			
0:30	0		0			12:30	9	20	3	10		
0:45		1	0 0		1	12:45	9	38	6	19		57
1:00	0		0			13:00	11		3			
1:15 1:30	0		0 0			13:15 13:30	10 5		6 7			
1:45		0	0 0		0	13:45	16	42	8	24		66
2:00	0		0			14:00	11	12	14			
2:15	0		0			14:15	23		5			
2:30	0		0			14:30	13		11			
2:45		0	0 0		0	14:45	41	88	2	32		120
3:00	0		0			15:00	17		76			
3:15	0		0			15:15	11		10			
3:30	0		0			15:30	17		10			
3:45	0	0	0 0		0	15:45	17	62	5	101		163
4:00	0		0			16:00	15		17			
4:15	0		0			16:15	11		9			
4:30	0		1			16:30	10		5			
4:45	0	0	1 2		2	16:45	16	52	6	37		89
5:00	0		0			17:00	8		5			
5:15	0		0			17:15	14		6			
5:30	0	_	0			17:30	20		5			
5:45		0	2 2		2	17:45	18	60	4	20		80
6:00	0		0			18:00	8		5			
6:15	1		2			18:15	10		4			
6:30	2	_	3		1.4	18:30	4	20	5	10		46
6:45		5	4 9		14	18:45	6	28	4	18		46
7:00	3		6			19:00	2		6			
7:15 7:30	6 3		3 6			19:15 19:30	3 5		3 1			
		22	9 24		46	19:45	3	13	0	10		23
	49		45		10	20:00	5	1.5	5	10		
	49		45 85			20:00	4		3			
8:30	9		10			20:30	2		1			
8:45	5 1	103	8 148		251	20:45		15	3	12		27
9:00	6		2			21:00	2		0			
9:15	7		10			21:15	2		0			
9:30	5		7			21:30	1		2			
9:45	8	26	9 28		54	21:45	3	8	2	4		12
10:00	5		8			22:00	2		0			
10:15	12		1			22:15	2		0			
10:30	7		3			22:30	1		1			
10:45	12	36	3 15		51	22:45	4	9	2	3		12
	10		5			23:00	1		1			
11:15	5		1			23:15	1		1			
11:30	7	24	1		45	23:30	2		1	2		7
11:45	12	34	4 11		45	23:45	0	4	0	3		7
otal Vol.	2	227	239		466			419		283		702
											Daily Totals	
							_	NB		SB		Combined
								646		522		1168
Split %		8.7%	51.3%	AM	39.9%			59.7%		40.3%	PM	60.1%
JPIIL 70	4											
			7.45		7:45			14:15		15:00		14:15
eak Hour Volume		7:45 108	7:45 149		257			94		101		188

cs@aimtd.com

Tell. 714 253 7888

Volume	s for:	Tuesday, N	lovember 15, 2022		CITY:	*******	*****	*****		PROJECT: SC3579	
Locati	ion:	ADT3 Ya	le south of Royce	Prepared by	/: Field Data Se	rvices	of Ariz	zona, Ir	ic.	Suhsduhg#e #DlpW	G#00F##who1#:47#58
					AY 1						
M Period 1	NB	SB			PM Period	NB		SB			
0:00	3	0			12:00	26		15			
0:15 0:30	0 1	1 0			12:15 12:30	19 16		13 7			
0:45	0 4	1 2		6	12:45	18	79	15	50		129
1:00	1	0			13:00	17		5			
1:15	0	0			13:15	13		10			
1:30 1:45	1 1 3	2 0 2		5	13:30 13:45	19 13	62	15 11	41		103
2:00	0	0 2			14:00	34	02	14	71		103
2:15	0	0			14:15	38		6			
2:30	1	0			14:30	18		12			
2:45	1 2	0 0		2	14:45		135	8	40		175
3:00	1	0			15:00	32		59			
3:15 3:30	0	1 0			15:15 15:30	10 15		22 6			
3:45	1 2	0 1		3	15:45	23	80	11	98		178
4:00	0	0			16:00	20	-	25			
4:15	0	0			16:15	13		9			
4:30	0	0		3	16:30	11	63	16	EC.		110
4:45	0 0	2 2		2	16:45	18	62	6	56		118
5:00 5:15	0	1 0			17:00 17:15	25 27		13 6			
5:30	1	3			17:30	37		7			
5:45	1 2	2 6		8	17:45	21	110	7	33		143
6:00	2	1			18:00	15		8			
6:15	1	2			18:15	19		8			
6:30 6:45	2 4 9	3 5 11		20	18:30 18:45	14 8	56	8	32		88
7:00	4	4		20	19:00	12	30	7	32		00
7:15	7	11			19:15	12		8			
7:30	6	14			19:30	4		7			
7:45	15 32	23 52		84	19:45	6	34	4	26		60
	37	55			20:00	9		7			
	47 13	86 14			20:15 20:30	13 5		4 2			
	11 108	18 173		281	20:45	5	32	4	17		49
	18	7			21:00	2		7			
9:15	8	4			21:15	4		1			
	15	10		05	21:30	4	17	4	15		22
	13 54	11 32		86	21:45	7	17	3	15		32
10:00 10:15	7 7	23 13			22:00 22:15	6 2		1 3			
10:30	9	14			22:30	6		2			
10:45	4 27	10 60		87	22:45	5	19	4	10		29
11:00	7	19			23:00	5		1			
11:15	6	14			23:15	4		0			
	10 12 35	9 15 57		92	23:30 23:45	2	14	3 1	5		19
otal Vol.	278	398		676	20110		700		423		1123
Jan VUI.	2/0	370		0/0			700		743	Daily Totals	1123
						_	NB		SB	. ,	Combined
							978		821		1799
blit 0/	44.70	/ 50.000	AM	27 60/	************************		ca 20/		37.7%	PM	62.4%
plit %	41.19			37.6%			62.3%				
eak Hour	7:45 112			7:45 290			14:00 135		14:30 101		14:15
Volume											218

cs@aimtd.com

Tell. 714 253 7888

Volumes for: Location:	Wednesday, Novembe	er 16, 2022						Joaquin	PROJECT: SC3579		
Locati	ion:	ADT3 Yale south of	of Royce	Prepared by: F	Field Data Service	es of A	rizona	a, Inc.		Suhsduhg#e #Dlp	WG#00F##who1#:47#586
				DA	Y 2						
M Period	NB	SB			PM Period	NB		SB			
0:00	2	1			12:00	14		12			
0:15	2	0			12:15	20		8			
0:30	1	0			12:30	13		7			
0:45	0 5	0 1		6	12:45	9	56	14	41		97
1:00	2	1			13:00	17		4			
1:15	1	1			13:15	13		13			
1:30 1:45	0 0 3	0 1 3		6	13:30 13:45	13 24	67	10 16	43		110
2:00	1	0			14:00	23	07	17	15		
2:15	1	0			14:15	29		8			
2:30	0	0			14:30	14		13			
2:45	0 2	0 0		2	14:45		106	10	48		154
3:00	0	2			15:00	23		75			
3:15	0	0			15:15	12		13			
3:30	0	1			15:30	16		10			
3:45	0 0	0 3		3	15:45	18	69	15	113		182
4:00	0	0			16:00	25		21			
4:15	0	0			16:15	22		12			
4:30	0	1		2	16:30	19	07	7	47		424
4:45	0 0	1 2		2	16:45	21	87	7	47		134
5:00	0	1			17:00	18		13			
5:15 5:30	0	1 0			17:15 17:30	20 34		10 7			
5:45	1 1	2 4		5	17:45	25	97	12	42		139
6:00	1	0			18:00	12		9			
6:15	2	6			18:15	21		10			
6:30	1	6			18:30	9		10			
6:45	3 7	5 17		24	18:45		53	4	33		86
7:00	4	8			19:00	16		10			
7:15	8	8			19:15	6		5			
7:30	7	14			19:30	11		4			
7:45	10 29	20 50		79	19:45	10	43	2	21		64
	49	59			20:00	12		7			
	46	93			20:15	10		2			
	12	16		202	20:30	4	20	4			46
	13 120	14 182		302	20:45	4	30	3	16		46
9:00	6	7			21:00	6		0			
9:15 9:30	8 4	13 11			21:15 21:30	4		1 2			
9:45	7 25	17 48		73	21:45		16	6	9		25
10:00	6	12			22:00	8	-	2			
10:15	9	7			22:15	2		3			
10:30	8	7			22:30	1		5			
10:45	13 36	8 34		70	22:45	5	16	3	13		29
11:00	9	12			23:00	3		2			
11:15	5	5			23:15	3		2			
	12	9			23:30	5		1			
11:45	18 44	9 35		79	23:45	3	14	11	6		20
tal Vol.	272	379		651			654		432		1086
										Daily Totals	
						_	NB		SB		Combined
							926		811		1737
plit %	41.89	% 58.2%	AM	37.5%	***************************************		60.2%		39.8%	PM	62.5%
eak Hour	8:00			7:45			14:00		15:00		14:15
Volume P.H.F.	120 0.61			305 0.55			106 0.69		113 0.38		212 0.54
	0.01	0.51		0.55			3.03		0.50		0.54

cs@aimtd.com Tell. 714 253 7888


South Yale Corridor Study -Intersection Turning Movement Count Summary


				N	ORTHBOU	ND	S	ОИТНВОИ	ND		EASTBOUN			WESTBOUN		1
					Yale			Yale			Michelsor			Michelson		
Intersection	Date	Peak	Hour Starting	NL	NT	NR	SL	ST	SR	EL	ET	ER	WL	WT	WR	TOTAL
		AM	7:45 AM	13	53	34	18	36	46	56	125	25	83	200	21	710
	Tue, Nov 15, 22	PM	2:30 PM	14	21	48	20	19	26	23	164	15	46	168	17	581
		PM	4:45 PM	15	1	65	1	0	1	1	283	4	14	212	0	597
		AM	7:45 AM	13	58	32	23	38	58	74	144	16	92	186	19	753
Yale/Michelson	Wed, Nov 16, 22	PM	2:30 PM	16	17	40	27	23	31	30	171	24	46	164	15	604
		PM	4:45 PM	12	0	49	2	0	5	2	285	10	12	196	2	575
		AM	7:45 AM	13	56	33	21	37	52	65	135	21	88	193	20	732
	Average	PM	2:30 PM	15	19	44	24	21	29	27	168	20	46	166	16	593
		PM	4:45 PM	14	1	57	2	0	3	2	284	7	13	204	1	586
				N	ORTHBOU	ND		OUTHBOU	ND		EASTBOUN	D	,	WESTBOUN	D	
					Yale	ND	3	Yale	ND		Royce		· ·	Royce	· ·	4
Intersection	Date	Peak	Hour Starting	NL	NT	NR	SL	ST	SR	EL	ET	ER	WL	WT	WR	TOTAL
Intersection	Date	AM	7:45 AM	13	87	12	3	130	11	16	27	22	26	31	2	380
	Tue, Nov 15, 22	PM	2:15 PM	13	97	23	3	64	8	14	26	7	12	16	2	285
	140, 1101 15, 22	PM	4:45 PM	27	64	16	1	8	8	14	34	14	10	16	2	214
		AM	7:45 AM	12	93	12	1	139	9	14	24	27	22	31	1	385
Yale/Royce	Wed, Nov 16, 22	PM	2:15 PM	14	70	22	0	83	11	20	26	6	16	19	4	291
14.0/10/00	1100/ 1101 10/ 11	PM	4:45 PM	26	50	17	2	13	7	7	22	11	13	8	1	177
		AM	7:45 AM	13	90	12	2	135	10	15	26	25	24	31	2	383
	Average	PM	2:15 PM	14	84	23	2	74	10	17	26	7	14	18	3	288
	0 -	PM	4:45 PM	27	57	17	2	11	8	11	28	13	12	12	2	196
		1	I.													1
				N	ORTHBOU	ND	S	OUTHBOU	ND		EASTBOUN	D	1	WESTBOUN	ID	i i
					Yale			Yale			University	/		University	/	4
Intersection	Date	Peak	Hour Starting	NL	NT	NR	SL	ST	SR	EL	ET	ER	WL	WT	WR	TOTAL
		AM	7:45 AM	0	0	0	76	0	103	74	729	0	0	1,373	36	2,393
	Tue, Nov 15, 22	PM	2:30 PM	0	0	0	32	0	70	89	627	0	0	727	33	1,578
		PM	4:45 PM	0	0	0	10	0	22	69	1,438	0	0	984	32	2,556
		AM	8:00 AM	0	0	0	75	0	105	87	809	0	0	1,264	33	2,373
Yale/University	Wed, Nov 16, 22	PM	2:30 PM	0	0	0	44	0	74	61	750	0	0	691	31	1,651
		PM	4:45 PM	0	0	0	16	0	20	66	1,393	0	0	1,018	31	2,544
		AM	8:00 AM	0	0	0	76	0	104	81	769	0	0	1,319	35	2,383
	Average	PM	2:30 PM	0	0	0	38	0	72	75	689	0	0	709	32	1,615
		PM	4:45 PM	0	0	0	13	0	21	68	1,416	0	0	1,001	32	2,550

INTERSECTION TURNING MOVEMENT COUNTS PREPARED BY: AimTD LLC. tel: 714 253 7888 cs@aimtd.com

Ī	<u>DATE:</u> Tue, Nov 15, 22	LOCATION NORTH & S EAST & WE	SOUTH:			cho San Joa			@aimtd.coi	PROJECT # LOCATION CONTROL:	#:	SC3579 1 STOP ALL			
Ī	NOTES:										AM		A		1
											PM MD OTHER OTHER	→ W	N S ▼	E►	Add U-Turns to Left Turns
Ī		N	ORTHBOUN Yale	ND	S	OUTHBOUN Yale	ID		EASTBOUN Michelson	D		WESTBOUN Michelson	D		U-TURNS
l	LANES:	NL 1	NT 1	NR 0	SL 1	ST 1	SR 0	EL 1	ET 1	ER 0	WL 1	WT 1	WR 0	TOTAL	NB SB EB WB TTL 0 0 0 0
Ī	7:00 AM 7:15 AM	1 2	0 2	2	0 2	0 3	0	1 4	15 11	1 2	0 4	17 21	2 5	39 58	0 0 0 0 0 0 0 0 0
	7:30 AM 7:45 AM 8:00 AM	1 3 2	3 4 17	2 1 9	3 0 7	2 2 12	6 3 10	5 20	18 27 49	2 5 9	4 5 22	21 62 30	3 6 9	69 123 196	$\begin{array}{c ccccccccccccccccccccccccccccccccccc$
İ	8:15 AM 8:30 AM	7	31 1	16 8	9	21 1	31 2	30 1	35 14	10	48 8	71 37	5 1	314 77	0 0 0 0 0 0 0 0 0 0
	8:45 AM /OLUMES	0 17	58 480/	7 46	3 26	42	55 450/	65 330/	27 196	30	99 230/	37 296	31	85 961	0 0 0 1 1 0 0 0 1 1
7	APPROACH % APP/DEPART BEGIN PEAK HR	14% 121	48% / 7:45 AM	38% 154	21% 123	34% /	45% 170	22% 291	67% /	10% 269	23% 426	69% /	7% 368	0	1
,	OLUMES APPROACH %	13 13%	53 53%	34 34%	18 18%	36 36%	46 46%	56 27%	125 61%	25 12%	83 27%	200 66%	21 7%	710	
	PEAK HR FACTOR APP/DEPART	100	0.463 /	130	100	0.410 /	144	206	0.660	177	304	0.613 /	259	0.565 0	1
T	02:00 PM 2:15 PM	2	2	25	2	0	0	1	27 43	3	3	41 49	0	103 127	$\begin{array}{c ccccccccccccccccccccccccccccccccccc$
ŀ	2:30 PM 2:45 PM 3:00 PM	1 3 7	8 6	10 19 13	0 2 12	0 1 14	0 1 19	9 8	59 36 37	3 6 3	4 4 29	34 32 60	6 5 4	125 126 212	$\begin{array}{c ccccccccccccccccccccccccccccccccccc$
ŀ	3:15 PM 3:30 PM	3 2	3 0	6 7	6 1	4 0	6 2	2 1	32 37	3	9 5	42 46	2	118 103	0 0 0 0 0 0 0 0 0
	3:45 PM 4:00 PM 4:15 PM	6 3 6	2 4 1	11 12 15	6 0	0 8 1	7 2	1 2 0	36 38 51	4 1 3	3 16 4	31 46 51	2 1 0	98 144 134	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0
E	4:30 PM 4:45 PM	2 6	0	5 8	1 0	0	1 0	0	48 55	5 1	5 2	37 45	1 0	105 117	0 0 0 0 0 0 0 0 0 0
ŀ	5:00 PM 5:15 PM	2 4 3	0 0	17 14 26	0 1 0	0 0 0	0 0 1	0 0	70 82	0 3 0	1	50 46 71	0 0	144 151	$\begin{array}{c ccccccccccccccccccccccccccccccccccc$
1	5:30 PM 5:45 PM /OLUMES	4 56	0 31	9 217	1 34	0 28	0 40	0 31	76 53 780	3 42	8 1 101	71 41 722	0 22	185 112 2,104	0 0 0 0 0 0 0 0 0 0 0 1 2 0 3
7	APPROACH % APP/DEPART	18% 304	10%	71% 83	33% 102	27% /	39% 171	4% 853	91% /	5% 1,030	12% 845	85% /	3% 820	0	
١	Begin Peak Hr /Olumes Approach %	15 19%	4:45 PM 1 1%	65 80%	1 50%	0 0%	1 50%	1 0%	283 98%	4 1%	14 6%	212 94%	0 0%	597	
þ	PEAK HR FACTOR APP/DEPART	81	0.698 /	1	2	0.500	18	288	0.847 /	349	226	0.715 /	229	0.807 0	}
						Yale									
						NORTH SID	E								
		Michelson	,	WEST SIDE				EAST SIDE	i.	Michelsor	1				
					:	SOUTH SIDI	E								
						Yale									
-	2:30 PM	14	21	48	20	19	26	23	164	15	46	168	17	581	

AimTD LLC TURNING MOVEMENT COUNTS







INTERSECTION TURNING MOVEMENT COUNTS PREPARED BY: AimTD LLC. tel: 714 253 7888 cs@aimtd.com

<u>DATE:</u> Wed, Nov 16, 22	NORTH & EAST & W	SOUTH:		Irvine Ran Yale Michelson	cho San Jo	aquin			PROJECT # LOCATION CONTROL:		SC3579 1 STOP ALL			
IOTES:										AM PM MD OTHER OTHER	■ W	N N S ▼	E▶	Add U-Turns to Left Tur
	N	ORTHBOU!	ND	S	OUTHBOUN Yale	ND.		EASTBOUN Michelson	D	,	WESTBOUNI Michelson)		U-TURNS
LANES:	NL 1	NT 1	NR 0	SL 1	ST 1	SR 0	EL 1	ET 1	ER 0	WL 1	WT	WR 0	TOTAL	NB SB EB WB T
7:00 AM	1	0	2	0	1	2	1	16	2	2	11	0	38	0 0 0 0
7:15 AM	0	0	4	0	0	0	1	12	3	0	30	6	56	0 0 0 0
7:30 AM	1	1	3	0	0	1	1	23	0	6	23	2	61	0 0 0 0
7:45 AM	3	4	3	0	1	7	15	32	6	4	46	4	125	0 0 0 0
8:00 AM	5	21	13	5	13	16	25	54	6	27	44	11	240	0 0 0 0
8:15 AM	2	32	11	14	23	34	33	41	3	53	64	3	313	0 0 0 0
8:30 AM	3	1 2	5 3	<u>4</u> 5	1	1	1	17	3	8 5	32 43	0	75 107	0 0 0 0
8:45 AM DLUMES	0 15	61	44	28	39	62	81	41 236	24	105	293	27	1,015	0 1 0 0 0 1 0 0
PROACH %	13%	51%	37%	22%	30%	48%	24%	69%	7%	25%	69%	6%	1,013	
P/DEPART	120	1	170	129	/	168	341	/	307	425	/	370	0	1
GIN PEAK HR		7:45 AM												1
DLUMES	13	58	32	23	38	58	74	144	16	92	186	19	753	
PPROACH %	13%	56%	31%	19%	32%	49%	32%	62%	7%	31%	63%	6%		
AK HR FACTOR	100	0.572		440	0.419	4.46	224	0.688	100	207	0.619	257	0.601	4
PP/DEPART	103	/	151	119	/	146	234	/	199	297	/	257	0	-
02:00 PM 2:15 PM	3	2	7 17	2	0	0	4 2	29 44	3	9	44 29	2	107 106	0 0 1 0 0
2:30 PM	2	4	6	2	1	0	3	37	4	10	21	2	92	0 0 0 0
2:45 PM	6	7	12	1	2	1	10	45	6	5	40	5	140	0 0 0 0
3:00 PM	7	4	13	14	18	26	16	45	13	26	62	5	249	1 0 0 0
3:15 PM	1	2	9	10	2	4	1	44	1	5	41	3	123	0 0 0 0
3:30 PM	4	0	11	2	0	1	2	28	1	5	32	0	86	0 0 0 0
3:45 PM	5	2	10	0	2	2	3	46	1	2	46	0	119	0 0 0 0
4:00 PM	3	5	6	4	6	9	2	52	5	5	53	0	150	0 0 0 0
4:15 PM 4:30 PM	2	0	9 7	0	0	0	0	43 54	1 4	8	37 48	0	101 115	0 0 0 0
4:45 PM	4	0	11	0	0	0	1	56	3	3	42	1	121	0 0 0 0
5:00 PM	2	0	8	2	0	3	1	61	1	4	44	0	126	0 0 0 0
5:15 PM	2	0	11	0	0	0	0	88	4	3	59	0	167	0 0 0 0
5:30 PM	4	0	19	0	0	2	0	80	2	2	51	1	161	0 0 0 0
5:45 PM	3	0	17	0	0	0	1	63	1	4	42	0	131	0 0 1 0
OLUMES	52	28	173	38	32	50	46	815	52	96	691	21	2,094	1 0 2 0
PPROACH % PP/DEPART	21% 253	11%	68% 93	32% 120	27%	42% 181	5% 913	89%	6% 1,026	12% 808	86%	3% 794	0	4
EGIN PEAK HR	233	2:30 PM	33	120		101	913		1,020	000	/	7 27	- 0	1
DLUMES	16	17	40	27	23	31	30	171	24	46	164	15	604	
PPROACH %	22%	23%	55%	33%	28%	38%	13%	76%	11%	20%	73%	7%		
EAK HR FACTOR		0.730			0.349			0.760			0.605		0.606	
PP/DEPART	73		62	81	/	94	225	/	238	225	/	210	0]
					Yale									
						_								
					NORTH SID	E								
	Michelson	,	WEST SIDE				EAST SIDE	=	Michelsor	1				
				1 ,	SOUTH SID	F								
					220111 210	_								
					Yale									

AimTD LLC TURNING MOVEMENT COUNTS





INTERSECTION TURNING MOVEMENT COUNTS PREPARED BY: AimTD LLC. tel: 714 253 7888 cs@aimtd.com

PROJECT #:

SC3579


Irvine Rancho San Joaquin


LOCATION:

DATE:

Tue, Nov 15, 22	NORTH & EAST & W	SOUTH:		Yale Royce	iciio saii soc	iquiii			LOCATION CONTROL:	#:	2 STOP E/W			
NOTES:										AM PM MD OTHER OTHER	■ W	N S V	E►	Add U-Turns to Left Turns
	N	NORTHBOUN Yale	ND	9	OUTHBOUN Yale	ID		EASTBOUNI Royce)	1	WESTBOUNI Royce)		U-TURNS
LANES:	NL 0	NT 1	NR 0	SL 0	ST 1	SR 0	EL 0	ET 1	ER 0	WL 0	WT 1	WR 0	TOTAL	NB SB EB WB TTL 0 0 0 0
7:00 AM 7:15 AM 7:35 AM 7:35 AM 8:00 AM 8:15 AM 8:30 AM 8:35 AM 8:35 AM VOLUMES APPROACH % APP/DEPART BEGIN PEAK HR VOLUMES APPROACH % PEAK HR FACTOR APP/DEPART 02:00 PM 2:15 PM 2:30 PM 2:45 PM 3:00 PM 3:15 PM 4:00 PM 4:15 PM 4:30 PM 4:35 PM 5:30 PM 5:35 PM 5:30 PM 5:45 PM 5:30 PM 5:45 PM 5:30 PM 5:45 PM 5:30 PM 5:45 PM	1 0 0 3 3 5 4 4 1 1 3 12% 140 13 12% 112 2 8 8 2 2 1 1 4 4 5 5 7 2 1 1 4 4 5 5 9 6 6 7 7 4 6 66 7 7 4 6 66 17% 387 13 10% 133	3 5 3 15 27 105 75% 1 7:45 AM 87 78% 0.667 1 20 23 37 22 4 8 14 15 10 4 9 9 13 17 22 24 4 9 9 7 7 15 15 17 17 18 17 18 18 19 19 19 19 19 19 19 19 19 19 19 19 19	0 2 3 3 2 5 5 2 3 1 18 13% 128 12 11% 105 12 7 1 8 8 7 5 5 2 2 2 3 3 4 4 5 5 5 73 19% 312 23 17% 113		1 4 9 9 13 37 72 8 77 151 89% / / 130 90% 0.439 / / 5 5 5 4 4 4 5 11 77 19 5 5 5 0 0 2 2 2 4 5 139 78% / / 64 85% 0.318 / / Yale NORTH SIDI		0 1 2 0 5 10 1 1 1 20 22% 91 16 25% 65 7 2 3 5 4 2 1 1 1 5 1 4 5 1 1 4 1 51 28% 183 14 30% 47	2 2 1 4 7 112 4 5 37 41% 7 27 42% 0.580 7 3 6 6 9 2 9 2 2 9 4 1 6 8 7 7 9 6 8 8 7 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9	2 3 2 3 10 6 6 3 5 34 37% 59 22 34% 42 3 1 1 2 2 2 2 2 2 0 3 3 1 1 1 6 6 4 8 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 4 4 3 7 8 8 8 3 4 47% 81 26 444% 59 6 0 0 6 2 4 4 3 3 5 2 3 3 2 4 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	0 4 4 2 10 7 10 4 2 39 48% / 31 53% 0.819 7 4 3 3 3 5 5 5 5 2 2 1 7 6 6 5 2 2 3 1 1 7 6 6 7 7 7 7 6 7 7 7 7 7 7 7 7 7 7	0 1 1 1 1 1 0 0 0 0 4 5% 70 2 3% 55 0 0 0 0 1 1 1 1 2 5 1 1 0 0 1 1 1 1 1 1 0 1 1 1 1 1 1 1 1	10 28 27 58 115 170 37 37 482 0 380 0.559 0 64 57 46 66 116 40 29 46 65 37 46 66 37 46 60 285 0.614 0	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0
4:45 PM	27	64	16	1	8	8	14	34	14	10	16	2	214	

AimTD LLC TURNING MOVEMENT COUNTS





INTERSECTION TURNING MOVEMENT COUNTS PREPARED BY: AimTD LLC. tel: 714 253 7888 cs@aimtd.com

PROJECT #:

SC3579


Irvine Rancho San Joaquin


LOCATION:

DATE:

Wed, Nov 16, 22	NORTH & S EAST & WE	SOUTH:		Yale Royce	icho San Joa	.qa			LOCATION CONTROL:	#:	2 STOP E/W			
NOTES:										AM PM MD OTHER	■ W	N S	E▶	✓ Add U-Turns to Left Turns
	NO	ORTHBOUN	ND	S	OUTHBOUN	D	1	ASTBOUN	D		WESTBOUND			U-TURNS
LANES:	NL 0	NT 1	NR 0	SL 0	ST 1	SR 0	EL 0	Royce ET 1	ER 0	WL 0	Royce WT 1	WR 0	TOTAL	NB SB EB WB TTL 0 0 0 0
7:00 AM 7:15 AM 7:30 AM 7:45 AM 8:00 AM 8:15 AM 8:30 AM 8:45 AM VOLUMES APPROACH % APP/DEPART BEGIN PEAK HR VOLUMES APPROACH % PEAK HR FACTOR APP/DEPART 02:00 PM 2:15 PM 2:30 PM 2:45 PM 3:00 PM 3:15 PM 3:30 PM 4:00 PM 4:15 PM 4:30 PM 4:45 PM 5:00 PM 5:15 PM 5:30 PM 5:45 PM 5:00 PM 5:48 PM 5:00 PM	0 3 4 0 2 7 7 3 3 3 2 22 15% 149 12 10% 117 8 9 1 4 0 4 1 2 3 8 8 4 4 1 2 2 3 8 8 4 1 1 1 4 1 1 2 3 8 8 1 1 1 4 1 1 2 1 3 8 8 8 4 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 3 2 8 43 35 7 5 104 70% 1 7:45 AM 93 79% 0.597 1 10 32 14 15 12 15 14 18 18 13 204 57% 1 2:15 PM 70 66% 0.663 1	3 2 1 2 4 4 4 2 5 23 15% 125 10% 108 6 6 6 6 3 3 4 9 9 3 3 3 1 1 8 4 5 4 9 9 9 1 9 1 9 1 9 1 9 1 9 1 9 1 9 1 9		4 2 6 9 9 43 78 9 8 159 92% / 139 93% 0.438 8 7 / 9 3 110 2 6 6 4 17 7 6 4 4 17 7 6 4 4 17 7 8 8 5 2 2 4 4 5 5 2 2 154 81% / 7 88 88% 0.309 / Yale SOUTH SIDI		2 2 2 0 0 2 2 6 5 1 1 0 9 5 14 22% 65 1 7 1 9 3 4 4 3 2 2 1 1 1 4 2 2 3 3 0 2 2 5 48 29% 167 20 38% 52	2 5 2 6 8 7 3 2 35 37% / 24 37% 0.677 / 1 111 5 8 2 1 2 3 3 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7	1 4 4 4 9 9 10 5 3 6 42 44% 59 27 42% 37 22 3 8 8 1 1 2 2 1 5 5 2 3 4 41 25% 153 6 12% 48	3 2 4 2 6 10 4 0 31 40% 77 22 41% 54 4 4 4 2 6 4 4 1 3 3 3 3 0 4 4 4 2 6 6 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	0 5 4 9 9 9 9 9 4 3 43 56% / 0.711 / 4 3 4 4 8 2 4 7 5 5 6 0 0 4 3 1 5 6 0 0 1 1 1 5 6 0 0 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	0 1 1 0 0 0 1 0 1 0 3 4% 777 1 2% 52 1 2 2 0 0 0 2 2 2 0 0 0 0 0 0 0 0 0 0	18 30 28 47 133 167 38 32 493 0 385 0.576 0 51 61 40 71 119 37 41 46 55 46 44 42 45 39 51 54 842 0 291 0.611	1
4:45 PM	26	50	17	2	13	7	7	22	11	13	8	1	177	

AimTD LLC TURNING MOVEMENT COUNTS







INTERSECTION TURNING MOVEMENT COUNTS PREPARED BY: AimTD LLC. tel: 714 253 7888 cs@aimtd.com

<u>DATE:</u> Tue, Nov 15, 22	LOCATION NORTH & S EAST & WI	SOUTH:		Irvine Ran Yale University	cho San Joa	aquin			PROJECT # LOCATION CONTROL:		SC3579 3 SIGNAL			
NOTES:										AM PM MD OTHER OTHER	→ W	N S V	E▶	Add U-Turns to Left Turns
	N	NORTHBOUND Yale			SOUTHBOUND Yale			EASTBOUND University			WESTBOUND University			U-TURNS
LANES:	NL X	NT X	NR X	SL 1	ST X	SR 1	EL 1	ET 2	ER X	WL X	WT 2	WR 0	TOTAL	NB SB EB WB TTI
7:00 AM	0	0	0	4	0	2	3	68	0	0	139	3	219	0 0 0 0 0
7:15 AM	0	0	0	4	0	7	5	115	0	0	204	4	339	0 0 0 0 0
7:30 AM	0	0	0	4	0	12	4	128	0	0	339	5	492	0 0 1 0 1
7:45 AM	0	0	0	7	0	17	9	155	0	0	370	7	565	0 0 0 0 0
8:00 AM	0	0	0	18	0	34	26	165	0	0	317	12	572	0 0 0 0 0
8:15 AM	0	0	0	40	0	43	29	190	0	0	339	13	654	$\begin{array}{c ccccccccccccccccccccccccccccccccccc$
8:30 AM 8:45 AM	0	0	0	11 6	0	9 11	10 5	219 122	0	0	347 320	5	600 469	$\begin{array}{c ccccccccccccccccccccccccccccccccccc$
/OLUMES	0	0	0	94	0	135	91	1,162	0	0	2,375	53	3,917	0 0 6 1 7
APPROACH %	0%	0%	0%	41%	0%	59%	7%	92%	0%	0%	98%	2%	3,317	
APP/DEPART	0	1	144	229	/	0	1,259	1	1,257	2,429	/	2,516	0	1
BEGIN PEAK HR OLUMES	0	7:45 AM 0		76	0	103	74	729	0	0	1,373	36	2,393	1
APPROACH %	0%	0%	0%	42%	0%	58%	9%	91%	0%	0%	97%	3%	_,_,_	
PEAK HR FACTOR		0.000			0.539			0.874			0.935		0.913	
APP/DEPART	0		110	179		0	804	1	806	1,410	1	1,477	0	1
02:00 PM	0	0	0	3	0	8	26	116	0	0	130	4	287	0 1 1 0 2
2:15 PM	0	0	0	1	0	6	31	117	0	0	176	9	340	0 0 6 0 6
2:30 PM	0	0	0	2	0	11	9	125	0	0	198	5	350	0 0 0 0 0
2:45 PM	0	0	0	3	0	6	35	117	0	0	156	12	329	0 0 0 0 0
3:00 PM	0	0	0	21	0	40	24	134	0	0	197	12	428	0 0 0 0 0
3:15 PM	0	0	0	5	0	18	7	189	0	0	203	4	426	0 0 0 0 0
3:30 PM 3:45 PM	0	0	0	2	0	6 8	23 14	187 296	0	0	171 195	5 9	395 524	0 0 0 0 0
4:00 PM	0	0	0	2	0	23	15	245	0	0	207	5	497	0 0 0 0 0
4:15 PM	0	0	0	2	0	6	11	297	0	0	231	2	549	0 0 0 0 0
4:30 PM	0	0	0	5	0	12	10	296	0	0	248	4	575	0 0 0 0 0
4:45 PM	0	0	0	3	0	3	8	384	0	0	245	7	650	0 0 0 0 0
5:00 PM	0	0	0	6	0	8	15	347	0	0	222	9	607	0 0 1 0 1
5:15 PM	0	0	0	0	0	5	18	401	0	0	256	8	688	0 0 0 0 0
5:30 PM	0	0	0	1	0	6	28	306	0	0	261	8	610	0 0 0 0 0
5:45 PM	0	0	0	3	0	4	14	294	0	0	251	5	571	0 0 1 0 1
/OLUMES	0	0	0	62	0	170	288	3,851	0	0	3,347	108	7,836	0 1 9 0 10
APPROACH % APP/DEPART	0% 0	0%	0% 397	27% 233	0%	73% 0	7% 4,148	93%	0% 3,913	0% 3,455	97%	3% 3,526	0	1
BEGIN PEAK HR	U	4:45 PM		233	/	U	7,140	/	3,313	ככד,כ	/	3,320		1
OLUMES	0	0	0	10	0	22	69	1,438	0	0	984	32	2,556	1
PPROACH %	0%	0%	0%	31%	0%	69%	5%	95%	0%	0%	97%	3%	_,	
EAK HR FACTOR		0.000			0.571			0.900			0.944		0.929	1
PP/DEPART	0	/	101	32	/	0	1,508	/	1,448	1,016	/	1,007	0]
					Yale		Î							
					NODTH CTO	_								
				'	NORTH SID	C	L							
	University		WEST SIDE				EAST SIDI	E	University	1				
					SOUTH SID	F								
					220111310	_								
				ı			1							
					Yale									
					Yale		I							
					Yale		1							

AimTD LLC TURNING MOVEMENT COUNTS







INTERSECTION TURNING MOVEMENT COUNTS PREPARED BY: AimTD LLC. tel: 714 253 7888 cs@aimtd.com

NC NL LANES: X NL X NL X NL X NL X NL X X NL X X NL X X X X X X X X X		University					CONTROL:		SIGNAL			
LANES: X 7:00 AM 0 7:15 AM 0 7:15 AM 0 7:30 AM 0 7:45 AM 0 8:00 AM 0 8:15 AM 0 8:30 AM 0 8:33 AM 0 8:34 AM 0 8:45 AM 0 DLUMES 0 PPROACH % 0% PP/DEPART 0 0:200 PM 0 2:15 PM 0 2:30 PM 0 3:00 PM 0 3:15 PM 0 3:30 PM 0 3:45 PM 0 3:30 PM 0 4:45 PM 0 4:30 PM 0 4:45 PM 0 5:50 PM 0 5:15 PM 0								AM PM MD OTHER OTHER	⋖ W	N S	E►	Add U-Turns to Left Tu
LANES: X	ORTHBOUND Yale	SO	EASTBOUND University			WESTBOUND University				U-TURNS		
7:15 AM 0 7:30 AM 0 7:30 AM 0 7:35 AM 0 8:00 AM 0 8:15 AM 0 8:15 AM 0 8:15 AM 0 8:15 AM 0 8:15 AM 0 8:15 AM 0 8:15 AM 0 8:15 AM 0 8:15 AM 0 8:15 AM 0 8:15 AM 0 8:15 AM 0 8:16 AM 0 8:17 AM 0 8:18 A	NT NR	SL 1	ST X	SR 1	EL 1	ET 2	ER X	WL X	WT 2	WR 0	TOTAL	NB SB EB WB 1
7:30 AM 0 7:45 AM 0 8:00 AM 0 8:15 AM 0 8:33 AM 0 8:345 AM 0 8:35 AM 0 8:35 AM 0 8:45 AM 0 8:45 AM 0 DLUMES 0 PPROACH % 0% PPROACH % 0% PPROACH % 0 2:15 PM 0 2:15 PM 0 2:30 PM 0 2:45 PM 0 3:30 PM 0 3:35 PM 0 3:30 PM 0 3:45 PM 0 3:55 PM 0 4:55 PM 0 4:55 PM 0 5:65 PM	0 0	2	0	7	2	71	0	0	129	3	214	0 0 0 0
7:45 AM 0 8:00 AM 0 8:10 AM 0 8:15 AM 0 8:30 AM 0 8:33 AM 0 8:45 AM 0 DLUMES 0 PPROACH % 0% PPROACH % 0% EAK HR FACTOR PP/DEPART 0 2:00 PM 0 2:15 PM 0 2:15 PM 0 2:30 PM 0 3:15 PM 0 4:00 PM 0 4:15 PM 0 4:10 PM 0 4:15 PM 0 5:10 PM 0 5:10 PM 0 5:10 PM 0 5:11 PM 0 5:11 PM 0 5:11 PM 0 5:12 PM 0 5:13 PM 0 5:11 PM 0 5:13 PM 0 5:14 PM 0 5:15 PM 0 5:15 PM 0 5:15 PM 0 5:10 PM 0 5:15 PM 0 5:11 PM 0 5:11 PM 0 5:11 PM 0 5:12 PM 0 5:13 PM 0 5:14 PM 0 5:15 PM 0 5:15 PM 0 5:15 PM 0 5:15 PM 0 5:15 PM 0 5:15 PM 0 5:16 PM 0 5:17 PM 0 5:18 PM 0 5:19	0 0	3	0	3	2	102	0	0	204	6	320	0 0 0 0
8:00 AM 0 8:15 AM 0 8:15 AM 0 8:30 AM 0 8:45 AM 0 8:45 AM 0 PP/DEPART 0 PPROACH % 0% PP/DEPART 0 CIN PEAK HR DLUMES 0 0 PPROACH % 0% PPROACH % 0% 2:45 PM 0 2:30 PM 0 2:45 PM 0 3:00 PM 0 3:15 PM 0 3:30 PM 0 3:45 PM 0 4:15 PM 0 4:30 PM 0 4:15 PM 0 5:30 PM 0 5:15 PM 0 5:30 PM 0 0 5:15 PM 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0	7	0	6	3	123	0	0	310	4	453	0 0 0 0
8:15 AM 0 8:30 AM 0 8:30 AM 0 8:45 AM 0 0 DLUMES 0 PPROACH % 0% PPP/DEPART 0 0 PPPROACH % 0% PPPCOACH % 0% PPROACH % 0% PPROACH % 0% PPROACH % 0 2:15 PM 0 2:15 PM 0 2:30 PM 0 3:00 PM 0 3:15 PM 0 3:30 PM 0 3:45 PM 0 3:30 PM 0 4:45 PM 0 4:30 PM 0 4:45 PM 0 5:00 PM 0 5:15 PM 0 5:15 PM 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0	7 17	0	14 32	8 37	160 164	0	0	334 381	5 10	528 641	0 0 1 0 0
8:30 AM 0 8:45 AM 0 DLUMES 0 PROACH % 0% PPROACH % 0% PPROACH % 0% EGIN PEAK HR DLUMES 0 PROACH % 0% EAK HR FACTOR PPROACH % 0% 2:30 PM 0 2:15 PM 0 2:30 PM 0 2:45 PM 0 3:30 PM 0 3:315 PM 0 3:315 PM 0 4:00 PM 0 4:15 PM 0 4:30 PM 0 5:15 PM 0 5:30 PM 0 5:15 PM 0 5:15 PM 0 5:10 PM 0 5:15 PM 0 5:10 PM 0 5:15 PM 0 5:10 PM 0 5:15 PM 0 5:10 PM 0 5:15 PM 0 5:10 PM 0 5:11 PM 0 5:11 PM 0 5:11 PM 0 5:11 PM 0 5:12 PM 0 5:13 PM 0 5:14 PM 0 5:15 PM 0 5:15 PM 0 5:15 PM 0 5:10 PM 0 5:15 PM 0 5:10 PM 0 5:15 PM 0 5:11 PM 0 5:11 PM 0 5:11 PM 0 5:11 PM 0 5:12 PM 0 5:13 PM 0 5:14 PM 0 5:15 PM 0 5:15 PM 0 5:15 PM 0 5:16 PM 0 5:17 PM 0 5:18 PM 0 5:18 PM 0 5:19 PM 0 5:19 PM 0 5:19 PM 0 5:11 PM 0 5:11 PM 0 5:11 PM 0 5:12 PM 0 5:13 PM 0 5:14 PM 0 5:15 PM 0 5:15 PM 0 5:15 PM 0 5:15 PM 0 5:15 PM 0 5:15 PM 0 5:16 PM 0 5:17 PM 0 5:18 PM 0 5:18 PM 0 5:19 PM 0 5:19 PM 0 5:19 PM 0 5:19 PM 0 5:11 PM 0 5:11 PM 0 5:11 PM 0 5:12 PM 0 5:12 PM 0 5:13 PM 0 5:14 PM 0 5:15 PM 0 5:15 PM 0 5:15 PM 0 5:15 PM 0 5:16 PM 0 5:17 PM 0 5:18 PM 0 5:18 PM 0 5:19 P	0 0	45	0	54	32	193	0	0	256	13	593	0 0 0 0
8:45 AM 0 0 DLUMES 0 0 PPROACH % 0% PPROACH % 0% PPROACH W 0% PPROACH W 0% PPROACH W 0% PPROACH W 0% PROACH W 0% PROACH W 0 0% PROACH W 0 0 PROACH W 0 0 PROACH W 0 0 PROACH W 0 0 PROACH W 0 0 PROACH W 0 0 PROACH W 0 0 PROACH W 0 0 PROACH W 0 0 PROACH W 0 0 PROACH W 0 0 PROACH W 0 0 PROACH W 0 0 PPROACH W 0 0	0 0	10	0	9	9	286	0	0	281	6	601	0 0 0 0
PP/DEPART 0 GGIN PEAK HR DLUMES 0 PP/DEPART 0 GEAK HR FACTOR PP/DEPART 0 0:2:00 PM 0 2:15 PM 0 2:35 PM 0 2:45 PM 0 3:30 PM 0 3:30 PM 0 3:45 PM 0 4:30 PM 0 4:15 PM 0 4:30 PM 0 5:50 PM 0 5:50 PM 0 5:50 PM 0 5:15 PM 0 5:15 PM 0 5:10 PM 0 6:15 PM 0 6:15 PM 0 6:16 PM 0 6:17 PM 0 6:18 PM	0 0	3	0	10	9	166	0	0	346	4	538	0 0 0 0
PP/DEPART 0 GGIN PEAK HR DLUMES 0 PP/DEPART 0 GEAK HR FACTOR PP/DEPART 0 0:2:00 PM 0 2:15 PM 0 2:35 PM 0 2:45 PM 0 3:30 PM 0 3:30 PM 0 3:45 PM 0 4:30 PM 0 4:15 PM 0 4:30 PM 0 5:50 PM 0 5:50 PM 0 5:50 PM 0 5:15 PM 0 5:15 PM 0 5:10 PM 0 6:15 PM 0 6:15 PM 0 6:16 PM 0 6:17 PM 0 6:18 PM	0 0	94	0	135	102	1,265	0	0	2,241	51	3,888	0 0 1 0
EGIN PEAK HR DLUMES 0 9PPROACH % 0% EAK HR FACTOR PPPROACH % 0 02:00 PM 0 2:15 PM 0 2:30 PM 0 3:30 PM 0 3:15 PM 0 3:30 PM 0 3:45 PM 0 4:30 PM 0 4:15 PM 0 4:30 PM 0 5:50 PM 0 5:15 PM 0 5:15 PM 0 5:10 PM 0 5:15 PM 0 5:10 PM 0 5:15 PM 0 5:10 PM 0 5:15 PM 0 5:10 PM 0 5:15 PM 0 5:10 PM 0 5:15 PM 0 5:10 PM 0 5:15 PM 0 5:10 PM 0 5:15 PM 0 5:10 PM 0 5:15 PM 0 5:10 PM 0 5:15 PM 0 5:10 PM 0 5:15 PM 0 5:10 PM 0 5:15 PM 0 5:10 PM 0 5:15 PM 0 5:10 PM 0 5:15 PM 0 5:10 PM 0 5:15 PM 0 5:15 PM 0 5:10 PM 0 5:15 PM 0 5:	0% 0%	41%	0%	59%	7%	93%	0%	0%	98%	2%		4
DLUMES OLUMES OPPROACH % OW AAK HR FACTOR PP/DEPART O 02:00 PM O 2:15 PM O 2:30 PM O 3:00 PM O 3:15 PM O 3:30 PM O 3:35 PM O 4:40 PM 4:45 PM O 4:30 PM O 4:45 PM O 5:30 PM O 5:30 PM O O C C C C C C C C C C C	/ 152	229	/	0	1,367	/	1,359	2,292	/	2,377	0	4
PPROACH % O% CAK HR FACTOR PP/DEPART O 02:00 PM O 2:15 PM O 2:30 PM O 2:45 PM O 3:30 PM O 3:15 PM O 3:30 PM O 3:35 PM O 3:35 PM O 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	8:00 AM 0 0	75	0	105	87	809	0	0	1,264	33	2,373	
EAK HR FACTOR PP/DEPART 0 2:00 PM 0 2:15 PM 0 2:30 PM 0 2:45 PM 0 3:00 PM 0 3:15 PM 0 3:30 PM 0 3:315 PM 0 0 3:345 PM 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0% 0%	42%	0%	58%	10%	90%	0%	0%	97%	3%	2,3/3	
PP/DEPART 0 02:00 PM 0 2:15 PM 0 2:30 PM 0 2:45 PM 0 3:00 PM 0 3:315 PM 0 3:30 PM 0 3:35 PM 0 4:00 PM 0 4:15 PM 0 4:37 PM 0 4:38 PM 0 5:45 PM 0 5:50 PM 0 5:45 PM 0 6:45 PM	0.000	12.70	0.455	30 /0	1070	0.759	0 70	0 70	0.829	370	0.926	
2:15 PM 0 2:30 PM 0 2:45 PM 0 3:00 PM 0 3:15 PM 0 3:315 PM 0 3:35 PM 0 4:00 PM 0 4:15 PM 0 4:30 PM 0 4:45 PM 0 5:00 PM 0 5:15 PM 0 5:30 PM 0 5:45	/ 120	180	/	0	896	/	884	1,297	/	1,369	0	1
2:30 PM 0 2:45 PM 0 3:00 PM 0 3:15 PM 0 3:35 PM 0 3:35 PM 0 3:45 PM 0 4:00 PM 0 4:15 PM 0 4:30 PM 0 5:50 PM 0 5:15 PM 0 5:30 PM 0 5:45 P	0 0	3	0	10	11	166	0	0	151	10	351	0 0 0 0
2:45 PM 0 3:00 PM 0 3:00 PM 0 3:15 PM 0 3:35 PM 0 4:00 PM 0 4:15 PM 0 4:30 PM 0 4:45 PM 0 5:00 PM 0 5:15 PM 0 5:30 PM 0 5:45 P	0 0	4	0	7	17	173	0	0	139	14	354	0 0 0 0
3:00 PM 0 3:15 PM 0 3:35 PM 0 3:35 PM 0 4:00 PM 0 4:15 PM 0 4:35 PM 0 4:35 PM 0 4:45 PM 0 5:00 PM 0 5:15 P	0 0	6	0	8	7	182	0	0	157	8	368	0 0 0 0
3:15 PM 0 3:30 PM 0 3:345 PM 0 4:00 PM 0 4:15 PM 0 4:15 PM 0 4:45 PM 0 5:00 PM 0 5:15 PM 0 5:30 PM 0 5:45 PM 0 6:45	0 0	3 33	0	9 42	31 15	186 180	0	0	171 186	10 9	410 465	0 0 0 0
3:30 PM 0 3:45 PM 0 4:00 PM 0 4:10 PM 0 4:15 PM 0 4:30 PM 0 4:45 PM 0 5:00 PM 0 5:15 PM 0 5:30 PM 0 5:45 PM 0 5:45 PM 0 5:45 PM 0 5:45 PM 0 5:45 PM 0 5:45 PM 0 5:45 PM 0 5:45 PM 0 5:45 PM 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0	2	0	15	8	202	0	0	177	4	408	0 0 0 0
4:00 PM 0 4:15 PM 0 4:15 PM 0 4:30 PM 0 4:45 PM 0 5:00 PM 0 5:15 PM 0 5:33 PM 0 5:45 PM 0 5:45 PM 0 0 DPROACH % 0% P/D/EPART 0 CAN BEAK HR DLUMES 0 PPROACH % 0% EAK HR FACTOR PP/DEPART 0	0 0	2	0	9	16	238	0	0	188	1	454	0 0 0 0
4:15 PM 0 4:30 PM 0 4:33 PM 0 4:45 PM 0 5:00 PM 0 5:15 PM 0 5:15 PM 0 5:30 PM 0 5:45 PM 0 DLUMES 0 PPROACH % 0% PPROACH % 0% EGIN PEAK HR DLUMES 0 PPROACH % 0% EAK HR FACTOR PP/DEPART 0	0 0	5	0	9	9	274	0	0	199	9	505	0 0 0 0
4:30 PM 0 4:45 PM 0 5:00 PM 0 5:00 PM 0 5:15 PM 0 5:30 PM 0 5:30 PM 0 5:45 PM 0 DLUMES 0 PPROACH % 0% PPPOBEPART 0 EGIN PEAK HR DLUMES 0 PPROACH % 0% PAK HR FACTOR PP/DEPART 0	0 0	5	0	16	22	276	0	0	193	7	519	0 0 0 0
4:45 PM 0 5:00 PM 0 5:10 PM 0 5:15 PM 0 5:33 PM 0 5:45 PM 0 DLUMES 0 PPROACH % 0% PP/DEPART 0 GGIN PEAK HR DULUMES 0 PPROACH % 0% EAK HR FACTOR PP/DEPART 0	0 0	1	0	12 4	11	341	0	0	181	7	553	0 0 0 0
5:00 PM 0 5:15 PM 0 5:15 PM 0 5:30 PM 0 5:45 PM 0 5:45 PM 0 5:45 PM 0 5:45 PM 0 5:45 PM 0 5:45 PM 0 5:45 PM 0 5:45 PM 0 5:45 PM 0 5:45 PM 0 5:45 PM 0 6:45 P	0 0	3 0	0	- 4 7	10 16	330 373	0	0	233 253	7	589 656	0 0 0 0 0
5:15 PM 0 5:30 PM 0 5:30 PM 0 5:45 PM 0 DLUMES 0 PPROACH % 0% PP/DEPART 0 EGIN PEAK HR DLUMES 0 PPROACH % 0% PP/DEPART 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0	6	0	6	8	326	0	0	261	10	617	0 0 0 0
5:45 PM 0 DLUMES 0 PPROACH % 0% PP/DEPART 0 GIN PEAK HR DLUMES 0 PPROACH % 0% EAK HR FACTOR PP/DEPART 0	0 0	8	0	2	16	371	0	0	227	4	628	0 0 0 0
DLUMES 0 PPROACH % 0% PP/OEPART 0 EGIN PEAK HR DLUMES 0 PPROACH % 0% 2AK HR FACTOR PP/DEPART 0	0 0	2 2	0	5	26	323	0	0	277	10	643	0 0 0 0
PPROACH % 0% PP/DEPART 0 EGIN PEAK HR DLUMES 0 PPROACH % 0% EAK HR FACTOR PP/DEPART 0	0 0		0	12	17	270	0	0	227	6	534	0 0 0 0
PP/DEPART 0 EGIN PEAK HR DOLUMES 0 PPROACH % 0% EAK HR FACTOR PP/DEPART 0	0 0	85	0	173	240	4,211	0	0	3,220	125	8,054	0 0 0 0
GIN PEAK HR DLUMES 0 PPROACH % 0% EAK HR FACTOR PP/DEPART 0	0% 0% / 365	33% 258	0%	67% 0	5% 4,451	95%	0% 4,296	0% 3,345	96%	4% 3,393	0	4
DLUMES 0 PPROACH % 0% EAK HR FACTOR PP/DEPART 0	4:45 PM	230	/	U	7,731		7,230	כז כוכ		دودرد	U	1
PPROACH % 0% EAK HR FACTOR PP/DEPART 0	0 0	16	0	20	66	1,393	0	0	1,018	31	2,544	
PP/DEPART 0	0% 0%	44%	0%	56%	5%	95%	0%	0%	97%	3%		
	0.000		0.750			0.938			0.914	1.05-	0.970]
University	/ 97	36	/	0	1,459	/	1,409	1,049	/	1,038	0	J
University		N/C	Yale	_								
University 			ORTH SIDE	-								
	WEST SI	DE			EAST SIDE	Ī	University	,				
		SC	OUTH SIDE	=								
			Yale									
		Į	rate		I							
2:30 PM 0												

AimTD LLC TURNING MOVEMENT COUNTS





LOCATION: Irvine Rancho San Joaquin NORTH & SOUTH: Yale EAST & WEST: Michelson

PROJECT #: LOCATION #: CONTROL:

SC3579 1 STOP ALL

								NORT	H SIDE							
			PE	DS			BYCI	CLIST			SCO	OTER		CVATE	BOARD	TOTAL
		А	dult	Scho	ol Age	В	ike	E-6	3ike	Sco	ooter	Mobility A	Assistance	SKATE	BUARD	TOTAL
		EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	
I	7:00 AM	0	1	1	0	0	0	0	0	0	0	0	0	0	0	2
I	7:15 AM	0	0	1	0	0	0	0	1	0	0	0	0	0	0	2
	7:30 AM	0	0	0	0	0	1	0	0	0	0	0	0	0	0	1
	7:45 AM	0	0	0	0	1	3	0	0	0	0	0	0	0	0	4
	8:00 AM	0	0	3	1	5	0	0	0	0	0	0	0	0	0	9
	8:15 AM	0	0	9	0	2	2	1	0	1	0	0	0	0	0	15
	8:30 AM	0	1	0	0	0	0	0	0	1	0	0	0	0	0	2
	8:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
1	OTAL AM	0	2	14	1	8	6	1	1	2	0	0	0	0	0	35
	02:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	2:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	2:30 PM	1	0	0	0	0	0	0	0	0	0	0	0	0	0	1
	2:45 PM	2	0	0	0	0	0	0	0	1	0	0	0	0	0	3
	3:00 PM	0	4	1	51	0	4	0	2	0	3	0	0	0	0	65
	3:15 PM	1	0	0	0	1	0	0	1	0	0	0	0	0	0	3
	3:30 PM	1	0	0	0	0	0	0	0	0	0	0	0	0	0	1
	3:45 PM	0	0	0	0	0	1	0	0	0	0	0	0	0	0	1
	1:00 PM	0	0	1	2	0	2	0	0	0	1	0	0	0	0	6
	4:15 PM	2	2	0	0	0	0	0	0	0	1	0	0	0	0	5
	4:30 PM	0	0	0	0	0	0	0	1	0	0	0	0	0	0	1
	4:45 PM	1	0	0	0	0	0	0	1	0	0	0	0	0	0	2
	5:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	5:15 PM	3	2	0	0	0	1	0	0	0	0	0	0	0	0	6
	5:30 PM	1	0	0	0	1	1	0	0	0	0	0	0	0	0	3
	5:45 PM	0	2	0	0	0	0	0	0	0	0	0	0	0	0	2
T	OTAL PM	12	10	2	53	2	9	0	5	1	5	0	0	0	0	99

								SOUT	H SIDE							
			PE	DS			BYCI	CLIST			SCO	OTER		CVATE	BOARD	TOTAL
		A	dult	Scho	ol Age	В	ike	E-8	Bike		ooter		Assistance	SKATE	BUARD	IOIAL
		EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	
	7:00 AM	0	2	0	0	0	0	0	0	0	0	0	0	0	0	2
	7:15 AM	1	0	1	0	1	1	0	0	0	0	0	0	0	0	4
	7:30 AM	1	5	2	0	0	3	0	0	0	0	0	0	0	0	11
Σ	7:45 AM	0	0	2	0	2	2	0	0	0	0	0	0	0	0	6
A	8:00 AM	0	1	4	0	5	3	0	0	0	0	0	0	0	0	13
	8:15 AM	1	0	8	1	1	0	0	0	0	0	0	0	1	0	12
	8:30 AM	0	1	0	0	1	0	0	0	0	0	0	0	0	0	2
	8:45 AM	0	1	0	0	0	0	0	0	0	0	0	0	0	0	1
	TOTAL AM	3	10	17	1	10	9	0	0	0	0	0	0	1	0	51
	02:00 PM	0	1	0	0	2	0	0	0	0	0	0	0	0	0	3
	2:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	2:30 PM	0	0	0	0	3	0	0	0	0	0	0	0	0	0	3
	2:45 PM	0	0	0	0	4	0	0	0	0	0	0	0	0	0	4
	3:00 PM	0	3	0	15	0	4	0	0	0	1	0	0	0	0	23
	3:15 PM	1	0	0	0	1	0	0	0	0	0	0	0	0	0	2
	3:30 PM	1	3	0	0	0	0	0	0	0	0	0	0	0	0	4
	3:45 PM	2	0	0	0	1	0	1	0	0	0	0	0	0	0	4
Σ	4:00 PM	1	1	1	0	0	7	0	0	0	0	0	0	0	0	10
_	4:15 PM	0	1	0	0	1	0	0	0	0	0	0	0	0	0	2
	4:30 PM	0	5	0	0	0	0	0	0	0	0	0	0	0	0	5
	4:45 PM	2	0	0	0	0	1	0	0	0	0	0	0	0	0	3
	5:00 PM	1	2	0	0	2	0	0	0	0	0	0	0	0	0	5
	5:15 PM	6	0	0	0	0	0	0	0	0	0	0	0	0	0	6
	5:30 PM	1	3	0	0	0	0	0	0	0	0	0	0	0	0	4
	5:45 PM	0	1	0	0	0	0	0	0	0	0	0	0	0	0	1
	TOTAL PM	15	20	1	15	14	12	1	0	0	1	0	0	0	0	79

								EAST	SIDE							
			PE	:DS			BYCI				SCO	OTER		CVATE	BOARD	TOTAL
		A	dult	Scho	ol Age	В	ike	E-8	3ike	Sco	oter	Mobility A	Assistance	SKAIL	BUARD	IOIAL
		NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	
	7:00 AM	1	2	0	0	0	0	0	0	0	0	0	0	0	0	3
	7:15 AM	1	1	3	0	3	1	0	0	0	0	0	0	0	0	9
	7:30 AM	1	3	2	0	1	0	0	0	0	0	0	0	0	0	7
Σ	7:45 AM	0	1	2	0	3	0	0	0	0	0	0	0	0	0	6
⋖	8:00 AM	0	1	11	0	11	0	1	0	2	0	0	0	0	0	26
	8:15 AM	1	2	22	0	4	0	0	1	0	0	0	0	1	0	31
	8:30 AM	2	0	0	0	0	1	0	0	0	0	0	0	0	0	3
	8:45 AM	0	2	0	0	1	0	0	0	0	0	0	0	0	0	3
	TOTAL AM	6	12	40	0	23	2	1	1	2	0	0	0	1	0	88
				•		•				•	•			•	•	•
	02:00 PM	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1
	2:15 PM	0	0	0	0	1	1	0	0	0	0	0	0	0	0	2
	2:30 PM	1	0	0	0	0	0	0	0	0	0	0	0	0	0	1
	2:45 PM	3	0	0	2	0	0	0	0	0	1	0	0	0	0	6
	3:00 PM	0	2	0	55	0	13	0	1	0	0	0	0	0	0	71
	3:15 PM	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1
	3:30 PM	1	0	0	0	0	0	0	0	0	0	0	0	0	0	1
	3:45 PM	2	0	0	0	1	1	0	0	0	0	0	0	0	0	4
Σ	4:00 PM	0	0	0	1	0	7	0	0	0	0	0	0	0	0	8
	4:15 PM	1	3	0	0	0	0	0	0	0	0	0	0	1	0	5
	4:30 PM	0	2	0	0	1	1	0	0	0	1	0	0	0	0	5
	4:45 PM	2	1	0	0	0	0	0	1	0	0	0	0	0	0	4
	5:00 PM	1	0	0	0	0	1	1	0	0	0	0	0	0	0	3
	5:15 PM	0	1	0	0	2	0	0	0	1	0	0	0	0	0	4
	5:30 PM	2	1	0	0	1	1	0	0	0	0	0	0	0	0	5
	5:45 PM	0	2	0	0	0	0	0	0	0	0	0	0	0	0	2
	TOTAL PM	13	12	0	58	8	25	1	2	1	2	0	0	1	0	123

								WEST	SIDE							
			PE	:DS			BYCI	CLIST			SCO	OTER		CVATE	BOARD	TOTAL
			lult		ol Age		ike		Bike		oter		Assistance			IOIAL
		NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	
	7:00 AM	0	0	1	0	0	0	0	0	0	0	0	0	0	0	1
	7:15 AM	0	0	1	0	0	1	0	0	0	0	0	0	0	0	2
	7:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Σ	7:45 AM	2	0	0	0	1	3	0	0	0	0	0	0	0	0	6
⋖	8:00 AM	0	0	3	0	2	1	0	0	0	0	0	0	0	0	6
	8:15 AM	0	1	3	1	1	4	0	0	1	0	0	0	0	0	11
	8:30 AM	0	0	0	0	1	1	0	0	0	0	0	0	0	0	2
	8:45 AM	1	0	0	0	1	4	1	0	0	0	0	0	0	0	7
	TOTAL AM	3	1	8	1	6	14	1	0	1	0	0	0	0	0	35
	02:00 PM	0	0	0	0	0	2	0	0	0	0	0	0	0	0	2
	2:15 PM	2	0	0	0	1	1	0	1	0	0	0	0	0	0	5
	2:30 PM	0	0	0	0	2	0	0	0	0	0	0	0	0	0	2
	2:45 PM	0	0	0	0	1	1	0	0	0	0	0	0	0	0	2
	3:00 PM	1	1	0	21	0	6	0	1	0	2	0	0	0	1	33
	3:15 PM	1	0	0	0	0	1	0	0	0	0	0	0	0	0	2
	3:30 PM	0	1	0	0	0	1	0	0	0	0	0	0	0	0	2
	3:45 PM	2	1	0	0	0	2	0	0	0	1	0	0	0	1	7
Σ	4:00 PM	1	0	0	1	0	1	0	0	0	1	0	0	0	0	4
_	4:15 PM	0	0	0	0	0	0	0	0	0	1	0	0	0	0	1
	4:30 PM	0	1	0	0	0	0	0	0	0	0	0	0	0	0	1
	4:45 PM	2	2	0	0	0	0	0	0	0	0	0	0	0	0	4
	5:00 PM	0	0	0	0	0	1	0	0	0	0	0	0	0	0	1
	5:15 PM	0	3	0	0	0	0	0	0	0	0	0	0	0	0	3
	5:30 PM	2	0	0	0	0	1	0	0	0	0	0	0	0	0	3
	5:45 PM	1	0	0	0	0	0	0	0	0	1	0	0	0	0	2
	TOTAL PM	12	9	0	22	4	17	0	2	0	6	0	0	0	2	74
	,															

LOCATION: Irvine Rancho San Joaquin NORTH & SOUTH: Yale EAST & WEST: Michelson

PROJECT #: LOCATION #: CONTROL:

SC3579 1 STOP ALL

	7:00 AM	Ac EB	PE fult WB	DS Scho	ol Ane			CLIST			SCO	OTER		SKATE	BOARD	TOTAL
				Scho	nl Δαe	n										
		EB	270			В	ike	E-8	Bike	Sco	oter	Mobility A	Assistance	Sietiz	DOARD	TOTAL
			WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	
		0	1	1	0	0	0	0	0	0	0	0	0	0	0	2
	7:15 AM	0	0	0	0	0	0	0	1	0	0	0	0	0	0	1
	7:30 AM	2	0	0	0	0	1	0	0	0	0	0	0	0	0	3
	7:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	8:00 AM	0	0	9	0	2	0	0	0	0	0	0	0	0	0	11
	8:15 AM	0	0	7	0	5	12	0	0	0	0	0	0	0	0	24
	8:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	8:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	TOTAL AM	2	1	17	0	7	13	0	1	0	0	0	0	0	0	41
	02:00 PM	0	1	0	1	0	1	0	0	1	0	0	0	0	0	4
	2:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	2:30 PM	0	1	0	0	0	0	0	0	0	0	0	0	0	0	1
	2:45 PM	1	0	0	0	0	0	0	0	0	1	0	0	0	0	2
	3:00 PM	0	4	3	52	0	5	0	1	0	0	0	0	0	0	65
	3:15 PM	0	0	2	7	0	0	0	0	0	0	0	0	0	0	9
	3:30 PM	0	0	1	0	1	0	0	0	0	0	0	0	0	0	2
	3:45 PM	0	0	0	1	0	0	0	0	0	0	0	0	0	0	1
M.	4:00 PM	0	1	0	2	0	5	0	0	0	2	0	0	0	0	10
	4:15 PM	0	2	0	0	0	0	1	1	0	0	0	0	0	0	4
	4:30 PM	0	0	0	0	0	1	0	0	0	0	0	0	0	0	1
	4:45 PM	1	0	0	1	0	1	0	0	0	0	0	0	0	0	3
	5:00 PM	0	2	0	0	0	0	0	1	0	1	0	0	0	0	4
	5:15 PM	2	2	0	0	0	0	0	0	0	0	0	0	0	0	4
				0	0	0	2	0	0	0	0	0	0	0	0	2
	5:30 PM	0	0													
	5:30 PM 5:45 PM TOTAL PM	0 1 5	1	0	0	ő	0	Ō	0	Ö	0	0	0	0	0	2

									H SIDE							
			PE	DS			BYCI	CLIST			SCO	OTER		CVATE	BOARD	TOTAL
			dult		ol Age	В	ike		Bike		oter		Assistance	SKATE		IOIAL
		EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	
	7:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	7:15 AM	0	3	0	0	0	0	0	0	0	0	0	0	0	0	3
	7:30 AM	0	0	0	0	2	3	0	0	0	0	0	0	0	0	5
Σ	7:45 AM	0	0	1	0	1	2	0	0	0	0	0	0	0	0	4
⋖	8:00 AM	0	2	4	0	1	2	0	0	0	0	0	0	0	0	9
	8:15 AM	0	2	5	0	3	1	0	0	1	0	0	0	1	0	13
	8:30 AM	0	1	0	0	0	0	0	0	0	0	0	0	0	0	1
	8:45 AM	0	1	0	0	2	0	0	0	0	0	0	0	0	0	3
	TOTAL AM	0	9	10	0	9	8	0	0	1	0	0	0	1	0	38
				•		•	•	•		•			•	•	•	•
	02:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	2:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	2:30 PM	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1
	2:45 PM	1	0	0	0	0	0	0	0	0	0	0	0	0	0	1
	3:00 PM	1	0	3	18	3	2	0	0	0	2	0	0	0	1	30
	3:15 PM	0	0	1	0	2	0	0	0	0	0	0	0	0	0	3
	3:30 PM	2	1	0	0	0	0	0	0	0	0	0	0	0	0	3
	3:45 PM	1	1	0	0	0	2	0	0	0	1	0	0	0	0	5
Σ	4:00 PM	5	1	0	0	0	3	1	0	0	0	0	0	0	0	10
-	4:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	4:30 PM	0	1	0	0	3	0	0	0	0	0	0	0	0	0	4
	4:45 PM	2	0	2	0	1	0	0	0	0	0	0	0	0	0	5
	5:00 PM	1	2	0	0	1	0	0	0	1	0	0	0	0	0	5
	5:15 PM	0	2	0	0	0	0	0	0	0	0	0	0	0	0	2
	5:30 PM	0	0	0	0	0	0	1	0	0	0	0	0	0	0	1
	5:45 PM	2	4	1	0	0	0	0	0	0	0	0	0	0	0	7
	TOTAL PM	15	12	7	18	11	7	2	0	1	3	0	0	0	1	77

								EAST	SIDE							
			PE	:DS			BYCI	CLIST			SCO	OTER		CVATE	BOARD	TOTAL
		A	dult	Scho	ol Age	В	ike		3ike		oter	Mobility A	Assistance	SKATE	BUARD	IOIAL
		NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	
	7:00 AM	0	1	0	0	0	0	0	0	0	0	0	0	0	0	1
	7:15 AM	1	1	2	0	0	0	0	0	0	0	0	0	0	0	4
	7:30 AM	2	0	0	0	1	0	0	0	0	0	0	0	0	0	3
Σ	7:45 AM	9	0	2	0	4	0	0	0	0	0	0	0	0	0	15
⋖	8:00 AM	3	4	14	0	5	0	0	0	0	0	0	0	0	0	26
	8:15 AM	1	3	15	0	11	0	1	1	1	0	0	0	2	0	35
	8:30 AM	0	0	0	0	3	0	0	0	0	0	0	0	0	0	3
	8:45 AM	0	4	0	0	1	0	0	0	0	0	0	0	0	0	5
	TOTAL AM	16	13	33	0	25	0	1	1	1	0	0	0	2	0	92
				•	•	•	•	•		•			•	•	•	•
	02:00 PM	1	2	0	0	4	0	1	0	0	0	0	0	0	0	- 8
	2:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	2:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	2:45 PM	1	0	1	1	0	0	0	0	0	0	0	0	0	0	3
	3:00 PM	0	2	0	53	3	13	0	1	0	2	0	0	0	1	75
	3:15 PM	2	1	1	0	1	0	0	0	0	0	0	0	0	0	5
	3:30 PM	1	2	0	0	0	2	1	0	0	0	0	0	0	0	6
	3:45 PM	1	3	0	0	2	0	0	0	0	0	0	0	0	0	6
Σ	4:00 PM	1	2	0	2	0	2	0	0	1	0	0	0	0	0	8
	4:15 PM	1	1	0	0	0	1	1	0	0	0	0	0	0	0	4
	4:30 PM	5	1	0	0	5	0	0	0	0	0	0	0	0	0	11
	4:45 PM	1	2	0	0	0	3	0	0	0	0	0	0	0	0	6
	5:00 PM	1	0	0	0	2	3	0	0	1	0	0	0	0	0	7
	5:15 PM	2	1	0	0	1	0	0	0	0	0	0	0	0	0	4
	5:30 PM	0	1	0	0	0	0	1	0	0	0	0	0	0	0	2
	5:45 PM	0	1	0	0	1	0	0	0	1	0	0	0	0	0	3
	TOTAL PM	17	19	2	56	19	24	4	1	3	2	0	0	0	1	148

								WEST	T SIDE							
				DS				CLIST				OTER		CVATE	BOARD	TOTAL
			dult		ol Age		ike		Bike		ooter		Assistance	0.0		IOIAL
		NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	
	7:00 AM	0	2	1	0	0	0	0	0	0	0	0	0	0	0	3
	7:15 AM	0	0	0	0	0	1	0	0	0	0	0	0	0	0	1
	7:30 AM	0	0	0	1	0	2	0	0	0	0	0	0	0	0	3
Σ	7:45 AM	1	0	1	0	1	1	0	0	0	0	0	0	0	0	4
⋖	8:00 AM	0	0	5	0	0	0	0	0	0	0	0	0	0	0	5
	8:15 AM	0	0	7	0	2	13	1	0	0	0	0	0	0	0	23
	8:30 AM	1	1	0	0	0	1	0	0	0	0	0	0	0	0	3
	8:45 AM	0	3	0	0	0	2	0	0	0	1	0	0	0	0	6
	TOTAL AM	2	6	14	1	3	20	1	0	0	1	0	0	0	0	48
	02:00 PM	3	0	0	1	0	4	0	0	0	0	0	0	0	0	8
	2:15 PM	1	1	0	0	0	0	0	1	0	0	0	0	0	0	3
	2:30 PM	2	1	0	0	0	0	0	0	0	0	0	0	0	0	3
	2:45 PM	1	1	0	0	1	1	0	0	0	0	0	0	0	0	4
	3:00 PM	1	1	0	25	0	3	0	0	0	0	0	0	0	0	30
	3:15 PM	0	1	0	0	1	1	0	0	0	0	0	0	0	0	3
	3:30 PM	2	1	0	0	2	2	0	0	0	0	0	0	0	0	7
	3:45 PM	0	0	0	1	0	2	0	0	0	0	0	0	0	0	3
Σ	4:00 PM	0	2	0	2	0	1	0	0	0	0	0	0	0	0	5
-	4:15 PM	1	1	0	0	0	0	1	0	1	0	0	0	0	0	4
	4:30 PM	1	1	0	0	0	0	0	1	0	0	0	0	0	0	3
	4:45 PM	0	2	0	1	0	0	0	0	0	0	0	0	0	0	3
	5:00 PM	1	2	0	0	0	0	0	1	0	1	0	0	0	0	5
	5:15 PM	1	1	0	0	0	0	0	0	0	0	0	0	0	0	2
	5:30 PM	1	1	0	0	0	2	0	0	0	0	0	0	0	0	4
	5:45 PM	1	0	0	0	1	1	0	0	0	0	0	0	0	0	3
	TOTAL PM	16	16	0	30	5	17	1	3	1	1	0	0	0	0	90

Irvine Rancho San Joaquin Yale Royce PROJECT #: LOCATION #: CONTROL: SC3579 2 STOP E/W

							SIDE	NORT						
тот	DOADD	SKATE		OTER	SCO			LIST	BYCIO			DS	PEI	
101	DUARD	SKATE	Assistance	Mobility A	oter	Sco	like	E-8	ke	Bi	ol Age	Schoo	lult	Ac
	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB
2	0	0	0	0	0	0	0	0	0	0	0	0	1	1
0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
2	0	0	0	0	0	0	0	1	0	0	0	0	1	0
9	0	0	0	0	0	0	0	0	0	3	0	2	0	4
1	0	0	0	0	0	0	0	0	1	0	0	0	0	0
0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
1	0	0	0	0	0	0	0	0	0	0	0	0	0	1
15	0	0	0	0	0	0	0	1	1	3	0	2	2	6
									•					
1	0	0	0	0	0	0	0	0	0	0	0	0	1	0
0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
1	0	0	0	0	0	0	0	0	0	0	0	0	1	0
5	0	0	0	0	0	0	0	0	5	0	0	0	0	0
3	0	0	0	0	0	0	0	0	0	1	0	2	0	0
0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4	0	0	0	0	0	0	1	0	0	0	1	0	2	0
2	0	0	0	0	0	0	0	1	1	0	0	0	0	0
5	0	0	0	0	0	0	0	1	0	0	0	0	2	2
2	0	0	0	0	0	0	0	0	0	0	0	1	0	1
3	0	0	0	0	0	0	0	0	3	0	0	0	0	0
3	0	0	0	0	0	0	0	0	0	2	0	0	1	0
2	0	0	0	0	0	0	0	0	0	0	0	0	0	2
1	0	0	0	0	0	0	0	0	0	0	0	0	1	0
32	0	0	0	0	0	0	1	2	9	3	1	3	8	5

									H SIDE							
			PE	:DS			BYCI	CLIST			SCO	OTER		CVATE	BOARD	TOTAL
			lult		ol Age		ike		Bike		ooter		Assistance			TOTAL
		EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	
	7:00 AM	0	1	0	0	0	0	0	0	0	0	0	0	1	0	2
	7:15 AM	2	1	0	0	0	0	0	0	0	0	0	0	0	0	3
	7:30 AM	0	1	0	0	0	0	0	0	0	0	0	0	0	0	1
A	7:45 AM	1	0	0	0	1	0	0	0	0	0	0	0	0	0	2
⋖	8:00 AM	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1
	8:15 AM	1	1	0	0	0	2	0	0	0	0	0	0	0	0	4
	8:30 AM	1	1	0	0	0	0	0	0	0	0	0	0	0	0	2
	8:45 AM	1	1	0	0	0	0	0	0	0	0	0	0	0	0	2
	TOTAL AM	6	6	0	0	2	2	0	0	0	0	0	0	1	0	17
	02:00 PM	0	0	0	0	3	0	0	0	0	0	0	0	0	0	3
	2:15 PM	1	2	0	0	0	0	0	0	0	0	0	0	0	0	3
	2:30 PM	0	0	0	0	0	0	0	0	1	0	0	0	0	0	1
	2:45 PM	0	0	0	0	0	0	1	0	0	0	0	0	0	0	1
	3:00 PM	0	0	0	0	0	2	0	0	0	0	0	0	0	0	2
	3:15 PM	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1
	3:30 PM	0	0	0	0	0	2	0	1	0	0	0	0	0	0	3
_	3:45 PM	2	0	0	0	0	0	0	0	0	0	0	0	0	0	2
M	4:00 PM	0	2	0	0	0	0	1	0	0	0	0	0	0	0	3
	4:15 PM	1	2	0	0	0	0	0	0	0	0	0	0	0	0	3
	4:30 PM	1	1	0	1	2	0	0	0	0	0	0	0	0	0	5
	4:45 PM	1	1	0	0	1	0	0	0	0	0	0	0	0	0	3
	5:00 PM	2	0	0	0	1	0	0	0	0	0	0	0	0	0	3
	5:15 PM	1	0	0	0	0	0	0	0	0	0	0	0	0	0	1
	5:30 PM	0	0	0	0	0	1	0	0	0	0	0	0	0	0	1
	5:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	TOTAL PM	9	8	0	1	8	5	2	1	1	0	0	0	0	0	35

									SIDE							
			PE	DS			BYCI				SCO	OTER		CVATE	BOARD	TOTAL
			dult		ol Age		ike		Bike	Sco		Mobility A	Assistance			IOIAL
		NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	
	7:00 AM	1	1	0	0	0	0	0	0	0	0	0	0	1	0	3
	7:15 AM	1	1	0	0	0	0	0	0	0	0	0	0	0	0	2
	7:30 AM	0	1	0	0	2	0	0	0	0	0	0	0	0	0	3
¥	7:45 AM	1	1	0	0	1	0	0	1	0	0	0	0	0	0	4
⋖	8:00 AM	2	2	2	0	2	0	1	0	0	0	0	0	0	0	9
	8:15 AM	0	1	0	0	2	4	0	1	0	0	0	0	0	0	8
	8:30 AM	0	1	0	0	0	0	0	0	0	0	0	0	0	0	1
	8:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	TOTAL AM	5	8	2	0	7	4	1	2	0	0	0	0	1	0	30
	02:00 PM	1	0	0	0	8	0	0	0	0	0	0	0	0	0	9
	2:15 PM	0	1	0	0	1	0	0	0	0	0	0	0	0	0	2
	2:30 PM	0	0	0	0	0	0	0	0	1	0	0	0	0	0	1
	2:45 PM	1	2	0	0	0	0	1	0	0	0	0	0	0	0	4
	3:00 PM	1	0	0	1	0	4	0	1	0	0	0	0	0	0	7
	3:15 PM	1	0	0	0	0	0	0	0	0	0	0	0	0	0	1
	3:30 PM	0	0	0	0	1	0	2	1	0	0	0	0	0	0	4
	3:45 PM	0	2	0	0	1	0	0	0	0	0	0	0	0	0	3
Σ	4:00 PM	1	2	0	1	0	0	0	0	1	0	0	0	0	0	5
_	4:15 PM	2	1	0	0	0	0	1	0	0	0	0	0	0	0	4
	4:30 PM	0	0	0	0	3	0	0	0	0	0	0	0	0	0	3
	4:45 PM	0	1	0	0	5	0	0	0	0	0	0	0	0	0	6
	5:00 PM	1	1	0	0	0	0	0	0	0	0	0	0	0	0	2
	5:15 PM	2	1	0	0	1	0	0	0	0	0	0	0	0	0	4
	5:30 PM	0	1	0	0	0	0	0	0	0	0	0	0	0	0	1
	5:45 PM	1	0	0	0	1	0	0	0	0	0	0	0	0	0	2
	TOTAL PM	11	12	0	2	21	4	4	2	2	0	0	0	0	0	58

								WES	T SIDE							
			PE	EDS				CLIST			SCO	OTER		CVATI	BOARD	TOTAL
		Ac	dult	Scho	ol Age	E	like	E-	Bike	Sco	oter	Mobility .	Assistance	SKATI	DUARD	IOIAL
		NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	
	7:00 AM	0	1	0	0	0	0	0	0	0	0	0	0	0	0	1
	7:15 AM	1	1	0	0	0	0	0	0	0	0	0	0	0	0	2
	7:30 AM	0	0	0	0	0	1	0	0	0	0	0	0	0	0	1
Ę	7:45 AM	2	1	1	0	0	3	1	0	0	0	0	0	0	0	8
⋖	8:00 AM	0	0	3	0	6	1	1	0	0	0	0	0	0	0	11
	8:15 AM	2	1	1	0	3	22	0	0	0	0	0	0	0	0	29
	8:30 AM	1	1	0	0	0	0	0	0	0	0	0	0	0	0	2
	8:45 AM	0	0	0	0	0	2	0	0	0	0	0	0	0	0	2
	TOTAL AM	6	5	5	0	9	29	2	0	0	0	0	0	0	0	56
ı																
	02:00 PM	2	2	0	0	2	3	0	0	0	0	0	0	0	0	9
	2:15 PM	1	1	0	0	0	0	0	1	0	0	0	0	0	0	3
	2:30 PM	2	1	0	0	1	0	0	0	0	0	0	0	0	0	4
	2:45 PM	1	0	0	0	0	0	0	0	0	0	0	0	0	0	1
	3:00 PM	0	2	0	1	0	6	0	0	0	0	0	0	0	0	9
П	3:15 PM	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1
	3:30 PM	1	1	0	0	2	2	0	0	0	0	0	0	0	0	6
	3:45 PM	0	1	0	0	1	0	0	0	0	0	0	0	0	0	2
	4:00 PM	0	2	0	3	0	4	1	0	0	0	0	0	0	0	10
1	4:15 PM	1	0	0	0	1	1	0	0	0	0	0	0	0	0	3
п	4:30 PM	1	1	0	0	2	1	0	0	0	0	0	0	0	0	5
П	4:45 PM	1	1	0	0	0	0	0	0	0	0	0	0	0	0	2
П	5:00 PM	2	0	0	0	0	1	0	0	0	1	0	0	0	0	4
	5:15 PM	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1
	5:30 PM	1	0	0	0	0	0	0	0	0	0	0	0	0	0	1
L	5:45 PM	1	0	0	0	1	4	0	0	0	0	0	0	0	0	6
	TOTAL PM	14	12	0	4	12	22	1	1	0	1	0	0	0	0	67

DATE: Tue, Nov 15, 22

SC3579 2 STOP E/W

							NORT	H SIDE							
		DE .			1	D) (01		H SIDE		000	OTER		1		
		PE	DS			BYCI	CLIST			SCO	OTER		SKATE	BOARD	TOTAL
	Ac	lult	School	ol Age	Bi	ke	E-6	Bike	Sco	oter	Mobility /	Assistance			
	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	
7:00 AM	0	1	0	0	0	0	0	0	0	0	0	0	0	0	1
7:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
7:30 AM	2	0	0	0	2	0	0	0	0	0	0	0	0	0	4
7:45 AM	1	0	0	0	1	2	0	0	0	0	0	0	0	0	4
8:00 AM	0	0	0	0	5	1	1	0	1	0	0	0	0	0	8
8:15 AM	1	1	0	0	0	2	0	1	0	0	0	0	0	0	5
8:30 AM	0	0	0	0	0	1	0	0	0	0	0	0	0	0	1
8:45 AM	3	1	0	0	0	0	0	0	0	0	0	0	0	0	4
TOTAL AM	7	3	0	0	8	6	1	1	1	0	0	0	0	0	27
02:00 PM	0	3	0	1	0	0	1	0	0	0	0	0	0	0	5
2:15 PM	0	1	0	0	0	0	0	0	0	0	0	0	0	0	1
2:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
2:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3:00 PM	0	1	0	1	0	4	0	1	0	0	0	0	0	0	7
3:15 PM	0	0	0	0	0	0	0	0	0	1	0	0	0	0	1
3:30 PM	0	1	0	0	0	0	0	0	0	0	0	0	0	0	1
3:45 PM	0	0	0	0	1	1	0	0	0	0	0	0	0	0	2
4:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4:15 PM	5	0	0	0	0	0	0	0	0	0	0	0	0	0	5
4:30 PM	3	0	0	0	0	1	0	0	0	0	0	0	0	0	4
4:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
5:00 PM	2	0	0	0	1	0	0	0	0	0	0	0	0	0	3
5:15 PM	1	1	0	0	0	1	0	0	0	0	0	0	0	0	3
5:30 PM	0	0				0						0	0	0	0
5:45 PM	1	7	0	0	0	7	0	0	0	0	0	0	0	0	1
TOTAL PM	12	/	0	2	2	/	1	1	0	1	0	0	0	0	33

							SOUT	H SIDE							
		PE	DS			BYCI				SCO	OTER		OVATO	20122	
	Ac	dult	Scho	ol Age	Bi	ke	E-8	Bike	Sco	oter	Mobility /	Assistance	SKATE	BOARD	TOTAL
	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	1 .
7:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1
7:15 AM	0	0	1	0	0	0	0	0	0	0	0	0	0	0	1
7:30 AM	0	2	0	0	0	1	0	0	0	0	0	0	0	0	3
7:45 AM	0	0	0	0	0	1	0	0	0	0	0	0	0	0	1
8:00 AM	0	2	0	0	0	1	0	0	0	0	0	0	0	0	3
8:15 AM	1	1	0	0	0	2	0	1	0	0	0	0	0	0	5
8:30 AM	0	2	0	0	0	0	0	0	0	0	0	0	0	0	2
8:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
TOTAL AM	1	7	1	0	0	5	0	1	0	0	0	0	1	0	16
02:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
2:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
2:30 PM	1	1	0	0	0	0	0	0	0	0	0	0	0	0	2
2:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3:00 PM	0	0	0	0	0	1	0	0	0	0	0	0	0	0	1
3:15 PM	2	0	1	0	0	0	0	0	0	1	0	0	0	0	4
3:30 PM	0	0	0	0	0	1	0	0	0	0	0	0	0	0	1
3:45 PM	1	0	0	0	0	1	0	0	0	0	0	0	0	0	2
4:00 PM	1	0	0	0	0	0	0	0	0	1	0	0	0	0	2
4:15 PM	2	1	0	0	3	1	0	0	0	0	0	0	0	0	/
4:30 PM	1	1	0	0	0	0	0	0	0	0	0	0	0	0	2
4:45 PM	3	1	1	0	1	0	0	0	0	0	0	0	0	0	6
5:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
5:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
5:30 PM 5:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1
		_	-	-		_			_		_				0
TOTAL PM	11	4	2	0	5	4	0	0	0	2	0	0	0	0	28

							EAST	SIDE							
		PE	DS			BYCI	CLIST			SCO	OTER		CVATE	BOARD	TOTAL
	A	dult	Scho	ol Age	Bi	ke	E-8	Bike	Sco	oter	Mobility .	Assistance	SKATE	BUARD	IUIAL
	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	
7:00 AM	0	0	0	0	1	0	0	0	0	0	0	0	1	0	2
7:15 AM	0	0	1	0	3	0	0	0	0	0	0	0	0	0	4
7:30 AM	1	2	0	1	0	0	0	0	0	0	0	0	0	0	4
7:45 AM	0	1	0	0	1	0	0	0	0	0	0	0	0	0	2
8:00 AM	5	0	3	0	2	0	0	0	0	0	0	0	0	0	10
8:15 AM	1	3	0	0	0	0	2	0	0	0	0	0	0	0	6
8:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
8:45 AM	2	1	0	0	2	1	0	0	0	0	0	0	0	0	6
TOTAL AM	9	7	4	1	9	1	2	0	0	0	0	0	1	0	34
02:00 PM	0	0	0	0	1	0	1	0	0	0	0	0	0	0	2
2:15 PM	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1
2:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
2:45 PM	1	0	0	0	0	0	0	0	0	0	0	0	0	0	1
3:00 PM	0	0	0	1	0	2	1	3	0	0	0	0	0	0	7
3:15 PM	2	0	0	0	2	0	0	0	0	1	0	0	0	0	5
3:30 PM	0	1	0	0	0	0	0	0	0	0	0	0	0	0	1
3:45 PM	1	1	0	0	3	0	0	0	0	0	0	0	0	0	5
4:00 PM	1	0	0	0	1	0	0	0	0	0	0	0	0	0	2
4:15 PM	3	0	0	0	0	0	0	0	0	0	0	0	0	0	3
4:30 PM	0	1	0	0	1	0	0	0	0	0	0	0	0	0	2
4:45 PM	1	1	1	0	0	0	0	0	0	0	0	0	0	0	3
5:00 PM	1	0	0	0	1	0	0	0	0	2	0	0	0	0	4
5:15 PM	0	0	0	0	2	0	0	0	1	0	0	0	0	0	3
5:30 PM	1	0	0	0	1	0	0	0	0	0	0	0	0	0	2
5:45 PM	1	1	0	0	0	0	0	0	0	0	0	0	0	0	2
TOTAL PM	12	5	1	1	13	2	2	3	1	3	0	0	0	0	43

								T SIDE							
			DS				CLIST				OTER		CKATE	BOARD	TOTAL
		dult	Scho	ol Age	Bi	ike	E-8	Bike	Sco	oter	Mobility A	Assistance	SIGNIE		IOIAL
	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	
7:00 AM	0	1	0	0	0	0	0	0	0	0	0	0	0	0	1
7:15 AM	0	0	0	0	0	1	0	0	0	0	0	0	0	0	1
7:30 AM	3	1	0	0	0	0	0	0	0	0	0	0	0	0	4
7:45 AM	3	2	0	0	0	2	0	0	0	0	0	0	0	0	7
8:00 AM	2	1	0	0	9	5	1	0	1	0	0	0	0	0	19
8:15 AM	0	1	1	0	4	9	0	3	0	0	0	0	0	0	18
8:30 AM	0	0	0	0	0	3	0	0	0	0	0	0	0	0	3
8:45 AM	3	0	0	0	0	3	1	0	0	0	0	0	0	0	7
TOTAL AM	11	6	1	0	13	23	2	3	1	0	0	0	0	0	60
02:00 PM	0	0	0	0	2	0	2	0	0	0	0	0	0	0	4
2:15 PM	1	0	0	0	2	1	0	1	0	0	0	0	0	0	5
2:30 PM	1	2	0	0	0	0	0	0	0	0	0	0	0	0	3
2:45 PM	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1
3:00 PM	0	2	0	5	0	8	0	2	0	2	0	0	0	0	19
3:15 PM	0	1	0	2	0	4	0	0	0	1	0	0	0	0	8
3:30 PM	1	2	0	0	1	0	1	0	0	0	0	0	0	0	5
3:45 PM	2	3	0	0	1	1	0	0	0	1	0	0	0	0	8
4:00 PM	1	1	0	1	2	5	0	0	0	1	0	0	0	0	11
4:15 PM	1	0	0	1	2	2	0	0	0	1	0	0	0	0	7
4:30 PM	0	0	0	0	0	1	0	0	0	0	0	0	0	0	1
4:45 PM	0	2	0	0	1	0	0	1	0	0	0	0	0	0	4
5:00 PM	3	0	0	0	1	1	0	0	0	0	0	0	0	0	5
5:15 PM	0	1	0	0	0	0	0	0	0	0	0	0	0	0	1
5:30 PM	5	1	0	0	0	0	0	0	0	0	0	0	0	0	6
5:45 PM	2	0	0	0	0	0	0	0	0	0	0	0	0	0	2
TOTAL PM	17	15	0	9	13	23	3	4	0	6	0	0	0	0	90

LOCATION: Irvine Rancho San Joaquin NORTH & SOUTH: Yale EAST & WEST: University

PROJECT #: LOCATION #: CONTROL:

									H SIDE	,						
			P	EDS			BYC	ICLIST			SCO	OTER		SKATI	BOARD	TOTA
			Adult		ool Age		Bike		Bike		ooter		Assistance			
		EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	
I	7:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
I	7:15 AM	0	0	0	0	2	1	0	0	0	0	0	0	0	0	3
I	7:30 AM	0	0	0	0	0	0	0	1	0	0	0	0	0	0	1
I	7:45 AM	0	0	0	0	1	3	0	0	0	0	0	0	0	0	4
I	8:00 AM	4	1	2	0	2	3	0	0	0	0	0	0	0	0	12
I	8:15 AM	0	3	0	0	0	4	0	0	0	0	0	0	0	0	7
ı	8:30 AM	0	0	0	0	1	0	0	0	1	0	0	0	0	0	2
I	8:45 AM	0	0	0	0	2	0	0	0	0	0	0	0	0	0	2
l	TOTAL AM	4	4	2	0	8	11	0	1	1	0	0	0	0	0	31
Į																
l	02:00 PM	1	0	0	0	9	0	1	0	0	1	0	0	0	0	12
l	2:15 PM	0	1	0	0	2	0	0	0	0	0	0	0	0	0	3
l	2:30 PM	1	0	0	0	2	1	0	0	0	0	0	0	0	0	4
l	2:45 PM	0	1	0	0	0	1	0	0	1	0	0	0	0	0	3
l	3:00 PM	0	0	0	0	0	0	0	0	1	1	0	0	0	0	2
l	3:15 PM	0	0	0	0	2	2	0	0	0	0	0	0	0	0	4
ı	3:30 PM	0	2	0	0	1	0	0	0	1	0	0	0	0	0	4
ı	3:45 PM	1	0	0	0	7	1	0	0	2	0	0	0	0	0	11
I	4:00 PM	0	0	0	0	0	2	0	0	0	0	0	0	0	0	2
ı	4:15 PM	1	0	0	0	0	0	0	0	0	0	0	0	1	0	2
ı	4:30 PM	0	0	0	0	2	0	0	2	0	0	0	0	0	0	4
ĺ	4:45 PM	0	1	0	0	0	1	0	0	0	0	0	0	0	0	2
ĺ	5:00 PM	0	0	0	0	1	1	1	1	1	0	0	0	0	0	5
ı	5:15 PM	0	0	0	0	2	0	0	1	1	0	0	0	0	0	4
İ	5:30 PM	1	0	0	0	0	0	0	0	0	0	0	0	0	0	1
ı	5:45 PM	1	1	0	0	0	0	0	0	0	0	0	0	0	0	2
ı	TOTAL PM	6	6	0	0	28	9	2	4	7	2	0	0	1	0	65

									1 SIDE							
			PE	DS			BYCI	CLIST			SCO	OTER		CVATE	BOARD	TOTAL
			dult		ol Age	В	ike		Bike		oter		Assistance	SKATE		TOTAL
		EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	
	7:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	7:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	7:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Σ	7:45 AM	0	0	0	0	0	0	1	0	0	0	0	0	0	0	1
⋖	8:00 AM	0	0	0	0	2	0	0	0	0	0	0	0	0	0	2
	8:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	8:30 AM	0	0	0	0	1	1	0	0	0	0	0	0	0	0	2
	8:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	TOTAL AM	0	0	0	0	3	1	1	0	0	0	0	0	0	0	5
				•	•	•	•			•			•	•	•	•
	02:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	2:15 PM	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1
	2:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	2:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	3:00 PM	0	0	0	0	2	0	0	0	0	0	0	0	0	0	2
	3:15 PM	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1
	3:30 PM	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1
	3:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Σ	4:00 PM	1	1	0	1	2	0	0	0	0	0	0	0	0	0	5
-	4:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	4:30 PM	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1
	4:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	5:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	5:15 PM	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1
	5:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	5:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	TOTAL PM	1	1	0	1	9	0	0	0	0	0	0	0	0	0	12

								EAST	SIDE							
			PE	DS			BYCI				SCO	OTER		CVATE	BOARD	TOTAL
			dult	Scho	ol Age		ike		Bike		oter		Assistance	SKATE	-	IOIAL
		NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	
	7:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	7:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	7:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
:	7:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
₹	8:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	8:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	8:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	8:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	TOTAL AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	02:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	2:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	2:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	2:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	3:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	3:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	3:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	3:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Σ	4:00 PM	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1
-	4:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	4:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	4:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	5:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	5:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	5:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	5:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	TOTAL PM	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1

								WEST	SIDE							
				DS			BYCI					OTER		SKATE	BOARD	TOTAL
			dult		ol Age		ike		Bike		ooter		Assistance			IOIAL
_		NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	
	7:00 AM	1	0	1	0	1	3	0	0	0	0	0	0	0	0	6
	7:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	7:30 AM	1	0	0	0	0	0	0	0	0	0	0	0	0	0	1
Σ	7:45 AM	0	2	0	1	2	6	0	0	0	0	0	0	0	0	11
⋖	8:00 AM	5	1	4	0	10	7	0	1	0	0	0	0	0	0	28
	8:15 AM	2	4	0	1	5	13	0	3	0	0	0	0	0	0	28
	8:30 AM	1	1	0	0	0	3	0	0	0	1	0	0	0	0	6
	8:45 AM	2	0	0	0	1	1	0	1	0	0	0	0	0	0	5
	TOTAL AM	12	8	5	2	19	33	0	5	0	1	0	0	0	0	85
	02:00 PM	1	1	0	0	10	0	3	0	0	0	0	0	0	0	15
	2:15 PM	2	1	0	0	3	1	0	1	0	0	0	0	0	0	8
	2:30 PM	0	0	0	0	2	0	0	0	0	0	0	0	0	0	2
	2:45 PM	1	0	0	0	3	0	0	0	1	0	0	0	0	0	5
	3:00 PM	0	5	0	0	1	9	0	0	0	1	0	0	0	0	16
	3:15 PM	0	0	0	0	2	4	0	0	0	1	0	0	0	0	7
	3:30 PM	0	1	0	0	1	0	1	0	1	0	0	0	0	0	4
	3:45 PM	2	1	0	0	6	2	0	0	1	2	0	0	0	0	14
Ξ	4:00 PM	1	0	1	0	3	5	0	0	0	1	0	0	0	0	11
_	4:15 PM	1	2	0	1	2	1	0	0	0	1	0	0	1	0	9
	4:30 PM	0	0	0	0	2	1	0	0	0	0	0	0	0	0	3
	4:45 PM	1	2	0	0	1	0	0	0	0	0	0	0	0	0	4
	5:00 PM	2	0	1	0	1	0	2	0	1	0	0	0	0	0	7
	5:15 PM	0	1	0	0	2	1	0	0	1	0	0	0	0	0	5
	5:30 PM	4	0	0	0	1	0	0	0	0	0	0	0	0	0	5
	5:45 PM	1	0	0	0	1	0	0	0	0	0	0	0	0	0	2
	TOTAL PM	16	14	2	1	41	24	6	1	5	6	0	0	1	0	117

LOCATION: Irvine Rancho San Joaquin NORTH & SOUTH: Yale EAST & WEST: University

PROJECT #: LOCATION #: CONTROL:

								NORT	H SIDE							
			PE	DS			BYCI	CLIST			SCO	OTER		SKATE	BOARD	тота
		A	dult	Scho	ol Age	В	like	E-I	3ike	Sco	ooter	Mobility	Assistance	Siotit		10
		EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	
Г	7:00 AM	0	0	0	0	0	1	0	0	0	0	0	0	0	0	1
Г	7:15 AM	1	0	0	0	0	0	0	0	0	0	0	0	0	0	1
Г	7:30 AM	0	0	0	0	1	0	0	2	0	1	0	0	0	0	4
Г	7:45 AM	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1
Г	8:00 AM	1	0	1	0	0	3	2	0	0	0	0	0	0	0	7
Г	8:15 AM	0	0	0	0	0	0	0	0	0	1	0	0	0	0	1
Г	8:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Г	8:45 AM	0	0	0	0	0	4	0	0	0	0	0	0	0	0	4
Г	TOTAL AM	2	0	1	0	2	8	2	2	0	2	0	0	0	0	19
Г				•	•	•		•	•	•				•		
Т	02:00 PM	0	0	0	0	6	0	1	1	0	0	0	0	0	0	8
Г	2:15 PM	0	0	1	0	1	0	0	0	0	0	0	0	0	0	2
Г	2:30 PM	0	3	0	0	2	0	0	0	0	0	0	0	0	0	5
Г	2:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Г	3:00 PM	1	0	0	0	0	1	0	0	0	0	0	0	0	0	2
	3:15 PM	0	0	0	0	1	1	0	1	0	0	0	0	0	0	3
Г	3:30 PM	1	0	0	0	1	0	1	1	0	0	0	0	0	0	4
Г	3:45 PM	3	0	0	0	3	0	0	0	1	0	0	0	0	0	7
	4:00 PM	0	0	1	0	0	0	0	0	1	0	0	0	0	0	2
	4:15 PM	0	1	0	0	0	0	0	0	0	0	0	0	0	0	1
Г	4:30 PM	1	0	0	0	2	1	0	0	0	0	0	0	0	0	4
Г	4:45 PM	0	1	0	0	5	0	0	0	1	0	0	0	0	0	7
	5:00 PM	0	0	0	0	2	0	0	0	1	0	0	0	0	0	3
Г	5:15 PM	1	0	0	0	2	0	0	0	0	0	0	0	0	0	3
Г	5:30 PM	1	0	0	0	0	1	0	0	0	0	0	0	0	0	2
Г	5:45 PM	Ö	Ö	Õ	Ö	Õ	1	Ö	Ö	Õ	Ö	Ö	Ö	Õ	Ö	1
	TOTAL PM	8	5	2	0	25	5	2	3	4	0	0	0	0	0	54

									1 SIDE							
			PE	DS			BYCI	CLIST			SCO	OTER		CVATE	BOARD	TOTAL
			dult		ol Age		ike		Bike		oter		Assistance			IOIAL
		EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	
	7:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	7:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	7:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Σ	7:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
⋖	8:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	8:15 AM	0	0	0	0	0	0	1	0	0	0	0	0	0	0	1
	8:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	8:45 AM	0	0	0	0	0	0	1	0	0	0	0	0	0	0	1
	TOTAL AM	0	0	0	0	0	0	2	0	0	0	0	0	0	0	2
				•		•	•			•	•	•	•	•	•	
	02:00 PM	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1
	2:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	2:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1
	2:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	3:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	3:15 PM	0	0	0	0	0	0	1	0	0	0	0	0	0	0	1
	3:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	3:45 PM	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1
Σ	4:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	4:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	4:30 PM	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1
	4:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	5:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	5:15 PM	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1
	5:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	5:45 PM	0	0	0	0	0	0	0	0	1	0	0	0	0	0	1
	TOTAL PM	0	0	0	0	4	0	1	0	1	0	0	0	1	0	7

								EAST	SIDE							
			PE	DS			BYCI				SCO	OTER		CVATE	BOARD	TOTAL
			dult	Scho	ol Age		ike		Bike		oter		Assistance	SKATE		IOIAL
		NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	
	7:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	7:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	7:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Σ	7:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
₹	8:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	8:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	8:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	8:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	TOTAL AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
				•		•	•	•		•	•			•	•	•
	02:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	2:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	2:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1
	2:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	3:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	3:15 PM	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1
	3:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	3:45 PM	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1
Σ	4:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
_	4:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	4:30 PM	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1
	4:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	5:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	5:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	5:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	5:45 PM	0	0	0	0	0	0	0	0	1	0	0	0	0	0	1
	TOTAL PM	0	0	0	0	3	0	0	0	1	0	0	0	1	0	5

								WES1	SIDE							
				DS				CLIST				OTER		SKATE	BOARD	TOTAL
			dult		ol Age		ke		Bike		oter		Assistance		-	IOIAL
		NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	
	7:00 AM	0	1	0	0	0	0	0	0	0	0	0	0	0	0	1
	7:15 AM	4	2	0	0	0	0	0	0	0	0	0	0	0	0	6
	7:30 AM	1	0	0	0	1	0	0	1	0	0	0	0	0	0	3
ξ	7:45 AM	2	1	2	0	1	3	0	1	0	0	0	0	0	0	10
۹	8:00 AM	6	0	4	0	9	8	0	1	0	0	0	0	0	0	28
	8:15 AM	0	2	0	1	3	9	0	1	0	1	0	0	0	0	17
	8:30 AM	1	2	0	1	0	1	0	0	0	0	0	0	0	0	5
	8:45 AM	0	1	0	0	0	2	0	0	0	0	0	0	0	0	3
	TOTAL AM	14	9	6	2	14	23	0	4	0	1	0	0	0	0	73
	02:00 PM	0	0	0	0	13	3	1	0	0	0	0	0	0	0	17
	2:15 PM	1	1	1	0	1	0	2	1	0	0	0	0	0	0	7
	2:30 PM	0	1	1	0	2	0	1	0	0	0	0	0	0	0	5
	2:45 PM	1	2	1	0	2	0	1	0	1	0	0	0	0	0	8
	3:00 PM	0	1	0	3	0	7	0	0	0	0	0	0	0	0	11
	3:15 PM	0	0	0	0	3	0	0	0	0	0	0	0	0	0	3
	3:30 PM	1	1	0	0	3	1	1	0	0	0	0	0	0	0	7
	3:45 PM	2	0	0	0	7	0	0	1	1	0	0	0	0	0	11
Ξ	4:00 PM	0	2	1	3	0	4	2	0	1	0	0	0	0	0	13
-	4:15 PM	0	1	0	0	1	1	0	0	0	0	0	0	0	0	3
	4:30 PM	0	0	0	0	6	0	0	1	0	0	0	0	0	0	7
	4:45 PM	0	1	0	0	5	0	0	0	1	0	0	0	0	0	7
	5:00 PM	1	1	0	1	3	1	0	0	0	0	0	0	0	0	7
	5:15 PM	2	0	0	0	1	0	0	0	0	0	0	0	0	0	3
	5:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	5:45 PM	0	0	0	0	1	1	0	0	0	0	0	0	0	0	2
	TOTAL PM	8	11	4	7	48	18	8	3	4	0	0	0	0	0	111

PREPARED BY: AimTD LLC. tel: 714 253 7888 cs@aimtd.com

<u>DATE:</u> Tue, Nov 15, 22 LOCATION: Irvine Rancho San Joaquin PROJECT #: SC3579

NORTH & SOUTH: Yale LOCATION #: 4

EAST & WEST: CONTROL: NO CONTROL

	7:00 AM
	7:15 AM
	7:30 AM
	7:45 AM
	8:00 AM
	8:15 AM
	8:30 AM
	8:45 AM
S	TOTAL
NT	
OU	2:00 PM
, C	2:15 PM
IΓΥ	2:30 PM
IAI	2:45 PM
[O	3:00 PM
DIRECTIONALLY COUNTS	3:15 PM
RE	3:30 PM
DI	3:45 PM
	4:00 PM
	4:15 PM
	4:30 PM
	4:45 PM
	5:00 PM
	5:15 PM
	5:30 PM
	5:45 PM TOTAL
	IUIAL

PE	DS	В	IKES	TOTAL
EB	WB	EB WB		
0	0	0	0	0
0	1	0	0	1
1	0	0	0	1
1	1	0	0	2
0	0	0	0	0
1	0	0	0	1
1	2	0	0	3
0	2	0	0	2
4	6	0	0	10
0	0	0	0	0
0	0	0	0	0
0	0	0	0	0
0	0	0	0	0
0	3	0	0	3
1	1	0	0	2
1	1	0	0	2
1	0	0	0	1
1	4	0	0	5
3	0	0	0	3
0	3	0	0	3
1	4	0	1	6
3	0	0	0	3
1	0	0	0	1
3	0	0	0	3
1	0	0	0	1
16	16	0	1	33

PREPARED BY: AimTD LLC. tel: 714 253 7888 cs@aimtd.com

DATE: Wed, Nov 16, 22 LOCATION: Irvine Rancho San Joaquin PROJECT #: SC3579

NORTH & SOUTH: Yale LOCATION #: 4 EAST & WEST:

CONTROL: NO CONTROL

	7:00 AM
	7:15 AM
	7:30 AM
	7:45 AM
	8:00 AM
	8:15 AM
	8:30 AM
	8:45 AM
S	TOTAL
Ë	
	2:00 PM
Ö	2:15 PM
Ϊ	2:30 PM
A	2:45 PM
Ö	3:00 PM
5	3:15 PM
DIRECTIONALLY COUNTS	3:30 PM
DI	3:45 PM
	4:00 PM
	4:15 PM
	4:30 PM
	4:45 PM
	5:00 PM
	5:15 PM
	5:30 PM
	5:45 PM
	TOTAL

PI	EDS	В	IKES	TOTAL
EB	WB	EB	WB	
3	0	0	0	3
0	1	0	0	1
1	1	0	0	2
0	0	0	0	0
0	0	0	0	0
0	0	0	0	0
4	1	0	0	5
0	2	0	0	2
8	5	0	0	13
0	1	1	0	2
1	0	0	0	1
0	0	0	0	0
0	1	0	0	1
0	0	0	0	0
0	0	0	0	0
1	0	0	0	1
0	2	0	0	2
0	0	0	0	0
2	2	0	0	4
0	2	0	0	2
1	0	0	0	1
0	1	0	0	1
2	0	0	0	2
2	1	0	0	3
0	1	0	0	1
9	11	1	0	21

<u>DATE:</u> Tue, Nov 15, 22

LOCATION: NORTH & SOUTH: EAST & WEST:

Irvine Rancho San Joaquin Yale

PROJECT #: SC3474 LOCATION #: 1 CONTROL: NO CONTROL

			PE	DS		BIKES			SK	ATEBOARD	S/SCOOTE	RS		
		AD	ULT	SCHO	OL AGE	ADI	ULT	SCHO	OL AGE	AD	ULT	SCHOO	OL AGE	TOTAL
		NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	
	7:00 AM	1	1	0	0	1	0	1	0	0	0	0	0	4
	7:15 AM	1	1	0	0	2	3	0	0	0	0	0	0	7
	7:30 AM	1	2	0	0	1	0	0	0	0	0	0	0	4
	7:45 AM	4	2	0	0	2	2	0	1	0	0	0	0	11
	8:00 AM	3	1	0	4	1	0	0	0	0	0	0	0	9
	8:15 AM	1	3	0	1	1	4	0	2	0	0	0	0	12
	8:30 AM	1	0	0	0	1	2	0	0	0	0	0	0	4
	8:45 AM	0	2	0	0	2	5	0	0	0	0	0	0	9
2	TOTAL	12	12	0	5	11	16	1	3	0	0	0	0	60
Ę														
OUN	2:00 PM	1	0	0	0	2	3	0	0	0	0	0	0	6
Ö	2:15 PM	3	0	0	0	2	3	0	0	0	0	0	0	8
Ė	2:30 PM	2	0	0	0	2	0	0	0	0	0	0	0	4
II	2:45 PM	0	0	0	0	1	2	0	0	0	1	0	0	4
CTIONA	3:00 PM	1	1	1	0	0	5	2	0	0	0	1	1	12
16	3:15 PM	2	1	3	0	2	2	0	0	0	0	0	0	10
ä	3:30 PM	0	0	0	0	0	1	0	0	0	0	0	0	1
DIRE	3:45 PM	2	4	2	1	2	2	0	0	0	2	0	0	15
	4:00 PM	0	1	2	0	0	1	2	0	0	0	0	0	6
	4:15 PM	3	3	0	0	0	1	0	0	1	0	0	0	8
	4:30 PM	1	2	1	1	1	0	0	0	0	0	0	0	6
	4:45 PM	1	5	0	0	0	0	0	1	0	0	0	0	7
	5:00 PM	1	0	0	0	1	3	0	0	0	0	0	0	5
	5:15 PM	2	1	0	0	3	0	0	0	0	0	0	0	6
	5:30 PM	1	2	0	0	1	0	0	0	0	0	0	0	4
	5:45 PM	0	3	0	0	0	1	0	0	0	0	0	0	4
	TOTAL	20	23	9	2	17	24	4	1	1	3	1	1	106

<u>DATE:</u> Wed, Nov 16, 22

LOCATION: NORTH & SOUTH: EAST & WEST:

Irvine Rancho San Joaquin Yale PROJECT #: SC3474 LOCATION #: 405 CONTROL: NO CONTROL

			PE	DS			В	IKES		SI	KATEBOAR	DS/SCOOTI	ERS		l
		AD	ULT	SCHO	OL AGE	AD	ULT	SCHO	OOL AGE	AD	DULT	SCHO	OL AGE	TOTAL	
		NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB		1
	7:00 AM	1	4	0	0	1	0	0	0	0	0	0	0	6]
	7:15 AM	0	0	0	0	0	1	0	0	0	0	0	0	1	
	7:30 AM	2	1	0	0	1	3	0	0	0	0	0	0	7	
	7:45 AM	8	0	0	0	5	1	0	2	0	0	0	0	16	
	8:00 AM	3	4	0	2	0	1	0	0	0	0	0	0	10	
	8:15 AM	1	3	0	0	0	2	0	1	0	0	0	0	7	
	8:30 AM	1	0	1	0	1	1	0	0	0	0	0	0	4	
	8:45 AM	0	4	0	0	2	1	0	0	0	1	0	0	8	1
ro.	TOTAL	16	16	1	2	10	10	0	3	0	1	0	0	59	I
COUNTS															
ᅙ	2:00 PM	1	4	0	0	4	2	1	0	0	0	0	0		SB - el powered wheelchair (1)
	2:15 PM	0	0	0	0	0	0	0	1	0	0	0	0	1	
Ξ	2:30 PM	0	0	0	0	1	0	0	1	0	0	0	0	2	
₹	2:45 PM	0	1	0	0	1	1	0	0	0	0	0	0	3	
ő	3:00 PM	0	0	2	0	3	0	2	1	0	1	0	1	10	
8	3:15 PM	3	1	1	0	1	1	0	0	0	0	0	0	7	
W.	3:30 PM	2	0	0	0	3	2	1	2	0	0	0	0	10	
DIRECTIONALLY	3:45 PM	2	1	0	1	3	2	0	0	1	0	0	0	10	
	4:00 PM	1	6	0	1	0	0	2	0	0	0	0	0	10	
	4:15 PM	3	1	0	0	2	0	0	0	1	0	0	0	7	1
	4:30 PM	5	6	0	0	2	1	1	0	0	0	0	0	15	1
	4:45 PM	0	5	0	1	4	2	0	0	0	1	0	0	13	1
	5:00 PM	1	0	1	0	0	1	0	0	0	0	0	0	3	1
	5:15 PM	2	0	0	0	1	1	0	0	0	0	0	0	4	1
	5:30 PM	1	1	0	0	4	1	0	0	0	0	0	0	7	
	5:45 PM	0	1	0	0	1	1	0	0	1	1	0	0	5	ļ
	TOTAL	21	27	4	3	30	15	7	5	3	3	0	1	119	1

<u>DATE:</u> Tue, Nov 15, 22

LOCATION: NORTH & SOUTH: EAST & WEST:

Irvine Rancho San Joaquin Yale

PROJECT #: SC3474 LOCATION #: 1 CONTROL: NO CONTROL

			PE	DS			В	IKES		Sł	(ATEBOARI	S/SCOOTE	RS	
		AD	ULT	SCHO	OL AGE	ADI	ULT	SCHO	OOL AGE	AD	ULT	SCHO	OL AGE	TOTAL
		NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	
	7:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0
	7:15 AM	1	0	0	0	0	0	0	0	0	0	0	0	1
	7:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0
	7:45 AM	2	0	0	0	0	0	0	1	0	0	0	0	3
	8:00 AM	0	1	0	4	0	0	0	0	0	0	0	0	5
	8:15 AM	0	1	0	1	0	0	0	2	0	0	0	0	4
	8:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0
	8:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0
S	TOTAL	3	2	0	5	0	0	0	3	0	0	0	0	13
NOO.	2:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0
Ö	2:15 PM	1	0	0	0	0	0	0	0	0	0	0	0	1
NALLY	2:30 PM	1	0	0	0	0	0	0	0	0	0	0	0	1
I	2:45 PM	0	0	0	0	0	0	0	0	0	1	0	0	1
á	3:00 PM	0	0	1	0	0	0	2	0	0	0	0	0	3
15	3:15 PM	0	0	3	0	0	1	0	0	0	0	0	0	4
2	3:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0
둼	3:45 PM	0	0	2	1	0	0	0	0	0	0	0	0	3
	4:00 PM	0	1	2	0	0	0	2	0	0	0	0	0	5
	4:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0
	4:30 PM	0	0	1	0	0	0	0	0	0	0	0	0	1
	4:45 PM	0	1	0	0	0	0	0	1	0	0	0	0	2
	5:00 PM	0	0	0	0	0	1	0	0	0	0	0	0	1
	5:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0
	5:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0
	5:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0
	TOTAL	2	2	9	1	0	2	4	1	0	1	0	0	22

<u>DATE:</u> Wed, Nov 16, 22

LOCATION: NORTH & SOUTH: EAST & WEST:

Irvine Rancho San Joaquin Yale

PROJECT #: SC3474 LOCATION #: 405 CONTROL: NO CONTROL

			PE	DS			В	IKES		Sł	(ATEBOARI	S/SCOOTE	RS	
		AD	ULT	SCHO	OL AGE	ADI	ULT	SCHO	OOL AGE	AD	ULT	SCHO	OL AGE	TOTAL
		NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	NB	SB	
	7:00 AM	1	1	0	0	0	0	0	0	0	0	0	0	2
	7:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0
	7:30 AM	1	1	0	0	0	0	0	0	0	0	0	0	2
	7:45 AM	0	0	0	0	0	0	0	2	0	0	0	0	2
	8:00 AM	0	0	0	2	0	1	0	0	0	0	0	0	3
	8:15 AM	1	1	0	0	0	0	0	1	0	0	0	0	3
	8:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0
	8:45 AM	0	0	0	0	1	0	0	0	0	0	0	0	1
S	TOTAL	3	3	0	2	1	1	0	3	0	0	0	0	13
OUN	2:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0
O	2:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0
NALLY	2:30 PM	0	0	0	0	1	0	0	1	0	0	0	0	2
록	2:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0
6	3:00 PM	0	0	2	0	0	0	2	0	0	0	0	0	4
E .	3:15 PM	0	0	1	0	0	0	0	0	0	0	0	0	1
W.	3:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0
둼	3:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0
	4:00 PM	0	2	0	0	0	0	2	0	0	0	0	0	4
	4:15 PM	2	1	0	0	0	0	0	0	0	0	0	0	3
	4:30 PM	0	3	0	0	0	0	0	0	0	0	0	0	3
	4:45 PM	0	2	0	0	1	0	0	0	0	0	0	0	3
	5:00 PM	1	0	1	0	0	0	0	0	0	0	0	0	2
	5:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0
	5:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0
	5:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0
	TOTAL	3	8	4	0	2	0	4	1	0	0	0	0	22

APPENDIX B- ICU Calculation Sheets

273 Yal	e Av. @ M	lichel	son Dr		
Existing Ln	А		Hour V/C	PM PK Vol	Hour V/C
	1700 5	3 0. 66 0. 33 0.	03*	14 1 57	0.01*
-	1700 2 1700 3 1700 5	7 0.		2 0 3	*
	1700 6 1700 13 1700 2	5 0.	04* 08 01	2 284 7	0.17*
WT 1		3 0.	05 11* 01	13 204 1	0.01* 0.12
Adjustmen Overlaps	nt		Clea	NB rance	
Tota	al ICU	0.	24		0.25

275 Yale	e Av. @ Uni	versity 1	Dr.	
Existing		PK Hour	DM DV	Hour
Ln	Cap Vol			
NL 0 NT 0 NR 0	0 0 0	*	0 0 0	*
SL 1 ST 0	1700 76	0.04*	13	0.01*
	1700 104	0.06	21	0.01
	1700 81 3400 769 0			
	0 3400 1319 1700 35			
Overlaps		Clea	arance	.05
Tota	al ICU	0.53		0.48

ITAM page 1

273 Yale	e Av. @ 1	Miche	lson Dr	•	
Existing Ln	-7	AM PK	l Hour V/C		K Hour V/C
NT 1	1700	56 0	.01 .03* .02		
ST 1	1700 1700 1700	37 0	.01* .02 .03	24 21 29	
ET 1		35 0	.04* .08	27 168 20	
WT 1		93 0	.11*	46 166 16	0.10
Overlaps			Clea	rance	.05
Tota	al ICU	0	.24		0.20

275 Yale	e Av. @ Uni	versity Dr.	
		ool PK Hour PM F V/C Vol	
NL 0 NT 0 NR 0	0 0 0	* 0 0 0	*
ST 0	1700 76 0 1700 104	0.04* 38 0 0.06 72	0.02*
1		0.05* 75 0.23 689 0	
	0 3400 1319 1700 35	0.39* 709 0.02 32	0.21* 0.02
Overlaps		Clearand	ce .05
Tota	al ICU	0.53	0.32

273 Yale	a Av. @	Mich	elson D	r.	
BO I-405 Ln		AM :	ne S Yai PK Hour V/C	PM P	K Hour
NT 2		236	0.02 0.07* 0.02		0.07*
ST 2		375	0.11* 0.11 0.11	117	0.04
ET 1		33	0.13* 0.02 0.04		0.03
WT 1	1700	37	0.04 0.02* 0.15	33	0.02*
Adjustmen Overlaps	nt	WBR		aranc	e .05
Tota	al ICU		0.43		0.46

275 Yale	e Av. @ Uni	versity Dr.	•
	Veh OC 4-L AM C Cap Vol	PK Hour PN	1 PK Hour
NL 0 NT 0 NR 0	0 0 0	*	0 0 * 0
ST 0	1700 191 0 1700 332		0
	1700 239 3400 843 0		
	0 3400 1305 1700 73		
Overlaps		Cleara	ance .05
Tota	al ICU	0.68	0.56

273 Yale	Av. 0	Mich	elson D	r.	
BO I-405 Ln	Veh OC Cap	AM I	ne S Yai PK Hour V/C	PM P	K Hour
NT 1			0.14*		0.14*
ST 1		346	0.12* 0.20 0.12	103	0.06
ET 1		33	0.14* 0.02 0.03		0.03
	1700 1700 1700	34	0.02*	14 29 173	0.02*
Adjustmen Overlaps	nt	WBR		aranc	e .05
Tota	al ICU		0.51		0.54

275 Yale	e Av. @ Uni	versity Dr.	
	AM	ane S Yale PK Hour PM 1 V/C Voi	PK Hour
NL 0 NT 0 NR 0	0 0 0	* 0	*
ST 0	0	0.10* 19 0 0.18 140	
		0.14* 341 0.25 1481 0	
		0.39* 1022 0.04 35	
Overlaps		Clearan	ce .05
Tota	al ICU	0.68	0.56

273 Ya	le Av. (Mich	nelson D	r.	
BO No I	-405 Vel		-Lane S PK Hour		
] 1	Ln Cap	Vol	V/C	Vol	V/C
NL NT	1 1700 1 1700	0		2 0	*
NR	D 1700	97	0.06	94	0.06
SL ST SR	1 1700 1 1700 D 1700	0 0 0	*	0 0 0	*
	2 1 7 0 0	ŭ			
EL ET ER	1 1700 1 1700 D 1700	0 169 139		0 311 3	0.18*
WL WT WR	1 1700 1 1700 D 1700		0.13* 0.11	81 235 0	0.05* 0.14
Adjustr Overlar			Cle	NI arance	BR .02 ≥ .05
То	otal ICU		0.32		0.30

275 Yal	e Av. @ Uni	versity Dr.	
	405 Veh OC AM: Cap Vol	PK Hour PM	I PK Hour
NL 0 NT 0 NR 0	0 0 0	*	0 0 * 0
ST 0	1700 159 0 1700 238		0 0.02* 0 6 0.04
	1700 129 3400 901 0		
	0 3400 1334 1700 44		
Overlaps		Cleara	nce .05
Tot	al ICU	0.61	0.55

273 Yale	. Av. 0	Mich	elson Di	r.	
BO No I-4	05 Veh	AM I	-Lane S PK Hour V/C	PM PI	K Hour
NT 1	1700 1700 1700	71 0 88		0 0 92	* 0.05
ST 1	1700 1700 1700	0 0 0	*	0 0 0	*
ET 1	1700 1700 1700	0 178 132		0 318 0	0.19*
WT 1	1700 1700 1700		0.12* 0.11	75 227 0	
Adjustmen Overlaps	nt		Cle	NI arance	BR .02
Tota	al ICU		0.31		0.30

275 Y	ale Av. 0	Universit	y Dr.	
		OC 2-Lane AM PK Hou: Vol V/C	r PM PK	Hour
NL NT NR	0 0 0	0 0 * 0	0 0 0	*
SL ST SR	0	146 0.09* 0 214 0.13	0	
1		121 0.07* 924 0.27 0		
		0 344 0.40* 42 0.02		
Overla	ps	C	learance	.05
To	otal ICU	0.61	0	.55

APPENDIX C- HCM Synchro Worksheets

Intersection												
Intersection Delay, s/veh	14.7											
Intersection LOS	В											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	Į.	<u></u>	7	ř		7	ሻ	^	7	7		7
Traffic Vol, veh/h	65	135	21	88	193	20	13	56	33	21	37	52
Future Vol, veh/h	65	135	21	88	193	20	13	56	33	21	37	52
Peak Hour Factor	0.67	0.67	0.67	0.62	0.62	0.62	0.52	0.52	0.52	0.41	0.41	0.41
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	97	201	31	142	311	32	25	108	63	51	90	127
Number of Lanes	1	1	1	1	1	1	1	1	1	1	1	1
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	3			3			3			3		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	3			3			3			3		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	3			3			3			3		
HCM Control Delay	14.1			17.7			12.1			12.1		
HCM LOS	В			С			В			В		
Lane		NBLn1	NBLn2	NBLn3	EBLn1	EBLn2	EBLn3	WBLn1	WBLn2	WBLn3	SBLn1	SBLn2
Vol Left, %		100%	0%	0%	100%	0%	0%	100%	0%	0%	100%	0%
Vol Thru, %		0%	100%	0%	0%	100%	0%	0%	100%	0%	0%	100%
Vol Right, %		0%	0%	100%	0%	0%	100%	0%	0%	100%	0%	0%
Sign Control		Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop
Traffic Vol by Lane		13	56	33	65	135	21	88	193	20	21	37

Vol Left, %	100%	0%	0%	100%	0%	0%	100%	0%	0%	100%	0%
Vol Thru, %	0%	100%	0%	0%	100%	0%	0%	100%	0%	0%	100%
Vol Right, %	0%	0%	100%	0%	0%	100%	0%	0%	100%	0%	0%
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop
Traffic Vol by Lane	13	56	33	65	135	21	88	193	20	21	37
LT Vol	13	0	0	65	0	0	88	0	0	21	0
Through Vol	0	56	0	0	135	0	0	193	0	0	37
RT Vol	0	0	33	0	0	21	0	0	20	0	0
Lane Flow Rate	25	108	63	97	201	31	142	311	32	51	90
Geometry Grp	8	8	8	8	8	8	8	8	8	8	8
Degree of Util (X)	0.058	0.235	0.126	0.213	0.414	0.058	0.299	0.612	0.057	0.117	0.193
Departure Headway (Hd)	8.362	7.862	7.162	7.903	7.403	6.703	7.573	7.073	6.373	8.19	7.69
Convergence, Y/N	Yes										
Сар	429	457	500	455	486	534	475	511	562	438	467
Service Time	6.109	5.609	4.909	5.645	5.145	4.445	5.31	4.81	4.11	5.934	5.434
HCM Lane V/C Ratio	0.058	0.236	0.126	0.213	0.414	0.058	0.299	0.609	0.057	0.116	0.193
HCM Control Delay	11.6	13	10.9	12.8	15.3	9.9	13.5	20.4	9.5	12	12.3
HCM Lane LOS	В	В	В	В	С	Α	В	С	Α	В	В
HCM 95th-tile Q	0.2	0.9	0.4	0.8	2	0.2	1.2	4.1	0.2	0.4	0.7

Existing AM Peak
12/20/2022
Synchro 11 Report
Page 1

Intersection												
Int Delay, s/veh	4.3											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		4			4			4	7		4	7
Traffic Vol, veh/h	15	26	25	24	31	2	13	90	12	2	135	10
Future Vol, veh/h	15	26	25	24	31	2	13	90	12	2	135	10
Conflicting Peds, #/hr	6	0	6	6	0	6	14	0	14	14	0	14
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	-	-	200	-	-	200
Veh in Median Storage	e,# -	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	59	59	59	77	77	77	52	52	52	39	39	39
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	25	44	42	31	40	3	25	173	23	5	346	26
Major/Minor I	Minor2			Minor1			Major1		N	Major2		
Conflicting Flow All	632	630	366	655	633	193	386	0	0	210	0	0
Stage 1	370	370	-	237	237	-	-	-	-	-	-	-
Stage 2	262	260	-	418	396	-	-	-	-	-	-	-
Critical Hdwy	7.12	6.52	6.22	7.12	6.52	6.22	4.12	-	-	4.12	-	-
Critical Hdwy Stg 1	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Follow-up Hdwy	3.518	4.018	3.318	3.518	4.018	3.318	2.218	-	-	2.218	-	-
Pot Cap-1 Maneuver	393	399	679	379	397	849	1172	-	-	1361	-	-
Stage 1	650	620	-	766	709	-	-	-	-	-	-	-
Stage 2	743	693	-	612	604	-	-	-	-	-	-	-
Platoon blocked, %								-	-		-	-
Mov Cap-1 Maneuver	346	378	668	311	376	835	1158	-	-	1345	-	-
Mov Cap-2 Maneuver	346	378	-	311	376	-	-	-	-	-	-	-
Stage 1	627	609	-	739	683	-	-	-	-	-	-	-
Stage 2	677	668	-	526	594	-	-	-	-	-	-	-
Approach	EB			WB			NB			SB		
HCM Control Delay, s	15.9			17.9			0.9			0.1		
HCM LOS	С			С								
Minor Lane/Major Mvm	nt	NBL	NBT	NBR	EBLn1V	VBLn1	SBL	SBT	SBR			
Capacity (veh/h)		1158	-	-	441	352	1345	-	-			
HCM Lane V/C Ratio		0.022	-	-	0.254		0.004	-	-			
HCM Control Delay (s)		8.2	0	-	15.9	17.9	7.7	0	-			
HCM Lane LOS		Α	A	-	С	С	Α	A	-			
HCM 95th %tile Q(veh)	0.1	-	-	1	0.8	0	-	-			

Existing AM Peak
12/20/2022
Synchro 11 Report
Page 2

Intersection												
Intersection Delay, s/veh	12.6											
Intersection LOS	В											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	ሻ	↑	7	ሻ	^	7	ሻ	↑	7	ሻ	†	7
Traffic Vol, veh/h	2	284	7	13	204	1	14	1	57	2	0	3
Future Vol, veh/h	2	284	7	13	204	1	14	1	57	2	0	3
Peak Hour Factor	0.83	0.83	0.83	0.78	0.78	0.78	0.68	0.68	0.68	0.43	0.43	0.43
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	2	342	8	17	262	1	21	1	84	5	0	7
Number of Lanes	1	1	1	1	1	1	1	1	1	1	1	1

Approach	EB	WB	NB	SB
Opposing Approach	WB	EB	SB	NB
Opposing Lanes	3	3	3	3
Conflicting Approach Left	SB	NB	EB	WB
Conflicting Lanes Left	3	3	3	3
Conflicting Approach Right	NB	SB	WB	EB
Conflicting Lanes Right	3	3	3	3
HCM Control Delay	14	12.2	9.4	9.2
HCM LOS	В	В	А	Α

Lane	NBLn1	NBLn2	NBLn3	EBLn1	EBLn2	EBLn3	WBLn1	WBLn2	WBLn3	SBLn1	SBLn2
Vol Left, %	100%	0%	0%	100%	0%	0%	100%	0%	0%	100%	0%
Vol Thru, %	0%	100%	0%	0%	100%	0%	0%	100%	0%	0%	100%
Vol Right, %	0%	0%	100%	0%	0%	100%	0%	0%	100%	0%	0%
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop
Traffic Vol by Lane	14	1	57	2	284	7	13	204	1	2	0
LT Vol	14	0	0	2	0	0	13	0	0	2	0
Through Vol	0	1	0	0	284	0	0	204	0	0	0
RT Vol	0	0	57	0	0	7	0	0	1	0	0
Lane Flow Rate	21	1	84	2	342	8	17	262	1	5	0
Geometry Grp	8	8	8	8	8	8	8	8	8	8	8
Degree of Util (X)	0.039	0.003	0.132	0.004	0.521	0.011	0.029	0.415	0.002	0.009	0
Departure Headway (Hd)	6.881	6.381	5.681	6.084	5.583	4.881	6.221	5.719	5.018	7.077	6.577
Convergence, Y/N	Yes										
Cap	522	563	634	592	650	738	579	633	717	508	0
Service Time	4.595	4.095	3.395	3.784	3.283	2.581	3.921	3.419	2.718	4.793	4.293
HCM Lane V/C Ratio	0.04	0.002	0.132	0.003	0.526	0.011	0.029	0.414	0.001	0.01	0
HCM Control Delay	9.9	9.1	9.3	8.8	14.2	7.6	9.1	12.4	7.7	9.9	9.3
HCM Lane LOS	Α	Α	Α	Α	В	Α	Α	В	Α	Α	N
HCM 95th-tile Q	0.1	0	0.5	0	3	0	0.1	2	0	0	0

Existing PM Peak Synchro 11 Report 1/18/2023 Page 3

Intersection												
Int Delay, s/veh	5.2											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		4			4			र्स	7		4	7
Traffic Vol, veh/h	11	28	13	12	12	2	27	57	17	2	11	8
Future Vol, veh/h	11	28	13	12	12	2	27	57	17	2	11	8
Conflicting Peds, #/hr	10	0	10	10	0	10	9	0	8	8	0	9
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	-	-	200	-	-	200
Veh in Median Storage	e,# -	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	71	71	71	73	73	73	70	70	70	76	76	76
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	15	39	18	16	16	3	39	81	24	3	14	11
Major/Minor I	Minor2			Minor1			Major1		<u> </u>	Major2		
Conflicting Flow All	220	220	33	231	207	99	34	0	0	113	0	0
Stage 1	29	29	-	167	167	-	-	-	-	-	-	-
Stage 2	191	191	-	64	40	-	-	-	-	-	-	-
Critical Hdwy	7.12	6.52	6.22	7.12	6.52	6.22	4.12	-	-	4.12	-	-
Critical Hdwy Stg 1	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Follow-up Hdwy	3.518	4.018	3.318	3.518	4.018	3.318	2.218	-	-	2.218	-	-
Pot Cap-1 Maneuver	736	678	1041	724	690	957	1578	-	-	1476	-	-
Stage 1	988	871	-	835	760	-	-	-	-	-	-	-
Stage 2	811	742	-	947	862	-	-	-	-	-	-	-
Platoon blocked, %								-	-		-	-
Mov Cap-1 Maneuver	693	650	1025	653	661	943	1566	-	-	1466	-	-
Mov Cap-2 Maneuver	693	650	-	653	661	-	-	-	-	-	-	-
Stage 1	954	863	-	807	734	-	-	-	-	-	-	-
Stage 2	763	717	-	878	854	-	-	-	-	-	-	-
Approach	EB			WB			NB			SB		
HCM Control Delay, s	10.5			10.6			2			0.7		
HCM LOS	В			В								
Minor Lane/Major Mvm	nt	NBL	NBT	NBR	EBLn1V	VBL n1	SBL	SBT	SBR			
Capacity (veh/h)		1566		-	726	673	1466	-	-			
HCM Lane V/C Ratio		0.025	-	_	0.101			_	<u>-</u>			
HCM Control Delay (s)		7.4	0	_	10.5	10.6	7.5	0				
HCM Lane LOS		7.4 A	A	_	10.3 B	В	7.5 A	A	_			
HCM 95th %tile Q(veh)	0.1	-		0.3	0.2	0		_			
HOW JOHN JUHIC WIVELL	1	0.1			0.0	0.2						

Existing PM Peak

1/18/2023

Synchro 11 Report
Page 4

Intersection												
Intersection Delay, s/veh	12.1											
Intersection LOS	В											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	ሻ	†	7	ሻ	^	7	ሻ	†	7	ሻ	†	7
Traffic Vol, veh/h	27	168	20	46	166	16	15	19	44	24	21	29
Future Vol, veh/h	27	168	20	46	166	16	15	19	44	24	21	29
Peak Hour Factor	0.76	0.76	0.76	0.61	0.61	0.61	0.71	0.71	0.71	0.36	0.36	0.36
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	36	221	26	75	272	26	21	27	62	67	58	81
Number of Lanes	1	1	1	1	1	1	1	1	1	1	1	1
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	3			3			3			3		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	3			3			3			3		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	3			3			3			3		
HCM Control Delay	12.5			13.3			10			10.4		
HCM LOS	В			В			Α			В		
Lane		NBLn1	NBLn2	NBLn3	EBLn1	EBLn2	EBLn3	WBLn1	WBLn2	WBLn3	SBLn1	SBLn2
Vol Left, %		100%	0%	0%	100%	0%	0%	100%	0%	0%	100%	0%
Vol Thru, %		0%	100%	0%	0%	100%	0%	0%	100%	0%	0%	100%
Vol Right %		0%	0%	100%	0%	0%	100%	0%	0%	100%	0%	0%

Lane	NBLn1	NBLn2	NBLn3	EBLn1	EBLn2	EBLn3	WBLn1	WBLn2	WBLn3	SBLn1	SBLn2
Vol Left, %	100%	0%	0%	100%	0%	0%	100%	0%	0%	100%	0%
Vol Thru, %	0%	100%	0%	0%	100%	0%	0%	100%	0%	0%	100%
Vol Right, %	0%	0%	100%	0%	0%	100%	0%	0%	100%	0%	0%
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop
Traffic Vol by Lane	15	19	44	27	168	20	46	166	16	24	21
LT Vol	15	0	0	27	0	0	46	0	0	24	0
Through Vol	0	19	0	0	168	0	0	166	0	0	21
RT Vol	0	0	44	0	0	20	0	0	16	0	0
Lane Flow Rate	21	27	62	36	221	26	75	272	26	67	58
Geometry Grp	8	8	8	8	8	8	8	8	8	8	8
Degree of Util (X)	0.044	0.052	0.108	0.068	0.394	0.042	0.141	0.471	0.04	0.134	0.109
Departure Headway (Hd)	7.476	6.976	6.276	6.914	6.414	5.714	6.735	6.235	5.535	7.251	6.751
Convergence, Y/N	Yes										
Cap	478	512	568	517	559	624	532	577	645	493	529
Service Time	5.242	4.742	4.042	4.669	4.169	3.469	4.487	3.987	3.287	5.013	4.513
HCM Lane V/C Ratio	0.044	0.053	0.109	0.07	0.395	0.042	0.141	0.471	0.04	0.136	0.11
HCM Control Delay	10.6	10.1	9.8	10.2	13.3	8.7	10.6	14.5	8.5	11.1	10.3
HCM Lane LOS	В	В	Α	В	В	Α	В	В	Α	В	В
HCM 95th-tile Q	0.1	0.2	0.4	0.2	1.9	0.1	0.5	2.5	0.1	0.5	0.4

Existing School Peak Synchro 11 Report 1/18/2023 Page 5

Intersection												
Int Delay, s/veh	3											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		4			4			4	7		4	7
Traffic Vol, veh/h	17	26	7	14	18	3	14	84	23	2	74	10
Future Vol, veh/h	17	26	7	14	18	3	14	84	23	2	74	10
Conflicting Peds, #/hr	3	0	4	4	0	3	14	0	6	6	0	14
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	-	-	200	_	-	200
Veh in Median Storage	e,# -	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	73	73	73	78	78	78	70	70	70	31	31	31
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	23	36	10	18	23	4	20	120	33	6	239	32
Major/Minor I	Minor2			Minor1			Major1		_	Major2		
Conflicting Flow All	458	464	257	460	463	129	285	0	0	159	0	0
Stage 1	265	265	-	166	166	-	-	-	-	-	-	_
Stage 2	193	199	-	294	297	-	-	-	-	-	-	-
Critical Hdwy	7.12	6.52	6.22	7.12	6.52	6.22	4.12	-	-	4.12	_	_
Critical Hdwy Stg 1	6.12	5.52	-	6.12	5.52	-	-	_	_	-	_	-
Critical Hdwy Stg 2	6.12	5.52	-	6.12	5.52	-	_	_	_	-	_	-
Follow-up Hdwy	3.518	4.018	3.318		4.018	3.318	2.218	_	-	2.218	-	_
Pot Cap-1 Maneuver	513	495	782	512	496	921	1277	-	-	1420	-	-
Stage 1	740	689	-	836	761	-	-	-	-	-	-	-
Stage 2	809	736	-	714	668	-	-	-	-	-	-	-
Platoon blocked, %								-	-		-	_
Mov Cap-1 Maneuver	477	476	770	465	477	914	1262	-	-	1413	-	-
Mov Cap-2 Maneuver	477	476	-	465	477	-	-	-	-	-	-	-
Stage 1	719	677	-	818	744	-	-	-	-	-	-	-
Stage 2	765	720	-	662	657	-	-	-	-	-	-	-
, and the second												
Approach	EB			WB			NB			SB		
HCM Control Delay, s	13.3			13.1			0.9			0.2		
HCM LOS	В			В			0.0			J.L		
Minor Lane/Major Mvm	nt	NBL	NBT	NRP	EBLn1V	VRI n1	SBL	SBT	SBR			
Capacity (veh/h)	IV.	1262	NDI	NDIN	503	492	1413	ODT	אומט			
HCM Lane V/C Ratio		0.016	_	_	0.136			_	_			
HCM Control Delay (s)		7.9	0	-	13.3	13.1	7.6	0	-			
HCM Control Delay (s)			A	-	13.3 B	13.1 B	7.6 A	A	-			
HCM 95th %tile Q(veh	١	A 0	- -	-	0.5	0.3	0	А	-			
HOW JULY WILL WINE	1	U	-	-	0.5	0.3	U	_	_			

Existing School Peak
1/18/2023
Synchro 11 Report
Page 6

1: Yale Ave & Michelson Dr

Intersection		
Intersection Delay, s/veh	251.5	
Intersection LOS	F	

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	Ţ	†	7	J.	†	7	,	ħβ		¥	↑ ↑	
Traffic Vol, veh/h	218	33	64	74	37	252	35	236	36	195	375	188
Future Vol, veh/h	218	33	64	74	37	252	35	236	36	195	375	188
Peak Hour Factor	0.83	0.83	0.83	0.78	0.78	0.78	0.68	0.68	0.68	0.43	0.43	0.43
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	263	40	77	95	47	323	51	347	53	453	872	437
Number of Lanes	1	1	1	1	1	1	1	2	0	1	2	0
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	3			3			3			3		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	3			3			3			3		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	3			3			3			3		
HCM Control Delay	67.7			83.3			44.7			388.4		
HCM LOS	F			F			Е			F		

Lane	NBLn1	NBLn2	NBLn3	EBLn1	EBLn2	EBLn3	WBLn1	WBLn2	WBLn3	SBLn1	SBLn2
Vol Left, %	100%	0%	0%	100%	0%	0%	100%	0%	0%	100%	0%
Vol Thru, %	0%	100%	69%	0%	100%	0%	0%	100%	0%	0%	100%
Vol Right, %	0%	0%	31%	0%	0%	100%	0%	0%	100%	0%	0%
Sign Control	Stop										
Traffic Vol by Lane	35	157	115	218	33	64	74	37	252	195	250
LT Vol	35	0	0	218	0	0	74	0	0	195	0
Through Vol	0	157	79	0	33	0	0	37	0	0	250
RT Vol	0	0	36	0	0	64	0	0	252	0	0
Lane Flow Rate	51	231	169	263	40	77	95	47	323	453	581
Geometry Grp	6	6	6	6	6	6	6	6	6	6	6
Degree of Util (X)	0.185	8.0	0.573	0.955	0.139	0.255	0.339	0.163	1.048	1.399	1.716
Departure Headway (Hd)	14.991	14.491	14.272	15.063	14.563	13.863	15.218	14.718	14.018	11.221	10.626
Convergence, Y/N	Yes										
Cap	241	252	255	242	248	261	238	245	262	327	343
Service Time	12.691	12.191	11.972	12.763	12.263	11.563	12.918	12.418	11.718	8.921	8.421
HCM Lane V/C Ratio	0.212	0.917	0.663	1.087	0.161	0.295	0.399	0.192	1.233	1.385	1.694
HCM Control Delay	21.1	57.3	34.5	88.7	19.6	21.2	25.5	20.3	109.5	226.7	359.5
HCM Lane LOS	С	F	D	F	С	С	D	С	F	F	F
HCM 95th-tile Q	0.7	6.1	3.2	8.6	0.5	1	1.4	0.6	10.8	23.2	36

Build Out Approve AM Peak
04/12/2024
Synchro 11 Report
Page 7

Intersection												
Int Delay, s/veh	6.1											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		4	7		4	7		414			4TÞ	
Traffic Vol, veh/h	21	37	35	29	37	2	14	284	14	9	459	45
Future Vol., veh/h	21	37	35	29	37	2	14	284	14	9	459	45
Conflicting Peds, #/hr	10	0	10	10	0	10	9	0	8	8	0	9
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	50	-	-	50	-	-	-	-	-	-
Veh in Median Storage,	,# -	0	-	-	0	-	-	0	-	-	0	-
Grade, %	_	0	-	-	0	-	-	0	_	-	0	-
Peak Hour Factor	71	71	71	73	73	73	70	70	70	76	76	76
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	30	52	49	40	51	3	20	406	20	12	604	59
Major/Minor N	/linor2		N	Minor1			Major1		N	Major2		
Conflicting Flow All	946	1141	351	826	1160	231	672	0	0	434	0	0
Stage 1	667	667	-	464	464		-	-	-	-	-	-
Stage 2	279	474	_	362	696	_	_	_	_	_	_	_
Critical Hdwy	7.54	6.54	6.94	7.54	6.54	6.94	4.14	-	_	4.14	_	_
Critical Hdwy Stg 1	6.54	5.54	-	6.54	5.54	-	-	-	_	-	-	_
Critical Hdwy Stg 2	6.54	5.54	-	6.54	5.54	-	-	-	-	-	_	-
Follow-up Hdwy	3.52	4.02	3.32	3.52	4.02	3.32	2.22	_	_	2.22	-	_
Pot Cap-1 Maneuver	216	199	645	264	194	771	915	-	_	1122	_	-
Stage 1	414	455	-	548	562	_	-	_	_	-	-	-
Stage 2	704	556	-	629	441	_	_	_	-	_	_	-
Platoon blocked, %								_	_		-	-
Mov Cap-1 Maneuver	161	187	635	182	183	759	908	-	-	1115	-	-
Mov Cap-2 Maneuver	161	187	-	182	183	-	-	-	-	-	-	-
Stage 1	399	444	-	529	542	-	-	-	-	-	-	-
Stage 2	612	536	-	499	430	-	-	-	-	-	-	-
, and the second												
Approach	EB			WB			NB			SB		
HCM Control Delay, s	30.2			41.5			0.5			0.2		
HCM LOS	D			E								
Minor Lane/Major Mvm	t	NBL	NBT	NBR I	EBLn1	EBLn2V	VBLn1V	VBLn2	SBL	SBT	SBR	
Capacity (veh/h)		908	-	-	177	635	183	759	1115	-	-	
HCM Lane V/C Ratio		0.022	_	_		0.078			0.011	_	_	
HCM Control Delay (s)		9.1	0.1	-	41.7	11.1	42.5	9.8	8.3	0.1	_	
HCM Lane LOS		A	A	_	E	В	E	A	A	A	_	
HCM 95th %tile Q(veh)		0.1	-	-	2.2	0.3	2.4	0	0	-	-	
(1011)												

Build Out Approve AM Peak
2/22/2024
Synchro 11 Report
Page 8

Intersection	
ntersection Delay, s/veh	14.3
Intersection Delay, s/veh	В

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		ર્ન	7		4	7		€ 1₽			414	
Traffic Vol, veh/h	21	37	35	29	37	2	14	284	14	9	459	45
Future Vol, veh/h	21	37	35	29	37	2	14	284	14	9	459	45
Peak Hour Factor	0.71	0.71	0.71	0.73	0.73	0.73	0.70	0.70	0.70	0.76	0.76	0.76
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	30	52	49	40	51	3	20	406	20	12	604	59
Number of Lanes	0	1	1	0	1	1	0	2	0	0	2	0
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	2			2			2			2		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	2			2			2			2		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	2			2			2			2		
HCM Control Delay	11.3			12.3			13			16		
HCM LOS	В			В			В			С		

Lane	NBLn1	NBLn2	EBLn1	EBLn2	WBLn1	WBLn2	SBLn1	SBLn2	
Vol Left, %	9%	0%	36%	0%	44%	0%	4%	0%	
Vol Thru, %	91%	91%	64%	0%	56%	0%	96%	84%	
Vol Right, %	0%	9%	0%	100%	0%	100%	0%	16%	
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	
Traffic Vol by Lane	156	156	58	35	66	2	239	275	
LT Vol	14	0	21	0	29	0	9	0	
Through Vol	142	142	37	0	37	0	230	230	
RT Vol	0	14	0	35	0	2	0	45	
Lane Flow Rate	223	223	82	49	90	3	314	361	
Geometry Grp	5	5	5	5	5	5	5	5	
Degree of Util (X)	0.39	0.383	0.173	0.092	0.194	0.005	0.523	0.588	
Departure Headway (Hd)	6.302	6.193	7.606	6.704	7.726	6.783	6	5.865	
Convergence, Y/N	Yes								
Cap	568	579	470	532	463	525	599	614	
Service Time	4.067	3.957	5.381	4.477	5.505	4.561	3.757	3.621	
HCM Lane V/C Ratio	0.393	0.385	0.174	0.092	0.194	0.006	0.524	0.588	
HCM Control Delay	13.1	12.8	12	10.2	12.4	9.6	15.2	16.7	
HCM Lane LOS	В	В	В	В	В	Α	С	С	
HCM 95th-tile Q	1.8	1.8	0.6	0.3	0.7	0	3	3.8	

Build Out Approve AM Peak
2/22/2024
Synchro 11 Report
Page 9

1: Yale Ave & Michelson Dr

Intersection		
Intersection Delay, s/veh	208	
Intersection LOS	F	

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	Ĭ	†	7	Ţ	†	7	ň	ħβ		7	ħβ	
Traffic Vol, veh/h	240	59	23	18	33	184	44	245	60	299	117	219
Future Vol, veh/h	240	59	23	18	33	184	44	245	60	299	117	219
Peak Hour Factor	0.83	0.83	0.83	0.78	0.78	0.78	0.68	0.68	0.68	0.43	0.43	0.43
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	289	71	28	23	42	236	65	360	88	695	272	509
Number of Lanes	1	1	1	1	1	1	1	2	0	1	2	0
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	3			3			3			3		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	3			3			3			3		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	3			3			3			3		
HCM Control Delay	63.1			35.4			34.5			341.5		
HCM LOS	F			Е			D			F		

Lane	NBLn1	NBLn2	NBLn3	EBLn1	EBLn2	EBLn3	WBLn1	WBLn2	WBLn3	SBLn1	SBLn2
Vol Left, %	100%	0%	0%	100%	0%	0%	100%	0%	0%	100%	0%
Vol Thru, %	0%	100%	58%	0%	100%	0%	0%	100%	0%	0%	100%
Vol Right, %	0%	0%	42%	0%	0%	100%	0%	0%	100%	0%	0%
Sign Control	Stop										
Traffic Vol by Lane	44	163	142	240	59	23	18	33	184	299	78
LT Vol	44	0	0	240	0	0	18	0	0	299	0
Through Vol	0	163	82	0	59	0	0	33	0	0	78
RT Vol	0	0	60	0	0	23	0	0	184	0	0
Lane Flow Rate	65	240	208	289	71	28	23	42	236	695	181
Geometry Grp	6	6	6	6	6	6	6	6	6	6	6
Degree of Util (X)	0.206	0.733	0.618	0.945	0.223	0.082	0.078	0.137	0.72	1.993	0.495
Departure Headway (Hd)	12.455	11.955	11.658	12.984	12.484	11.784	13.209	12.709	12.009	10.318	9.818
Convergence, Y/N	Yes										
Сар	290	305	312	280	289	306	273	284	304	355	368
Service Time	10.155	9.655	9.358	10.684	10.184	9.484	10.909	10.409	9.709	8.073	7.573
HCM Lane V/C Ratio	0.224	0.787	0.667	1.032	0.246	0.092	0.084	0.148	0.776	1.958	0.492
HCM Control Delay	18.4	41.5	31.5	78.6	18.7	15.5	17	17.4	40.4	479.9	21.9
HCM Lane LOS	С	Е	D	F	С	С	С	С	Е	F	С
HCM 95th-tile Q	0.8	5.4	3.8	9	0.8	0.3	0.3	0.5	5.2	48.4	2.6

Build Out Approve PM Peak 04/12/2024

Intersection												
Int Delay, s/veh	2.9											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		सी	7		4	7		414			4î}∍	
Traffic Vol, veh/h	12	31	14	12	13	2	33	336	20	1	154	3
Future Vol, veh/h	12	31	14	12	13	2	33	336	20	1	154	3
Conflicting Peds, #/hr	10	0	10	10	0	10	9	0	8	8	0	9
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	<u>-</u>	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	50	-	-	50	-	-	-	-	-	-
Veh in Median Storage,	# -	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	71	71	71	73	73	73	70	70	70	76	76	76
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	17	44	20	16	18	3	47	480	29	1	203	4
Major/Minor N	/linor2		N	/linor1		1	Major1		ı	Major2		
Conflicting Flow All	569	827	123	733	815	273	216	0	0	517	0	0
Stage 1	216	216	-	597	597			-	_	-	_	-
Stage 2	353	611	_	136	218	_	_	_	_	_	_	_
Critical Hdwy	7.54	6.54	6.94	7.54	6.54	6.94	4.14	_	_	4.14	_	-
Critical Hdwy Stg 1	6.54	5.54	-	6.54	5.54	-	-	_	-	-	-	-
Critical Hdwy Stg 2	6.54	5.54	-	6.54	5.54	_	-	-	-	-	_	-
Follow-up Hdwy	3.52	4.02	3.32	3.52	4.02	3.32	2.22	_	-	2.22	_	_
Pot Cap-1 Maneuver	405	305	905	309	310	725	1351	-	-	1045	-	-
Stage 1	766	723	-	456	490		-	_	-		-	_
Stage 2	637	482	-	853	721	-	-	-	-	-	-	-
Platoon blocked, %								-	-		-	-
Mov Cap-1 Maneuver	364	286	891	253	290	714	1341	-	-	1038	-	-
Mov Cap-2 Maneuver	364	286	-	253	290	-	-	-	-	-	-	-
Stage 1	723	717	-	431	463	-	-	-	-	-	-	-
Stage 2	575	455	-	776	715	-	-	-	-	-	-	-
-												
Approach	EB			WB			NB			SB		
HCM Control Delay, s	17.2			19.5			0.8			0.1		
HCM LOS	С			С								
Minor Lane/Major Mvmt	t	NBL	NBT	NBR I	EBLn1 I	EBLn2V	VBLn1V	VBLn2	SBL	SBT	SBR	
Capacity (veh/h)		1341	-	-	304	891	271	714	1038	-	-	
HCM Lane V/C Ratio		0.035	-	_		0.022				_	_	
HCM Control Delay (s)		7.8	0.2	-	19.8	9.1	20.2	10.1	8.5	0	_	
HCM Lane LOS		A	A	_	С	A	C	В	A	A	_	
HCM 95th %tile Q(veh)		0.1	-	-	0.7	0.1	0.4	0	0	-	-	
75						• • • • • • • • • • • • • • • • • • • •						

Build Out Approve PM Peak
2/22/2024
Synchro 11 Report
Page 11

Intersection	
Intersection Delay, s/veh Intersection LOS	10.5
Intersection LOS	В
illersection LOS	Б

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		ર્ન	7		र्स	7		€1 }			€ 1₽	
Traffic Vol, veh/h	12	31	14	12	13	2	33	336	20	1	154	3
Future Vol, veh/h	12	31	14	12	13	2	33	336	20	1	154	3
Peak Hour Factor	0.71	0.71	0.71	0.73	0.73	0.73	0.70	0.70	0.70	0.76	0.76	0.76
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	17	44	20	16	18	3	47	480	29	1	203	4
Number of Lanes	0	1	1	0	1	1	0	2	0	0	2	0
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	2			2			2			2		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	2			2			2			2		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	2			2			2			2		
HCM Control Delay	9.7			9.8			11.2			9.2		
HCM LOS	Α			Α			В			Α		

Lane	NBLn1	NBLn2	EBLn1	EBLn2	WBLn1	WBLn2	SBLn1	SBLn2	
Vol Left, %	16%	0%	28%	0%	48%	0%	1%	0%	
Vol Thru, %	84%	89%	72%	0%	52%	0%	99%	96%	
Vol Right, %	0%	11%	0%	100%	0%	100%	0%	4%	
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	
Traffic Vol by Lane	201	188	43	14	25	2	78	80	
LT Vol	33	0	12	0	12	0	1	0	
Through Vol	168	168	31	0	13	0	77	77	
RT Vol	0	20	0	14	0	2	0	3	
Lane Flow Rate	287	269	61	20	34	3	103	105	
Geometry Grp	5	5	5	5	5	5	5	5	
Degree of Util (X)	0.413	0.374	0.108	0.031	0.063	0.004	0.155	0.158	
Departure Headway (Hd)	5.172	5.014	6.437	5.587	6.614	5.661	5.443	5.41	
Convergence, Y/N	Yes								
Cap	692	714	552	635	537	625	655	659	
Service Time	2.924	2.767	4.225	3.375	4.41	3.457	3.212	3.179	
HCM Lane V/C Ratio	0.415	0.377	0.111	0.031	0.063	0.005	0.157	0.159	
HCM Control Delay	11.5	10.8	10	8.6	9.9	8.5	9.2	9.2	
HCM Lane LOS	В	В	Α	Α	Α	Α	Α	Α	
HCM 95th-tile Q	2	1.7	0.4	0.1	0.2	0	0.5	0.6	

Build Out Approve PM Peak
2/22/2024
Synchro 11 Report
Page 12

Intersection	
Intersection Delay, s/veh	558.5
Intersection LOS	F

III.OIOOOLIOII EOO	•											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	J.		7	*	+	7	Ť	Ą.		7	ĵ»	_
Traffic Vol, veh/h	232	33	56	60	34	248	32	230	33	203	346	196
Future Vol, veh/h	232	33	56	60	34	248	32	230	33	203	346	196
Peak Hour Factor	0.83	0.83	0.83	0.78	0.78	0.78	0.68	0.68	0.68	0.43	0.43	0.43
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	280	40	67	77	44	318	47	338	49	472	805	456
Number of Lanes	1	1	1	1	1	1	1	1	0	1	1	0
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	3			3			2			2		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	2			2			3			3		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	2			2			3			3		
HCM Control Delay	57.9			57.1			133.3			903.6		
HCM LOS	F			F			F			F		

Lane	NBLn1	NBLn2	EBLn1	EBLn2	EBLn3	WBLn1	WBLn2	WBLn3	SBLn1	SBLn2	
Vol Left, %	100%	0%	100%	0%	0%	100%	0%	0%	100%	0%	
Vol Thru, %	0%	87%	0%	100%	0%	0%	100%	0%	0%	64%	
Vol Right, %	0%	13%	0%	0%	100%	0%	0%	100%	0%	36%	
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	
Traffic Vol by Lane	32	263	232	33	56	60	34	248	203	542	
LT Vol	32	0	232	0	0	60	0	0	203	0	
Through Vol	0	230	0	33	0	0	34	0	0	346	
RT Vol	0	33	0	0	56	0	0	248	0	196	
Lane Flow Rate	47	387	280	40	67	77	44	318	472	1260	
Geometry Grp	6	6	6	6	6	6	6	6	6	6	
Degree of Util (X)	0.152	1.183	0.909	0.124	0.197	0.249	0.135	0.922	1.41	3.505	
Departure Headway (Hd)	12.988	12.395	13.61	13.092	12.366	13.622	13.104	12.378	11.373	10.592	
Convergence, Y/N	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	
Cap	278	298	268	276	292	265	275	296	326	353	
Service Time	10.688	10.095	11.31	10.792	10.066	11.322	10.804	10.078	9.073	8.292	
HCM Lane V/C Ratio	0.169	1.299	1.045	0.145	0.229	0.291	0.16	1.074	1.448	3.569	
HCM Control Delay	18	147.3	73.2	17.6	18.1	20.8	17.8	71.3	231.7	1155.2	
HCM Lane LOS	С	F	F	С	С	С	С	F	F	F	
HCM 95th-tile Q	0.5	15.1	8.1	0.4	0.7	1	0.5	8.7	23.4	110.5	

Intersection Int Delay, s/veh
Movement EBL EBT EBR WBL WBT WBR NBL NBT NBR SBL SBT SBR
Traffic Vol, veh/h 22 37 36 27 35 2 15 271 14 9 409 44 Future Vol, veh/h 22 37 36 27 35 2 15 271 14 9 409 44 Conflicting Peds, #/hr 10 0 10 0 10 9 0 8 8 0 9 Sign Control Stop Stop Stop Stop Stop Stop Stop Stop Free
Traffic Vol, veh/h 22 37 36 27 35 2 15 271 14 9 409 44 Future Vol, veh/h 22 37 36 27 35 2 15 271 14 9 409 44 Conflicting Peds, #/hr 10 0 10 0 10 9 0 8 8 0 9 Sign Control Stop Stop Stop Stop Stop Stop Stop Free
Conflicting Peds, #/hr 10 0 10 10 9 0 8 8 0 9 Sign Control Stop Stop Stop Stop Stop Stop Free Fre
Sign Control Stop Stop Stop Stop Stop Stop Stop Free 2 2 2
RT Channelized - - None - - None - 0 - - 0 - - - 0 - - - - - - 0 - - - -
RT Channelized - - None - - None - 0 - - 0 - - - 0 - - - - - - 0 - - - -
Veh in Median Storage, # 0 - 0
Grade, % - 0 - - 0 - - 0 - - 0 - - 0 - - 0 - - 0 - - 0 - - 0 - - 0 - - 0 - - 0 - - 0 - - 0 - - 0 - - 0 - - 0 - - 0 - 76 78 78 78 78 78
Peak Hour Factor 71 71 71 73 73 73 70 70 70 76 76 76 Heavy Vehicles, % 2
Major/Minor Minor2 Minor1 Major1 Major2 Conflicting Flow All 1075 1057 586 1100 1076 415 605 0 0 415 0 <
Mvmt Flow 31 52 51 37 48 3 21 387 20 12 538 58 Major/Minor Minor2 Minor1 Major1 Major2 Major2 Conflicting Flow All Stage 1 1075 1057 586 1100 1076 415 605 0 0 415 0 0 Stage 1 600 600 - 447 447 -
Major/Minor Minor2 Minor1 Major1 Major2 Conflicting Flow All 1075 1057 586 1100 1076 415 605 0 0 415 0 0 Stage 1 600 600 - 447 447 -<
Conflicting Flow All 1075 1057 586 1100 1076 415 605 0 0 415 0 0 Stage 1 600 600 - 447 447 -
Conflicting Flow All 1075 1057 586 1100 1076 415 605 0 0 415 0 0 Stage 1 600 600 - 447 447 -
Conflicting Flow All 1075 1057 586 1100 1076 415 605 0 0 415 0 0 Stage 1 600 600 - 447 447 -
Stage 1 600 600 - 447 447 -
Stage 2 475 457 - 653 629
Critical Hdwy 7.12 6.52 6.22 7.12 6.52 6.22 4.12 4.12
Critical Hdwy Stg 1 6.12 5.52 - 6.12 5.52
Critical Hdwy Stg 2 6.12 5.52 - 6.12 5.52
Follow-up Hdwy 3.518 4.018 3.318 3.518 4.018 3.318 2.218 2.218
Pot Cap-1 Maneuver 197 225 510 190 219 637 973 1144
Stage 1 488 490 - 591 573
Stage 2 570 568 - 456 475
Platoon blocked, %
Mov Cap-1 Maneuver 153 212 502 132 207 627 966 1136
Mov Cap-2 Maneuver 153 212 - 132 207
Stage 1 471 479 - 571 553
Stage 2 500 548 - 357 464
Approach EB WB NB SB
HCM Control Delay, s 29.4 46.3 0.4 0.2
HCM LOS D E
Minor Lane/Major Mvmt NBL NBT NBR EBLn1 EBLn2WBLn1WBLn2 SBL SBT SBR
Capacity (veh/h) 966 185 502 166 627 1136
HCM Lane V/C Ratio 0.022 0.449 0.101 0.512 0.004 0.01
HCM Control Delay (s) 8.8 0 - 39.4 13 47.4 10.8 8.2 0 -
HCM Lane LOS A A - E B E B A A -
HCM 95th %tile Q(veh) 0.1 2.1 0.3 2.5 0 0

Intersection												
Intersection Delay, s/veh	27.5											
Intersection LOS	D											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		ર્ન	7		4	7		4			4	
Traffic Vol, veh/h	22	37	36	27	35	2	15	271	14	9	409	44
Future Vol, veh/h	22	37	36	27	35	2	15	271	14	9	409	44
Peak Hour Factor	0.71	0.71	0.71	0.73	0.73	0.73	0.70	0.70	0.70	0.76	0.76	0.76
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	31	52	51	37	48	3	21	387	20	12	538	58
Number of Lanes	0	1	1	0	1	1	0	1	0	0	1	0
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	2			2			1			1		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	1			1			2			2		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	1			1			2			2		
HCM Control Delay	11.5			12.3			19.6			38.8		
HCM LOS	В			В			С			Е		
Lane		NBLn1	EBLn1	EBLn2	WBLn1	WBLn2	SBLn1					
Lane Vol Left, %		5%	37%	0%	44%	0%	2%					
		5% 90%	37% 63%	0% 0%	44% 56%	0% 0%	2% 89%					
Vol Left, %		5%	37%	0%	44%	0%	2%					
Vol Left, % Vol Thru, %		5% 90%	37% 63% 0% Stop	0% 0% 100% Stop	44% 56% 0% Stop	0% 0%	2% 89% 10% Stop					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane		5% 90% 5% Stop 300	37% 63% 0% Stop 59	0% 0% 100%	44% 56% 0% Stop 62	0% 0% 100%	2% 89% 10% Stop 462					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol		5% 90% 5% Stop 300 15	37% 63% 0% Stop 59 22	0% 0% 100% Stop	44% 56% 0% Stop 62 27	0% 0% 100% Stop	2% 89% 10% Stop 462 9					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol		5% 90% 5% Stop 300 15 271	37% 63% 0% Stop 59	0% 0% 100% Stop 36 0	44% 56% 0% Stop 62	0% 0% 100% Stop 2 0	2% 89% 10% Stop 462 9 409					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol		5% 90% 5% Stop 300 15 271	37% 63% 0% Stop 59 22 37	0% 0% 100% Stop 36 0 0	44% 56% 0% Stop 62 27 35	0% 0% 100% Stop 2 0 0	2% 89% 10% Stop 462 9 409					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate		5% 90% 5% Stop 300 15 271 14 429	37% 63% 0% Stop 59 22 37 0	0% 0% 100% Stop 36 0 0	44% 56% 0% Stop 62 27 35 0	0% 0% 100% Stop 2 0 0 2 3	2% 89% 10% Stop 462 9 409 44 608					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp		5% 90% 5% Stop 300 15 271 14 429	37% 63% 0% Stop 59 22 37 0 83	0% 0% 100% Stop 36 0 0 36 51	44% 56% 0% Stop 62 27 35 0 85	0% 0% 100% Stop 2 0 0 2 3	2% 89% 10% Stop 462 9 409 44 608					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X)		5% 90% 5% Stop 300 15 271 14 429 2	37% 63% 0% Stop 59 22 37 0 83 5	0% 0% 100% Stop 36 0 0 36 51 5	44% 56% 0% Stop 62 27 35 0 85 5	0% 0% 100% Stop 2 0 0 2 3 5	2% 89% 10% Stop 462 9 409 44 608 2 0.905					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd)		5% 90% 5% Stop 300 15 271 14 429 2 0.671 5.637	37% 63% 0% Stop 59 22 37 0 83 5 0.179 7.771	0% 0% 100% Stop 36 0 0 36 51 5 0.097 6.856	44% 56% 0% Stop 62 27 35 0 85 5 0.187 7.927	0% 0% 100% Stop 2 0 0 2 3 5 0.005 6.978	2% 89% 10% Stop 462 9 409 44 608 2 0.905 5.357					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd) Convergence, Y/N		5% 90% 5% Stop 300 15 271 14 429 2 0.671 5.637 Yes	37% 63% 0% Stop 59 22 37 0 83 5 0.179 7.771 Yes	0% 0% 100% Stop 36 0 0 36 51 5 0.097 6.856 Yes	44% 56% 0% Stop 62 27 35 0 85 5 0.187 7.927 Yes	0% 0% 100% Stop 2 0 0 2 3 5 0.005 6.978 Yes	2% 89% 10% Stop 462 9 409 44 608 2 0.905 5.357 Yes					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd) Convergence, Y/N Cap		5% 90% 5% Stop 300 15 271 14 429 2 0.671 5.637 Yes 634	37% 63% 0% Stop 59 22 37 0 83 5 0.179 7.771 Yes 465	0% 0% 100% Stop 36 0 0 36 51 5 0.097 6.856 Yes 525	44% 56% 0% Stop 62 27 35 0 85 5 0.187 7.927 Yes 455	0% 0% 100% Stop 2 0 0 2 3 5 0.005 6.978 Yes 515	2% 89% 10% Stop 462 9 409 44 608 2 0.905 5.357 Yes 669					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd) Convergence, Y/N Cap Service Time		5% 90% 5% Stop 300 15 271 14 429 2 0.671 5.637 Yes 634 3.731	37% 63% 0% Stop 59 22 37 0 83 5 0.179 7.771 Yes 465 5.477	0% 0% 100% Stop 36 0 0 36 51 5 0.097 6.856 Yes 525 4.561	44% 56% 0% Stop 62 27 35 0 85 5 0.187 7.927 Yes 455 5.634	0% 0% 100% Stop 2 0 0 2 3 5 0.005 6.978 Yes 515 4.685	2% 89% 10% Stop 462 9 409 44 608 2 0.905 5.357 Yes 669 3.44					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd) Convergence, Y/N Cap Service Time HCM Lane V/C Ratio		5% 90% 5% Stop 300 15 271 14 429 2 0.671 5.637 Yes 634 3.731 0.677	37% 63% 0% Stop 59 22 37 0 83 5 0.179 7.771 Yes 465 5.477 0.178	0% 0% 100% Stop 36 0 0 36 51 5 0.097 6.856 Yes 525 4.561 0.097	44% 56% 0% Stop 62 27 35 0 85 5 0.187 7.927 Yes 455 5.634 0.187	0% 0% 100% Stop 2 0 0 2 3 5 0.005 6.978 Yes 515 4.685 0.006	2% 89% 10% Stop 462 9 409 44 608 2 0.905 5.357 Yes 669 3.44 0.909					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd) Convergence, Y/N Cap Service Time HCM Lane V/C Ratio HCM Control Delay		5% 90% 5% Stop 300 15 271 14 429 2 0.671 5.637 Yes 634 3.731 0.677	37% 63% 0% Stop 59 22 37 0 83 5 0.179 7.771 Yes 465 5.477 0.178 12.2	0% 0% 100% Stop 36 0 0 36 51 5 0.097 6.856 Yes 525 4.561 0.097 10.3	44% 56% 0% Stop 62 27 35 0 85 5 0.187 7.927 Yes 455 5.634 0.187 12.4	0% 0% 100% Stop 2 0 0 2 3 5 0.005 6.978 Yes 515 4.685 0.006 9.7	2% 89% 10% Stop 462 9 409 44 608 2 0.905 5.357 Yes 669 3.44 0.909 38.8					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd) Convergence, Y/N Cap Service Time HCM Lane V/C Ratio		5% 90% 5% Stop 300 15 271 14 429 2 0.671 5.637 Yes 634 3.731 0.677	37% 63% 0% Stop 59 22 37 0 83 5 0.179 7.771 Yes 465 5.477 0.178	0% 0% 100% Stop 36 0 0 36 51 5 0.097 6.856 Yes 525 4.561 0.097	44% 56% 0% Stop 62 27 35 0 85 5 0.187 7.927 Yes 455 5.634 0.187	0% 0% 100% Stop 2 0 0 2 3 5 0.005 6.978 Yes 515 4.685 0.006	2% 89% 10% Stop 462 9 409 44 608 2 0.905 5.357 Yes 669 3.44 0.909					

1: Yale Ave & Michelson Dr

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	7	†	7	*		7	*	ĵ»		Ţ	ĵ.	
Traffic Vol, veh/h	247	57	19	14	29	173	41	243	56	303	103	222
Future Vol, veh/h	247	57	19	14	29	173	41	243	56	303	103	222
Peak Hour Factor	0.83	0.83	0.83	0.78	0.78	0.78	0.68	0.68	0.68	0.43	0.43	0.43
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	298	69	23	18	37	222	60	357	82	705	240	516
Number of Lanes	1	1	1	1	1	1	1	1	0	1	1	0
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	3			3			2			2		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	2			2			3			3		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	2			2			3			3		
HCM Control Delay	57.3			30.1			147.9			456.8		
HCM LOS	F			D			F			F		

Lane	NBLn1	NBLn2	EBLn1	EBLn2	EBLn3	WBLn1	WBLn2	WBLn3	SBLn1	SBLn2	
Vol Left, %	100%	0%	100%	0%	0%	100%	0%	0%	100%	0%	
Vol Thru, %	0%	81%	0%	100%	0%	0%	100%	0%	0%	32%	
Vol Right, %	0%	19%	0%	0%	100%	0%	0%	100%	0%	68%	
Sign Control	Stop										
Traffic Vol by Lane	41	299	247	57	19	14	29	173	303	325	
LT Vol	41	0	247	0	0	14	0	0	303	0	
Through Vol	0	243	0	57	0	0	29	0	0	103	
RT Vol	0	56	0	0	19	0	0	173	0	222	
Lane Flow Rate	60	440	298	69	23	18	37	222	705	756	
Geometry Grp	6	6	6	6	6	6	6	6	6	6	
Degree of Util (X)	0.182	1.249	0.913	0.201	0.063	0.058	0.115	0.642	1.973	1.913	
Departure Headway (Hd)	11.547	10.911	12.435	11.917	11.191	13.035	12.514	11.784	10.702	9.693	
Convergence, Y/N	Yes										
Cap	313	339	295	303	322	276	288	308	345	385	
Service Time	9.247	8.611	10.135	9.617	8.891	10.735	10.214	9.484	8.402	7.393	
HCM Lane V/C Ratio	0.192	1.298	1.01	0.228	0.071	0.065	0.128	0.721	2.043	1.964	
HCM Control Delay	16.8	165.9	69.7	17.6	14.6	16.5	16.8	33.4	472	442.6	
HCM Lane LOS	С	F	F	С	В	С	С	D	F	F	
HCM 95th-tile Q	0.7	18.6	8.5	0.7	0.2	0.2	0.4	4.1	46.3	47.9	

Intersection												
Int Delay, s/veh	2.8											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		4	7		र्स	7		4			4	
Traffic Vol, veh/h	12	31	14	11	12	1	30	327	19	1	134	2
Future Vol, veh/h	12	31	14	11	12	1	30	327	19	1	134	2
Conflicting Peds, #/hr	10	0	10	10	0	10	9	0	8	8	0	9
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	50	-	-	50	-	-	-	-	-	-
Veh in Median Storage	e,# -	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	71	71	71	73	73	73	70	70	70	76	76	76
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	17	44	20	15	16	1	43	467	27	1	176	3
Major/Minor	Minor2			Minor1			Major1			Major2		
Conflicting Flow All	774	777	197	797	765	499	188	0	0	502	0	0
Stage 1	189	189	-	575	575	-	-	-	-	-	-	-
Stage 2	585	588	-	222	190	_	_	_	_	-	-	-
Critical Hdwy	7.12	6.52	6.22	7.12	6.52	6.22	4.12	-	-	4.12	_	_
Critical Hdwy Stg 1	6.12	5.52		6.12	5.52	-	-	_	_	-	-	_
Critical Hdwy Stg 2	6.12	5.52	-	6.12	5.52	-	-	-	_	-	-	-
Follow-up Hdwy	3.518	4.018	3.318	3.518	4.018	3.318	2.218	-	_	2.218	-	-
Pot Cap-1 Maneuver	316	328	844	305	333	572	1386	-	-	1062	-	-
Stage 1	813	744	-	503	503	-	-	-	-	-	-	-
Stage 2	497	496	-	780	743	-	-	-	-	-	-	-
Platoon blocked, %								-	-		-	-
Mov Cap-1 Maneuver	288	309	831	253	314	563	1376	-	-	1055	-	-
Mov Cap-2 Maneuver	288	309	-	253	314	-	-	-	-	-	-	-
Stage 1	772	738	-	478	478	-	-	-	-	-	-	-
Stage 2	454	471	-	710	737	-	-	-	-	-	-	-
Approach	EB			WB			NB			SB		
HCM Control Delay, s				19.1			0.6			0.1		
HCM LOS	C			C			0.0			J. 1		
Minor Long/Major Maria	nt	NDI	NDT	NDD	EDI 51	EDI ~0\	MDI ~4\	MDI ∽Ω	CDI	CDT	CDD	
Minor Lane/Major Myn	IIL	NBL	NBT	NBK		EBLn2V			SBL	SBT	SBR	
Capacity (veh/h)		1376	-	-	303	831	282	563	1055	-	-	
HCM Cantral Dalay (a	\	0.031	-	-		0.024				-	-	
HCM Control Delay (s)	7.7	0	-	19.8	9.4	19.4	11.4	8.4	0	-	
HCM Lane LOS	.\	A	Α	-	C	Α	C	В	A	Α	-	
HCM 95th %tile Q(veh	1)	0.1	-	-	0.7	0.1	0.4	0	0	-	-	

Intersection												
Intersection Delay, s/veh	13.8											
Intersection LOS	В											
intersection LOS	U											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		4	7		र्स	7		4			↔	
Traffic Vol, veh/h	12	31	14	11	12	1	30	327	19	1	134	2
Future Vol, veh/h	12	31	14	11	12	1	30	327	19	1	134	2
Peak Hour Factor	0.71	0.71	0.71	0.73	0.73	0.73	0.70	0.70	0.70	0.76	0.76	0.76
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	17	44	20	15	16	1	43	467	27	1	176	3
Number of Lanes	0	1	1	0	1	1	0	1	0	0	1	0
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	2			2			1			1		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	1			1			2			2		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	1			1			2			2		
HCM Control Delay	9.6			9.6			16.1			9.5		
HCM LOS	Α			Α			С			Α		
Lane		NBLn1	EBLn1	EBLn2	WBLn1	WBLn2	SBLn1					
Lane Vol Left, %		NBLn1 8%	EBLn1 28%	EBLn2 0%	WBLn1 48%	WBLn2	SBLn1 1%					
Vol Left, % Vol Thru, %			28% 72%		48% 52%		1% 98%					
Vol Left, %		8%	28%	0%	48%	0%	1%					
Vol Left, % Vol Thru, %		8% 87% 5% Stop	28% 72% 0% Stop	0% 0% 100% Stop	48% 52% 0% Stop	0% 0%	1% 98% 1% Stop					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane		8% 87% 5% Stop 376	28% 72% 0% Stop 43	0% 0% 100% Stop 14	48% 52% 0% Stop 23	0% 0% 100%	1% 98% 1%					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol		8% 87% 5% Stop 376 30	28% 72% 0% Stop 43 12	0% 0% 100% Stop 14 0	48% 52% 0% Stop 23	0% 0% 100% Stop 1	1% 98% 1% Stop 137					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol		8% 87% 5% Stop 376 30 327	28% 72% 0% Stop 43 12 31	0% 0% 100% Stop 14 0	48% 52% 0% Stop 23 11	0% 0% 100% Stop 1 0	1% 98% 1% Stop 137 1					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol		8% 87% 5% Stop 376 30 327	28% 72% 0% Stop 43 12 31	0% 0% 100% Stop 14 0 0	48% 52% 0% Stop 23 11 12	0% 0% 100% Stop 1 0	1% 98% 1% Stop 137 1 134					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate		8% 87% 5% Stop 376 30 327 19 537	28% 72% 0% Stop 43 12 31 0 61	0% 0% 100% Stop 14 0 0 14 20	48% 52% 0% Stop 23 11 12 0	0% 0% 100% Stop 1 0 0	1% 98% 1% Stop 137 1 134 2					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp		8% 87% 5% Stop 376 30 327 19 537	28% 72% 0% Stop 43 12 31 0 61	0% 0% 100% Stop 14 0 0 14 20	48% 52% 0% Stop 23 11 12 0 32	0% 0% 100% Stop 1 0 0	1% 98% 1% Stop 137 1 134 2 180					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X)		8% 87% 5% Stop 376 30 327 19 537 2	28% 72% 0% Stop 43 12 31 0 61 5	0% 0% 100% Stop 14 0 0 14 20 5	48% 52% 0% Stop 23 11 12 0 32 5	0% 0% 100% Stop 1 0 0 1 1 5	1% 98% 1% Stop 137 1 134 2 180 2 0.243					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd)		8% 87% 5% Stop 376 30 327 19 537 2 0.667 4.469	28% 72% 0% Stop 43 12 31 0 61 5 0.107 6.351	0% 0% 100% Stop 14 0 0 14 20 5 0.03 5.497	48% 52% 0% Stop 23 11 12 0 32 5 0.058 6.639	0% 0% 100% Stop 1 0 0 1 1 5 0.002 5.582	1% 98% 1% Stop 137 1 134 2 180 2 0.243 4.852					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X)		8% 87% 5% Stop 376 30 327 19 537 2 0.667 4.469 Yes	28% 72% 0% Stop 43 12 31 0 61 5 0.107 6.351 Yes	0% 0% 100% Stop 14 0 0 14 20 5 0.03 5.497 Yes	48% 52% 0% Stop 23 11 12 0 32 5 0.058 6.639 Yes	0% 0% 100% Stop 1 0 0 1 1 5 0.002 5.582 Yes	1% 98% 1% Stop 137 1 134 2 180 2 0.243 4.852 Yes					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd) Convergence, Y/N Cap		8% 87% 5% Stop 376 30 327 19 537 2 0.667 4.469 Yes 806	28% 72% 0% Stop 43 12 31 0 61 5 0.107 6.351 Yes 560	0% 0% 100% Stop 14 0 0 14 20 5 0.03 5.497 Yes 644	48% 52% 0% Stop 23 11 12 0 32 5 0.058 6.639 Yes 543	0% 0% 100% Stop 1 0 0 1 1 5 0.002 5.582 Yes 634	1% 98% 1% Stop 137 1 134 2 180 2 0.243 4.852 Yes 735					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd) Convergence, Y/N Cap Service Time		8% 87% 5% Stop 376 30 327 19 537 2 0.667 4.469 Yes 806 2.511	28% 72% 0% Stop 43 12 31 0 61 5 0.107 6.351 Yes 560 4.144	0% 0% 100% Stop 14 0 0 14 20 5 0.03 5.497 Yes 644 3.289	48% 52% 0% Stop 23 11 12 0 32 5 0.058 6.639 Yes 543 4.339	0% 0% 100% Stop 1 0 0 1 1 5 0.002 5.582 Yes 634 3.381	1% 98% 1% Stop 137 1 134 2 180 2 0.243 4.852 Yes 735 2.913					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd) Convergence, Y/N Cap Service Time HCM Lane V/C Ratio		8% 87% 5% Stop 376 30 327 19 537 2 0.667 4.469 Yes 806 2.511 0.666	28% 72% 0% Stop 43 12 31 0 61 5 0.107 6.351 Yes 560 4.144 0.109	0% 0% 100% Stop 14 0 0 14 20 5 0.03 5.497 Yes 644 3.289 0.031	48% 52% 0% Stop 23 11 12 0 32 5 0.058 6.639 Yes 543 4.339 0.059	0% 0% 100% Stop 1 0 0 1 1 5 0.002 5.582 Yes 634 3.381 0.002	1% 98% 1% Stop 137 1 134 2 180 2 0.243 4.852 Yes 735 2.913 0.245					
Vol Left, % Vol Thru, % Vol Right, % Sign Control Traffic Vol by Lane LT Vol Through Vol RT Vol Lane Flow Rate Geometry Grp Degree of Util (X) Departure Headway (Hd) Convergence, Y/N Cap Service Time		8% 87% 5% Stop 376 30 327 19 537 2 0.667 4.469 Yes 806 2.511	28% 72% 0% Stop 43 12 31 0 61 5 0.107 6.351 Yes 560 4.144	0% 0% 100% Stop 14 0 0 14 20 5 0.03 5.497 Yes 644 3.289	48% 52% 0% Stop 23 11 12 0 32 5 0.058 6.639 Yes 543 4.339	0% 0% 100% Stop 1 0 0 1 1 5 0.002 5.582 Yes 634 3.381	1% 98% 1% Stop 137 1 134 2 180 2 0.243 4.852 Yes 735 2.913					

5.2

0.4

0.1

0.2

0

0.9

HCM 95th-tile Q

1: Yale Ave & Michelson Dr

IIICI3CCIOII LOO	U											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	7	†	7	ň	†	7	7	f.		Ť	ĵ»	
Traffic Vol, veh/h	50	119	139	229	173	12	22	94	56	22	39	55
Future Vol, veh/h	50	119	139	229	173	12	22	94	56	22	39	55
Peak Hour Factor	0.83	0.83	0.83	0.78	0.78	0.78	0.68	0.68	0.68	0.43	0.43	0.43
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	60	143	167	294	222	15	32	138	82	51	91	128
Number of Lanes	1	1	1	1	1	1	1	1	0	1	1	0
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	3			3			2			2		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	2			2			3			3		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	2			2			3			3		
HCM Control Delay	15			24.2			19.1			18.1		
HCM LOS	В			С			С			С		

Lane	NBLn1	NBLn2	EBLn1	EBLn2	EBLn3	WBLn1	WBLn2	WBLn3	SBLn1	SBLn2	
Vol Left, %	100%	0%	100%	0%	0%	100%	0%	0%	100%	0%	
Vol Thru, %	0%	63%	0%	100%	0%	0%	100%	0%	0%	41%	
Vol Right, %	0%	37%	0%	0%	100%	0%	0%	100%	0%	59%	
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	
Traffic Vol by Lane	22	150	50	119	139	229	173	12	22	94	
LT Vol	22	0	50	0	0	229	0	0	22	0	
Through Vol	0	94	0	119	0	0	173	0	0	39	
RT Vol	0	56	0	0	139	0	0	12	0	55	
Lane Flow Rate	32	221	60	143	167	294	222	15	51	219	
Geometry Grp	6	6	6	6	6	6	6	6	6	6	
Degree of Util (X)	0.083	0.519	0.152	0.341	0.364	0.7	0.497	0.031	0.131	0.503	
Departure Headway (Hd)	9.239	8.466	9.071	8.554	7.831	8.589	8.074	7.353	9.205	8.281	
Convergence, Y/N	Yes										
Cap	388	426	396	420	459	423	446	487	390	435	
Service Time	6.987	6.214	6.82	6.303	5.579	6.335	5.82	5.099	6.952	6.028	
HCM Lane V/C Ratio	0.082	0.519	0.152	0.34	0.364	0.695	0.498	0.031	0.131	0.503	
HCM Control Delay	12.8	20	13.4	15.7	15	29.1	18.6	10.3	13.3	19.2	
HCM Lane LOS	В	С	В	С	В	D	С	В	В	С	
HCM 95th-tile Q	0.3	2.9	0.5	1.5	1.6	5.2	2.7	0.1	0.4	2.8	

Intersection												
Int Delay, s/veh	5.1											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		ની	7		र्स	7		414			4î.	
Traffic Vol, veh/h	21	36	34	33	43	2	19	136	18	13	330	64
Future Vol, veh/h	21	36	34	33	43	2	19	136	18	13	330	64
Conflicting Peds, #/hr	10	0	10	10	0	10	9	0	8	8	0	9
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	50	-	-	50	-	-	-	-	-	-
Veh in Median Storage	,# -	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	71	71	71	73	73	73	70	70	70	76	76	76
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	30	51	48	45	59	3	27	194	26	17	434	84
Major/Minor N	Minor2		N	/linor1			Major1		_	Major2		
Conflicting Flow All	710	801	278	556	830	128	527	0	0	228	0	0
Stage 1	519	519	-	269	269	120	-	-	-	-	-	-
Stage 2	191	282	_	287	561	_	_	_	<u>-</u>	_	_	<u>-</u>
Critical Hdwy	7.54	6.54	6.94	7.54	6.54	6.94	4.14	_	_	4.14	_	_
Critical Hdwy Stg 1	6.54	5.54	-	6.54	5.54	- 0.0		_	_	-	_	_
Critical Hdwy Stg 2	6.54	5.54	_	6.54	5.54	_	_	-	_	-	_	-
Follow-up Hdwy	3.52	4.02	3.32	3.52	4.02	3.32	2.22	-	-	2.22	-	_
Pot Cap-1 Maneuver	321	316	719	414	304	898	1036	-	_	1337	_	_
Stage 1	508	531	-	713	685	-	-	_	_	_	_	_
Stage 2	792	676	-	696	508	-	-	-	_	-	_	_
Platoon blocked, %								-	-		-	_
Mov Cap-1 Maneuver	256	297	708	319	285	885	1028	_	-	1328	-	-
Mov Cap-2 Maneuver	256	297	-	319	285	-	-	-	-	-	-	-
Stage 1	489	518	-	687	660	-	-	-	-	-	-	-
Stage 2	692	651	-	570	495	-	-	-	-	-	-	-
Approach	EB			WB			NB			SB		
HCM Control Delay, s	18.3			22.9			1			0.3		
HCM LOS	10.3 C			22.9 C			1			0.5		
TIOWI LOG	U			U								
Minor Lane/Major Mvm	it	NBL	NBT	NBR I		EBLn2V			SBL	SBT	SBR	
Capacity (veh/h)		1028	-	-	280	708	299	885	1328	-	-	
HCM Lane V/C Ratio		0.026	-	-		0.068				-	-	
HCM Control Delay (s)		8.6	0.1	-	22.9	10.5	23.3	9.1	7.7	0.1	-	
HCM Lane LOS		Α	Α	-	С	В	С	Α	Α	Α	-	
HCM 95th %tile Q(veh)		0.1	-	-	1.2	0.2	1.5	0	0	-	-	

Intersection	
Intersection Delay, s/veh	14.9
Intersection LOS	В

	_											/
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	7	†	7	ň	†	7	ň	f)		ň	f)	
Traffic Vol, veh/h	2	309	3	81	234	1	18	1	77	2	0	3
Future Vol, veh/h	2	309	3	81	234	1	18	1	77	2	0	3
Peak Hour Factor	0.83	0.83	0.83	0.78	0.78	0.78	0.68	0.68	0.68	0.43	0.43	0.43
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	2	372	4	104	300	1	26	1	113	5	0	7
Number of Lanes	1	1	1	1	1	1	1	1	0	1	1	0
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	3			3			2			2		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	2			2			3			3		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	2			2			3			3		
HCM Control Delay	18.1			13.7			10.4			9.9		
HCM LOS	С			В			В			Α		

Lane	NBLn1	NBLn2	EBLn1	EBLn2	EBLn3	WBLn1	WBLn2	WBLn3	SBLn1	SBLn2	
Vol Left, %	100%	0%	100%	0%	0%	100%	0%	0%	100%	0%	
Vol Thru, %	0%	1%	0%	100%	0%	0%	100%	0%	0%	0%	
Vol Right, %	0%	99%	0%	0%	100%	0%	0%	100%	0%	100%	
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	
Traffic Vol by Lane	18	78	2	309	3	81	234	1	2	3	
LT Vol	18	0	2	0	0	81	0	0	2	0	
Through Vol	0	1	0	309	0	0	234	0	0	0	
RT Vol	0	77	0	0	3	0	0	1	0	3	
Lane Flow Rate	26	115	2	372	4	104	300	1	5	7	
Geometry Grp	6	6	6	6	6	6	6	6	6	6	
Degree of Util (X)	0.054	0.196	0.004	0.624	0.005	0.188	0.501	0.002	0.01	0.013	
Departure Headway (Hd)	7.353	6.159	6.534	6.031	5.326	6.514	6.01	5.305	7.719	6.513	
Convergence, Y/N	Yes										
Cap	487	582	548	599	671	550	600	673	462	547	
Service Time	5.107	3.914	4.274	3.771	3.066	4.254	3.751	3.046	5.486	4.279	
HCM Lane V/C Ratio	0.053	0.198	0.004	0.621	0.006	0.189	0.5	0.001	0.011	0.013	
HCM Control Delay	10.5	10.4	9.3	18.3	8.1	10.8	14.7	8.1	10.6	9.4	
HCM Lane LOS	В	В	Α	С	Α	В	В	Α	В	Α	
HCM 95th-tile Q	0.2	0.7	0	4.3	0	0.7	2.8	0	0	0	

Intersection												
Int Delay, s/veh	4.5											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		र्स	7		ર્ન	7		र्सीक			414	
Traffic Vol, veh/h	11	30	13	17	17	2	34	72	21	1	76	7
Future Vol, veh/h	11	30	13	17	17	2	34	72	21	1	76	7
Conflicting Peds, #/hr	10	0	10	10	0	10	9	0	8	8	0	9
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-		-	-	None	-	-	None
Storage Length	-	-	50	-	-	50	-	-	-	-	-	-
Veh in Median Storage	,# -	0	-	-	0	-	-	0	-	-	0	-
Grade, %	_	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	71	71	71	73	73	73	70	70	70	76	76	76
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	15	42	18	23	23	3	49	103	30	1	100	9
Major/Minor N	Minor2		N	/linor1			Major1		N	Major2		
Conflicting Flow All	287	355	74	307	344	85	118	0	0	141	0	0
Stage 1	116	116	_	224	224	-		_	_		_	_
Stage 2	171	239	_	83	120	_	_	_	_	_	_	_
Critical Hdwy	7.54	6.54	6.94	7.54	6.54	6.94	4.14	_	_	4.14	_	_
Critical Hdwy Stg 1	6.54	5.54	-	6.54	5.54	-	-	_	_	-	_	_
Critical Hdwy Stg 2	6.54	5.54	_	6.54	5.54	_	_	_	_	_	_	_
Follow-up Hdwy	3.52	4.02	3.32	3.52	4.02	3.32	2.22	_	_	2.22	_	_
Pot Cap-1 Maneuver	643	569	973	622	577	957	1468	_	-	1440	_	-
Stage 1	876	799	-	758	717	-	00	_	_	-	_	_
Stage 2	814	706	_	916	796	-	_	_	_	_	_	_
Platoon blocked, %	- VII	. 00		010	. 00			_	_		_	_
Mov Cap-1 Maneuver	593	541	958	549	548	943	1457	_	-	1430	_	-
Mov Cap-2 Maneuver	593	541	-	549	548	- 510	0.	_	_		_	_
Stage 1	838	793	_	726	686	-	_	_	-	-	_	-
Stage 2	750	676	_	843	790	_	_	_	_	_	_	_
5.00 Z	. 00	3.0		3.0								
Approach	EB			WB			NB			SB		
HCM Control Delay, s	11.5			12			2.1			0.1		
HCM LOS	11.5 B			B			۷. ۱			0.1		
TOW LOO	U			U								
Minor Lane/Major Mvm	+	NBL	NBT	NIPD	ERI n1	EBLn2\	VRI 51V	VRI 52	SBL	SBT	SBR	
				NDK					1430	ODT	אמט	
Capacity (veh/h)		1457	-	-	554	958	548	943		-	-	
HCM Control Dolay (a)		0.033	- 0.1	-		0.019			0.001	-	-	
HCM Control Delay (s)		7.6	0.1	-	12.3	8.8	12.2	8.8	7.5	0	-	
HCM Lane LOS		A	Α	-	В	A	В	A	A	Α	-	
HCM 95th %tile Q(veh)		0.1	-	-	0.3	0.1	0.3	0	0	-	-	

1: Yale Ave & Michelson Dr

Intersection												
Intersection Delay, s/veh	17.6											
Intersection LOS	С											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	¥	†	7	, N	†	7	J.	f)		J.	f)	
Traffic Vol, veh/h	53	125	132	202	178	13	20	87	52	22	39	55
Future Vol, veh/h	53	125	132	202	178	13	20	87	52	22	39	55
Peak Hour Factor	0.83	0.83	0.83	0.78	0.78	0.78	0.68	0.68	0.68	0.43	0.43	0.43
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	64	151	159	259	228	17	29	128	76	51	91	128
Number of Lanes	1	1	1	1	1	1	1	1	0	1	1	0
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	3			3			2			2		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	2			2			3			3		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	2			2			3			3		
HCM Control Delay	14.4			20.4			17.3			17.1		
HCM LOS	В			С			С			С		

Lane	NBLn1	NBLn2	EBLn1	EBLn2	EBLn3	WBLn1	WBLn2	WBLn3	SBLn1	SBLn2	
Vol Left, %	100%	0%	100%	0%	0%	100%	0%	0%	100%	0%	
Vol Thru, %	0%	63%	0%	100%	0%	0%	100%	0%	0%	41%	
Vol Right, %	0%	37%	0%	0%	100%	0%	0%	100%	0%	59%	
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	
Traffic Vol by Lane	20	139	53	125	132	202	178	13	22	94	
LT Vol	20	0	53	0	0	202	0	0	22	0	
Through Vol	0	87	0	125	0	0	178	0	0	39	
RT Vol	0	52	0	0	132	0	0	13	0	55	
Lane Flow Rate	29	204	64	151	159	259	228	17	51	219	
Geometry Grp	6	6	6	6	6	6	6	6	6	6	
Degree of Util (X)	0.073	0.466	0.155	0.344	0.331	0.6	0.496	0.033	0.126	0.483	
Departure Headway (Hd)	8.977	8.205	8.728	8.213	7.492	8.344	7.831	7.112	8.878	7.957	
Convergence, Y/N	Yes										
Cap	397	437	409	435	477	430	459	500	402	450	
Service Time	6.777	6.004	6.528	6.012	5.291	6.136	5.622	4.903	6.677	5.755	
HCM Lane V/C Ratio	0.073	0.467	0.156	0.347	0.333	0.602	0.497	0.034	0.127	0.487	
HCM Control Delay	12.5	18	13.1	15.3	14	23	18.2	10.1	13	18.1	
HCM Lane LOS	В	С	В	С	В	С	С	В	В	С	
HCM 95th-tile Q	0.2	2.4	0.5	1.5	1.4	3.8	2.7	0.1	0.4	2.6	

Interception												
Intersection Int Delay, s/veh	5.4											
IIII Delay, 5/VeII												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		सी	7		सी	₹ .		4			4	
Traffic Vol, veh/h	21	36	35	31	41	2	18	128	17	13	294	66
Future Vol, veh/h	21	36	35	31	41	2	18	128	17	13	294	66
Conflicting Peds, #/hr	10	0	10	10	0	10	9	0	8	8	0	9
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	_	-	50	-	-	50	-	-	-	_	-	-
Veh in Median Storage	е,# -	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	71	71	71	73	73	73	70	70	70	76	76	76
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	30	51	49	42	56	3	26	183	24	17	387	87
Major/Minor	Minor2			Minor1			Major1			Major2		
		741	450	780	772	213	483	0	0		0	^
Conflicting Flow All	761						403		U	215		0
Stage 1	474	474 267	-	255	255	-	-	-	-	-	-	-
Stage 2	287		6 22	525	517	6.22	4.12	-	-	4 10	-	-
Critical Hdwy	7.12	6.52	6.22	7.12 6.12	6.52	0.22	4.12	-	-	4.12	-	-
Critical Hdwy Stg 1	6.12	5.52	-		5.52	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.12	5.52	3.318	6.12	5.52	2 240	2.218	-	-	2.218	-	-
Follow-up Hdwy	3.518	4.018		3.518	4.018	3.318		-	-		-	-
Pot Cap-1 Maneuver	322	344	609	313	330	827	1080	-	-	1355	-	-
Stage 1	571	558	-	749	696	-	-	-	-	-	-	-
Stage 2	720	688	-	536	534	-	-	-	-	-	-	-
Platoon blocked, %	000	204	EOO	044	244	045	1070	-	-	1240	-	-
Mov Cap-1 Maneuver	263	324	599	241	311	815	1072	-	-	1346	-	-
Mov Cap-2 Maneuver	263	324	-	241	311	-	-	-	-	-	-	-
Stage 1	552	545	-	724	672	-	-	-	-	-	-	-
Stage 2	635	665	-	435	521	-	-	-	-	-	-	-
Approach	EB			WB			NB			SB		
HCM Control Delay, s	17.7			24.7			0.9			0.3		
HCM LOS	С			С								
Minor Long/Major M.	-1	ND	NDT	NDD	EDI =4	EDIO	MDL = 41	VDI O	CDI	CDT	CDD	
Minor Lane/Major Mvn	nt	NBL	NBT			EBLn2\			SBL	SBT	SBR	
Capacity (veh/h)		1072	-	-	298	599	276	815	1346	-	-	
HCM Lane V/C Ratio		0.024	-	-		0.082				-	-	
HCM Control Delay (s)		8.4	0	-	21.5	11.5	25.1	9.4	7.7	0	-	
HCM Lane LOS		Α	Α	-	С	В	D	Α	Α	Α	-	
HCM 95th %tile Q(veh	1)	0.1	-	-	1.1	0.3	1.6	0	0	-	-	

ntersection Delay, s/veh 15
ntersection LOS B


Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	J.	†	7	¥	†	7	J.	f)		J.	f)	
Traffic Vol, veh/h	2	316	0	75	226	1	17	1	74	2	0	3
Future Vol, veh/h	2	316	0	75	226	1	17	1	74	2	0	3
Peak Hour Factor	0.83	0.83	0.83	0.78	0.78	0.78	0.68	0.68	0.68	0.43	0.43	0.43
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	2	381	0	96	290	1	25	1	109	5	0	7
Number of Lanes	1	1	1	1	1	1	1	1	0	1	1	0
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	3			3			2			2		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	2			2			3			3		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	2			2			3			3		
HCM Control Delay	18.4			13.4			10.4			9.9		
HCM LOS	С			В			В			Α		

Lane	NBLn1	NBLn2	EBLn1	EBLn2	EBLn3	WBLn1	WBLn2	WBLn3	SBLn1	SBLn2	
Vol Left, %	100%	0%	100%	0%	0%	100%	0%	0%	100%	0%	
Vol Thru, %	0%	1%	0%	100%	100%	0%	100%	0%	0%	0%	
Vol Right, %	0%	99%	0%	0%	0%	0%	0%	100%	0%	100%	
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop	
Traffic Vol by Lane	17	75	2	316	0	75	226	1	2	3	
LT Vol	17	0	2	0	0	75	0	0	2	0	
Through Vol	0	1	0	316	0	0	226	0	0	0	
RT Vol	0	74	0	0	0	0	0	1	0	3	
Lane Flow Rate	25	110	2	381	0	96	290	1	5	7	
Geometry Grp	6	6	6	6	6	6	6	6	6	6	
Degree of Util (X)	0.051	0.19	0.004	0.632	0	0.174	0.484	0.002	0.01	0.013	
Departure Headway (Hd)	7.403	6.2	6.478	5.975	5.975	6.519	6.015	5.309	7.768	6.55	
Convergence, Y/N	Yes										
Cap	483	577	552	605	0	550	600	673	459	544	
Service Time	5.159	3.955	4.217	3.714	3.714	4.261	3.756	3.05	5.536	4.317	
HCM Lane V/C Ratio	0.052	0.191	0.004	0.63	0	0.175	0.483	0.001	0.011	0.013	
HCM Control Delay	10.6	10.4	9.2	18.5	8.7	10.6	14.3	8.1	10.6	9.4	
HCM Lane LOS	В	В	Α	С	N	В	В	Α	В	Α	
HCM 95th-tile Q	0.2	0.7	0	4.4	0	0.6	2.6	0	0	0	


Intersection												
Int Delay, s/veh	4.6											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		ર્ન	7		ર્ન	7		4			4	
Traffic Vol, veh/h	11	30	14	16	17	2	32	69	20	1	66	7
Future Vol, veh/h	11	30	14	16	17	2	32	69	20	1	66	7
Conflicting Peds, #/hr	10	0	10	10	0	10	9	0	8	8	0	9
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-		-	-	None	-	-	None
Storage Length	-	-	50	-	-	50	-	-	-	-	-	-
Veh in Median Storage	e,# -	0	-	-	0	-	-	0	-	-	0	-
Grade, %	_	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	71	71	71	73	73	73	70	70	70	76	76	76
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	15	42	20	22	23	3	46	99	29	1	87	9
Major/Minor	Minor2			Minor1			Major1			Major2		
Conflicting Flow All	332	331	111	349	321	132	105	0	0	136	0	0
Stage 1	103	103	-	214	214	-	-	-	-	-	-	-
Stage 2	229	228	_	135	107	_	_	_	_	_	_	_
Critical Hdwy	7.12	6.52	6.22	7.12	6.52	6.22	4.12	-	-	4.12	-	-
Critical Hdwy Stg 1	6.12	5.52		6.12	5.52	-		_	_	-	_	_
Critical Hdwy Stg 2	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Follow-up Hdwy	3.518	4.018	3.318	3.518	4.018	3.318	2.218	-	_	2.218	_	_
Pot Cap-1 Maneuver	621	588	942	606	596	917	1486	-	_	1448	_	-
Stage 1	903	810	-	788	725		-	_	_	-	-	_
Stage 2	774	715	-	868	807	-	_	-	_	-	_	-
Platoon blocked, %				300				_	_		_	_
Mov Cap-1 Maneuver	574	560	927	536	567	903	1475	_	_	1438	_	-
Mov Cap-2 Maneuver	574	560	-	536	567	-	-	_	_		-	_
Stage 1	866	804	-	756	695	_	_	-	_	_	_	-
Stage 2	714	686	_	797	801	_	_	_	_	_	_	_
g		300			301							
Approach	EB			WB			NB			SB		
HCM Control Delay, s	11.3			11.9			2			0.1		
HCM LOS	В			В						J. 1		
TOW LOO	J			U								
Minor Lane/Major Mvm	nt	NBL	NBT	NRP	FRI n1	EBLn2\	WRI n1\	VRI n2	SBL	SBT	SBR	
Capacity (veh/h)	IL.	1475	-	NDI	564	927	552	903	1438	ODT	ODIN	
HCM Lane V/C Ratio		0.031	-	-		0.021			0.001	-	-	
		7.5	_	-	12.1	0.021	12.1		7.5	0	-	
HCM Control Delay (s) HCM Lane LOS			0	-				9		0	-	
	\	Α	Α	-	В	A	В	A	A	Α	-	
HCM 95th %tile Q(veh)	0.1	-	-	0.3	0.1	0.3	0	0	-	-	

APPENDIX D- Traffic Signal Warrants


Buildout Year I-405 Vehicular OC With 4-Lane Yale Ave AM/PM Peaks at Yale Ave / Michelson Dr




Buildout Year I-405 Vehicular OC With 4-Lane Yale Ave AM/PM Peaks at Yale Ave / Royce Rd



Buildout Year I-405 Vehicular OC With 2-Lane Yale Ave AM/PM Peaks at Yale Ave / Michelson Dr



Buildout Year I-405 Vehicular OC With 2-Lane Yale Ave AM/PM Peaks at Yale Ave / Royce Rd





© 2023 Iteris, Inc. All rights reserved.



Attachment F – Yale Avenue and U	University Drive B	ike and Pedestrian T	raffic Analysis

Technical Memorandum

To: City of Irvine From: Iteris, Inc.

Date: April 25, 2024

RE: South Yale Corridor Improvements Traffic Analysis (Bicycle Scramble for Yale/University)

This memorandum analyzes the traffic impacts of the addition of a bicycle scramble phase or bicycle/pedestrian scramble phase at the intersection of Yale Avenue/University Drive in the City of Irvine.

A diagonal bicycle crossing signal phase has been proposed at the intersection of Yale Avenue and University Drive in the City of Irvine. The City typically uses Intersection Capacity Utilization (ICU) analysis to evaluate intersection capacity. However, this diagonal bicycle crossing signal phase at this intersection would not have an effect on the ICU analysis, but the signal operations. Therefore, the City would like to analyze the intersection using the Highway Capacity Manual 6 (HCM) methodology, using Synchro software version 11.

Study Background

1.1 Study Scenarios

A total of three (3) study scenarios were identified and analyzed. The scenarios include:

- 1. Future Year No Build Scenario
 - Current signal timing will be used for no build conditions.
- 2. Future Year Build Scenario Alternative 1
 - Proposed conditions Alternative 1 includes exclusive bicycle only phase (bicycle scramble). A bicycle
 phase will be added to the existing signal timing, which is in addition to the existing pedestrian
 phases.
- Future Year Build Scenario Alternative 2
 - Proposed conditions Alternative 2 includes exclusive bicycle and pedestrian phase (bicycle/pedestrian scramble). An exclusive bicycle and pedestrian phase will be added to the existing signal phasing assuming pedestrian travel at 3.5 feet per second. Additionally, the pedestrian phase concurrent with Yale Avenue motor vehicle phase (west leg of the intersection) will be removed. The crosswalks would not be modified, but the signal phasing would provide bicycle and pedestrian travel only during the exclusive scramble phase when actuated by a pedestrian or cyclist.

1.2 Study Periods

Traffic operations were evaluated for all 3 scenarios during the weekday AM (7:00AM – 9:00AM) and PM (4:00PM – 6:00PM) peak hours under typical weekday conditions.

Traffic Volume Input

1.3 Data Source

Traffic volumes used at the study intersection were obtained from the South Yale Corridor Improvements Traffic Analysis, prepared by Iteris in May 2023. And are based on the Irvine Transportation Analysis Model (ITAM). In the South Yale Corridor Improvements Traffic Analysis, four future scenarios were analyzed. Traffic volumes for Buildout Year No I-405 Vehicular Overcrossing (OC) with Two-lane Yale Avenue was used for the purpose of this analysis, since the future scenario analyzes the removal of street modification of Yale Avenue, keeping Yale Avenue two-lane

Commuter Street between University Drive and Michelson Drive. I-405 OC along Yale Avenue will remain as pedestrians and bicycles only. **Figure 1** illustrates the South Yale Corridor under Buildout Year No I-405 Vehicular OC with Two-lane Yale Avenue. **Table 1** summarizes the intersection traffic volumes for all scenarios.

→ PROPOSED STREET LIGHT

Figure 1: South Yale Corridor (Buildout Year No I-405 Vehicular OC with Two-lane Yale Avenue)

Table 2: Buildout Intersection Traffic Volumes (All Scenarios)

#	Intersection	Time Period	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
1	1 Yale Avenue and University Drive	AM Peak Hour	Doe	s Not i	Exist	146	-	214	121	924	-	-	1,344	42
	,	PM Peak Hour				22	-	74	101	1,650	-	-	1,021	20

Note:

NB: Northbound, SB: Southbound, EB: Eastbound, WB: Westbound

L: Left, T: Through, R: Right

It should be noted that traffic volumes for the intersection of Yale Avenue/University are consistent across all 3 scenarios for their respective AM and PM peak hours. The 3 study scenarios only involve the addition of bicycle scramble or bicycle/pedestrian scramble of the intersection, without considering any future street upgrade of Yale Avenue from an existing two-lane commuter street to a four-lane secondary arterial between Michelson Drive and University Drive.

Traffic Operations Analysis

Traffic operations for the three alternatives are documented in this section of the technical memorandum for the intersection of Yale Avenue/University Drive consistent with the current *City of Irvine Traffic Study Guidelines, dated December 2020.*

1.4 Intersection Analysis Methodology

The Highway Capacity Manual (HCM) 6th Edition methodology will be used to evaluate the study intersections. This approach defines the level of service (LOS) by the average vehicle delay in seconds for the turning movements and intersection characteristics at signalized and unsignalized intersections. LOS A represents free-flow activity and LOS F represents overcapacity operation. Traffic operations analysis for HCM methodologies will be completed using Synchro 11 traffic analysis software. Signal timing for future year no build scenario is based on the existing signal timing, which was confirmed on February 6, 2024.

The length of the proposed bicycle crossing or bicycle/pedestrian crossing was provided by Mark Thomas. The diagonal length of crossing was provided as 130 feet. Signal timing for the exclusive bicycle only phase (bicycle scramble) and exclusive bicycle/pedestrian phase (bicycle/pedestrian scramble) was based on the Caltrans speed for bicycles and pedestrians and California Manual on Uniform Traffic Control Devices (CA MUTCD). Following are the Caltrans and CA MUTCD suggested speed for bicycles and pedestrians:

- Bicycle Speed: 14.7 feet/sec
 - As a note, the minimum green time for bicycle was calculated using a 10 second startup time to provide adequate/additional time for less experienced cyclists
- Pedestrian Speed: 3.5 feet/sec

LOS definitions for signalized intersections are provided in Table 2.

Table 2: Level of Service Definitions

LOS	Description
А	At this LOS, traffic volumes are low, and speed is not restricted by other vehicles. All
	signal cycles clear with no vehicles waiting through more than one original cycle.
	At this LOS, traffic volumes begin to be affected by other traffic. Between one and ten
В	percent of the signal cycles have one or more vehicles which wait through more than
	one signal cycle during peak traffic periods.
	At this LOS, operating speeds and maneuverability are closely controlled by other traffic.
С	Between 11 and 30 percent of the signal cycles have one or more vehicles which wait
	through more than one signal cycle during peak traffic periods.
D	At this LOS, traffic will operate at tolerable operating speeds, although with restricted
	maneuverability.
	Traffic will experience restricted speeds, vehicles will frequently have to wait through
E	two or more cycles at signalized intersections, and any additional traffic will result in
	breakdown of the traffic carrying ability of the system.
	Long queues of traffic, unstable flow, stoppages of long duration with traffic volumes
F	and traffic, speed can drop to zero. Traffic volumes will be less than the volume which
	occurs at LOS E.

Table 3 and **Table 4** list the signal timing for each phase for all analysis scenarios during AM and PM peak hours, separately. Please note that the total cycle length for each scenario remains consistent.

Table 3: Signal Timing (Total Spilt) for All Analysis Scenarios (AM Peak Hour)

#	Intersection	Analysis Scenario	AM Peak Hour										
			EBL	EBT	WBT	SBL	BIKE/PED	Total Cycle Length					
		Future Year No Build	30.0	140.0	110.0	60.0	-	200.0					
1	Yale Avenue and University Drive	Future Year Build Alternative 1 (Exclusive Bicycle Only Phase)	50.0	130.0	80.0	50.0	20.0	200.0					
	Offiversity Drive	Future Year Build Alternative 2 (Exclusive Bicycle and Pedestrian Phase)	23.0	125.0	102.0	25.0	50.0	200.0					

Note:

 $\textit{NB: Northbound, SB: Southbound, EB: Eastbound, WB: Westbound. All timings \ are \ in \ seconds.}$

L: Left, T: Through, R: Right

Table 4: Signal Timing (Total Spilt) for All Analysis Scenarios (PM Peak Hour)

#	Intersection	Analysis Scenario			PM Pe	eak Hour		
			EBL	EBT	WBT	SBL	BIKE/PED	Total Cycle Length
		Future Year No Build	20.0	106.0	86.0	34.0	-	140.0
1	Yale Avenue and University Drive	Future Year Build Alternative 1 (Exclusive Bicycle Only Phase)	25.0	86.0	61.0	34.0	20.0	140.0
	Offiversity Drive	Future Year Build Alternative 2 (Exclusive Bicycle and Pedestrian Phase)	20.0	56.0	36.0	34.0	50.0	140.0

Note:

NB: Northbound, SB: Southbound, EB: Eastbound, WB: Westbound. All timings are in seconds.

L: Left, T: Through, R: Right

According to the City of Irvine Traffic Study Guidelines, LOS D shall be considered acceptable for the study area. A traffic LOS impact occurs when the intersection operates at an acceptable LOS in the baseline condition and the project causes the location to become deficient. If an intersection is determined to have an LOS impact, then the project will be required to mitigate the intersection, at a minimum, back to the baseline condition.

Table 5 summarizes the intersection LOS results for all analysis scenarios during AM and PM peak hours. Synchro worksheets are provided in **Appendix A**.

Table 5: Intersection LOS for All Analysis Scenarios

#	Yale Avenue and University Drive Future Year (Exclusive Bi Future Year)	Analysis Scenario	AM Pe	ak Hour	PM Peak Hour		
			Intersection Delay (s)	LOS	Intersection Delay (s)	LOS	
		Future Year No Build	25.7	С	13.3	В	
1		Future Year Build Alternative 1 (Exclusive Bicycle Only Phase)	33.9	С	19.8	В	
	Offiverally Drive	Future Year Build Alternative 2 (Exclusive Bicycle and Pedestrian Phase)	53.1	D	32.8	С	

Note: Permissive + Overlap phasing has been added to SBR Alternative 2 in this analysis.

As indicated in **Table 5**, the study intersection is anticipated to operate at LOS D or better during both AM and PM peak hours for all analysis scenarios, with the addition of permissive + overlap phasing for the southbound right turn (SBR) movement in Alternative 2. The additional intersection delay associated with Alternative 1 and Alternative 2 are solely related to the addition of exclusive non-vehicular phase, reducing the vehicular green time, and maintaining the overall cycle length.

In conclusion, the addition of an exclusive bicycle only phase (bicycle scramble) or the addition of an exclusive bicycle and pedestrian phase (bicycle/pedestrian scramble) will not result in any deficient level of service at the study intersection. However, it should be noted that any increase in active transportation cycle length will degrade the vehicular delay at an intersection. The intersection of Yale Avenue/University Drive will continue to operate at a satisfactory LOS based on traffic volumes from "Buildout Year No I-405 Vehicular Overcrossing with Two-lane Yale Avenue" scenario in the South Yale Corridor Improvements Traffic Analysis.

Appendix A

Future Year No Build

	•	→	←	*	1	1
Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	7	^	↑	77017) j	7
Traffic Volume (vph)	121	924	1344	42	146	214
Future Volume (vph)	121	924	1344	42	146	214
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Storage Length (ft)	145	1300	1300	225	0	150
Storage Lanes	143			223	1	150
Taper Length (ft)	75				25	I
Lane Util. Factor	1.00	0.95	0.95	1.00	1.00	1.00
Ped Bike Factor	1.00	0.95	0.95	0.94	1.00	0.90
Frt				0.850		0.850
	0.050			0.850	0.050	0.650
Flt Protected	0.950	2520	2520	1500	0.950	1500
Satd. Flow (prot)	1770	3539	3539	1583	1770	1583
Flt Permitted	0.950	0500	0500	4400	0.950	4404
Satd. Flow (perm)	1770	3539	3539	1489	1770	1431
Right Turn on Red				Yes		Yes
Satd. Flow (RTOR)				22		227
Link Speed (mph)		55	50		40	
Link Distance (ft)		583	683		620	
Travel Time (s)		7.2	9.3		10.6	
Confl. Peds. (#/hr)				7		23
Confl. Bikes (#/hr)				12		45
Peak Hour Factor	0.82	0.82	0.88	0.88	0.80	0.80
Adj. Flow (vph)	148	1127	1527	48	183	268
Shared Lane Traffic (%)						
Lane Group Flow (vph)	148	1127	1527	48	183	268
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Left	Left	Right	Left	Right
Median Width(ft)		12	12		12	
Link Offset(ft)		0	0		0	
Crosswalk Width(ft)		16	16		16	
Two way Left Turn Lane		10	10		10	
Headway Factor	1.00	1.00	1.00	1.00	1.00	1.00
Turning Speed (mph)	1.00	1.00	1.00	9	1.00	9
Number of Detectors	1	2	2	1	1	1
Detector Template	Left	Thru	Thru	Right	Left	Right
Leading Detector (ft)	20	100	100	20	20	20
Trailing Detector (ft)	0	0	0	0	0	0
Detector 1 Position(ft)	0	0	0	0	0	0
Detector 1 Size(ft)	20	6	6	20	20	20
Detector 1 Type	Cl+Ex	Cl+Ex	CI+Ex	Cl+Ex	Cl+Ex	CI+Ex
Detector 1 Channel						
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 2 Position(ft)		94	94			
Detector 2 Size(ft)		6	6			
Detector 2 Type		Cl+Ex	CI+Ex			
Detector 2 Channel						
Detector 2 Extend (s)		0.0	0.0			
Dotector 2 Exterio (3)		0.0	0.0			

	۶	→	←	*	-	4
Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Turn Type	Prot	NA	NA	Perm	Prot	Perm
Protected Phases	5	2	6		4	
Permitted Phases				6		4
Detector Phase	5	2	6	6	4	4
Switch Phase		_			<u> </u>	
Minimum Initial (s)	14.0	10.0	9.0	9.0	14.0	14.0
Minimum Split (s)	19.2	17.4	29.4	29.4	32.9	32.9
Total Split (s)	30.0	140.0	110.0	110.0	60.0	60.0
Total Split (%)	15.0%	70.0%	55.0%	55.0%	30.0%	30.0%
Maximum Green (s)	24.8	132.6	102.6	102.6	54.1	54.1
Yellow Time (s)	3.2	5.4	5.4	5.4	3.9	3.9
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
• ()	5.2		7.4	7.4	5.9	
Total Lost Time (s)		7.4			5.9	5.9
Lead/Lag	Lead		Lag	Lag		
Lead-Lag Optimize?	Yes	0.0	Yes	Yes		0.0
Vehicle Extension (s)	3.0	2.0	2.0	2.0	2.0	2.0
Recall Mode	None	C-Max	C-Max	C-Max	None	None
Walk Time (s)			5.0	5.0	5.0	5.0
Flash Dont Walk (s)			17.0	17.0	22.0	22.0
Pedestrian Calls (#/hr)			7	7	23	23
Act Effct Green (s)	21.9	161.1	134.0	134.0	25.6	25.6
Actuated g/C Ratio	0.11	0.81	0.67	0.67	0.13	0.13
v/c Ratio	0.76	0.40	0.64	0.05	0.81	0.70
Control Delay	110.3	6.4	22.3	8.6	110.0	25.1
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	110.3	6.4	22.3	8.6	110.0	25.1
LOS	F	Α	С	Α	F	С
Approach Delay		18.5	21.9		59.6	
Approach LOS		В	С		E	
Intersection Summary						
Area Type:	Other					
Cycle Length: 200	Otrici					
Actuated Cycle Length: 20	Λ					
Offset: 124 (62%), Referen		o 2.EDT	and 6:\\/E	OT Start o	of 1ct Gro	on
	iceu io prias	e Z.EDI	and 0.vvc	or, Start C	151 016	CII
Natural Cycle: 105	ام مام مناسب					
Control Type: Actuated-Co	ordinated					
Maximum v/c Ratio: 0.81	05.7					100.0
Intersection Signal Delay:					ntersectio	
Intersection Capacity Utiliz	ation 81.7%)		I(JU Level	of Service
Analysis Period (min) 15						
Splits and Phases: 1: Ur	niversity Dr	& Yale Av	⁄e			
26 waster 1920s	,					
→ Ø2 (R)						
140 s						
<i>▶</i> ar +						
Ø5	Ø6 (R)					

	•	→	•	•	1	1
Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	ሻ	^	↑ ↑	7	7	7
Traffic Volume (vph)	101	1650	1021	20	22	74
Future Volume (vph)	101	1650	1021	20	22	74
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Storage Length (ft)	145	1300	1300	225	1900	150
Storage Lanes	143			1	1	150
	75			1	25	l I
Taper Length (ft)		0.05	0.05	1.00		1.00
Lane Util. Factor	1.00	0.95	0.95	1.00	1.00	
Ped Bike Factor				0.96		0.95
Frt	0.050			0.850	0.050	0.850
Flt Protected	0.950	0500	0500	4500	0.950	4500
Satd. Flow (prot)	1770	3539	3539	1583	1770	1583
Flt Permitted	0.950				0.950	,
Satd. Flow (perm)	1770	3539	3539	1522	1770	1512
Right Turn on Red				Yes		Yes
Satd. Flow (RTOR)				22		93
Link Speed (mph)		55	50		40	
Link Distance (ft)		583	683		620	
Travel Time (s)		7.2	9.3		10.6	
Confl. Peds. (#/hr)				4		9
Confl. Bikes (#/hr)				10		18
Peak Hour Factor	0.92	0.92	0.93	0.93	0.80	0.80
Adj. Flow (vph)	110	1793	1098	22	28	93
Shared Lane Traffic (%)		.,,,,,				
Lane Group Flow (vph)	110	1793	1098	22	28	93
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Left	Left	Right	Left	Right
Median Width(ft)	LGIL	12	12	ragni	12	ragni
Link Offset(ft)		0	0		0	
Crosswalk Width(ft)		16	16		16	
\ /		10	10		10	
Two way Left Turn Lane	4.00	1.00	1.00	1.00	1.00	1.00
Headway Factor	1.00	1.00	1.00	1.00	1.00	1.00
Turning Speed (mph)	15	_		9	15	9
Number of Detectors	1	2	2	1	1	1
Detector Template	Left	Thru	Thru	Right	Left	Right
Leading Detector (ft)	20	100	100	20	20	20
Trailing Detector (ft)	0	0	0	0	0	0
Detector 1 Position(ft)	0	0	0	0	0	0
Detector 1 Size(ft)	20	6	6	20	20	20
Detector 1 Type	CI+Ex	Cl+Ex	CI+Ex	Cl+Ex	Cl+Ex	CI+Ex
Detector 1 Channel						
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 2 Position(ft)	0.0	94	94	0.0	0.0	0.0
Detector 2 Size(ft)		6	6			
. ,						
Detector 2 Type		Cl+Ex	Cl+Ex			
Detector 2 Channel			2.0			
Detector 2 Extend (s)		0.0	0.0			

	٠	→	←	•	1	4
Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Turn Type	Prot	NA	NA	Perm	Prot	Perm
Protected Phases	5	2	6		4	
Permitted Phases				6		4
Detector Phase	5	2	6	6	4	4
Switch Phase						
Minimum Initial (s)	14.0	10.0	9.0	9.0	14.0	14.0
Minimum Split (s)	19.2	17.4	29.4	29.4	32.9	32.9
Total Split (s)	20.0	106.0	86.0	86.0	34.0	34.0
Total Split (%)	14.3%	75.7%	61.4%	61.4%	24.3%	24.3%
Maximum Green (s)	14.8	98.6	78.6	78.6	28.1	28.1
Yellow Time (s)	3.2	5.4	5.4	5.4	3.9	3.9
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	5.2	7.4	7.4	7.4	5.9	5.9
Lead/Lag	Lead		Lag	Lag		
Lead-Lag Optimize?	Yes		Yes	Yes		
Vehicle Extension (s)	3.0	2.0	2.0	2.0	2.0	2.0
Recall Mode	None	C-Max	C-Max	C-Max	None	None
Walk Time (s)		- 11101	5.0	5.0	5.0	5.0
Flash Dont Walk (s)			17.0	17.0	22.0	22.0
Pedestrian Calls (#/hr)			4	4	9	9
Act Effct Green (s)	14.8	110.1	90.1	90.1	16.6	16.6
Actuated g/C Ratio	0.11	0.79	0.64	0.64	0.12	0.12
v/c Ratio	0.59	0.64	0.48	0.02	0.13	0.36
Control Delay	72.9	8.4	14.5	4.4	54.6	13.5
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	72.9	8.4	14.5	4.4	54.6	13.5
LOS	E	A	В	Α	D	В
Approach Delay	_	12.2	14.3		23.0	_
Approach LOS		В	В		C	
Intersection Summary						
Area Type:	Other					
Cycle Length: 140						
Actuated Cycle Length: 1						
Offset: 104 (74%), Refere	enced to phas	e 2:EBT	and 6:WE	3T, Start o	of 1st Gree	en
Natural Cycle: 85						
Control Type: Actuated-C						
Maximum v/c Ratio: 0.64						
Intersection Signal Delay:					ntersection	
Intersection Capacity Utili	ization 71.2%			IC	CU Level	of Service (
Analysis Period (min) 15						
Splits and Phases: 1: U	Jniversity Dr 8	¾ Yale Av	re			
● Ø2 (R)						
100 -						
106 s						

Future Year Build Alternative 1 (Exclusive Bicycle Only Phase)

	•	→	•	*	-	1	
Lane Group	EBL	EBT	WBT	WBR	SBL	SBR	Ø9
Lane Configurations	*	^	^	7	*	7	
Traffic Volume (vph)	121	924	1344	42	146	214	
Future Volume (vph)	121	924	1344	42	146	214	
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	
Storage Length (ft)	145	1000	1000	225	0	150	
Storage Lanes	1			1	1	1	
Taper Length (ft)	75			•	25	•	
Lane Util. Factor	1.00	0.95	0.95	1.00	1.00	1.00	
Ped Bike Factor	1.00	0.00	0.00	0.94	1.00	0.94	
Frt				0.850		0.850	
Flt Protected	0.950			0.000	0.950	0.000	
Satd. Flow (prot)	1770	3539	3539	1583	1770	1583	
Flt Permitted	0.950	- 5500		. 300	0.950	. 300	
Satd. Flow (perm)	1770	3539	3539	1484	1770	1485	
Right Turn on Red	.,,,	- 5500		Yes	.,,,	Yes	
Satd. Flow (RTOR)				17		237	
Link Speed (mph)		55	50		40		
Link Distance (ft)		583	683		620		
Travel Time (s)		7.2	9.3		10.6		
Confl. Peds. (#/hr)			5.0	7		23	
Confl. Bikes (#/hr)				12			
Peak Hour Factor	0.82	0.82	0.88	0.88	0.80	0.80	
Adj. Flow (vph)	148	1127	1527	48	183	268	
Shared Lane Traffic (%)							
Lane Group Flow (vph)	148	1127	1527	48	183	268	
Enter Blocked Intersection	No	No	No	No	No	No	
Lane Alignment	Left	Left	Left	Right	Left	Right	
Median Width(ft)		12	12		12		
Link Offset(ft)		0	0		0		
Crosswalk Width(ft)		16	16		16		
Two way Left Turn Lane							
Headway Factor	1.00	1.00	1.00	1.00	1.00	1.00	
Turning Speed (mph)	15			9	15	9	
Number of Detectors	1	2	2	1	1	1	
Detector Template	Left	Thru	Thru	Right	Left	Right	
Leading Detector (ft)	20	100	100	20	20	20	
Trailing Detector (ft)	0	0	0	0	0	0	
Detector 1 Position(ft)	0	0	0	0	0	0	
Detector 1 Size(ft)	20	6	6	20	20	20	
Detector 1 Type	CI+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	CI+Ex	
Detector 1 Channel							
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(ft)		94	94				
Detector 2 Size(ft)		6	6				
Detector 2 Type		Cl+Ex	Cl+Ex				
Detector 2 Channel							
Detector 2 Extend (s)		0.0	0.0				

	٠	→	←	*	-	1			
Lane Group	EBL	EBT	WBT	WBR	SBL	SBR	Ø9		
Turn Type	Prot	NA	NA	Perm	Prot	Perm			
Protected Phases	5	2	6		4		9		
Permitted Phases				6		4			
Detector Phase	5	2	6	6	4	4			
Switch Phase									
Minimum Initial (s)	14.0	10.0	9.0	9.0	14.0	14.0	15.0		
Minimum Split (s)	19.2	17.4	29.4	29.4	32.9	32.9	20.0		
Total Split (s)	50.0	130.0	80.0	80.0	50.0	50.0	20.0		
Total Split (%)	25.0%	65.0%	40.0%	40.0%	25.0%	25.0%	10%		
Maximum Green (s)	44.8	122.6	72.6	72.6	44.1	44.1	15.0		
rellow Time (s)	3.2	5.4	5.4	5.4	3.9	3.9	3.0		
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0		
ost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	2.0		
Total Lost Time (s)	5.2	7.4	7.4	7.4	5.9	5.9			
Lead/Lag	Lead	7.4	Lag	Lag	5.5	5.9			
Lead-Lag Optimize?	Yes		Yes	Yes					
/ehicle Extension (s)	3.0	2.0	2.0	2.0	2.0	2.0	2.0		
Recall Mode	None	C-Max	C-Max	C-Max	None	None	None		
	None	C-IVIAX	5.0		5.0	5.0	5.0		
Valk Time (s)				5.0					
Flash Dont Walk (s)			17.0	17.0	22.0 23	22.0	6.0		
Pedestrian Calls (#/hr)	00.4	445.0	7	7		23	45		
Act Effct Green (s)	22.1	145.2	117.9	117.9	25.5	25.5			
Actuated g/C Ratio	0.11	0.73	0.59	0.59	0.13	0.13			
/c Ratio	0.76	0.44	0.73	0.05	0.81	0.68			
Control Delay	109.2	12.9	35.6	15.7	110.5	21.5			
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0			
Total Delay	109.2	12.9	35.6	15.7	110.5	21.5			
.OS	F	В	D	В	F	С			
Approach Delay		24.1	35.0		57.6				
Approach LOS		С	С		Е				
ntersection Summary									
Area Type:	Other								
Cycle Length: 200									
Actuated Cycle Length: 200									
Offset: 124 (62%), Referen	ced to phas	se 2:EBT	and 6:WE	3T, Start o	of 1st Gre	en			
Natural Cycle: 135									
Control Type: Actuated-Co	ordinated								
Maximum v/c Ratio: 0.81									
ntersection Signal Delay: 3					ntersectio				
ntersection Capacity Utiliza	ation 81.7%	,)		[(CU Level	of Service	e D		
Analysis Period (min) 15									
Splits and Phases: 1: Un	niversity Dr	& Yale Av	re						
→ø2 (R)	•						4	04	# ko
130 s						- 3	50 s	<i>-</i> 1	20 s
	4	Ø6 (R)							
50 e	90	20 (10)	<u></u>						

	•	→	•	*	/	1	
Lane Group	EBL	EBT	WBT	WBR	SBL	SBR	Ø9
Lane Configurations	*	^	^	7	*	7	
Traffic Volume (vph)	101	1650	1021	20	22	74	
Future Volume (vph)	101	1650	1021	20	22	74	
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	
Storage Length (ft)	145	1500	1500	225	0	150	
Storage Lanes	1			1	1	130	
Taper Length (ft)	75				25	l I	
Lane Util. Factor	1.00	0.95	0.95	1.00	1.00	1.00	
Ped Bike Factor	1.00	0.33	0.33	0.96	1.00	0.97	
Frt				0.850		0.850	
Flt Protected	0.950			0.050	0.950	0.050	
		3539	3539	1583	1770	1583	
Satd. Flow (prot)	1770	ანაშ	ანამ	1303		1503	
Flt Permitted	0.950	2520	2520	1517	0.950	1542	
Satd. Flow (perm)	1770	3539	3539	1517	1770	1543	
Right Turn on Red				Yes		Yes	
Satd. Flow (RTOR)				16	40	93	
Link Speed (mph)		55	50		40		
Link Distance (ft)		583	683		620		
Travel Time (s)		7.2	9.3		10.6	^	
Confl. Peds. (#/hr)				4		9	
Confl. Bikes (#/hr)	0.00	0.00	0.00	10	0.00	0.00	
Peak Hour Factor	0.92	0.92	0.93	0.93	0.80	0.80	
Adj. Flow (vph)	110	1793	1098	22	28	93	
Shared Lane Traffic (%)							
Lane Group Flow (vph)	110	1793	1098	22	28	93	
Enter Blocked Intersection	No	No	No	No	No	No	
Lane Alignment	Left	Left	Left	Right	Left	Right	
Median Width(ft)		12	12		12		
Link Offset(ft)		0	0		0		
Crosswalk Width(ft)		16	16		16		
Two way Left Turn Lane							
Headway Factor	1.00	1.00	1.00	1.00	1.00	1.00	
Turning Speed (mph)	15			9	15	9	
Number of Detectors	1	2	2	1	1	1	
Detector Template	Left	Thru	Thru	Right	Left	Right	
Leading Detector (ft)	20	100	100	20	20	20	
Trailing Detector (ft)	0	0	0	0	0	0	
Detector 1 Position(ft)	0	0	0	0	0	0	
Detector 1 Size(ft)	20	6	6	20	20	20	
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	CI+Ex	CI+Ex	
Detector 1 Channel							
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(ft)		94	94				
Detector 2 Size(ft)		6	6				
Detector 2 Type		Cl+Ex	Cl+Ex				
Detector 2 Channel							
Detector 2 Extend (s)							

	٠	→	•	*	1	4		
Lane Group	EBL	EBT	WBT	WBR	SBL	SBR	Ø9	
Turn Type	Prot	NA	NA	Perm	Prot	Perm		
Protected Phases	5	2	6		4		9	
Permitted Phases				6		4		
Detector Phase	5	2	6	6	4	4		
Switch Phase								
Minimum Initial (s)	14.0	10.0	9.0	9.0	14.0	14.0	15.0	
Minimum Split (s)	19.2	17.4	29.4	29.4	32.9	32.9	20.0	
otal Split (s)	25.0	86.0	61.0	61.0	34.0	34.0	20.0	
otal Split (%)	17.9%	61.4%	43.6%	43.6%	24.3%	24.3%	14%	
Maximum Green (s)	19.8	78.6	53.6	53.6	28.1	28.1	15.0	
'ellow Time (s)	3.2	5.4	5.4	5.4	3.9	3.9	3.0	
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0	
ost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0		
otal Lost Time (s)	5.2	7.4	7.4	7.4	5.9	5.9		
ead/Lag	Lead		Lag	Lag	0.0	0.0		
ead-Lag Optimize?	Yes		Yes	Yes				
/ehicle Extension (s)	3.0	2.0	2.0	2.0	2.0	2.0	2.0	
Recall Mode	None	C-Max	C-Max	C-Max	None	None	None	
Valk Time (s)	INOTIC	O-IVIAX	5.0	5.0	5.0	5.0	5.0	
lash Dont Walk (s)			17.0	17.0	22.0	22.0	6.0	
edestrian Calls (#/hr)			4	4	9	9	18	
Act Effct Green (s)	15.5	102.1	81.4	81.4	16.6	16.6	10	
Actuated g/C Ratio	0.11	0.73	0.58	0.58	0.12	0.12		
/c Ratio	0.11	0.73	0.53	0.02	0.12	0.12		
Control Delay	70.2	15.2	22.1	11.1	54.6	13.3		
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0		
Total Delay	70.2	15.2	22.1	11.1	54.6	13.3		
.OS	70.2 E	13.2 B	ZZ.1	В	D D	13.3 B		
Approach Delay	L	18.4	21.9	D	22.9	U		
Approach LOS		10.4 B	Z1.9		22.9 C			
Approach LOS		Ь	C		C			
ntersection Summary								
rea Type:	Other							
Cycle Length: 140								
Actuated Cycle Length: 140								
Offset: 104 (74%), Reference	ced to phas	e 2:EBT	and 6:WE	31, Start c	t 1st Gree	en		
Natural Cycle: 115								
Control Type: Actuated-Coo	ordinated							
Maximum v/c Ratio: 0.69								
ntersection Signal Delay: 1					tersection			
ntersection Capacity Utiliza	ation 71.2%			IC	CU Level	of Service	C	
Analysis Period (min) 15								
Splits and Phases: 1: Un	iversity Dr	& Yale Av	'e					
→ø2 (R)							Ø4	Å ₽ø9
36 s							34 s	20 s
A	4							

Future Year Build Alternative 2
(Exclusive Bicycle and Pedestrian Phase)

	•	→	•	*	1	1	
Lane Group	EBL	EBT	WBT	WBR	SBL	SBR	Ø9
Lane Configurations	*	^	^	7	*	7	
Traffic Volume (vph)	121	924	1344	42	146	214	
Future Volume (vph)	121	924	1344	42	146	214	
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	
Storage Length (ft)	145	1500	1000	225	0	150	
Storage Lanes	1			1	1	1	
Taper Length (ft)	75			•	25	•	
Lane Util. Factor	1.00	0.95	0.95	1.00	1.00	1.00	
Ped Bike Factor	1.00	0.50	0.50	0.94	1.00	1.00	
Frt				0.850		0.850	
Flt Protected	0.950			0.000	0.950	0.000	
Satd. Flow (prot)	1770	3539	3539	1583	1770	1583	
Flt Permitted	0.950	0000	0000	1000	0.950	1000	
Satd. Flow (perm)	1770	3539	3539	1488	1770	1583	
Right Turn on Red	1770	3333	3333	Yes	1770	Yes	
Satd. Flow (RTOR)				20		227	
Link Speed (mph)		55	50	20	40	221	
Link Opeed (mpn) Link Distance (ft)		583	683		620		
Travel Time (s)		7.2	9.3		10.6		
. ,		1.2	ყ.ა	7	10.0		
Confl. Peds. (#/hr) Confl. Bikes (#/hr)				12			
Peak Hour Factor	0.82	0.82	0.88	0.88	0.80	0.80	
	148	1127	1527	48	183	268	
Adj. Flow (vph)	140	1121	1321	40	100	200	
Shared Lane Traffic (%)	148	1127	1527	48	183	268	
Lane Group Flow (vph) Enter Blocked Intersection	No	No	152 <i>1</i>	46 No	No	Zoo No	
	Left	Left	Left		Left		
Lane Alignment	Leit	12	12	Right	12	Right	
Median Width(ft) Link Offset(ft)		0	0		0		
. ,							
Crosswalk Width(ft)		16	16		16		
Two way Left Turn Lane	1.00	1.00	1.00	1.00	1.00	1.00	
Headway Factor	1.00	1.00	1.00	1.00	1.00	1.00	
Turning Speed (mph)	15	0	0	9	15	9	
Number of Detectors	1	2	2	Dialet	1	1 Diamet	
Detector Template	Left	Thru	Thru	Right	Left	Right	
Leading Detector (ft)	20	100	100	20	20	20	
Trailing Detector (ft)	0	0	0	0	0	0	
Detector 1 Position(ft)	0	0	0	0	0	0	
Detector 1 Size(ft)	20	6	6	20	20	20	
Detector 1 Type	CI+Ex	Cl+Ex	CI+Ex	CI+Ex	CI+Ex	CI+Ex	
Detector 1 Channel							
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(ft)		94	94				
Detector 2 Size(ft)		6	6				
Detector 2 Type		Cl+Ex	CI+Ex				
Detector 2 Channel							
Detector 2 Extend (s)		0.0	0.0				

	٠	→	•	*	1	4			
_ane Group	EBL	EBT	WBT	WBR	SBL	SBR	Ø9		
Turn Type	Prot	NA	NA	Perm	Prot	pm+ov			
Protected Phases	5	2	6		4	5	9		
Permitted Phases				6		4			
Detector Phase	5	2	6	6	4	5			
Switch Phase									
Minimum Initial (s)	14.0	10.0	9.0	9.0	14.0	14.0	45.0		
Minimum Split (s)	19.2	17.4	29.4	29.4	19.9	19.2	50.0		
Total Split (s)	23.0	125.0	102.0	102.0	25.0	23.0	50.0		
Fotal Split (%)	11.5%	62.5%	51.0%	51.0%	12.5%	11.5%	25%		
Maximum Green (s)	17.8	117.6	94.6	94.6	19.1	17.8	45.0		
Yellow Time (s)	3.2	5.4	5.4	5.4	3.9	3.2	3.0		
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0		
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0			
Total Lost Time (s)	5.2	7.4	7.4	7.4	5.9	5.2			
_ead/Lag	Lead		Lag	Lag		Lead			
_ead-Lag Optimize?	Yes		Yes	Yes		Yes			
Vehicle Extension (s)	3.0	2.0	2.0	2.0	2.0	3.0	2.0		
Recall Mode	None	C-Max	C-Max	C-Max	None	None	None		
Walk Time (s)		·	5.0	5.0			5.0		
Flash Dont Walk (s)			17.0	17.0			35.0		
Pedestrian Calls (#/hr)			7	7			68		
Act Effct Green (s)	17.8	117.6	94.6	94.6	19.1	37.6			
Actuated g/C Ratio	0.09	0.59	0.47	0.47	0.10	0.19			
v/c Ratio	0.94	0.54	0.91	0.07	1.08	0.56			
Control Delay	145.1	26.1	58.2	18.1	171.6	12.0			
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0			
Total Delay	145.1	26.1	58.2	18.1	171.6	12.0			
LOS	F	С	E	В	F	В			
Approach Delay	•	39.9	57.0	_	76.7	_			
Approach LOS		D	E		E				
Intersection Summary									
Area Type:	Other								
Cycle Length: 200	_								
Actuated Cycle Length: 20		0 EDT	10145	- o					
Offset: 124 (62%), Referer	nced to phas	se 2:EBT	and 6:WE	31, Start o	of 1st Gre	en			
Natural Cycle: 150									
Control Type: Actuated-Co	ordinated								
Maximum v/c Ratio: 1.08	-0 4					100.5			
ntersection Signal Delay:						n LOS: D			
ntersection Capacity Utiliz	ation /5.9%) 		IC	U Level	of Service	υ		
Analysis Period (min) 15									
Splits and Phases: 1: Ui	niversity Dr	& Yale Av	re						
→ Ø2 (R)	•					la de	Ø4	A Agg	
125 s							25 s	50 s	
Ø5 Ø6 (R)								

	•	-	←	*	1	4	
Lane Group	EBL	EBT	WBT	WBR	SBL	SBR	Ø9
Lane Configurations	*	^	^	7	*	7	
Traffic Volume (vph)	101	1650	1021	20	22	74	
Future Volume (vph)	101	1650	1021	20	22	74	
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	
Storage Length (ft)	145	1000	1000	225	0	150	
Storage Lanes	1			1	1	1	
Taper Length (ft)	75			•	25	•	
Lane Util. Factor	1.00	0.95	0.95	1.00	1.00	1.00	
Ped Bike Factor	1.00	0.00	0.00	0.95	1.00	1.00	
Frt				0.850		0.850	
Flt Protected	0.950			0.000	0.950	0.000	
Satd. Flow (prot)	1770	3539	3539	1583	1770	1583	
Flt Permitted	0.950	0000	0000	1000	0.950	1000	
Satd. Flow (perm)	1770	3539	3539	1504	1770	1583	
Right Turn on Red	1110	0000	0000	Yes	1770	Yes	
Satd. Flow (RTOR)				12		93	
Link Speed (mph)		55	50	12	40	30	
Link Distance (ft)		583	683		620		
Travel Time (s)		7.2	9.3		10.6		
Confl. Peds. (#/hr)		1.2	9.5	4	10.0		
Confl. Bikes (#/hr)				10			
Peak Hour Factor	0.92	0.92	0.93	0.93	0.80	0.80	
Adj. Flow (vph)	110	1793	1098	22	28	93	
Shared Lane Traffic (%)	110	1793	1090	22	20	33	
Lane Group Flow (vph)	110	1793	1098	22	28	93	
Enter Blocked Intersection	No	No	No	No	No	No	
Lane Alignment	Left	Left	Left		Left		
Median Width(ft)	Leit	12	12	Right	12	Right	
Link Offset(ft)		0	0		0		
Crosswalk Width(ft)		16	16		16		
` ,		10	10		10		
Two way Left Turn Lane	1.00	1.00	1.00	1.00	1.00	1.00	
Headway Factor	1.00 15	1.00	1.00	1.00	1.00 15	1.00	
Turning Speed (mph)		2	2	9		9	
Number of Detectors	1	2 Thru	2 Thru	1 Diaht	1		
Detector Template	Left	Thru	Thru	Right	Left	Right	
Leading Detector (ft)	20	100	100	20	20	20	
Trailing Detector (ft)	0	0	0	0	0	0	
Detector 1 Position(ft)	0	0	0	0	0	0	
Detector 1 Size(ft)	20	6	6	20	20	20	
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	CI+Ex	CI+Ex	
Detector 1 Channel	2.2	2.2	2.2	2.2	2.2	2.2	
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(ft)		94	94				
Detector 2 Size(ft)		6	6				
Detector 2 Type		Cl+Ex	CI+Ex				
Detector 2 Channel							
Detector 2 Extend (s)		0.0	0.0				

	۶	→	—	•	1	4	
Lane Group	EBL	EBT	WBT	WBR	SBL	SBR	Ø9
Turn Type	Prot	NA	NA	Perm	Prot	pm+ov	
Protected Phases	5	2	6		4	5	9
Permitted Phases	•	_		6	-	4	-
Detector Phase	5	2	6	6	4	5	
Switch Phase	•	_			-	-	
Minimum Initial (s)	14.0	10.0	9.0	9.0	14.0	14.0	45.0
Minimum Split (s)	19.2	17.4	29.4	29.4	19.9	19.2	50.0
Total Split (s)	20.0	56.0	36.0	36.0	34.0	20.0	50.0
Total Split (%)	14.3%	40.0%	25.7%	25.7%	24.3%	14.3%	36%
Maximum Green (s)	14.8	48.6	28.6	28.6	28.1	14.8	45.0
Yellow Time (s)	3.2	5.4	5.4	5.4	3.9	3.2	3.0
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	2.0
Total Lost Time (s)	5.2	7.4	7.4	7.4	5.9	5.2	
Lead/Lag	Lead	7.7	Lag	Lag	J.J	Lead	
Lead-Lag Optimize?	Yes		Yes	Yes		Yes	
Vehicle Extension (s)	3.0	2.0	2.0	2.0	2.0	3.0	2.0
Recall Mode	None	C-Max	C-Max	C-Max	None	None	None
Walk Time (s)	INOILE	O-IVIAX	5.0	5.0	INOHE	NOHE	5.0
Flash Dont Walk (s)			17.0	17.0			35.0
Pedestrian Calls (#/hr)			4	4			27
Act Effct Green (s)	15.5	93.6	70.0	70.0	14.0	24.3	21
Actuated g/C Ratio	0.11	0.67	0.50	0.50	0.10	0.17	
v/c Ratio	0.11	0.07	0.62	0.00	0.10	0.17	
	70.3	29.6	36.1	22.4	60.0	5.9	
Control Delay	0.0	0.0	0.0	0.0	0.0	0.0	
Queue Delay	70.3	29.6	36.1	22.4	60.0		
Total Delay LOS						5.9	
	E	C	D	С	10.4	Α	
Approach Delay		31.9	35.9		18.4		
Approach LOS		С	D		В		
Intersection Summary	0.11						
Area Type:	Other						
Cycle Length: 140	40						
Actuated Cycle Length: 1		0 EDT	LOME	T 01. 1.	14.10		
Offset: 104 (74%), Refere	enced to phas	se 2:EBT	and 6:VVE	31, Start c	of 1st Gre	en	
Natural Cycle: 150							
Control Type: Actuated-C	Coordinated						
Maximum v/c Ratio: 0.76							
Intersection Signal Delay:						n LOS: C	
Intersection Capacity Utili	ization 68.4%			IC	CU Level	of Service	C C
Analysis Period (min) 15							
Splits and Phases: 1: U	Jniversity Dr	& Yale Av	re				
→ @2 (p)				Ø4			ARos
J → Ø2 (R) 56 s				34 s			50 s
JA							30.5
Ø5	Ø6 (R)						
20 s 36 s							











prepared by:

