

---

# **Appendix E**

## Geotechnical Evaluation



June 5, 2023

Project No. 23052-01

Ms. Johanna Crooker  
**Meritage Homes**  
5 Peters Canyon Road, Suite 310  
Irvine, CA 92606

**Subject: Preliminary Geotechnical Subsurface Due Diligence Evaluation for the Proposed Residential Development, 9407 Jericho Road, La Mesa, California**

In accordance with your request, LGC Geotechnical, Inc. has performed a geotechnical subsurface due diligence evaluation for the proposed residential development located at 9407 Jericho Road in the City of La Mesa, California. This report summarizes the results of our background review, subsurface exploration, and geotechnical analyses of the data collected, and presents our findings, conclusions, and preliminary recommendations for the proposed residential project.

If you should have any questions regarding this report, please do not hesitate to contact our office. We appreciate this opportunity to be of service.

Respectfully,

**LGC Geotechnical, Inc.**




Dennis Boratyniec, GE 2770  
Vice President



Branden Petersen, EIT  
Senior Staff Engineer

DJB/BPP/ala

Distribution: (1) Addressee (electronic copy, wet signed copies can be provided upon request)



## **TABLE OF CONTENTS**

<b><u>Section</u></b>	<b><u>Page</u></b>
<b>1.0 INTRODUCTION.....</b>	<b>2</b>
1.1 Purpose and Scope of Services.....	2
1.2 Existing Site Conditions and Proposed Improvements.....	2
1.3 Subsurface Evaluation .....	3
1.4 Field Percolation Testing.....	3
1.5 Laboratory Testing.....	4
<b>2.0 GEOTECHNICAL CONDITIONS .....</b>	<b>6</b>
2.1 Regional Geology.....	6
2.2 Site Geology and Generalized Subsurface Conditions.....	6
2.3 Groundwater .....	6
2.4 Faulting and Seismic Hazards .....	7
2.4.1 Liquefaction and Dynamic Settlement.....	7
2.4.2 Lateral Spreading .....	7
2.5 Seismic Design Criteria.....	8
2.7 Oversized Material .....	10
2.8 Expansion Potential .....	10
<b>3.0 CONCLUSIONS.....</b>	<b>11</b>
<b>4.0 RECOMMENDATIONS .....</b>	<b>12</b>
4.1 Site Earthwork .....	12
4.1.1 Site Preparation .....	12
4.1.2 Removal Depths and Limits .....	13
4.1.4 Temporary Excavations.....	14
4.1.5 Removal Bottoms Subgrade Preparation .....	15
4.1.6 Material for Fill.....	15
4.1.7 Placement and Compaction of Fills.....	16
4.1.8 Trench and Retaining Wall Backfill and Compaction .....	16
4.1.9 Shrinkage and Subsidence.....	17
4.1.9 Shrinkage and Subsidence.....	17
4.2 Preliminary Foundation Recommendations .....	17
4.2.1 Preliminary Conventional Foundation Design Parameters.....	18
4.2.2 Provisional Post-Tensioned Foundation Design Parameters.....	18
4.2.3 Shallow Foundation Maintenance.....	19
4.2.4 Slab Underlayment Guidelines .....	20
4.4 Foundation Setback from Top-of-Slope and Bottom-of-Slope .....	20
4.3 Soil Bearing and Lateral Resistance.....	21
4.4 Lateral Earth Pressures and Retaining Wall Design Considerations .....	21
4.5 Corrosivity to Concrete and Metal .....	23
4.6 Preliminary Asphalt Concrete Pavement Sections .....	23
4.7 Nonstructural Concrete Flatwork .....	24



## **TABLE OF CONTENTS (Cont'd)**

4.8	Subsurface Water Infiltration.....	25
4.9	Control of Surface Water and Drainage Control.....	26
4.10	Geotechnical Plan Review .....	26
4.11	Geotechnical Observation and Testing .....	27
<b>5.0</b>	<b>LIMITATIONS.....</b>	<b>28</b>

## **LIST OF TABLES, ILLUSTRATIONS, & APPENDICES**

### **Tables**

Table 1 – Summary of Infiltration Testing (Page 4)
Table 2 – Seismic Design Parameters (Page 9)
Table 3 – Preliminary Post-Tensioned Foundation Design Parameters (Page 19)
Table 4 – Lateral Earth Pressures – Approved Imported Sandy Soils (Page 22)
Table 5 – Preliminary Pavement Sections (Page 24)
Table 6 – Nonstructural Concrete Flatwork for Low Expansion Potential (Page 25)

### **Figures**

Figure 1 – Site Location Map (Page 5)
Figure 2 – Geotechnical Map (Rear of Text)
Figure 3 – Retaining Wall Backfill Detail (Rear of Text)

### **Appendices**

Appendix A – References
Appendix B – Boring Logs
Appendix C – Laboratory Test Results
Appendix D – Infiltration Test Data
Appendix E – General Earthwork and Grading Specifications for Rough Grading

## **1.0 INTRODUCTION**

### **1.1 Purpose and Scope of Services**

This report presents the results of our geotechnical subsurface due diligence evaluation for the proposed residential development located at 9407 Jericho Road in the City of La Mesa, California (see Site Location Map, Figure 1). The purpose of our work was to collect subsurface data in order to confirm that the site can be developed from a geotechnical perspective. Our scope of services included:

- Review of pertinent readily available geotechnical information and geologic maps (Appendix A).
- Subsurface investigation including excavation, sampling, and logging of five small-diameter hollow stem borings.
- Infiltration testing at two of the small-diameter hollow-stem borings.
- Laboratory testing of representative samples obtained during our subsurface evaluation (Appendix C).
- Geotechnical analysis and evaluation of the data obtained, including:
  - Suitability of the site for the proposed development from a geotechnical standpoint;
  - Description of the site geology, and subsurface soil and groundwater conditions;
  - Evaluation of the seismic conditions at the site, including seismic design criteria based on the 2022 California Building Code (CBC); and
  - Recommendations for remedial grading operations and site preparation.
- Preparation of this report presenting our findings, conclusions and recommendations with respect to the proposed site development.

### **1.2 Existing Site Conditions and Proposed Improvements**

The approximately 3.5-acre rectangularly shaped site is bound to the north, west, and south by existing residential communities and to the east by Jericho Road. Review of historical aerial photographs suggests the site has been developed since at least 1964. As far back as 1953 there had been a single structure with a driveway and open space. Since 1964 there have been multiple buildings added, improvements to the parking lot, and improvements to the playground. By 1978 communities to the northeast and southwest had also been completely developed. The site is currently a church and contains multiple buildings, a concrete parking lot, an asphalt basketball court, and multiple open grassy areas.

The proposed development will consist of single-family residential with associated improvements. We expect the proposed residential development will be at-grade with relatively light building loads (column and wall loads assumed to be a maximum of approximately 30 kips and 3 kips per lineal foot, respectively). We expect minimal cuts and fills throughout the site on the order of approximately 5 or less.

The recommendations provided herein are based upon the estimated structural loading and expected layout information above. We understand that the project plans are currently being developed at this time; LGC Geotechnical should be provided with updated project plans (including grading plans, retaining walls, etc.) and any changes to the assumed structural loads

when they become available, in order to either confirm or modify the recommendations provided herein.

### **1.3 Subsurface Evaluation**

LGC Geotechnical performed a subsurface geotechnical evaluation of the site consisting of the excavation of 5 hollow-stem auger borings.

Five hollow-stem borings (HS-1 through HS-3, I-1, and I-2) were drilled to depths ranging from approximately 6.5 to 14 feet below existing grade. An LGC Geotechnical representative observed the drilling operations, logged the borings, and collected soil samples for laboratory testing. The borings were excavated using a truck-mounted drill rig equipped with 8-inch-diameter hollow-stem augers. Driven soil samples were collected by means of the Standard Penetration Test (SPT) and Modified California Drive (MCD) sampler generally obtained at 2.5 to 5-foot vertical increments. The MCD is a split-barrel sampler with a tapered cutting tip and lined with a series of 1-inch-tall brass rings. The SPT sampler and MCD sampler were driven using a 140-pound automatic hammer falling 30 inches to advance the sampler a total depth of 18 inches. The raw blow counts for each 6-inch increment of penetration were recorded on the boring logs. Bulk samples were also collected and logged at select depths for laboratory testing. At the completion of drilling, the borings were backfilled with the native soil cuttings and tamped. Some settlement of the backfill soils may occur over time.

The approximate locations of borings are shown on the Geotechnical Map (Figure 2). Boring logs are presented in Appendix B.

### **1.4 Field Percolation Testing**

Two falling head field percolation tests (I-1 and I-2) were performed in the approximate locations indicated on our Geotechnical Map (Figure 2). Estimation of infiltration rates for the site was accomplished in general accordance with the guidelines set forth by the County of San Diego (2020). A 3-inch diameter perforated PVC pipe with filter sock was placed in the borehole, and the annulus was backfilled with gravel, including placement of approximately 2 inches of gravel at the bottom of the borehole. The infiltration wells were pre-soaked the day prior to testing. During the pre-test, if the water level drops more than 6 inches in 25 minutes for two consecutive readings, the test procedure for coarse-grained soils was followed. If the water level did not drop 6 inches in one or both pre-test readings, the procedure for fine-grained soils was followed. The procedure for coarse-grained soils requires performing the test for one hour and taking one reading every 10 minutes from a fixed reference point. The procedure for fine-grained soils requires performing the test for six hours and taking one reading every 30 minutes from a fixed reference point.

The pre-tests indicated the procedure for fine-grained soils should be followed. The calculated infiltration is normalized relative to the three-dimensional flow that occurs within the field test to a one-dimensional flow out of the bottom of the boring only (i.e., "Porchet Method"). The measured infiltration rates (for feasibility purposes only) are provided in Table 1 below. Please note that infiltration is discussed in Section 4.8 and field data is provided in Appendix D.

**TABLE 1**  
**Summary of Field Infiltration Testing**

<b>Infiltration Test No.</b>	<b>Approx. Depth Below Existing Grade (ft)</b>	<b>Measured Infiltration Rate* (in./hr.)</b>
I-1	10	0.005
I-2	10	0.007

\*Measured Infiltration Rates Do Not Include Factor of Safety.

### **1.5 Laboratory Testing**


Laboratory testing was performed on representative soil samples obtained from our subsurface evaluation. Laboratory testing included in-situ moisture and density tests, fines content, collapse testing, expansion index, laboratory compaction and corrosion.

The following is a summary of the laboratory test results.

- Dry density of the samples collected ranged from approximately 92 pounds per cubic foot (pcf) to 113 pcf, with an average of approximately 104 pcf. Field moisture contents ranged from approximately 4 percent to 23 percent, with an average of approximately 11 percent.
- Two samples were tested for fines content indicating a fines content (passing No. 200 sieve) ranging from 26 to 32 percent. According to the Unified Soils Classification System (USCS), the tested samples are classified “coarse grained” soil.
- Two collapse tests were performed. The deformation versus vertical stress plot is provided in Appendix C.
- Two Expansion Index (EI) tests were performed. The results indicate an EI value ranging from 23 to 31, corresponding to “Low” expansion potential.
- Two laboratory compaction tests of near surface samples indicated maximum dry density ranging from 124.5 to 129.5 pcf with an optimum moisture content ranging from 7.5 to 10.5 percent.
- Corrosion testing indicated soluble sulfate content of 66 parts per million (ppm), chloride content of 200 ppm, and pH value of 7.29, and minimum resistivity of 1870 ohm-cm.

A summary of the results is presented in Appendix C. The moisture and dry density test results are presented on the boring logs in Appendix B.





**FIGURE 1**  
**Site Location Map**

PROJECT NAME	Meritage - 9407 Jericho Road, La Mesa
PROJECT NO.	23052-01
ENG. / GEOL.	DJB
SCALE	Not to Scale
DATE	June 2023



## **2.0 GEOTECHNICAL CONDITIONS**

### **2.1 Regional Geology**

Regionally the site is located within the coastal sub-province of the Peninsular Ranges Geomorphic Province, near the western edge of the Southern California batholith. The topography at the edge of the batholith changes from the rugged landforms developed on the batholith to the more subdued landforms, which typify the softer, sedimentary formations of the coastal plain. Tertiary and Quaternary rocks are generally comprised of marine and non-marine sediments consisting of sandstone, mudstones, conglomerates, and occasional volcanic units. Erosion and regional tectonic uplift created the valleys and ridges of the area.

Regional geologic mapping and local topographic expressions do not indicate the presence of large-scale landslides within or adjacent to the project area.

### **2.2 Site Geology and Generalized Subsurface Conditions**

Based on regional mapping (USGS, 2002), the subject site is underlain by the Mission Valley Formation (Tmv). Throughout the site the Mission Valley Formation is overlain by older artificial fill that was placed during the development of the existing development. The depth of this older artificial fill was found to range from approximately 2.5 to 7.5 feet below existing grade during our evaluation but may be found at deeper depths during grading. As indicated in our field explorations, site soils generally consisted of very loose/soft to very dense/hard clayey sands and sandy clays with varying amount of gravel/cobbles to the maximum explored depth of approximately 14 feet below existing grade. Difficult drilling conditions and auger refusal were encountered during drilling.

It should be noted that borings are only representative of the location and time where/when they are performed, and varying subsurface conditions may exist outside of the performed location. In addition, subsurface conditions can change over time. The soil descriptions provided should not be construed to mean that the subsurface profile is uniform, and that soil is homogenous within the project area. Descriptions of the subsurface conditions are presented on the boring and geotechnical trench logs located in Appendix B.

### **2.3 Groundwater**

Groundwater was not encountered to the maximum explored depth of approximately 14 feet.

In general, groundwater levels fluctuate with the seasons and local zones of perched groundwater may be present within the near-surface deposits due to local seepage or during rainy seasons. Groundwater conditions below the site may be variable, depending on numerous factors including seasonal rainfall, local irrigation and groundwater pumping, among others.

## **2.4 Faulting and Seismic Hazards**

Prompted by damaging earthquakes in California, State legislation and policies concerning the classification and land-use criteria associated with faults have been developed. Their purpose was to prevent the construction of urban developments across the trace of active faults, resulting in the Alquist-Priolo Earthquake Fault Zoning Act. Earthquake Fault Zones have been delineated along the traces of active faults within California. Where developments for human occupation are proposed within these zones, the State requires detailed fault evaluations be performed so that engineering geologists can mitigate the hazards associated with active faulting by identifying the location of active faults and allowing for a setback from zones of previous ground rupture.

The subject site is not located within an Alquist-Priolo Earthquake Fault Zone and no faults were identified on the site during our site evaluation. The possibility of damage due to ground rupture is considered low since no active faults are known to cross the site.

Secondary effects of seismic shaking resulting from large earthquakes on the major faults in the Southern California region, which may affect the site, include ground lurching, shallow ground rupture, soil liquefaction and dynamic settlement. These secondary effects of seismic shaking are a possibility throughout the Southern California region and are dependent on the distance between the site and causative fault and the onsite geology. Some of the major active nearby faults that could produce these secondary effects include the Rose Canyon and Oceanside Faults, among others (CGS, 2018). A discussion of these secondary effects is provided in the following sections.

### **2.4.1 Liquefaction and Dynamic Settlement**

Liquefaction is a seismic phenomenon in which loose, saturated, granular soils behave similarly to a fluid when subject to high-intensity ground shaking. Liquefaction occurs when three general conditions coexist: 1) shallow groundwater; 2) low density non-cohesive (granular) soils; and 3) high-intensity ground motion. Studies indicate that loose, saturated, near-surface, cohesionless soils exhibit the highest liquefaction potential, while dry, dense, cohesionless soils, and cohesive soils exhibit low to negligible liquefaction potential. In general, cohesive soils are not considered susceptible to liquefaction. Effects of liquefaction on level ground include settlement, sand boils, and bearing capacity failures below structures. Furthermore, dynamic settlement of dry sands can occur as the sand particles tend to settle and densify as a result of a seismic event.

Based on our review of the San Diego County Liquefaction Hazard Map, the subject site is not located in an area of liquefaction susceptibility. Based on our evaluation, site soils are generally not susceptible to liquefaction due to very dense/hard native soils; therefore, liquefaction potential is considered low.

### **2.4.2 Lateral Spreading**

Lateral spreading is a type of liquefaction induced ground failure associated with the

lateral displacement of surficial blocks of sediment resulting from liquefaction in a subsurface layer. Once liquefaction transforms the subsurface layer into a fluid mass, gravity plus the earthquake inertial forces may cause the mass to move downslope towards a free face (such as a river channel or an embankment). Lateral spreading may cause large horizontal displacements and such movement typically damages pipelines, utilities, bridges, and structures.

Due to the low probability of liquefaction, the potential for lateral spreading is considered low.

## **2.5 Seismic Design Criteria**

The site seismic characteristics were evaluated per the guidelines set forth in Chapter 16, Section 1613 of the 2022 California Building Code (CBC) and applicable portions of ASCE 7-16 which has been adopted by the CBC. Please note that the following seismic parameters are only applicable for code-based acceleration response spectra and are not applicable for where site-specific ground motion procedures are required by ASCE 7-16. Representative site coordinates of latitude 32.786725 degrees north and longitude -116.994087 degrees west were utilized in our analyses. The maximum considered earthquake (MCE) spectral response accelerations ( $S_{MS}$  and  $S_{M1}$ ) and adjusted design spectral response acceleration parameters ( $S_{DS}$  and  $S_{D1}$ ) for Site Class C are provided in Table 2 on the following page. The structural designer should contact the geotechnical consultant if structural conditions (e.g., number of stories, seismically isolated structures, etc.) require site-specific ground motions.



**TABLE 2**  
**Seismic Design Parameters**

<b>Selected Parameters from 2022 CBC, Section 1613 - Earthquake Loads</b>	<b>Seismic Design Values</b>	<b>Notes/Exceptions</b>
Distance to applicable faults classifies the site as a “Near-Fault” site.		Section 11.4.1 of ASCE 7
Site Class	C	Chapter 20 of ASCE 7
S <sub>s</sub> (Risk-Targeted Spectral Acceleration for Short Periods)	0.780g	From SEAOC, 2023
S <sub>1</sub> (Risk-Targeted Spectral Accelerations for 1-Second Periods)	0.285g	From SEAOC, 2023
F <sub>a</sub> (per Table 1613.2.3(1))	1.2	For Simplified Design Procedure of Section 12.14 of ASCE 7, F <sub>a</sub> shall be taken as 1.4 (Section 12.14.8.1)
F <sub>v</sub> (per Table 1613.2.3(2))	1.5	-
S <sub>MS</sub> for Site Class C [Note: S <sub>MS</sub> = F <sub>a</sub> S <sub>s</sub> ]	0.936g	-
S <sub>M1</sub> for Site Class C [Note: S <sub>M1</sub> = F <sub>v</sub> S <sub>1</sub> ]	0.428g	-
S <sub>DS</sub> for Site Class C [Note: S <sub>DS</sub> = (2/3) S <sub>MS</sub> ]	0.624g	-
S <sub>D1</sub> for Site Class C [Note: S <sub>D1</sub> = (2/3) S <sub>M1</sub> ]	0.285g	-
C <sub>RS</sub> (Mapped Risk Coefficient at 0.2 sec)	0.917	ASCE 7 Chapter 22
C <sub>R1</sub> (Mapped Risk Coefficient at 1 sec)	0.922	ASCE 7 Chapter 22

A deaggregation of the PGA based on a 2,475-year average return period (MCE) indicates that an earthquake magnitude of 6.42 at a distance of approximately 17.7 km from the site would contribute the most to this ground motion. A deaggregation of the PGA based on a 475-year average return period (Design Earthquake) indicates that an earthquake magnitude of 6.52 at a distance of approximately 28.1 km from the site would contribute the most to this ground motion (USGS, 2014).

Section 1803.5.12 of the 2022 CBC (per Section 11.8.3 of ASCE 7) states that the maximum considered earthquake geometric mean (MCE<sub>G</sub>) Peak Ground Acceleration (PGA) should be used for liquefaction potential. The PGA<sub>M</sub> for the site is equal to 0.402g (SEAOC, 2023). The design PGA is equal to 0.268g (2/3 of PGA<sub>M</sub>).

## **2.6 Oversized Material**

Oversized material (material larger than 8 inches in maximum dimension) are very likely to be encountered during site grading based on our subsurface evaluation and an observation of oversized materials located in the landscaping areas onsite and in the surrounding neighborhood. Recommendations are provided for appropriate handling of oversized materials in Appendix E. If feasible, crushing oversized materials onsite or exporting oversized materials may be considered. Incorporating oversized materials into “rock fills” (windrows, rock blankets or individual rock burial) is likely not feasible due to the limited depth of grading. Special handling recommendations should be provided on a case-by case basis, if necessary.

## **2.7 Expansion Potential**

Based on the results of laboratory testing from our evaluation and by others, finished grade soils are anticipated to have a “Low” expansion potential. Final expansion potential of site soils should be determined at the completion of grading.

### **3.0 CONCLUSIONS**

Based on the results of our subsurface geotechnical evaluation, it is our opinion that the proposed improvements are feasible from a geotechnical standpoint, provided that the recommendations contained in the following sections are incorporated during site grading and development. A summary of our geotechnical conclusions are as follows:

- The near-surface loose and compressible soils are not suitable for the planned improvements in their present condition (refer to Section 4.1).
- Groundwater was not encountered during our subsurface evaluation to a maximum depth of approximately 14 feet below current grade.
- The subject study area is not located within a mapped State of California Earthquake Fault Zone, and based upon our review of published geologic mapping, no known active or potentially active faults are known to exist within or in the immediate vicinity of the site. Therefore, the potential for ground rupture as a result of faulting is considered very low.
- The main seismic hazard that may affect the site is ground shaking from one of the active regional faults. The subject site will likely experience strong seismic ground shaking during its design life.
- Based on our evaluation, site soils are generally not susceptible to liquefaction due to very dense/hard native soils; therefore, liquefaction potential is considered low.
- Based on the results of preliminary laboratory testing, site soils are anticipated to have “Low” expansion potential. Final design expansion potential must be determined at the completion of grading.
- Excavations into the existing site soils should be feasible with heavy construction equipment in good working order. We anticipate that soils generated from the excavations will be generally suitable for re-use as compacted fill, provided they are relatively free of rocks larger than 8 inches in dimension, construction debris, and significant organic material.
- Oversized materials (greater than 8 inches in maximum dimension) are very likely to be encountered during site grading. Recommendations are provided for appropriate handling of oversized materials in Appendix E.
- Some portions of the onsite soils have high fines content/expansion potential; therefore, are not suitable for backfill of site retaining walls. Therefore, stockpiling of on-site sandy material or import of sandy soils meeting project recommendations may be required.
- Field testing resulted in measured infiltration rates ranging from 0.005 to 0.007 inches per hour. The measured infiltration rates do not include a factor of safety. Discussion regarding infiltration is provided in Section 4.8.

#### **4.0 RECOMMENDATIONS**

The following recommendations are to be considered preliminary and should be confirmed upon completion of grading and earthwork operations. In addition, they should be considered minimal from a geotechnical viewpoint, as there may be more restrictive requirements from the architect, structural engineer, building codes, governing agencies, or the owner.

It should be noted that the following geotechnical recommendations are intended to provide sufficient information to develop the site in general accordance with the 2022 CBC requirements. With regard to the possible occurrence of potentially catastrophic geotechnical hazards such as fault rupture, earthquake-induced landslides, liquefaction, etc. the following geotechnical recommendations should provide adequate protection for the proposed development to the extent required to reduce seismic risk to an “acceptable level.” The “acceptable level” of risk is defined by the California Code of Regulations as “that level that provides reasonable protection of the public safety, though it does not necessarily ensure continued structural integrity and functionality of the project” [Section 3721(a)]. Therefore, repair and remedial work of the proposed improvement may be required after a significant seismic event. With regards to the potential for less significant geologic hazards to the proposed development, the recommendations contained herein are intended as a reasonable protection against the potential damaging effects of geotechnical phenomena such as expansive soils, fill settlement, groundwater seepage, etc. It should be understood, however, that our recommendations are intended to maintain the structural integrity of the proposed development and structures given the site geotechnical conditions but cannot preclude the potential for some cosmetic distress or nuisance issues to develop as a result of the site geotechnical conditions.

The geotechnical recommendations contained herein must be confirmed to be suitable or modified based on the actual as-graded conditions.

#### **4.1 Site Earthwork**

Rough grading shall include remedial earthwork grading and placement of engineered compacted fill to design grades. Geotechnical recommendations for precise grading and construction of the proposed new improvements will be provided, as necessary.

We recommend that earthwork onsite be performed in accordance with the following recommendations, future grading plan review report(s), the 2022 CBC/City of La Mesa requirements, and the General Earthwork and Grading Specifications for Rough Grading included in Appendix E. In case of conflict, the following recommendations shall supersede those included in Appendix E. The following recommendations may be revised within future grading plan review reports or based on the actual conditions encountered during site grading.

##### **4.1.1 Site Preparation**

Prior to grading, areas to be developed should undergo the stripping and clearing of vegetation and clearing of surface obstructions, pavements, foundation and slab elements

from the site. Vegetation, debris from the previous land use and excessive organic material should be removed and properly disposed of offsite. Holes resulting from removals of buried obstructions, which extend below proposed remedial and/or finish grades, should be replaced with suitable compacted fill material. If the demolition contractor removes subsurface utilities below the proposed remedial grading depth we recommend the excavations either be left open until grading operations begin or properly compacted to the depth of remedial grading.

If cesspools or septic systems are encountered, they should be removed in their entirety. The resulting excavation should be backfilled with properly compacted fill soils. As an alternative, cesspools can be backfilled with lean sand-cement slurry. Any encountered wells should be properly abandoned in accordance with regulatory requirements.

#### **4.1.2 Removal Depths and Limits**

In order to provide a relatively uniform bearing condition for the planned building structure and improvements, we recommend the site soils be removed and recompacted. Compressible near surface soils shall be removed to suitable, competent native materials prior to re-placement as compacted fill to design grades. Subsurface site soils should be removed and recompacted according to the criteria outlined below.

Buildings: We recommend that soils within the proposed building footprint areas be removed and recompacted to a minimum depth of 5 to 10 feet below existing grade or 3 feet beneath the base of the foundations, whichever is deeper. The estimated minimum removal depth below existing grade locations can be found in the Geotechnical Map (Figure 2). Additionally, existing undocumented fill encountered during grading should be removed and recompacted for use as compacted fill. The envelope for removal and recompaction should extend laterally a minimum distance equal to the depth of the removal and recompaction below finish grade or 5 feet beyond the edges of the proposed building improvements, whichever is larger. Localized deeper removal and recompaction may be required.

Note: Remedial grading recommendations along the descending slope along the southeasterly side of the site will be provided once the grading plan (and retaining wall plans) have been developed. For budgetary purposes we recommend a toe of slope "keyway" be included that is 15 feet wide and wraps around the entire descending slope. Additional subsurface geotechnical explorations, lab testing and analysis will likely be required to assess the stability of the descending slope.

For minor site structures, such as free-standing, minor retaining walls, etc., removal and recompaction should extend at least 3 feet beneath existing grade or 2 feet beneath the base of foundations, whichever is deeper. In general, the envelope for removal and recompaction should extend laterally a minimum distance of 3 feet beyond the edges of the proposed improvements mentioned above. It is our understanding that some mid-slope retaining walls are proposed near the southeastern edge of the property line. It is recommended that these retaining walls be supported by deepened footings/deep

foundations in order to eliminate added lateral loads to the existing slope or retaining walls below the proposed retaining walls. To eliminate this added lateral load, the retaining wall footing must project a 1:1 below the existing toe of slope. Depending on the proximity of the proposed retaining wall inside property line and the offsite homeowners modified slopes or retaining walls, this slope will require additional subsurface field work and analysis during final engineering depending on the finalized grading plan.

Within pavement and hardscape areas, the soils should be removed and replaced as properly compacted fill to a minimum depth of 2 feet below existing grade or 1-foot below the proposed finished subgrade, whichever is deeper. In general, the envelope for removal and recompaction should extend laterally a minimum distance of 2 feet beyond the edges of the proposed improvements mentioned above.

Local conditions may be encountered which could require additional removal and recompaction beyond the above-noted minimum to obtain an acceptable subgrade. The actual depths and lateral extents of removal and recompaction should be determined by the geotechnical consultant based on the subsurface conditions encountered during grading. Removal and recompaction areas and areas should be accurately staked/recorded in the field by the Project Surveyor.

#### **4.1.3 Temporary Excavations**

Temporary excavations should be performed in accordance with project plans, specifications, and applicable Occupational Safety and Health Administration (OSHA) requirements. Excavations should be laid back or shored in accordance with OSHA requirements before personnel or equipment are allowed to enter. Based on our field investigation, the majority of site soils are anticipated to be OSHA Type "C" soils (refer to the attached boring logs). Sandy soils are present and should be considered susceptible to caving. Soil conditions should be regularly evaluated during construction to verify conditions are as anticipated. The contractor shall be responsible for providing the "competent person" required by OSHA standards to evaluate soil conditions. Close coordination with the geotechnical consultant should be maintained to facilitate construction while providing safe excavations. Excavation safety is the sole responsibility of the contractor.

Where proposed improvements will be adjacent to property lines, the potential for impacting existing offsite improvements may be reduced by performing "ABC" slot cuts while performing earthwork removal and recompaction. "ABC" slot cuts are defined as excavations perpendicular to sensitive property boundaries that are divided into multiple "slots" of equal width. If slots are labeled A, B, C, A, B, C, etc., then all "A" slots can be excavated at the same time but must be backfilled before all "B" slots can be excavated, etc. Any given slot should be backfilled immediately with properly compacted fill to finish grade prior to excavation of the adjacent two slots. Please note some sands susceptible to caving are present at the site. Recommendations for slot cut dimensions should be evaluated during grading. Protection of the existing offsite improvements during grading is the responsibility of the contractor.

Vehicular traffic, stockpiles, and equipment storage should be set back from the perimeter of excavations a minimum distance equivalent to a 1:1(horizontal to vertical) projection from the bottom of the excavation or 5 feet, whichever is greater. Once an excavation has been initiated, it should be backfilled as soon as practical. Prolonged exposure of temporary excavations may result in some localized instability. Excavations should be planned so that they are not initiated without sufficient time to shore/fill them prior to weekends, holidays, or forecasted rain.

It should be noted that any excavation that extends below a 1:1 (horizontal to vertical) projection of an existing foundation will remove existing support of the structure foundation. If requested, temporary shoring parameters will be provided.

#### **4.1.4 Removal Bottoms and Subgrade Preparation**

In general, areas to receive compacted fill should be scarified to a minimum depth of 6 inches, brought to a near-optimum moisture condition (generally within optimum and 2 percent above optimum moisture content), and re-compacted per project requirements.

Removal bottoms, over-excavation bottoms and areas to receive fill should be observed and accepted by the geotechnical consultant prior to subsequent fill placement. Soil subgrade for planned footings and improvements (e.g., slabs, etc.) should be firm and competent.

#### **4.1.5 Material for Fill**

From a geotechnical perspective, the onsite soils are generally considered suitable for use as general compacted fill, provided they are screened of significant organic materials, construction debris and any oversized material (8 inches in greatest dimension).

From a geotechnical viewpoint, import soils for general fill (i.e., non-retaining wall backfill) should consist of clean, granular soils of Low expansion potential (expansion index 50 or less based on ASTM D4829). Import for retaining wall backfill should meet the criteria outlined in the paragraph below. Source samples should be provided to the geotechnical consultant for laboratory testing a minimum of three working days prior to any planned importation.

Retaining wall backfill should consist of imported sandy soils with a maximum of 35 percent fines (passing the No. 200 sieve) per ASTM Test Method D1140 (or ASTM D6913/D422) and a "Very Low" expansion potential (EI of 20 or less per ASTM D4829). Soils should also be screened of organic materials, construction debris, and any material greater than 3 inches in maximum dimension.

Aggregate base should conform to the requirements of Section 200-2 of the most recent version of the Standard Specifications for Public Works Construction ("Greenbook") for untreated base materials and/or City of La Mesa requirements.

The placement of demolition materials in compacted fill is acceptable from a geotechnical viewpoint provided the demolition material is broken up into pieces not larger than typically used for aggregate base (approximately 2 to 4 inches in maximum dimension) and well blended into fill soils with essentially not resulting voids. Demolition material placed in fills must be free of construction debris (wood, organics, etc.) and reinforcing steel. If you elect to incorporate asphalt concrete fragments into the fill materials, approval from an environmental viewpoint and/or local agency may be required and is not the purview of the geotechnical consultant. From our previous experience, we recommend that asphalt concrete fragments be limited to fill areas within planned street areas (i.e. not within building pad areas).

#### **4.1.6 Placement and Compaction of Fills**

Material to be placed as fill should be brought to near-optimum moisture content (generally within optimum and 2 percent above optimum moisture content) and recompacted to at least 90 percent relative compaction (per ASTM D1557). Moisture conditioning of site soils will be required in order to achieve adequate compaction. Drying and/or mixing the very moist soils will be required prior to reusing the materials in compacted fills. Soils are also present that will require additional moisture in order to achieve the required compaction.

The optimum lift thickness to produce a uniformly compacted fill will depend on the type and size of compaction equipment used. In general, fill should be placed in uniform lifts not exceeding 8 inches in compacted thickness. Each lift should be thoroughly compacted and accepted prior to subsequent lifts. Generally, placement and compaction of fill should be performed in accordance with local grading ordinances and with observation and testing by LGC Geotechnical. Oversized material as previously defined should be removed from site fills.

During backfill of excavations, the fill should be properly benched into firm and competent soils of temporary backcut slopes as it is placed in lifts.

Aggregate base material should be compacted to a minimum of 95 percent relative compaction at or slightly above optimum moisture content per ASTM D1557. Subgrade below aggregate base should be compacted to a minimum of 90 percent relative compaction per ASTM D1557 at near-optimum moisture content (generally within optimum and 2 percent above optimum moisture content).

#### **4.1.7 Trench and Retaining Wall Backfill and Compaction**

The onsite soils may generally be suitable as trench backfill, provided the soils are screened of rocks and other material greater than 6 inches in diameter and organic matter. If trenches are shallow or the use of conventional equipment may result in damage to the utilities, sand having a sand equivalent (SE) of 30 or greater (per California Test Method [CTM] 217) may be used to bed and shade the pipes. Sand backfill within the pipe bedding zone may be densified by jetting or flooding and then tamping to ensure



adequate compaction. Subsequent trench backfill should be compacted in uniform thin lifts by mechanical means to at least the recommended minimum relative compaction (per ASTM D1557).

Retaining wall backfill should consist of sandy soils or native soils as outlined in preceding Section 4.1.5. The contractor should anticipate the importing of soils for the required retaining wall backfill. The limits of select sandy backfill should extend a minimum  $\frac{1}{2}$  the height of the retaining wall or the width of the heel (if applicable), whichever is greater, refer to Figure 3. Retaining wall backfill soils should be compacted in relatively uniform thin lifts to at least 90 percent relative compaction (per ASTM D1557). Jetting or flooding of retaining wall backfill materials should not be permitted.

A representative from LGC Geotechnical should observe, probe, and test the backfill to verify compliance with the project recommendations.

#### **4.1.8 Shrinkage and Subsidence**

Allowance in the earthwork volumes budget should be made for an estimated 10-15 percent reduction in volume of the upper approximate 2.5 feet of site soils and 0-10 percent reduction in the soils below 2.5 feet. It should be stressed that these values are only estimates and that an actual shrinkage factor would be extremely difficult to predetermine. Subsidence due to earthwork equipment is expected to be on the order of 0.1 feet. These values are estimates only and exclude losses due to removal of vegetation or debris. The effective shrinkage of onsite soils will depend primarily on the type of compaction equipment, method of compaction used onsite by the contractor and accuracy of the topographic survey. The above shrinkage estimates are intended as an aid for project engineers in determining preliminary earthwork quantities. However, these estimates should be used with some caution since they are not absolute values. Contingencies such as a balance pad should be made for balancing earthwork quantities based on actual shrinkage and subsidence that occurs during grading. The shrinkage and bulking are also expected to vary with variations in survey accuracy during rough grading.

#### **4.2 Preliminary Foundation Recommendations**

Provided that the remedial grading recommendations provided herein are implemented, the site may be considered suitable for the support of the residential structures using a conventional or post-tensioned foundation system designed to resist the impacts of expansive soils. Site soils are anticipated to be of Low expansion potential (EI of 50 or less per ASTM D4829). However, this must be verified based on as-graded conditions. Please note that the following foundation recommendations are preliminary and must be confirmed by LGC Geotechnical at the completion of project plans (i.e., foundation, grading and site layout plans) as well as completion of earthwork. Recommended soil bearing and estimated static settlement are provided in Section 4.3.

#### **4.2.1 Preliminary Conventional Foundation Design Parameters**

Conventional foundations may be designed in accordance with Wire Reinforcement Institute (WRI) procedure for slab-on-ground foundations per Section 1808 of the 2022 CBC to resist expansive soils. The following preliminary soil parameters may be used:

- Effective Plasticity Index: 15
- Climatic Rating:  $C_w = 15$
- Reinforcement: Per structural designer.
- 12-inch minimum perimeter footing/thickened edge embedment below finish grade.
- Moisture condition subgrade soils to 100 % of optimum moisture content to a depth of 12 inches prior to trenching for footings.

#### **4.2.2 Provisional Post-Tensioned Foundation Design Parameters**

The geotechnical parameters provided herein may be used for post-tensioned slab foundations with a deepened perimeter footing or a post-tensioned mat slab. These parameters have been determined in general accordance with the Post-Tensioning Institute (PTI) Standard Requirements for Design of Shallow Post-Tensioned Concrete Foundations on Expansive Soils, referenced in Chapter 18 of the 2022 CBC. In utilizing these parameters, the foundation engineer should design the foundation system in accordance with the allowable deflection criteria of applicable codes and the requirements of the structural designer/architect. Other types of stiff slabs may be used in place of the CBC post-tensioned slab design provided that, in the opinion of the foundation structural designer, the alternative type of slab is at least as stiff and strong as that designed by the CBC/PTI method.

Our design parameters are based on our experience with similar projects, test results onsite, and the anticipated nature of the soil (with respect to expansion potential). Please note that implementation of our recommendations will not eliminate foundation movement (and related distress) should the moisture content of the subgrade soils fluctuate. It is the intent of these recommendations to help maintain the integrity of the proposed structures and reduce (not eliminate) movement, based upon the anticipated site soil conditions. Should future owners and/or property maintenance personnel not properly maintain the areas surrounding the foundation, for example by overwatering, then we anticipate for highly expansive soils the maximum differential movement of the perimeter of the foundation to the center of the foundation to be on the order of a couple of inches. Soils of lower expansion potential are anticipated to show less movement.

**TABLE 3****Preliminary Post-Tensioned Foundation Design Parameters**

<b>Parameter</b>	<b>PT Slab with Perimeter Footing</b>	<b>PT Mat with Thicken ed Edge</b>
Expansion Index	Low <sup>1</sup>	Low <sup>1</sup>
Thornthwaite Moisture Index	-20	-20
Constant Soil Suction	PF 3.9	PF 3.9
Center Lift		
Edge moisture variation distance, $e_m$	9.0 feet	9.0 feet
Center lift, $y_m$	0.25 inch	0.3 inch
Edge Lift		
Edge moisture variation distance, $e_m$	5.5 feet	5.5 feet
Edge lift, $y_m$	0.55 inches	0.66 inches
Modulus of Subgrade Reaction, $k$ (assuming presoaking as indicated below)	200 pci	200 pci
Minimum perimeter footing/thickened edge embedment below finish grade	12 inches	6 inches
Minimum Slab Thickness	5 inches <sup>2</sup>	8 inches <sup>2</sup>
Presoak	100% of Opt. 12 inches	100% of Opt. 12 inches
1. Assumed for preliminary design purposes. Further evaluation is needed at the completion of grading. 2. Recommendations for foundation reinforcement and slab thickness are ultimately the purview of the foundation engineer/structural engineer based upon geotechnical criteria and structural engineering considerations. 3. Recommendations for vapor retarders below slabs are also the purview of the foundation engineer/structural engineer and should be provided in accordance with applicable code requirements.		

**4.2.3 Shallow Foundation Maintenance**

The geotechnical parameters provided herein assume that if the areas adjacent to the foundation are planted and irrigated, these areas will be designed with proper drainage and adequately maintained so that ponding, which causes significant moisture changes below the foundation, does not occur. Our recommendations do not account for excessive irrigation and/or incorrect landscape design. Plants should only be provided with sufficient irrigation for life and not overwatered to saturate subgrade soils. Sunken planters placed adjacent to the foundation should either be designed with an efficient drainage system or liners to prevent moisture infiltration below the foundation. Some

lifting of the perimeter foundation beam should be expected even with properly constructed planters.

In addition to the factors mentioned above, future owners/property management personnel should be made aware of the potential negative influences of trees and/or other large vegetation. Roots that extend near the vicinity of foundations can cause distress to foundations. Future owners (and the owner's landscape architect) should not plant trees/large shrubs closer to the foundations than a distance equal to half the mature height of the tree or 20 feet, whichever is more conservative unless specifically provided with root barriers to prevent root growth below the building foundation.

It is the owner's responsibility to perform periodic maintenance during hot and dry periods to ensure that adequate watering has been provided to keep soil from separating or pulling back from the foundation. Future owners and property management personnel should be informed and educated regarding the importance of maintaining a constant level of soil-moisture. The owners should be made aware of the potential negative consequences of both excessive watering, as well as allowing potentially expansive soils to become too dry. Expansive soils can undergo shrinkage during drying, and swelling during the rainy winter season, or when irrigation is resumed. This can result in distress to building structures and hardscape improvements. The builder should provide these recommendations to future owners and property management personnel.

#### **4.2.4 Slab Underlayment Guidelines**

The following is for informational purposes only since slab underlayment (e.g., moisture retarder, sand or gravel layers for concrete curing and/or capillary break) is unrelated to the geotechnical performance of the foundation and thereby not the purview of the geotechnical consultant. Post-construction moisture migration should be expected below the foundation. The foundation engineer/architect should determine whether the use of a capillary break (sand or gravel layer), in conjunction with the vapor retarder, is necessary or required by code. Sand layer thickness and location (above and/or below vapor retarder) should also be determined by the foundation engineer/architect.

#### **4.2.5 Foundation Setback from Top-of-Slope and Bottom-of-Slope**

Foundations should be setback from the top and bottom of slopes in accordance with the City of La Mesa grading code or California Building Code (CBC), whichever is more conservative. Per the 2022 CBC, the minimum top-of-slope setback is  $H/3$ , with a maximum required setback of 40 feet, where  $H$  is the total height of the slope. The minimum bottom-of-slope setback is  $H/2$ , with a maximum required setback of 15 feet. Refer to Chapter 18 of the 2022 CBC for additional information. It is the purview of the project civil engineer to implement the appropriate foundation setbacks.

#### **4.3 Soil Bearing and Lateral Resistance**

Provided our earthwork recommendations are implemented, an allowable soil bearing pressure of 1,500 pounds per square foot (psf) may be used for the design of footings having a minimum width of 12 inches and minimum embedment of 12 inches below lowest adjacent ground surface. This value may be increased by 300 psf for each additional foot of embedment and 150 psf for each additional foot of foundation width to a maximum value of 2,500 psf. A mat foundation a minimum of 6 inches below lowest adjacent grade may be designed for an allowable soil bearing pressure of 1,200 psf. These allowable bearing pressures are applicable for level (ground slope equal to or flatter than 5H:1V) conditions only. Bearing values indicated are for total dead loads and frequently applied live loads and may be increased by  $\frac{1}{3}$  for short duration loading (i.e., wind or seismic loads).

In utilizing the above-mentioned allowable bearing capacity and provided our earthwork recommendations are implemented, foundation settlement due to structural loads is anticipated to be 1-inch or less. Differential settlement may be taken as half of the total settlement (i.e.,  $\frac{1}{2}$ -inch over a horizontal span of 40 feet).

Resistance to lateral loads can be provided by friction acting at the base of foundations and by passive earth pressure. For concrete/soil frictional resistance, an allowable coefficient of friction of 0.3 may be assumed with dead-load forces. An allowable passive lateral earth pressure of 200 psf per foot of depth (or pcf) to a maximum of 2,000 psf may be used for the sides of footings poured against properly compacted fill. Allowable passive pressure may be increased to 270 pcf (maximum of 2,700 psf) for short duration seismic loading. This passive pressure is applicable for level (ground slope equal to or flatter than 5H:1V) conditions only. Frictional resistance and passive pressure may be used in combination without reduction. We recommend that the upper foot of passive resistance be neglected if finished grade will not be covered with concrete or asphalt. The provided allowable passive pressures are based on a factor of safety of 1.5 and 1.1 for static and seismic loading conditions, respectively. The structural designer should incorporate appropriate factors of safety and/or load factors in their design.

#### **4.4 Lateral Earth Pressures and Retaining Wall Design Considerations**

The following may be used for design of site retaining walls. Lateral earth pressures are provided as equivalent fluid unit weights, in psf per foot of depth (or pcf). These values do not contain an appreciable factor of safety, so the retaining wall designer should apply the applicable factors of safety and/or load factors during design. A soil unit weight of 120 pcf may be assumed for calculating the actual weight of soil over the wall footing.

The following lateral earth pressures are presented in Table 4 below, for approved import free draining, clean granular (sandy) soils with a maximum of 35 percent fines (passing the No. 200 sieve per ASTM D-421/422) and a "Very Low" expansion potential (EI of 20 or less per ASTM D4829). The site soils are not suitable for retaining wall backfill due to their fines content and expansion index; therefore, import of soils meeting the criteria outlined above will be required by the contractor for obtaining suitable retaining wall backfill soil. The wall designer should clearly indicate on the retaining wall plans the required select sandy soil backfill criteria. These preliminary findings should be confirmed during grading.

**TABLE 4**

**Lateral Earth Pressures –Approved Imported Sandy Soils**

<b>Conditions</b>	<b>Equivalent Fluid Unit Weight (pcf)</b>	<b>Equivalent Fluid Unit Weight (pcf)</b>
	<b>Level Backfill</b>	<b>2:1 Sloped Backfill</b>
	<b>Approved Imported Sandy Soils</b>	<b>Approved Imported Sandy Soils</b>
Active	35	55
At-Rest	55	70

If the wall can yield enough to mobilize the full shear strength of the soil, it can be designed for “active” pressure. If the wall cannot yield under the applied load, the earth pressure will be higher. This would include 90-degree corners of retaining walls. Such walls should be designed for “at-rest.” The equivalent fluid pressure values assume free-draining conditions and a drainage system will be installed and maintained to prevent the build-up of hydrostatic pressures. If conditions other than those assumed above are anticipated, the equivalent fluid pressure values should be provided on an individual-case basis by the geotechnical engineer.

Retaining wall structures should be provided with appropriate drainage and appropriately waterproofed. To reduce, but not eliminate, saturation of near-surface (upper approximate 1-foot) soils in front of the retaining walls, the perforated subdrain pipe should be located as low as possible behind the retaining wall. The outlet pipe should be sloped to drain to a suitable outlet. In general, we do not recommend retaining wall outlet pipes be connected to area drains. If subdrains are connected to area drains, special care should be taken to maintain these drains. Typical conventional retaining wall drainage is shown on Figure 3. It should be noted that the recommended subdrain does not provide protection against seepage through the face of the wall and/or efflorescence. Waterproofing and outlet systems are not the purview of the geotechnical consultant.

Surcharge loading effects from any adjacent structures should be evaluated by the retaining wall designer. In general, structural loads within a 1:1 (horizontal to vertical) upward projection from the bottom of the proposed retaining wall footing will surcharge the proposed retaining wall. In addition to the recommended earth pressure, retaining walls adjacent to streets should be designed to resist a uniform lateral pressure of 85 pounds per square foot (psf) due to normal street vehicle traffic, if applicable. Uniform lateral surcharges may be estimated using the applicable coefficient of lateral earth pressure using a rectangular distribution. A factor of 0.45 and 0.3 may be used for at-rest and active conditions, respectively. The retaining wall designer should contact the geotechnical consultant for any required geotechnical input in estimating surcharge loads.

If retaining walls greater than 6 feet in height are proposed, the retaining wall designer should contact the geotechnical engineer for specific seismic lateral earth pressure increments based on the configuration of the planned retaining wall structures.

Soil bearing and lateral resistance (friction coefficient and passive resistance) are provided in Section 4.3. Earthwork considerations (temporary backcuts, backfill, compaction, etc.) for retaining walls are provided in Section 4.1 (Site Earthwork) and the subsequent earthwork related sub-sections.

#### **4.5 Corrosivity to Concrete and Metal**

Although not corrosion engineers (LGC Geotechnical is not a corrosion consultant), several governing agencies in Southern California require the geotechnical consultant to determine the corrosion potential of soils to buried concrete and metal facilities. We therefore present the results of our testing with regard to corrosion for the use of the client and other consultants, as they determine necessary.

Corrosion testing of near-surface bulk samples indicated a soluble sulfate content value of 66 ppm (less than 0.007 percent), a chloride content of 200 ppm, pH of 7.29, and a minimum resistivity of 1870 ohm-centimeters. Based on Caltrans Corrosion Guidelines (2021), soils are considered corrosive if the pH is 5.5 or less, or the chloride concentration is 500 ppm or greater, or the sulfate concentration is 2,000 ppm (0.2 percent) or greater. Based on the test results, soils are not considered corrosive using Caltrans criteria. Note that based on minimum resistivity the soils are considered severely corrosive to metallic improvements. If improvements that may be susceptible to corrosion are proposed, it is recommended that further evaluation by a corrosion engineer be performed.

Based on our laboratory test results of representative site soil samples, onsite soils should be considered as having a severity categorization of “not applicable” and are designated class “S0” per ACI 318, Table 19.3.1.1 with respect to sulfates. Concrete in direct contact with the onsite soils can be designed according to ACI 318, Table 19.3.2.1 using the “S0” sulfate classification.

Laboratory testing may need to be performed at the completion of grading by the project corrosion engineer to further evaluate the as-graded soil corrosivity characteristics. Accordingly, revision of the corrosion potential may be needed, should future test results differ substantially from the conditions reported herein. The client and/or other members of the development team should consider this during the design and planning phase of the project and formulate an appropriate course of action.

#### **4.6 Preliminary Asphalt Concrete Pavement Sections**

For the purposes of these preliminary recommendations, we have selected a preliminary design R-value of 10 and calculated pavement sections for Traffic Indices of 5.0, 5.5 and 6.0. R-value testing of the street subgrade will need to be performed to confirm our preliminary testing results/assumptions once the streets have been graded to finish subgrade elevations and the final Traffic Index is determined by the Civil Engineer.

**TABLE 5**

**Preliminary Pavement Sections**

<b>Assumed Traffic Index</b>	5.0	5.5	6.0
<b>R -Value Subgrade</b>	10	10	10
<b>AC Thickness</b>	4.0 inches	4.0 inches	5.0 inches
<b>AB Thickness</b>	6.5 inches	8.5 inches	8.5 inches

Due to anticipated construction traffic prior to the completion of the project, we recommend that the total thickness (base course and capping course) of AC be placed at essentially the same time. Construction traffic loading on only the base course of the AC will increase the potential for pavement distress. It should be noted that construction traffic such as concrete trucks will likely exceed traffic loading after completion of construction.

Increasing the thickness of asphalt or adding additional base material will reduce the likelihood of the pavement experiencing distress during its service life. The above recommendations are based on the assumption that proper maintenance and irrigation of the areas adjacent to the roadway will occur through the design life of the pavement. Failure to maintain a proper maintenance and/or irrigation program may jeopardize the integrity of the pavement.

Earthwork recommendations regarding aggregate base and subgrade are provided in the previous Section "Site Earthwork" and the related sub-sections of this report.

**4.7 Nonstructural Concrete Flatwork**

Nonstructural concrete flatwork (such as walkways, private drives, patio slabs, etc.) has a potential for cracking due to changes in soil volume related to soil-moisture fluctuations. To reduce the potential for excessive cracking and lifting, concrete may be designed in accordance with the minimum guidelines outlined in Table 6 below. These guidelines will reduce the potential for irregular cracking and promote cracking along construction joints but will not eliminate all cracking or lifting. Thickening the concrete and/or adding additional reinforcement will further reduce cosmetic distress.



**TABLE 6**

**Nonstructural Concrete Flatwork for Low Expansion Potential**

	<b>Homeowner Sidewalks</b>	<b>Private Drives</b>	<b>Patios/ Entryways</b>	<b>City Sidewalk Curb and Gutters</b>
<b>Minimum Thickness (in.)</b>	4 (nominal)	4 (full)	4 (full)	City/Agency Standard
<b>Presoaking</b>	Wet down prior to placing	Wet down prior to placing	Wet down prior to placing	City/Agency Standard
<b>Reinforcement</b>	—	No. 3 at 24 inches on centers	No. 3 at 24 inches on centers	City/Agency Standard
<b>Thickened Edge (in.)</b>	—	8 x 8	—	City/Agency Standard
<b>Crack Control Joints</b>	Saw cut or deep open tool joint to a minimum of $\frac{1}{3}$ the concrete thickness	Saw cut or deep open tool joint to a minimum of $\frac{1}{3}$ the concrete thickness	Saw cut or deep open tool joint to a minimum of $\frac{1}{3}$ the concrete thickness	City/Agency Standard
<b>Maximum Joint Spacing</b>	5 feet	10 feet or quarter cut whichever is closer	6 feet	City/Agency Standard
<b>Aggregate Base Thickness (in.)</b>	—	—	—	City/Agency Standard

To reduce the potential for driveways to separate from the garage slab, the builder may elect to install dowels to tie these two elements together. Similarly, future homeowners should consider the use of dowels to connect flatwork to the foundation.

#### **4.8 Subsurface Water Infiltration**

Recent regulatory changes have occurred that mandate that storm water be infiltrated below grade into subsurface soils rather than collected in a conventional storm drain system. Typically, a combination of methods are implemented to reduce surface water runoff and increase infiltration including; permeable pavements/pavers for roadways and walkways, directing surface water runoff to grass-lined swales, retention areas, and/or drywells, etc.

It should be noted that collecting and concentrating surface water for the purpose of intentionally infiltrating below grade, conflicts with the geotechnical engineering objective of directing surface water away from slopes, structures and other improvements. The geotechnical stability and integrity of a site is reliant upon appropriately handling surface water. In general,

the vast majority of geotechnical distress issues are directly related to improper drainage. In general, distress in the form of movement of improvements could occur as a result of soil saturation and loss of soil support, expansion, internal soil erosion, collapse and/or settlement.

The results of our field infiltration testing indicate the observed 1-D infiltration rate for I-1 and I-2 (not including required factors of safety for design) were 0.005 and 0.007 inches per hour, respectively. The design infiltration rate is thereby equal to the Observed Infiltration Rate divided by the design factor of safety. The design factor of safety must be a minimum of 2.0 but may be increased at the discretion of the design engineer (County of San Diego, 2020).

Based on the results of field infiltration testing indicating very low infiltration rates, anticipated subsurface conditions consisting of compacted fill over very dense native materials, and hillside nature of the site, we strongly recommend against the intentional infiltration of stormwater into the subsurface soils.

#### **4.9 Control of Surface Water and Drainage Control**

From a geotechnical perspective, we recommend that compacted finished grade soils adjacent to proposed structures be sloped away from the proposed structures and towards an approved drainage device or unobstructed swale. Drainage swales, wherever feasible, should not be constructed within 5 feet of buildings. Where lot and building geometry necessitates that drainage swales be routed closer than 5 feet to structural foundations, we recommend the use of area drains together with drainage swales. Drainage swales used in conjunction with area drains should be designed by the project civil engineer so that a properly constructed and maintained system will prevent ponding within 5 feet of the foundation. Code compliance of grades is not the purview of the geotechnical consultant.

Planters with open bottoms adjacent to buildings should be avoided. Planters should not be designed adjacent to buildings unless provisions for drainage, such as catch basins, liners, and/or area drains, are made. Overwatering must be avoided.

#### **4.10 Top of Slope Improvements**

As with all top-of-slope improvements (fences, flatwork, etc.) some amount of future settlement and/or rotation should be expected. We recommend top-of-slope improvements be flexible (tube steel or vinyl fencing) or pavers instead of concrete flatwork. Alternatively, masonry fences or other rigid improvement can be constructed on deepened footings or if concrete is desired, inclusion of frequently spaced construction joints.

#### **4.11 Geotechnical Plan Review**

Project plans (grading, foundation, retaining wall, etc.) should be reviewed by this office prior to construction to verify that our geotechnical recommendations have been incorporated. Additional or modified geotechnical recommendations may be required based on the proposed layout.

#### ***4.12 Geotechnical Observation and Testing***

The recommendations provided in this report are based on limited subsurface observations and geotechnical analysis. The interpolated subsurface conditions should be checked in the field during construction by a representative of LGC Geotechnical. Geotechnical observation and testing is required per Section 1705 of the 2022 California Building Code (CBC).

Geotechnical observation and/or testing should be performed by LGC Geotechnical at the following stages:

- During grading (removal bottoms, fill placement, etc.);
- During retaining wall backfill and compaction;
- During utility trench backfill and compaction;
- After presoaking building pad and other concrete-flatwork subgrades, and prior to placement of aggregate base or concrete;
- Preparation of pavement subgrade and placement of aggregate base;
- After building and wall footing excavation and prior to placement of steel reinforcement and/or concrete; and
- When any unusual soil conditions are encountered during any construction operation subsequent to issuance of this report.

## **5.0 LIMITATIONS**

Our services were performed using the degree of care and skill ordinarily exercised, under similar circumstances, by reputable soils engineers and geologists practicing in this or similar localities. No other warranty, expressed or implied, is made as to the conclusions and professional advice included in this report.


This report is based on data obtained from limited observations of the site, which have been extrapolated to characterize the site. While the scope of services performed is considered suitable to adequately characterize the site geotechnical conditions relative to the proposed development, no practical evaluation can completely eliminate uncertainty regarding the anticipated geotechnical conditions in connection with a subject site. Variations may exist and conditions not observed or described in this report may be encountered during grading and construction.

This report is issued with the understanding that it is the responsibility of the owner, or of his/her representative, to ensure that the information and recommendations contained herein are brought to the attention of the other consultants (at a minimum the civil engineer, structural engineer, landscape architect) and incorporated into their plans. The contractor should properly implement the recommendations during construction and notify the owner if they consider any of the recommendations presented herein to be unsafe, or unsuitable.


The findings of this report are valid as of the present date. However, changes in the conditions of a site can and do occur with the passage of time, whether they be due to natural processes or the works of man on this or adjacent properties. The findings, conclusions, and recommendations presented in this report can be relied upon only if LGC Geotechnical has the opportunity to observe the subsurface conditions during grading and construction of the project, in order to confirm that our preliminary findings are representative for the site. This report is intended exclusively for use by the client, any use of or reliance on this report by a third party shall be at such party's sole risk.

In addition, changes in applicable or appropriate standards may occur, whether they result from legislation or the broadening of knowledge. Accordingly, the findings of this report may be invalidated wholly or partially by changes outside our control. Therefore, this report is subject to review and modification.









**FIGURE 3**  
**Retaining Wall**  
**Backfill Detail**

PROJECT NAME	Meritage - 9407 Jericho Road, La Mesa
PROJECT NO.	23052-01
ENG. / GEOL.	DJB
SCALE	Not to Scale
DATE	June 2023

# ***Appendix A***

## ***References***

## ***APPENDIX A***

### **References**

- American Concrete Institute, 2019, Building Code Requirements for Structural Concrete (ACI 318-19) and Commentary (ACI 318R-19).
- American Society of Civil Engineers (ASCE), 2017, Minimum Design Loads for Buildings and Other Structures, ASCE/SEI 7-16, Third Printing, 2017.
- ASTM International, Annual Book of ASTM Standards, Volume 04.08.
- California Building Standards Commission, 2022, California Building Code, California Code of Regulations Title 24, Volumes 1 and 2, dated July 2022.
- California Department of Conservation, Division of Mines and Geology, 1997, Guidelines for Evaluating and Mitigating Seismic Hazards in California, CDMG Special Publication 117.
- \_\_\_\_\_, 2000, Digital Images of Official Maps of Alquist-Priolo Earthquake Fault Zones of California, Southern Region, CDMG CD 2000-03.
- California Department of Transportation (Caltrans), 2021, Corrosion Guidelines, Version 3.2, dated May 2021.
- \_\_\_\_\_, 2017, Highway Design Manual, Updated November 20, 2017.
- California Geological Survey (CGS), 2008, California Geological Society Special Publication 117A: Guidelines for Evaluating and Mitigating Seismic Hazards in California.
- \_\_\_\_\_, 2018, Special Publication 42: Earthquake Fault Zones, A Guide for Government Agencies, Property Owners/Developers, and Geoscience Practitioners for Assessing Fault Rupture Hazards in California, Revised 2018.
- County of San Diego, 2020, County of San Diego BMP Design Manual, dated September 15, 2020.
- Structural Engineers Association of California (SEAOC), 2023, U.S. Seismic Design Maps, Retrieved May 11, 2023, from <https://seismicmaps.org/>.
- United States Geological Survey (USGS), 2014, Unified Hazard Tool, Dynamic: Conterminous U.S. 2014 (v4.2.0), Retrieved May 11, 2023, from <https://earthquake.usgs.gov/hazards/interactive/>.
- \_\_\_\_\_, 2002, Geologic Map of the El Cajon 7.5' Quadrangle, San Diego County, California, by Siang S. Tan, dated 2002.



***Appendix B***  
***Boring & Geotechnical Trench Logs***

# Geotechnical Boring Log Borehole HS-1

<b>Date:</b> 3/28/2023	<b>Drilling Company:</b> Martini Drilling
<b>Project Name:</b> Meritage - Jericho Road, La Mesa	<b>Type of Rig:</b> Truck Mounted Rig
<b>Project Number:</b> 23052-01	<b>Drop:</b> 30" <b>Hole Diameter:</b> 8"
<b>Elevation of Top of Hole:</b> ~645' MSL	<b>Drive Weight:</b> 140 pounds
<b>Hole Location:</b> See Geotechnical Map	Page 1 of 1

Elevation (ft)	Depth (ft)	Graphic Log	Sample Number	Blow Count	Dry Density (pcf)	Moisture (%)	USCS Symbol	Logged By JMN Sampled By JMN Checked By DJB  DESCRIPTION	Type of Test
640	0	B-1	R-1	5 3	106.9	9.6	CL	<b>@0' to 7.5' - Older Artificial Fill (afo):</b> @ 0' - Sandy CLAY: dark brown, slight moist; vegetation  @ 2.5' - Sandy CLAY with Gravel: brown, slightly moist, medium stiff	#200 MD EI CR
640	5		R-2	2 2	100.5	12.2	CL-SC	@ 5' - Sandy CLAY to Clayey SAND: grayish brown, moist, soft/very loose	
635	10		R-3	3 7 11	107.2	14.9	CL	<b>@7.5' to T.D. - Mission Valley Formation (Tmv):</b> @ 7.5' - Sandy CLAY with Gravel: brown, moist, stiff	CO
635	10		R-4	44 50/5"		4.2	GC	@ 10' - Clayey Gravel with SAND: light brown, slightly moist, very dense	
630	15							@ 14' - Auger Refusal	
630	15							Total Depth = 14' Groundwater Not Encountered Backfilled with Cuttings on 3/28/2023	
625	20								
620	25								
615	30								



THIS SUMMARY APPLIES ONLY AT THE LOCATION OF THIS BORING AND AT THE TIME OF DRILLING. SUBSURFACE CONDITIONS MAY DIFFER AT OTHER LOCATIONS AND MAY CHANGE AT THIS LOCATION WITH THE PASSAGE OF TIME. THE DATA PRESENTED IS A SIMPLIFICATION OF THE ACTUAL CONDITIONS ENCOUNTERED. THE DESCRIPTIONS PROVIDED ARE QUALITATIVE FIELD DESCRIPTIONS AND ARE NOT BASED ON QUANTITATIVE ENGINEERING ANALYSIS.

**SAMPLE TYPES:**  
 B BULK SAMPLE  
 R RING SAMPLE (CA Modified Sampler)  
 G GRAB SAMPLE  
 SPT STANDARD PENETRATION TEST SAMPLE



**TEST TYPES:**  
 DS DIRECT SHEAR  
 MD MAXIMUM DENSITY  
 SA SIEVE ANALYSIS  
 S&H SIEVE AND HYDROMETER  
 EI EXPANSION INDEX  
 CN CONSOLIDATION  
 CR CORROSION  
 AL ATTERBERG LIMITS  
 CO COLLAPSE/SWELL  
 RV R-VALUE  
 -#200 % PASSING # 200 SIEVE

# Geotechnical Boring Log Borehole HS-2

<b>Date:</b> 3/28/2023	<b>Drilling Company:</b> Martini Drilling
<b>Project Name:</b> Meritage - Jericho Road, La Mesa	<b>Type of Rig:</b> Truck Mounted Rig
<b>Project Number:</b> 23052-01	<b>Drop:</b> 30" <b>Hole Diameter:</b> 8"
<b>Elevation of Top of Hole:</b> ~652' MSL	<b>Drive Weight:</b> 140 pounds
<b>Hole Location:</b> See Geotechnical Map	Page 1 of 1

Elevation (ft)	Depth (ft)	Graphic Log	Sample Number	Blow Count	Dry Density (pcf)	Moisture (%)	USCS Symbol	Logged By JMN Sampled By JMN Checked By DJB  DESCRIPTION	Type of Test
650	0		R-1	50/6"		7.1	CL	<b>@0' to 2.5' - Older Artificial Fill (afo):</b> @ 0' - Clayey SAND: brown, dry; vegetation <b>@2.5' to T.D. - Mission Valley Formation (Tmv):</b> @ 2.5' - Gravelly CLAY with Sand: reddish brown, slightly moist, hard  @ 5' - No Recovery  @ 7.5' - Clayey SAND with Gravel: light brown, moist, very dense  @ 10' - Clayey SAND with Gravel: light brown, moist, very dense; auger refusal	#200 MD EI
	5		R-2	50/3"					
645			R-3	50/5"		8.7	SC		
640	10		R-4	50/1"	112.7	7.3			
	15							Total Depth = 10' Groundwater Not Encountered Backfilled with Cuttings on 3/28/2023	
635									
	20								
630									
	25								
625									
	30								



THIS SUMMARY APPLIES ONLY AT THE LOCATION OF THIS BORING AND AT THE TIME OF DRILLING. SUBSURFACE CONDITIONS MAY DIFFER AT OTHER LOCATIONS AND MAY CHANGE AT THIS LOCATION WITH THE PASSAGE OF TIME. THE DATA PRESENTED IS A SIMPLIFICATION OF THE ACTUAL CONDITIONS ENCOUNTERED. THE DESCRIPTIONS PROVIDED ARE QUALITATIVE FIELD DESCRIPTIONS AND ARE NOT BASED ON QUANTITATIVE ENGINEERING ANALYSIS.

**SAMPLE TYPES:**  
 B BULK SAMPLE  
 R RING SAMPLE (CA Modified Sampler)  
 G GRAB SAMPLE  
 SPT STANDARD PENETRATION TEST SAMPLE



**TEST TYPES:**  
 DS DIRECT SHEAR  
 MD MAXIMUM DENSITY  
 SA SIEVE ANALYSIS  
 S&H SIEVE AND HYDROMETER  
 EI EXPANSION INDEX  
 CN CONSOLIDATION  
 CR CORROSION  
 AL ATTERBERG LIMITS  
 CO COLLAPSE/SWELL  
 RV R-VALUE  
 #200 % PASSING # 200 SIEVE

# Geotechnical Boring Log Borehole HS-3

<b>Date:</b> 3/28/2023	<b>Drilling Company:</b> Martini Drilling
<b>Project Name:</b> Meritage - Jericho Road, La Mesa	<b>Type of Rig:</b> Truck Mounted Rig
<b>Project Number:</b> 23052-01	<b>Drop:</b> 30" <b>Hole Diameter:</b> 8"
<b>Elevation of Top of Hole:</b> ~652' MSL	<b>Drive Weight:</b> 140 pounds
<b>Hole Location:</b> See Geotechnical Map	Page 1 of 1

Elevation (ft)	Depth (ft)	Graphic Log	Sample Number	Blow Count	Dry Density (pcf)	Moisture (%)	USCS Symbol	Logged By JMN Sampled By JMN Checked By DJB  DESCRIPTION	Type of Test
650	0	B-1	R-1	10 13 14	91.8	14.1	SC	<b>@0' to 2.5' - Older Artificial Fill (afo):</b> @ 0' - Clayey SAND: light brown, slightly moist; vegetation <b>@2.5' to T.D. - Mission Valley Formation (Tmv):</b> @ 2.5' - Clayey SAND: brown, very moist, medium dense @ 5' - No Recovery @6.5' - Auger Refusal	
	5		R-2	9 11 43					
645								Total Depth = 6.5' Groundwater Not Encountered Backfilled with Cuttings on 3/28/2023	
	10								
640									
	15								
635									
	20								
630									
	25								
625									
	30								



THIS SUMMARY APPLIES ONLY AT THE LOCATION OF THIS BORING AND AT THE TIME OF DRILLING. SUBSURFACE CONDITIONS MAY DIFFER AT OTHER LOCATIONS AND MAY CHANGE AT THIS LOCATION WITH THE PASSAGE OF TIME. THE DATA PRESENTED IS A SIMPLIFICATION OF THE ACTUAL CONDITIONS ENCOUNTERED. THE DESCRIPTIONS PROVIDED ARE QUALITATIVE FIELD DESCRIPTIONS AND ARE NOT BASED ON QUANTITATIVE ENGINEERING ANALYSIS.

**SAMPLE TYPES:**  
 B BULK SAMPLE  
 R RING SAMPLE (CA Modified Sampler)  
 G GRAB SAMPLE  
 SPT STANDARD PENETRATION TEST SAMPLE

GROUNDWATER TABLE

**TEST TYPES:**  
 DS DIRECT SHEAR  
 MD MAXIMUM DENSITY  
 SA SIEVE ANALYSIS  
 S&H SIEVE AND HYDROMETER  
 EI EXPANSION INDEX  
 CN CONSOLIDATION  
 CR CORROSION  
 AL ATTERBERG LIMITS  
 CO COLLAPSE/SWELL  
 RV R-VALUE  
 -#200 % PASSING # 200 SIEVE

# Geotechnical Boring Log Borehole I-1

<b>Date:</b> 3/28/2023	<b>Drilling Company:</b> Martini Drilling
<b>Project Name:</b> Meritage - Jericho Road, La Mesa	<b>Type of Rig:</b> Truck Mounted Rig
<b>Project Number:</b> 23052-01	<b>Drop:</b> 30" <b>Hole Diameter:</b> 8"
<b>Elevation of Top of Hole:</b> ~647' MSL	<b>Drive Weight:</b> 140 pounds
<b>Hole Location:</b> See Geotechnical Map	Page 1 of 1

Elevation (ft)	Depth (ft)	Graphic Log	Sample Number	Blow Count	Dry Density (pcf)	Moisture (%)	USCS Symbol	Logged By JMN Sampled By JMN Checked By DJB  DESCRIPTION	Type of Test
645	0							<b>@0' to 2.5' - Older Artificial Fill (afo):</b> @ 0' - 5" of Concrete Pavement <b>@2.5' to T.D. - Mission Valley Formation (Tmv):</b> @ 2.5' - Sandy CLAY: brown, slightly moist, hard	
	5		R-2	15 50/4"	109.2	7.7	SC	@ 5' - Clayey SAND with Gravel: light brown, moist, very dense	
640									
	10		SPT-2	43 28 41		10.7		@ 8.5' - Clayey SAND: light brown, moist, very dense	
635								Total Depth = 10' Groundwater Not Encountered 3" Perforated Pipe with Filter Sock Installed Surrounded by Gravel, and Presoaked on 3/28/23 Backfilled with Cuttings and Capped with Concrete on 3/29/2023	
	15								
630									
	20								
625									
	25								
620									
	30								



THIS SUMMARY APPLIES ONLY AT THE LOCATION OF THIS BORING AND AT THE TIME OF DRILLING. SUBSURFACE CONDITIONS MAY DIFFER AT OTHER LOCATIONS AND MAY CHANGE AT THIS LOCATION WITH THE PASSAGE OF TIME. THE DATA PRESENTED IS A SIMPLIFICATION OF THE ACTUAL CONDITIONS ENCOUNTERED. THE DESCRIPTIONS PROVIDED ARE QUALITATIVE FIELD DESCRIPTIONS AND ARE NOT BASED ON QUANTITATIVE ENGINEERING ANALYSIS.

**SAMPLE TYPES:**  
 B BULK SAMPLE  
 R RING SAMPLE (CA Modified Sampler)  
 G GRAB SAMPLE  
 SPT STANDARD PENETRATION TEST SAMPLE



**TEST TYPES:**  
 DS DIRECT SHEAR  
 MD MAXIMUM DENSITY  
 SA SIEVE ANALYSIS  
 S&H SIEVE AND HYDROMETER  
 EI EXPANSION INDEX  
 CN CONSOLIDATION  
 CR CORROSION  
 AL ATTERBERG LIMITS  
 CO COLLAPSE/SWELL  
 RV R-VALUE  
 -#200 % PASSING # 200 SIEVE

# Geotechnical Boring Log Borehole I-2

<b>Date:</b> 3/28/2023	<b>Drilling Company:</b> Martini Drilling
<b>Project Name:</b> Meritage - Jericho Road, La Mesa	<b>Type of Rig:</b> Truck Mounted Rig
<b>Project Number:</b> 23052-01	<b>Drop:</b> 30" <b>Hole Diameter:</b> 8"
<b>Elevation of Top of Hole:</b> ~651' MSL	<b>Drive Weight:</b> 140 pounds
<b>Hole Location:</b> See Geotechnical Map	Page 1 of 1

Elevation (ft)	Depth (ft)	Graphic Log	Sample Number	Blow Count	Dry Density (pcf)	Moisture (%)	USCS Symbol	<div>                     Logged By JMN                      Sampled By JMN                      Checked By DJB                 </div> DESCRIPTION	Type of Test
650	0							<b>@0' to 7.5' - Older Artificial Fill (afo):</b> @ 0' - 6" of Concrete Pavement	
645	5		R-1	6 4 4	102.9	22.8	CL	@ 5' - CLAY with Sand: brown,very moist, medium stiff	CO
640	10		R-2	42 50/2"		7.1		<b>@7.5' to T.D. - Mission Valley Formation (Tmv):</b>  @ 10' - Gravelly CLAY with Sand: light yellowish brown, slightly moist, hard	
635	15							Total Depth = 10' Groundwater Not Encountered 3" Perforated Pipe with Filter Sock Installed Surrounded by Gravel, and Presoaked on 3/28/23 Backfilled with Cuttings and Capped with Concrete on 3/29/2023	
630	20								
625	25								
	30								



THIS SUMMARY APPLIES ONLY AT THE LOCATION OF THIS BORING AND AT THE TIME OF DRILLING. SUBSURFACE CONDITIONS MAY DIFFER AT OTHER LOCATIONS AND MAY CHANGE AT THIS LOCATION WITH THE PASSAGE OF TIME. THE DATA PRESENTED IS A SIMPLIFICATION OF THE ACTUAL CONDITIONS ENCOUNTERED. THE DESCRIPTIONS PROVIDED ARE QUALITATIVE FIELD DESCRIPTIONS AND ARE NOT BASED ON QUANTITATIVE ENGINEERING ANALYSIS.

**SAMPLE TYPES:**  
 B BULK SAMPLE  
 R RING SAMPLE (CA Modified Sampler)  
 G GRAB SAMPLE  
 SPT STANDARD PENETRATION TEST SAMPLE



**TEST TYPES:**  
 DS DIRECT SHEAR  
 MD MAXIMUM DENSITY  
 SA SIEVE ANALYSIS  
 S&H SIEVE AND HYDROMETER  
 EI EXPANSION INDEX  
 CN CONSOLIDATION  
 CR CORROSION  
 AL ATTERBERG LIMITS  
 CO COLLAPSE/SWELL  
 RV R-VALUE  
 -#200 % PASSING # 200 SIEVE

***Appendix C***  
***Laboratory Test Results***

## ***APPENDIX C***

### **Laboratory Testing Procedures and Test Results**

The laboratory testing program was formulated towards providing data relating to the relevant engineering properties of the soils with respect to residential construction. Samples considered representative of site conditions were tested in general accordance with American Society for Testing and Materials (ASTM) procedure and/or California Test Methods (CTM), where applicable. The following summary is a brief outline of the test type and a table summarizing the test results.

**Moisture and Density Determination Tests:** Moisture content (ASTM D2216) and dry density determinations (ASTM D2937) were performed on relatively undisturbed samples obtained from the test borings and/or trenches. The results of these tests are presented in the boring logs. Where applicable, only moisture content was determined from undisturbed or disturbed samples.

**Expansion Index:** The expansion potential of selected samples was evaluated by the Expansion Index Test, Standard ASTM D4829. Specimens are molded under a given compactive energy to approximately the optimum moisture content and approximately 50 percent saturation or approximately 90 percent relative compaction. The prepared 1-inch-thick by 4-inch-diameter specimens are loaded to an equivalent 144 psf surcharge and are inundated with tap water until volumetric equilibrium is reached. The results of these tests are presented in the table below.

<b>Sample Location</b>	<b>Expansion Index</b>	<b>Expansion Potential*</b>
HS-1 @ 0-5 feet	31	Low
HS-2 @ 0-5 feet	23	Low

\* ASTM D4829

**Grain Size Distribution/Fines Content:** Representative samples were dried, weighed and soaked in water until individual soil particles were separated (per ASTM D421) and then washed on a No. 200 sieve (ASTM D1140). Where applicable, the portion retained on the No. 200 sieve and dried and then sieved on a U.S. Standard brass sieve set in accordance with ASTM D6913 (sieve).

<b>Sample Location</b>	<b>Description</b>	<b>% Passing # 200 Sieve</b>
HS-1 @ 0-5 feet	Clayey Sand with Gravel	32
HS-2 @ 0-5 feet	Clayey Sand with Gravel	26



## ***APPENDIX C (Cont'd)***

### **Laboratory Testing Procedures and Test Results**

**Collapse/Swell Potential:** Two collapse tests were performed per ASTM D4546. Samples (2.4 inches in diameter and 1-inch in height) were placed in a consolidometer and loaded to their approximate in-situ effective stress. The results are in this appendix.

**Maximum Density Tests:** The maximum dry density and optimum moisture content of typical materials were determined in accordance with ASTM D1557. The results of these tests are presented in the table below:

<b>Sample Location</b>	<b>Sample Description</b>	<b>Maximum Dry Density (pcf)</b>	<b>Optimum Moisture Content (%)</b>
*HS-1 @ 0-5 feet	Clayey Sand with Gravel	124.5	10.5
**HS-2 @ 0-5 feet	Clayey Sand with Gravel	129.5	7.5

\*Note: This max dry density result is based on a rock correction with approximately 20% retained on the No. 4 sieve.

\*\*Note: This max dry density result is based on a rock correction with approximately 24% retained on the No. 4 sieve.

**Chloride Content:** Chloride content was tested in accordance with Caltrans Test Method (CTM) 422. The results are presented below.

<b>Sample Location</b>	<b>Chloride Content, ppm</b>
HS-1 @ 0-5 feet	200

**Soluble Sulfates:** The soluble sulfate contents of selected samples were determined by standard geochemical methods (CTM 417). The soluble sulfate content is used to determine the appropriate cement type and maximum water-cement ratios. The test results are presented in the table below.

<b>Sample Location</b>	<b>Sulfate Content (ppm)</b>	<b>Sulfate Exposure Class *</b>
HS-1 @ 0-5 feet	66	S0

\*Based on ACI 318R-14, Table 19.3.1.1

***APPENDIX C (Cont'd)***

**Laboratory Testing Procedures and Test Results**

Minimum Resistivity and pH Tests: Minimum resistivity and pH tests were performed in general accordance with CTM 643 and standard geochemical methods. The results are presented in the table below.

<b>Sample Location</b>	<b>pH</b>	<b>Minimum Resistivity (ohms-cm)</b>
HS-1 @ 0-5 feet	7.29	1870

# ONE-DIMENSIONAL SWELL OR SETTLEMENT POTENTIAL OF COHESIVE SOILS ASTM D 4546

Project Name: Meritage - 9407 Jericho Road  
 Project No.: 23052-01  
 Boring No.: HS-1  
 Sample No.: R-3  
 Sample Description: Strong brown sandy lean clay with gravel s(CL)g

Tested By: G. Bathala Date: 04/04/23  
 Checked By: J. Ward Date: 04/13/23  
 Sample Type: Ring  
 Depth (ft.): 7.5


Initial Dry Density (pcf):	97.7
Initial Moisture (%):	14.91
Initial Length (in.):	1.0000
Initial Dial Reading:	0.0460
Diameter(in):	2.415

Final Dry Density (pcf):	99.4
Final Moisture (%) :	20.2
Initial Void ratio:	0.7258
Specific Gravity(assumed):	2.70
Initial Saturation (%)	55.5

Pressure (p) (ksf)	Final Reading (in)	Apparent Thickness (in)	Load Compliance (%)	Swell (+) Settlement (-) % of Sample Thickness	Void Ratio	Corrected Deformation (%)
0.100	0.0473	0.9987	0.00	-0.13	0.7235	-0.13
1.000	0.0609	0.9851	0.16	-1.49	0.7028	-1.33
H2O	0.0615	0.9845	0.16	-1.55	0.7018	-1.39

**Percent Swell (+) / Settlement (-) After Inundation = -0.06**

Void Ratio - Log Pressure Curve



# ONE-DIMENSIONAL SWELL OR SETTLEMENT POTENTIAL OF COHESIVE SOILS ASTM D 4546

Project Name: Meritage - 9407 Jericho Road  
 Project No.: 23052-01  
 Boring No.: I-2  
 Sample No.: R-1  
 Sample Description: Strong brown lean clay with sand (CL)s

Tested By: G. Bathala Date: 04/04/23  
 Checked By: J. Ward Date: 04/13/23  
 Sample Type: Ring  
 Depth (ft.): 5.0


Initial Dry Density (pcf):	103.8
Initial Moisture (%):	22.75
Initial Length (in.):	1.0000
Initial Dial Reading:	0.1193
Diameter(in):	2.415

Final Dry Density (pcf):	110.2
Final Moisture (%) :	17.8
Initial Void ratio:	0.6240
Specific Gravity(assumed):	2.70
Initial Saturation (%)	98.5

Pressure (p) (ksf)	Final Reading (in)	Apparent Thickness (in)	Load Compliance (%)	Swell (+) Settlement (-) % of Sample Thickness	Void Ratio	Corrected Deformation (%)
0.100	0.1228	0.9965	0.00	-0.35	0.6183	-0.35
1.000	0.1542	0.9651	0.16	-3.49	0.5699	-3.33
H2O	0.1760	0.9433	0.16	-5.67	0.5345	-5.51

**Percent Swell (+) / Settlement (-) After Inundation = -2.26**

Void Ratio - Log Pressure Curve



***Appendix D***  
***Infiltration Test Data***

## Infiltration Test Data Sheet

### LGC Geotechnical, Inc

131 Calle Iglesia Suite 200, San Clemente, CA 92672 tel. (949) 369-6141

**Project Name:** Meritage - La Mesa  
**Project Number:** 23052-01  
**Date:** 3/29/2023  
**Boring Number:** I-1

#### Test hole dimensions (if circular)

Boring Depth (feet)\*: 10  
Boring Diameter (inches): 8  
Pipe Diameter (inches): 3

\*measured at time of test

Minimum test Head ( $D_o$ ):

(What the sounder tape should read)

Boring Depth - (5 x Boring Radius)

8.4 ft

#### Test pit dimensions (if rectangular)

Pit Depth (feet):

Pit Length (feet):

Pit Breadth (feet):

(Shallow) The value on the sounder tape should be close to this value during testing for **DEEP** testing fill to 4 feet below top of hole

#### Pre-Test (Sandy Soil Criteria)\*

Trial No.	Start Time (24:HR)	Stop Time (24:HR)	Time Interval (min)	Initial Depth to Water (feet)	Final Depth to Water (feet)	Total Change in Water Level (feet)	Greater Than or Equal to 0.5 feet (yes/no)
1	9:14	9:39	25.0	2.05	2.06	0.01	No
2	9:39	10:04	25.0	2.06	2.08	0.02	No

\*If two consecutive measurements show that six inches of water seeps away in less than 25 minutes, the test shall be run for an additional hour with measurements taken every 10 minutes. Otherwise, pre-soak (fill) overnight, and then obtain at least twelve measurements per hole over at least six hours (approximately 30 minute intervals) with a precision of at least 0.25 inches

#### Main Test Data

Trial No.	Start Time (24:HR)	Stop Time (24:HR)	Time Interval, $\Delta t$ (min)	Initial Depth to Water, $D_o$ (feet)	Final Depth to Water, $D_f$ (feet)	Change in Water Level, $\Delta D$ (feet)	Percolation Rate (in/hr)	Calculated Infiltration Rate (in/hr)
1	10:04	10:34	30.0	2.08	2.09	0.01	0.2	0.005
2	10:34	11:04	30.0	2.09	2.10	0.01	0.2	0.005
3	11:04	11:34	30.0	2.10	2.12	0.02	0.5	0.010
4	11:34	12:04	30.0	2.12	2.13	0.01	0.2	0.005
5	12:04	12:34	30.0	2.13	2.14	0.01	0.2	0.005
6	12:34	13:04	30.0	2.14	2.16	0.02	0.5	0.010
7	13:04	13:34	30.0	2.16	2.17	0.01	0.2	0.005
8	13:34	14:04	30.0	2.17	2.18	0.01	0.2	0.005
9	14:04	14:34	30.0	2.18	2.19	0.01	0.2	0.005
10	14:34	15:04	30.0	2.19	2.20	0.01	0.2	0.005
11	15:04	15:34	30.0	2.20	2.21	0.01	0.2	0.005
12	15:34	16:04	30.0	2.21	2.22	0.01	0.2	0.005

Calculated Infiltration Rate (No factors of safety)

0.005

Factor of Safety

See Report

Calculated Infiltration Rate (With Factor of Safety)

See Report

Sketch:

Notes:

Based on Guidelines from: San Diego County 05/19/2011

Spreadsheet Revised on: 2/6/2017



## Infiltration Test Data Sheet

### LGC Geotechnical, Inc

131 Calle Iglesia Suite 200, San Clemente, CA 92672 tel. (949) 369-6141

**Project Name:** Meritage - La Mesa  
**Project Number:** 23052-01  
**Date:** 3/29/2023  
**Boring Number:** I-2

#### Test hole dimensions (if circular)

Boring Depth (feet)\*: 10  
Boring Diameter (inches): 8  
Pipe Diameter (inches): 3

\*measured at time of test

Minimum test Head ( $D_o$ ):

(What the sounder tape should read)

Boring Depth - (5 x Boring Radius)

8.4 ft

#### Test pit dimensions (if rectangular)

Pit Depth (feet):

Pit Length (feet):

Pit Breadth (feet):

(Shallow) The value on the sounder tape should be close to this value during testing for **DEEP** testing fill to 4 feet below top of hole

#### Pre-Test (Sandy Soil Criteria)\*

Trial No.	Start Time (24:HR)	Stop Time (24:HR)	Time Interval (min)	Initial Depth to Water (feet)	Final Depth to Water (feet)	Total Change in Water Level (feet)	Greater Than or Equal to 0.5 feet (yes/no)
1	9:10	9:35	25.0	4.28	4.29	0.01	No
2	9:35	10:00	25.0	4.29	4.3	0.01	No

\*If two consecutive measurements show that six inches of water seeps away in less than 25 minutes, the test shall be run for an additional hour with measurements taken every 10 minutes. Otherwise, pre-soak (fill) overnight, and then obtain at least twelve measurements per hole over at least six hours (approximately 30 minute intervals) with a precision of at least 0.25 inches

#### Main Test Data

Trial No.	Start Time (24:HR)	Stop Time (24:HR)	Time Interval, $\Delta t$ (min)	Initial Depth to Water, $D_o$ (feet)	Final Depth to Water, $D_f$ (feet)	Change in Water Level, $\Delta D$ (feet)	Percolation Rate (in/hr)	Calculated Infiltration Rate (in/hr)
1	10:00	10:30	30.0	4.30	4.30	0.00	0.0	0.000
2	10:30	11:00	30.0	4.30	4.30	0.00	0.0	0.000
3	11:00	11:30	30.0	4.30	4.30	0.00	0.0	0.000
4	11:30	12:00	30.0	4.30	4.31	0.01	0.2	0.007
5	12:00	12:30	30.0	4.31	4.31	0.00	0.0	0.000
6	12:30	13:00	30.0	4.31	4.31	0.00	0.0	0.000
7	13:00	13:30	30.0	4.31	4.32	0.01	0.2	0.007
8	13:30	14:00	30.0	4.32	4.32	0.00	0.0	0.000
9	14:00	14:30	30.0	4.32	4.32	0.00	0.0	0.000
10	14:30	15:00	30.0	4.32	4.32	0.00	0.0	0.000
11	15:00	15:30	30.0	4.32	4.32	0.00	0.0	0.000
12	15:30	16:00	30.0	4.32	4.33	0.01	0.2	0.007

Calculated Infiltration Rate (No factors of safety)

0.007

Factor of Safety

See Report

Calculated Infiltration Rate (With Factor of Safety)

See Report

Sketch:

Notes:

Based on Guidelines from: San Diego County 05/19/2011

Spreadsheet Revised on: 2/6/2017



***Appendix E***  
***General Earthwork and Grading***  
***Specifications for Rough Grading***



## **General Earthwork and Grading Specifications for Rough Grading**

### **1.0 General**

#### **1.1 Intent**

These General Earthwork and Grading Specifications are for the grading and earthwork shown on the approved grading plan(s) and/or indicated in the geotechnical report(s). These Specifications are a part of the recommendations contained in the geotechnical report(s). In case of conflict, the specific recommendations in the geotechnical report shall supersede these more general Specifications. Observations of the earthwork by the project Geotechnical Consultant during the course of grading may result in new or revised recommendations that could supersede these specifications or the recommendations in the geotechnical report(s).

#### **1.2 The Geotechnical Consultant of Record**

Prior to commencement of work, the owner shall employ a qualified Geotechnical Consultant of Record (Geotechnical Consultant). The Geotechnical Consultant shall be responsible for reviewing the approved geotechnical report(s) and accepting the adequacy of the preliminary geotechnical findings, conclusions, and recommendations prior to the commencement of the grading.

Prior to commencement of grading, the Geotechnical Consultant shall review the "work plan" prepared by the Earthwork Contractor (Contractor) and schedule sufficient personnel to perform the appropriate level of observation, mapping, and compaction testing.

During the grading and earthwork operations, the Geotechnical Consultant shall observe, map, and document the subsurface exposures to verify the geotechnical design assumptions. If the observed conditions are found to be significantly different than the interpreted assumptions during the design phase, the Geotechnical Consultant shall inform the owner, recommend appropriate changes in design to accommodate the observed conditions, and notify the review agency where required.

The Geotechnical Consultant shall observe the moisture-conditioning and processing of the subgrade and fill materials and perform relative compaction testing of fill to confirm that the attained level of compaction is being accomplished as specified. The Geotechnical Consultant shall provide the test results to the owner and the Contractor on a routine and frequent basis.

#### **1.3 The Earthwork Contractor**

The Earthwork Contractor (Contractor) shall be qualified, experienced, and knowledgeable in earthwork logistics, preparation and processing of ground to receive fill, moisture-conditioning and processing of fill, and compacting fill. The Contractor shall review and accept the plans, geotechnical report(s), and these Specifications prior to commencement of grading. The Contractor shall be solely responsible for performing the grading in accordance with the project plans and specifications. The Contractor shall prepare and submit to the owner and the Geotechnical Consultant a work plan that indicates the sequence of earthwork grading, the number of "equipment" of work and the estimated quantities of daily earthwork

contemplated for the site prior to commencement of grading. The Contractor shall inform the owner and the Geotechnical Consultant of changes in work schedules and updates to the work plan at least 24 hours in advance of such changes so that appropriate personnel will be available for observation and testing. The Contractor shall not assume that the Geotechnical Consultant is aware of all grading operations.

The Contractor shall have the sole responsibility to provide adequate equipment and methods to accomplish the earthwork in accordance with the applicable grading codes and agency ordinances, these Specifications, and the recommendations in the approved geotechnical report(s) and grading plan(s). If, in the opinion of the Geotechnical Consultant, unsatisfactory conditions, such as unsuitable soil, improper moisture condition, inadequate compaction, insufficient buttress key size, adverse weather, etc., are resulting in a quality of work less than required in these specifications, the Geotechnical Consultant shall reject the work and may recommend to the owner that construction be stopped until the conditions are rectified. It is the contractor's sole responsibility to provide proper fill compaction.

## **2.0 Preparation of Areas to be Filled**

### **2.1 Clearing and Grubbing**

Vegetation, such as brush, grass, roots, and other deleterious material shall be sufficiently removed and properly disposed of in a method acceptable to the owner, governing agencies, and the Geotechnical Consultant.

The Geotechnical Consultant shall evaluate the extent of these removals depending on specific site conditions. Earth fill material shall not contain more than 1 percent of organic materials (by volume). Nesting of the organic materials shall not be allowed.

If potentially hazardous materials are encountered, the Contractor shall stop work in the affected area, and a hazardous material specialist shall be informed immediately for proper evaluation and handling of these materials prior to continuing to work in that area.

As presently defined by the State of California, most refined petroleum products (gasoline, diesel fuel, motor oil, grease, coolant, etc.) have chemical constituents that are considered to be hazardous waste. As such, the indiscriminate dumping or spillage of these fluids onto the ground may constitute a misdemeanor, punishable by fines and/or imprisonment, and shall not be allowed. The contractor is responsible for all hazardous waste relating to his work. The Geotechnical Consultant does not have expertise in this area. If hazardous waste is a concern, then the Client should acquire the services of a qualified environmental assessor.

### **2.2 Processing**

Existing ground that has been declared satisfactory for support of fill by the Geotechnical Consultant shall be scarified to a minimum depth of 6 inches. Existing ground that is not satisfactory shall be over-excavated as specified in the following section. Scarification shall continue until soils are broken down and free of oversize material and the working surface is reasonably uniform, flat, and free of uneven features that would inhibit uniform compaction.

### **2.3 Over-excavation**

In addition to removals and over-excavations recommended in the approved geotechnical report(s) and the grading plan, soft, loose, dry, saturated, spongy, organic-rich, highly fractured or otherwise unsuitable ground shall be over-excavated to competent ground as evaluated by the Geotechnical Consultant during grading.

### **2.4 Benching**

Where fills are to be placed on ground with slopes steeper than 5:1 (horizontal to vertical units), the ground shall be stepped or benched. Please see the Standard Details for a graphic illustration. The lowest bench or key shall be a minimum of 15 feet wide and at least 2 feet deep, into competent material as evaluated by the Geotechnical Consultant. Other benches shall be excavated a minimum height of 4 feet into competent material or as otherwise recommended by the Geotechnical Consultant. Fill placed on ground sloping flatter than 5:1 shall also be benched or otherwise over-excavated to provide a flat subgrade for the fill.

### **2.5 Evaluation/Acceptance of Fill Areas**

All areas to receive fill, including removal and processed areas, key bottoms, and benches, shall be observed, mapped, elevations recorded, and/or tested prior to being accepted by the Geotechnical Consultant as suitable to receive fill. The Contractor shall obtain a written acceptance from the Geotechnical Consultant prior to fill placement. A licensed surveyor shall provide the survey control for determining elevations of processed areas, keys, and benches.

## **3.0 Fill Material**

### **3.1 General**

Material to be used as fill shall be essentially free of organic matter and other deleterious substances evaluated and accepted by the Geotechnical Consultant prior to placement. Soils of poor quality, such as those with unacceptable gradation, high expansion potential, or low strength shall be placed in areas acceptable to the Geotechnical Consultant or mixed with other soils to achieve satisfactory fill material.

### **3.2 Oversize**

Oversize material defined as rock, or other irreducible material with a maximum dimension greater than 8 inches, shall not be buried or placed in fill unless location, materials, and placement methods are specifically accepted by the Geotechnical Consultant. Placement operations shall be such that nesting of oversized material does not occur and such that oversize material is completely surrounded by compacted or densified fill. Oversize material shall not be placed within 10 vertical feet of finish grade or within 2 feet of future utilities or underground construction.

### **3.3 Import**

If importing of fill material is required for grading, proposed import material shall meet the requirements of the geotechnical consultant. The potential import source shall be given to the Geotechnical Consultant at least 48 hours (2 working days) before importing begins so that its suitability can be determined and appropriate tests performed.

## **4.0 Fill Placement and Compaction**

### **4.1 Fill Layers**

Approved fill material shall be placed in areas prepared to receive fill (per Section 3.0) in near-horizontal layers not exceeding 8 inches in loose thickness. The Geotechnical Consultant may accept thicker layers if testing indicates the grading procedures can adequately compact the thicker layers. Each layer shall be spread evenly and mixed thoroughly to attain relative uniformity of material and moisture throughout.

### **4.2 Fill Moisture Conditioning**

Fill soils shall be watered, dried back, blended, and/or mixed, as necessary to attain a relatively uniform moisture content at or slightly over optimum. Maximum density and optimum soil moisture content tests shall be performed in accordance with the American Society of Testing and Materials (ASTM Test Method D1557).

### **4.3 Compaction of Fill**

After each layer has been moisture-conditioned, mixed, and evenly spread, it shall be uniformly compacted to not less than 90 percent of maximum dry density (ASTM Test Method D1557). Compaction equipment shall be adequately sized and be either specifically designed for soil compaction or of proven reliability to efficiently achieve the specified level of compaction with uniformity.

### **4.4 Compaction of Fill Slopes**

In addition to normal compaction procedures specified above, compaction of slopes shall be accomplished by backrolling of slopes with sheepfoot rollers at increments of 3 to 4 feet in fill elevation, or by other methods producing satisfactory results acceptable to the Geotechnical Consultant. Upon completion of grading, relative compaction of the fill, out to the slope face, shall be at least 90 percent of maximum density per ASTM Test Method D1557.

### **4.5 Compaction Testing**

Field tests for moisture content and relative compaction of the fill soils shall be performed by the Geotechnical Consultant. Location and frequency of tests shall be at the Consultant's discretion based on field conditions encountered. Compaction test locations will not necessarily be selected on a random basis. Test locations shall be selected to verify adequacy of compaction levels in areas that are judged to be prone to inadequate compaction (such as close to slope faces and at the fill/bedrock benches).

#### **4.6 Frequency of Compaction Testing**

Tests shall be taken at intervals not exceeding 2 feet in vertical rise and/or 1,000 cubic yards of compacted fill soils embankment. In addition, as a guideline, at least one test shall be taken on slope faces for each 5,000 square feet of slope face and/or each 10 feet of vertical height of slope. The Contractor shall assure that fill construction is such that the testing schedule can be accomplished by the Geotechnical Consultant. The Contractor shall stop or slow down the earthwork construction if these minimum standards are not met.

#### **4.7 Compaction Test Locations**

The Geotechnical Consultant shall document the approximate elevation and horizontal coordinates of each test location. The Contractor shall coordinate with the project surveyor to assure that sufficient grade stakes are established so that the Geotechnical Consultant can determine the test locations with sufficient accuracy. At a minimum, two grade stakes within a horizontal distance of 100 feet and vertically less than 5 feet apart from potential test locations shall be provided.

#### **5.0 Subdrain Installation**

Subdrain systems shall be installed in accordance with the approved geotechnical report(s), the grading plan, and the Standard Details. The Geotechnical Consultant may recommend additional subdrains and/or changes in subdrain extent, location, grade, or material depending on conditions encountered during grading. All subdrains shall be surveyed by a land surveyor/civil engineer for line and grade after installation and prior to burial. Sufficient time should be allowed by the Contractor for these surveys.

#### **6.0 Excavation**

Excavations, as well as over-excavation for remedial purposes, shall be evaluated by the Geotechnical Consultant during grading. Remedial removal depths shown on geotechnical plans are estimates only. The actual extent of removal shall be determined by the Geotechnical Consultant based on the field evaluation of exposed conditions during grading. Where fill-over-cut slopes are to be graded, the cut portion of the slope shall be made, evaluated, and accepted by the Geotechnical Consultant prior to placement of materials for construction of the fill portion of the slope, unless otherwise recommended by the Geotechnical Consultant.

#### **7.0 Trench Backfills**


**7.1** The Contractor shall follow all OHSA and Cal/OSHA requirements for safety of trench excavations.

**7.2** All bedding and backfill of utility trenches shall be done in accordance with the applicable provisions of Standard Specifications of Public Works Construction. Bedding material shall have a Sand Equivalent greater than 30 (SE>30). The bedding shall be placed to 1 foot over


the top of the conduit and densified by jetting. Backfill shall be placed and densified to a minimum of 90 percent of maximum from 1 foot above the top of the conduit to the surface.

- 7.3** The jetting of the bedding around the conduits shall be observed by the Geotechnical Consultant.
- 7.4** The Geotechnical Consultant shall test the trench backfill for relative compaction. At least one test should be made for every 300 feet of trench and 2 feet of fill.
- 7.5** Lift thickness of trench backfill shall not exceed those allowed in the Standard Specifications of Public Works Construction unless the Contractor can demonstrate to the Geotechnical Consultant that the fill lift can be compacted to the minimum relative compaction by his alternative equipment and method.

## Fill Slope




## Fill-Over-Cut Slope




\* Construct Cut Slope First


## Cut-Over-Fill Slope




Note: Natural Slopes Steeper Than 5:1 (H:V) Must Be Benched.









# SUBDRAIN OUTLET MARKER -6" & 8" PIPE



# SUBDRAIN OUTLET MARKER -4" PIPE




## Cut Lot (Exposing Unsuitable Soils at Design Grade)



Note 1: Removal Bottom Should be Graded With Minimum 2% Fall Towards Street or Other Suitable Area (as Determined by Soils Engineer) to Avoid Ponding Below Building

Note 2: Where Design Cut Lots are Excavated Entirely Into Competent Material, Overexcavation May Still be Required for Hard-Rock Conditions or for Materials With Variable Expansion Characteristics.


## Cut/Fill Transition Lot




\*Deeper if Specified by Soils Engineer




## CUT AND TRANSITION LOT OVEREXCAVATION DETAIL



### Proposed Outlet Detail









NO CONSTRUCTION EQUIPMENT WITHIN 25 FEET  
OF ANY INSTALLED SETTLEMENT MONUMENTS




## TYPICAL SURFACE SETTLEMENT MONUMENT



1. SURVEY FOR HORIZONTAL AND VERTICAL LOCATION TO NEAREST .01 INCH PRIOR TO BACKFILL USING KNOW LOCATIONS THAT WILL REMAIN INTACT DURING THE DURATION OF THE MONITORING PROGRAM. KNOW POINTS EXPLICITLY NOT ALLOWED ARE THOSE LOCATED ON FILL OR THAT WILL BE DESTROYED DURING GRADING.
2. IN THE EVENT OF DAMAGE TO SETTLEMENT PLATE DURING GRADING, CONTRACTOR SHALL IMMEDIATELY NOTIFY THE GEOTECHNICAL ENGINEER AND SHALL BE RESPONSIBLE FOR RESTORING THE SETTLEMENT PLATES TO WORKING ORDER.
3. DRILL TO RECOVER AND ATTACH RISER PIPE.



Windrow Parallel to Slope Face



Note: Oversize Rock is Larger than 8" in Maximum Dimension.

**Section A-A'**

