

**ENVISION MOTORS
MERCEDES BENZ DEALERSHIP PROJECT
Initial Study and Mitigated Negative Declaration (IS/MND)**



CEQA Analysis Prepared for:

City of West Covina
Planning Division
1444 W. Garvey Avenue S
West Covina, CA 91790

Prepared by:



UltraSystems Environmental Inc.
16431 Scientific Way
Irvine, CA 92618-4355
Telephone: 949-788-4900
FAX: 949/788-4901

October 2024

Project No. 7212

This page has been left intentionally blank.



PROJECT INFORMATION SHEET

- 1. Project Title**

Envision Mercedes Benz Dealership, City of West Covina Project
- 2. CEQA Lead Agency**

City of West Covina
Community Development Department
Planning Division
1444 West Garvey Ave # 208
West Covina, CA 91790
Jo-Anne Burns, Deputy Community Development Director
E: jburns@westcovina.org
- 3. Project Applicant**

Envision Motors
2010 E Garvey Ave S
West Covina, CA 91791
Boyd Sumner, Director Franchise Operations
E: boyd.sumner@envisionmotors.com
- 4. Project Location**

1800 East Garvey Avenue, West Covina, CA 91791
- 5. Assessor's Parcel Numbers**

APNs 8478-007-025; -031; and -042
- 6. Project Site General Plan Designation(s)**

Commercial (C), Auto Plaza Overlay Zone
- 7. Project Site Zoning Designation(s)**

Service Commercial Mixed-Use (SMU) and Neighborhood Commercial Mixed Use (NMU)
- 8. Surrounding Land Uses and Setting**

The site is surrounded by an auto dealership to the east and south opposite East Garvey Avenue; a restaurant and a gas station to the west opposite Azusa Avenue; and the I-10 freeway to the north.
- 9. Description of Project**

The proposed project would involve demolition of an existing auto dealership (Envision Motors Toyota) and an operating Valero gas station, and construction of a new two-story automotive sales and dealership building housing Envision Motors Mercedes Benz, selling four related brands – Mercedes Benz, Maybach, AMG and Sprinter – as well as associated surface parking, landscaping, and facilities for EV charging.

Refer to **Section 3.0** of this document for additional information.



The project applicant is requesting the following discretionary actions, which are discussed in detail in **Section 3.0** of this document:

- Site Plan approval and building permits.
- Zone Change

11. Selected Agencies whose Approval is Required

City of West Covina

12. Have California Native American tribes traditionally and culturally affiliated with the project area requested consultation pursuant to Public Resources Code § 21080.3.1? If so, has consultation begun?

Letters were sent by the City of West Covina (the Lead Agency), on September 5, 2024 to local Native American tribes asking if they wished to participate in AB 52 and SB 18 consultation concerning the proposed project. Tribes had up to 30 days and 90 days respectively in which to respond to notification of the project. For the proposed project, those tribe(s) that requested consultation were contacted by the City per Public Resources Code § 21074. On September 6, 2024, the City received a communication from the Gabrielino – Kizh Nation requesting consultation. No other tribes responded. The Kizh Nation submitted Tribal Cultural Resource mitigation measures which were adopted and consultation was concluded.

13. Other Public Agencies

Agencies that will review the proposed project include the following:

- California Regional Water Quality Control Board – Los Angeles
- South Coast Air Quality Management District
- City of West Covina Fire Department
- California Department of Motor Vehicles



Table of Contents

Project Information Sheet	i
Table of Contents	i
Acronyms and Abbreviations.....	i
1.0 INTRODUCTION.....	1-1
1.1 Proposed Project.....	1-1
1.1.1 Project Components.....	1-1
1.1.2 Estimated Construction Schedule	1-2
1.2 Lead Agencies – Environmental Review Implementation	1-2
1.3 CEQA Overview.....	1-2
1.3.1 Purpose of CEQA.....	1-2
1.3.2 Authority to Mitigate under CEQA	1-3
1.4 Purpose of Initial Study	1-3
1.5 Review and Comment by Other Agencies.....	1-4
1.6 Impact Terminology	1-4
1.7 Organization of Initial Study	1-5
1.8 Findings from the Initial Study.....	1-5
1.8.1 No Impact or Impacts Considered Less than Significant	1-5
1.8.2 Impacts Considered Less than Significant with Mitigation Measures.....	1-6
2.0 ENVIRONMENTAL SETTING	2-1
2.1 Project Location.....	2-1
2.2 Project Setting.....	2-1
2.2.1 Land Use and Zoning.....	2-1
2.3 Existing Characteristics of the Site	2-1
2.3.1 Climate and Air Quality.....	2-1
2.3.2 Geology and Soils.....	2-1
2.3.3 Hydrology.....	2-1
2.3.4 Biology	2-1
2.3.5 Public Services.....	2-1
2.3.6 Utilities	2-2
3.0 PROJECT DESCRIPTION	3-1
Project Location	3-1
Project Setting.....	3-1
General Plan and Zoning Designations	3-1
Project Overview	3-1
3.1.1 Access, Circulation, and Parking	3-8
3.1.2 Trash.....	3-8
3.1.3 Landscaping.....	3-9
3.2 Employment.....	3-11
3.3 Construction.....	3-11
3.3.1 Demolition.....	3-11
3.3.2 Hazardous Materials Assessment and Remediation	3-11
3.3.3 Construction Phasing.....	3-12



3.3.4	Grading	3-12
Required Approvals.....		3-13
Other Public Agencies Whose Approval is Required		3-13
4.0	Environmental Checklist	4-1
	Environmental Factors Potentially Affected	4-1
	Determination (To Be Completed by the Lead Agency)	4-1
	Evaluation of Environmental Impacts.....	4-2
4.1	Aesthetics	4-1
4.2	Agriculture and Forestry Resources	4.2-7
4.3	Air Quality	4.3-1
4.3.1	Pollutants of Concern	4.3-1
4.3.2	Climate/Meteorology	4.3-3
4.3.3	Local Air Quality	4.3-4
4.3.4	Air Quality Management Plan (AQMP).....	4.3-5
4.3.5	Sensitive Receptors	4.3-5
4.3.6	Applicable South Coast Air Quality Management District Rules	4.3-6
4.3.7	Impact Analysis.....	4.3-6
4.4	Biological Resources.....	4.4-1
4.4.1	Discussion of Impacts.....	4.4-2
4.5	Cultural Resources	4.5-1
4.5.1	Methodology.....	4.5-1
4.5.2	Existing Conditions.....	4.5-1
4.5.3	Impact Analysis.....	4.5-3
4.6	Energy.....	4.6-8
4.7	Geology and Soils	4.7-14
4.8	Greenhouse Gas Emissions	4.8-1
4.8.1	Background Information on Greenhouse Gas Emissions	4.8-1
4.8.2	Regulatory Setting	4.8-2
4.8.3	GHG Emissions	4.8-7
4.8.4	Impact Thresholds.....	4.8-8
4.8.5	Impact Analysis.....	4.8-8
4.9	Hazards and Hazardous Materials.....	4.9-1
4.10	Hydrology and Water Quality	4.10-2
4.11	Land Use and Planning	4.11-1
4.12	Mineral Resources.....	4.12-1
4.13	Noise.....	4.13-1
4.13.1	Characteristics of Sound.....	4.13-1
4.13.2	Noise Measurement Scales.....	4.13-1
4.13.3	Existing Noise	4.13-2
4.13.4	Regulatory Setting	4.13-6
4.13.5	Significance Thresholds.....	4.13-9
4.13.6	Impact Analysis.....	4.13-10
4.14	Population and Housing.....	4.14-1
4.15	Public Services	4.15-1
4.16	Recreation.....	4.16-1
4.17	Transportation	4.17-1
4.18	Tribal Cultural Resources	4.18-6
4.19	Utilities and Service Systems	4.19-1



4.20	Wildfire	4.20-1
4.21	Mandatory Findings of Significance	4.21-1
5.0	REFERENCES.....	5-1
6.0	LIST OF PREPARERS	6-1
6.1	CEQA Lead Agency.....	6-1
6.2	Project Applicant.....	6-1
6.3	UltraSystems Environmental, Inc.....	6-1
6.3.1	Environmental Planning Team.....	6-1
6.3.2	Technical Team	6-1
7.0	MITIGATION MONITORING AND REPORTING PROGRAM	7-1

TABLES

Table 2.2-1	- Summary of Existing Land Use and Zoning Designations.....	2-1
Table 3.4-1	- Square Feet by Use in Proposed Building.....	3-8
Table 3.4-1	- Construction Phasing and Equipment.....	3-12
Table 4.1-1	- Project Compliance with Applicable City of West Covina General Plan Policies Regarding Scenic Quality.....	4.1-5
Table 4.3-1	- Federal and State Attainment Status	4.3-2
Table 4.3-2	- Ambient Air Quality Monitoring Data	4.3-4
Table 4.3-3	- SCAQMD Thresholds of Significance.....	4.3-7
Table 4.3-4	- Construction Schedule.....	4.3-8
Table 4.3-5	- Maximum Daily Regional Construction Emissions	4.3-8
Table 4.3-6	- Maximum Daily Existing Operational Emissions.....	4.3-10
Table 4.3-7	- Maximum Daily Project Operational Emissions.....	4.3-10
Table 4.3-8	- Maximum Daily Net Change in Operational Emissions.....	4.3-11
Table 4.3-9	- Results of Unmitigated Localized Significance Analysis.....	4.3-12
Table 4.6-1	- Estimated Existing Operational Energy Use.....	4.6-9
Table 4.6-2	- Estimated Proposed Project Operational Energy Use	4.6-9
Table 4.6-3	- Estimated Net Change in Operational Energy Use	4.6-10
Table 4.7-2	- Fossil Localities in the Project Region.....	4.7-4
Table 4.8-2	- Project Construction-Related GHG Emissions	4.8-10
Table 4.8-3	- Existing Operational GHG Emissions.....	4.8-10
Table 4.8-4	- Project Operational GHG Emissions.....	4.8-11
Table 4.8-5	- Net Change of Operational GHG Emissions	4.8-11
Table 4.10-1	- Hydrology Analysis Summary for Existing and Proposed Conditions.....	4.10-5
Table 4.11	- Consistency Analysis: Proposed Project Compared to Applicable City of West Covina General Plan Land Use, Policies and Actions.....	4.11-4
Table 4.13-1	- Sensitive Receivers in Project Area	4.13-2
Table 4.13-2	- Ambient Noise Measurement Results	4.13-4
Table 4.13-3	- California Land Use Compatibility for Community Noise Sources	4.13-6
Table 4.13-4	- Construction Equipment Characteristics	4.13-10
Table 4.13-5	- Noise Analytical Framework.....	4.13-11
Table 4.13-6	- Estimated Maximum Construction Noise Exposures	4.13-12
Table 4.13-7	- Vibration Levels of Typical Construction Equipment.....	4.13-14



Table 4.17-1 - Project Compliance with City of Placentia General Plan Policies Regarding Mobility and Transportation.....	4.17-2
Table 4.19-1 - Estimated Project Water Demand.....	4.19-4
Table 4.19-2 - Supply & Demand Predictions for the San Jose Hills Service Area by Source (afy)	4.19-4
Table 4.19-3 - San Jose Hills Area Normal Year Supply & Demand Comparison (afy)	4.19-5
Table 4.19-4 - San Jose Hills Service Area Single Dry Year Supply & Demand Comparison (afy)	4.19-5
Table 4.19-5 - San Jose Service Area Multiple Dry Year Supply & Demand Comparison (afy) ...	4.19-5
Table 4.19-6 - Landfills Serving West Covina	4.19-7
Table 4.19-7 - Estimated Project-Generated Solid Waste.....	4.19-8
Table 7.0-1 - Mitigation Monitoring and Reporting Program	7-2

LIST OF FIGURES

Figure 2.1-1 - Regional Location.....	2-2
Figure 2.1-2 - Project Vicinity.....	2-1
Figure 2.1-3 - Project Location.....	2-2
Figure 2.2-1 - Topographic Map	2-3
Figure 2.2-2 - Project Site Photographs.....	2-4
Figure 3.4-1 - Site Plan.....	3-2
Figure 3.4-2 - First Floor Plan.....	3-3
Figure 3.4-3 - Second Floor Plan	3-4
Figure 3.4-4 - Elevations.....	3-5
Figure 3.4-5 - Renderings (1 of 2)	3-6
Figure 3.4-6 - Renderings (2 of 2).....	3-7
Figure 3.4-7 - Landscape Plan.....	3-10
Figure 4.1-1 - State Scenic Highways.....	4.1-4
Figure 4.2-1 - Important Farmland Categories	4.2-8
Figure 4.4-1 - National Wetlands Inventory	4.4-4
Figure 4.5-1 - Topographic Map	4.5-2
Figure 4.7-1 - Alquist Priolo Fault Zones.....	4.7-16
Figure 4.7-2 - Regionally Active Faults	4.7-17
Figure 4.7-3 - Landslides and Liquefaction.....	4.7-1
Figure 4.9-1 - Cortese List Sites	4.9-8
Figure 4.9-2 - Airport Influence Area Map for French Valley Airport.....	4.9-9
Figure 4.9-3 - Fire Hazard Severity Zones - State Responsibility Area.....	4.9-12
Figure 4.9-4 - Fire Hazard Severity Zones - Local Responsibility Area.....	4.9-1
Figure 4.10-1 - USGS Surface Waters and Watersheds.....	4.10-4
Figure 4.10-2 - Groundwater Basins Map	4.10-3
Figure 4.10-3 - FEMA Flood Insurance Rate Map.....	4.10-6
Figure 4.11-1 - General Plan Land Use Designation.....	4.11-2
Figure 4.11-2 - Zoning Designation.....	4.11-3
Figure 4.12-1 - Designated Mineral Resource Zone	4.12-2
Figure 4.12-2 - Oil and Gas Wells and Fields	4.12-3
Figure 4.12-3 - Geothermal Wells	4.12-4
Figure 4.13-1 - Sensitive Receivers Near the Project Site.....	4.13-3
Figure 4.13-2 - Ambient Noise Measurement Locations.....	4.13-5



ATTACHMENTS

Appendix A	Project Plans and Drawings
Appendix B	Air Quality and Greenhouse Gas Emissions Data
Appendix C	Biological Resources-Species Tables
Appendix D	Cultural Resources Report
Appendix E1	Preliminary Geotechnical Investigation
Appendix E2	Paleontological Resources Records Search
Appendix F1	Phase I ESA-Envision
Appendix F2	Asbestos Sampling-Testing Records-Envision
Appendix F3	Phase I ESA-Shell
Appendix G1	Preliminary Hydrology Report
Appendix G2	Low Impact Development (LID) Plan
Appendix H	Noise Assessment
Appendix I	RK Engineering VMT Analysis



ACRONYMS AND ABBREVIATIONS

Acronym/Abbreviation	Term
AAQS	ambient air quality standards
AB 32	California Global Warming Solutions Act of 2006 (Assembly Bill 32)
AB 52	Assembly Bill 52
ACM(s)	Asbestos-Containing Material(s)
ADA	Americans with Disabilities Act
AFY	Acre-feet per year
AIA	Airport Influence Area
amsl	above mean sea level
APE	Area of Potential Effects
APN	Assessor's Parcel Number
AQA	Air Quality Analysis
AQMP	Air Quality Management Plan
ARB	California Air Resources Board
BAU	business as usual
BIOS	Biogeographic Information and Observation System
BMPs	Best Management Practices
CAAQS	California Ambient Air Quality Standards
CalEEMod	California Emissions Estimator Model
CAL FIRE	California Department of Forestry and Fire Protection
CALGreen	California Green Building Standards
Caltrans	California Department of Transportation
CAO(s)	Cleanup and Abatement Order(s)
CAPCOA	California Air Pollution Control Officers Association
CASGEM	California Statewide Groundwater Elevation Monitoring
CAT	Climate Action Team
CBC	California Building Code
CCAA	California Clean Air Act
CCR	California Code of Regulations
CDO(s)	Cease and Desist Order(s)
CDFW	California Department of Fish and Wildlife
CEQA	California Environmental Quality Act
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
CESA	California Endangered Species Act
CFGF	California Fish and Game Code
cfs	cubic feet per second
CGS	California Geological Survey
CH ₄	methane
CHRIS	California Historic Resources Inventory System
City	City of West Covina
CIWMP	Los Angeles Countywide Integrated Waste Management Plan
CMP	Congestion Management Program
CNEL	Community Noise Equivalent Level
CNPS	California Native Plant Society
CO	carbon monoxide



Acronym/Abbreviation	Term
CO ₂	carbon dioxide
CO ₂ e	carbon dioxide equivalent
CWA	Clean Water Act
dB	decibel
dBA	A-weighted decibel scale
DOC	California Department of Conservation
DOSH	California Division of Safety and Health
DTSC	Department of Toxic Substances Control
du/ac	Dwelling units per acre
DWR	Department of Water Resources
EIR	Environmental Impact Report
EMS	Emergency Medical Services
EO	Executive Order
EPA	Environmental Protection Agency
ESA	Endangered Species Act
ESA	Environmental Site Assessment
EV	electric vehicle
EVCS	electric vehicle charging station
°F	degrees Fahrenheit
FAR	floor area ratio
FEMA	Federal Emergency Management Agency
GWP	global warming potential
HABS	Historic American Building Survey
HCP	Habitat Conservation Plan
HFCs	hydroflourocarbons
HU	Hydrologic Unit
HVAC	heating, ventilation and air conditioning
IPCC	Intergovernmental Panel on Climate Change
ISA	International Society of Arboriculture
IS/MND	Initial Study/Mitigated Negative Declaration
ITE	Institute of Transportation Engineers
L ₉₀	noise level that is exceeded 90% of the time
L _{eq}	equivalent noise level
LACFCD	Los Angeles County Flood Control District
LACPW	Los Angeles County Public Works
LARWCB	Los Angeles Regional Water Quality Control Board
LBP	Lead-Based Paint
LID	Low Impact Development
L _{max}	root mean square maximum noise level
LOS	Level of Service
LRA	Local Responsibility Area
LSTs	Localized Significance Thresholds
LUST	Leaking Underground Storage Tank
MBTA	Migratory Bird Treaty Act
mgd	million gallons per day
MLD	Most Likely Descendant



Acronym/Abbreviation	Term
MM(s)	mitigation measure(s)
MMRP	Mitigation Monitoring and Reporting Program
MMTCO ₂ e	million metric tons of CO ₂ e
MND	Mitigated Negative Declaration
MRF	Material Recovery Facility
MRZ	Mineral Resource Zone
MS4	Municipal Separate Storm Sewer permit
MT	Metric tons
MWD	Metropolitan Water District of Southern California
N ₂ O	nitrous oxide
NAAQS	National Ambient Air Quality Standards
NAHC	Native American Heritage Commission
National Core	National Community Renaissance
NASA	National Aeronautics and Space Administration
NCCP	Natural Communities Conservation Plan
ND	Negative Declaration
NO	nitric oxide
NO _x	nitrogen oxides
NO ₂	nitrogen dioxide
NPDES	National Pollutant Discharge Elimination System
O ₃	Ozone
OPR	Governor's Office of Planning and Research
OSHA	Occupational Safety and Health Administration
Pb	lead
PCB	polychlorinated biphenyl
PFCs	perfluorocarbons
PM	particulate matter
PM ₁₀	respirable particulate matter
PM _{2.5}	fine particulate matter
ppm	parts per million
PPV	peak particle velocity
RCRA	Resource Conservation and Recovery Act
RECs	Recognized Environmental Condition(s)
R-G	Medium Density Residential zoning designation
RHNA	Regional Housing Needs Allocation
RMS	root mean square
ROG	Reactive organic gases
ROW	Right-of-way
RPS	Renewables Portfolio Standard
RWQCB	Regional Water Quality Control Board
§	section
SB	Senate Bill
SCAB	South Coast Air Basin
SCAG	Southern California Association of Governments
SCAQMD	South Coast Air Quality Management District
SCCIC	South Central Coastal Information Center



Acronym/Abbreviation	Term
SCE	Southern California Edison Company
SF ₆	sulfur hexafluoride
SIP	State Implementation Plan
SLF	Sacred Lands File
SMARA	Surface Mining and Reclamation Act
SO ₂	sulfur dioxide
SoCalGas	Southern California Gas Company
SRA	State Responsibility Area
SRAs	source receptor areas
SRRE	Source Reduction and Recycling Element
STIP	Statewide Transportation Improvement Program
SWC	Southwest Water Company
Suburban	Suburban Water Systems
SWPPP	Stormwater Pollution Prevention Plan
SWRCB	State Water Resources Control Board
TAPs	Transportation Assembly Points
T-C	Town Center zoning designation
TCRs	Tribal Cultural Resources
TMP	Traffic Management Plan
UFPO	Urban Forest Protection Ordinance
UEI	UltraSystems Environmental, Inc.
U.S.	United States
USDA	United States Department of Agriculture
USEPA	United States Environmental Protection Agency
VdB	vibration decibels
VCP	vittrified clay pipe
VHFHSZ(s)	very high fire hazard severity zone(s)
VMT	vehicle miles traveled
VOC	volatile organic compound
WCFD	West Covina Fire Department
WCPD	West Covina Police Department
WCUSD	West Covina Unified School District
WEG	wind erodibility group
WQMP	Water Quality Management Plan
WRI	World Resources Institute
ybp	years before present



1.0 INTRODUCTION

1.1 Proposed Project

The City of West Covina (City) is processing a request to implement a series of discretionary actions that would ultimately allow the demolition of an existing auto dealership (Envision Motors Toyota) and an operating Valero gas station, and the development of a new two-story automotive sales and dealership building housing Envision Motors Mercedes Benz of West Covina, selling four related new car brands – Mercedes Benz, Maybach, AMG, and Sprinter automotive lines along with pre-owned vehicles. Development would also include associated surface parking, landscaping, and Electric Vehicle (EV) charging facilities.

The project is located at 1800 East Garvey Avenue South and 200 South Azusa Avenue in West Covina on the southeast corner of the I-10 freeway and the South Azusa Avenue interchange. The site area encompasses 3.53 acres on three parcels, with plans for a total building area of 85,390 square feet, including the enclosed first and second floors, along with a second-floor delivery deck.

1.1.1 Project Components

The proposed project would consist of:

Demolition

- The existing dealership, Envision Toyota of West Covina.
- The 10-VFP (vehicle fueling position) Valero gas station.

Proposed Buildings

Construction of a two-story commercial building with a total of 85,390 square feet.

- First Floor: 42,890 square feet.
- Second Floor: 42,500 square feet.
- Second Floor Roof Overhang: 8,920 square feet.

Parking

First Level

- Display Parking: 144 spaces
- Pre-owned Showroom: 98 spaces
- Customer Parking: 25 spaces
- Parking (undesignated): 43 spaces
- EV Parking: 20 spaces
- Sprinter Showroom: 11 spaces
- New Vehicle Delivery: 4 spaces
- Detail Bays: 8 spaces

Second Floor

- Showroom: 42 spaces

Total Parking Spaces: 395 spaces



Utilities

- EV Transformers
- Trash Yard (enclosure)

1.1.2 Estimated Construction Schedule

Section 3.0 of the Initial Study provides a summary of the timeline, equipment, and number of workers for each phase of the construction project. As stated, the construction phase is anticipated to have duration of approximately 14 months, commencing in June 2025 and concluding in July 2026.

1.2 Lead Agencies – Environmental Review Implementation

The City of West Covina is the Lead Agency for the proposed project. Pursuant to the California Environmental Quality Act (CEQA) and its implementing regulations,¹ the Lead Agency has the principal responsibility for implementing and approving a project that may have a significant effect on the environment.

1.3 CEQA Overview

1.3.1 Purpose of CEQA

All discretionary projects within California are required to undergo environmental review under CEQA. A Project is defined in CEQA Guidelines § 15378 as the whole of the action having the potential to result in a direct physical change or a reasonably foreseeable indirect change to the environment and is any of the following:

- An activity directly undertaken by any public agency including but not limited to public works construction and related activities, clearing or grading of land, improvements to existing public structures, enactment and amendment of zoning ordinances, and the adoption and amendment of local General Plans or elements.
- An activity undertaken by a person which is supported in whole or in part through public agency contracts, grants, subsidies, loans, or other forms of assistance from one or more public agencies.
- An activity involving the issuance to a person of a lease, permit, license, certificate, or other entitlement for use by one or more public agencies.

CEQA Guidelines § 15002 lists the basic purposes of CEQA as follows:

- Inform governmental decision makers and the public about the potential, significant environmental effects of proposed activities.
- Identify the ways that environmental damage can be avoided or significantly reduced.
- Prevent significant, avoidable damage to the environment by requiring changes in projects through the use of alternatives or mitigation measures (MMs) when the governmental agency finds the changes to be feasible.

¹ Public Resources Code §§ 21000 - 21177 and California Code of Regulations Title 14, Division 6, Chapter 3.



- Disclose to the public the reasons why a governmental agency approved the project in the manner the agency chose if significant environmental effects are involved.

1.3.2 Authority to Mitigate under CEQA

CEQA establishes a duty for public agencies to avoid or minimize environmental damage where feasible. Under CEQA Guidelines § 15041 a Lead Agency for a project has authority to require feasible changes in any or all activities involved in the project in order to substantially lessen or avoid significant effects on the environment, consistent with applicable constitutional requirements such as the “nexus”² and “rough proportionality”³ standards.

CEQA allows a Lead Agency to approve a project even though the project would cause a significant effect on the environment if the agency makes a fully informed and publicly disclosed decision that there is no feasible way to lessen or avoid the significant effect. In such cases, the Lead Agency must specifically identify expected benefits and other overriding considerations from the project that outweigh the policy of reducing or avoiding significant environmental impacts of the project.

1.4 Purpose of Initial Study

The CEQA process begins with a public agency making a determination as to whether the project is subject to CEQA at all. If the project is exempt, the process does not need to proceed any farther. If the project is not exempt, the Lead Agency takes the second step and conducts an Initial Study to determine whether the project may have a significant effect on the environment.

The purposes of an Initial Study as listed in § 15063(c) of the CEQA Guidelines are to:

- Provide the Lead Agency with information necessary to decide if an Environmental Impact Report (EIR), Negative Declaration (ND), or Mitigated Negative Declaration (MND) should be prepared.
- Enable a Lead Agency to modify a project to mitigate adverse impacts before an EIR is prepared, thereby enabling the project to qualify for a ND or MND.
- Assist in the preparation of an EIR, if required, by focusing the EIR on adverse effects determined to be significant, identifying the adverse effects determined not to be significant, explaining the reasons for determining that potentially significant adverse effects would not be significant, and identifying whether a program EIR, or other process, can be used to analyze adverse environmental effects of the project.
- Facilitate an environmental assessment early during project design.
- Provide documentation in the ND or MND that a project would not have a significant effect on the environment.
- Eliminate unnecessary EIRs.
- Determine if a previously prepared EIR could be used for the Project.

2 A nexus (i.e., connection) must be established between the mitigation measure and a legitimate governmental interest.

3 The mitigation measure must be “roughly proportional” to the impacts of the Project.



In cases where no potentially significant impacts are identified, the Lead Agency may issue a ND, and no MMs would be needed. Where potentially significant impacts are identified, the Lead Agency may determine that MMs would adequately reduce these impacts to less than significant levels. The Lead Agency would then prepare a MND for the proposed project. If the Lead Agency determines that individual or cumulative effects of the proposed project would cause a significant adverse environmental effect that cannot be mitigated to less than significant levels, then the Lead Agency would require an EIR to further analyze these impacts.

1.5 Review and Comment by Other Agencies

Other public agencies are provided the opportunity to review and comment on the IS/MND. Each of these agencies is described briefly below.

- A Responsible Agency (14 CCR § 15381) is a public agency, other than the Lead Agency, that has discretionary approval power over the Project, such as permit issuance or plan approval authority.
- A Trustee Agency⁴ (14 CCR § 15386) is a state agency having jurisdiction by law over natural resources affected by a project that are held in trust for the people of the State of California.
- Agencies with Jurisdiction by Law (14 CCR § 15366) are any public agencies who have authority (1) to grant a permit or other entitlement for use; (2) to provide funding for the project in question; or (3) to exercise authority over resources which may be affected by the project. Furthermore, a city or county will have jurisdiction by law with respect to a project when the city or county having primary jurisdiction over the area involved is: (1) the site of the project; (2) the area in which the major environmental effects will occur; and/or (3) the area in which reside those citizens most directly concerned by any such environmental effects.

1.6 Impact Terminology

The following terminology is used to describe the level of significance of potential impacts:

- A finding of ***no impact*** is appropriate if the analysis concludes that the project would not affect the particular environmental threshold in any way.
- An impact is considered ***less than significant*** if the analysis concludes that the project would cause no substantial adverse change to the environment and requires no mitigation.
- An impact is considered ***less than significant with mitigation incorporated*** if the analysis concludes that the project would cause no substantial adverse change to the environment with the inclusion of environmental commitments, or other enforceable measures, that would be adopted by the lead agency.
- An impact is considered potentially significant if the analysis concludes that the project could have a substantial adverse effect on the environment.

An EIR is required if an impact is identified as ***potentially significant***.

⁴ The four Trustee Agencies in California listed in CEQA Guidelines § 15386 are California Department of Fish and Wildlife, State Lands Commission, State Department of Parks and Recreation, and University of California.



1.7 Organization of Initial Study

This document is organized to satisfy CEQA Guidelines § 15063(d), and includes the following sections:

- **Section 1.0 - Introduction**, which identifies the purpose and scope of the IS/MND.
- **Section 2.0 - Environmental Setting**, which describes location, existing site conditions, land uses, zoning designations, topography, and vegetation associated with the project site and surroundings.
- **Section 3.0 - Project Description**, which provides an overview of the project, a description of the proposed development, project phasing during construction, and discretionary actions for project approval.
- **Section 4.0 - Environmental Checklist**, which presents checklist responses for each resource topic to identify and assess impacts associated with the proposed project, and proposes MMs, as needed, to reduce potential environmental impacts to less than significant.
- **Section 5.0 - References**, which includes a list of documents cited in the IS/MND.
- **Section 6.0 - List of Preparers**, which identifies the primary authors and technical experts that prepared the IS/MND.

Technical studies and other documents, which include supporting information or analyses used to prepare the IS/MND, are included in the following appendices:

Appendix A	Project Plans and Drawings
Appendix B	Air Quality and Greenhouse Gas Emissions Data
Appendix C	Biological Resources-Species Tables
Appendix D	Cultural Resources Report
Appendix E1	Preliminary Geotechnical Investigation
Appendix E2	Paleontological Resources Records Search
Appendix F1	Phase I ESA-Envision
Appendix F2	Asbestos Sampling-Testing Records-Envision
Appendix F3	Phase I ESA-Shell
Appendix G1	Preliminary Hydrology Report
Appendix G2	Low Impact Development (LID) Plan
Appendix H	Noise Assessment
Appendix I	RK Engineering VMT Analysis

1.8 Findings from the Initial Study

1.8.1 No Impact or Impacts Considered Less than Significant

Based on IS findings, the project would have no impact or a less than significant impact on the following environmental categories listed from Appendix G of the CEQA Guidelines.

- Aesthetics
- Agriculture and Forestry Resources
- Air Quality



- Energy
- Greenhouse Gas Emissions
- Hydrology and Water Quality
- Land Use and Planning
- Mineral Resources
- Noise
- Population and Housing
- Public Services
- Recreation
- Transportation and Traffic
- Utilities and Service Systems
- Wildfire

1.8.2 Impacts Considered Less than Significant with Mitigation Measures

Based on IS findings, the project would have a less than significant impact on the following environmental categories listed in Appendix G of the CEQA Guidelines when proposed MMs are implemented.

- Biological Resources
- Cultural Resources
- Geology and Soils
- Hazards and Hazardous Materials
- Tribal Cultural Resources
- Mandatory Findings of Significance



2.0 ENVIRONMENTAL SETTING

2.1 Project Location

The proposed Envision Motors Mercedes Benz Dealership Project is located at 1800 East Garvey Avenue in the City of West Covina, California, on an approximately 3.54-acre site (APNs: 8478-007-025; -031; and -042). Refer to **Figure 2.1-1**, which shows the project's location in a regional context. **Figure 2.1-2** shows the project vicinity. Local surface streets adjacent to the site include North Azuza Avenue to the west and East Garvey Avenue to the south. **Figure 2.1-3** depicts an aerial photo of the project site and the surrounding land.

2.2 Project Setting

The project site consists of the existing Envision Toyota Dealership of West Covina, a surface parking lot, and a Valero gas station. See **Figure 2.2-1**, which depicts the topography of the site, and surrounding area. The project site is relatively flat with an elevation between 441 to 454 feet above mean sea level (amsl) (Google Earth Pro, 2024). Site photographs are provided in **Figure 2.2-2**.

2.2.1 Land Use and Zoning

The land use, zoning, and existing developments of the project site and its immediate vicinity are listed in **Table 2.2-1**. The project site has a General Plan land use designation of Commercial (C) and a zoning designation of Service Commercial Mixed Use (SMU) and Neighborhood Commercial Mixed Use (NMU) and is located within the Auto Plaza Overlay Zone. (City of West Covina, 2024).

Table 2.2-1
SUMMARY OF EXISTING LAND USE, ZONING AND EXISTING DEVELOPMENTS

Location	General Plan Designation	Zoning Designation	Existing Development
Project Site	Commercial (C)	Service Commercial Mixed Use (SMU) and Neighborhood Commercial Mixed Use (NMU)	Car dealership and gas station
North	Right-of-Way (ROW)	Right-of-Way (ROW)	I-10 freeway
South	Commercial (C)	Service Commercial Mixed Use (SMU)	Car dealership
East	Commercial (C)	Service Commercial Mixed Use (SMU)	Car dealership
West	Commercial (C)	Neighborhood Commercial Mixed Use (NMU)	Restaurant and gas station

Source: City of West Covina, 2024; Google Earth Pro, 2024



**Figure 2.1-1
REGIONAL LOCATION**



Path: rd:\projects\7212_WCovina_Environ\Declarations\BMD\BMDs\7212_WCovina_2_0_Regional_Location_2024_05_13.mxd
Service Layer Credits: Sources: Esri, HERE, DeLorme, Intermap, INCREMENT P, NRCan, Esri Japan, METI, Esri China (Hong Kong), Swis, Esri (France), IGN, (c) OpenStreetMap contributors, and the GIS User Community, Los Angeles County, 2021, UltraSystems Environmental, Inc., 2024

May 13, 2024

Scale: 1:633,600

0 5 10 Miles

0 5.5 11 Kilometers

Legend

● Project Location


Envision Motors
West Covina Mercedes Benz

Regional Location

UltraSystems



**Figure 2.1-2
PROJECT VICINITY**



Path: \\GIS\Projects\212_WCovina_Envision_Dealership_ISM\HDMXD\212-WCovina_3_0_Project_Vicinity_2024_05_13.mxd
Service Layer Credits: Sources: Esri, HERE, Garmin, USGS, Intermap, INCREMENT P, NRCan, Esri Japan, METI, Esri China (Hong Kong), Esri Korea, Esri (Thailand), NGCC, (c) OpenStreetMap contributors, and the GIS User Community, Los Angeles County, 2021; UltraSystems Environmental, Inc., 2024.

May 13, 2024

Scale: 1:30,000



0 1,250 2,500 Feet

0 300 600 Meters

Legend

 Project Boundary

**Envision Motors
West Covina Mercedes Benz**
Project Vicinity





❖ SECTION 2.0 – ENVIRONMENTAL SETTING ❖

**Figure 2.1-3
PROJECT LOCATION**



Path: \\G:\s\p\p\7212_Mercedes-Benz_Dealership_151\H\U\X\7212_Mercedes-Benz_Dealership_151_0_Project_Location_2024_04_18.mxd
Service Layer Credits: Sources: Esri, HERE, Garmin, USGS, Intermap, INCREMENT P, NRCan, Esri Japan, Esri Korea, Esri (Thailand), NGCC, (c) OpenStreetMap contributors, and the GIS User Community; Source: Esri, Mikaz, Earthstar Geographics, and the GIS User Community; UltraSystems Environmental, Inc., 2024

April 18, 2024








Figure 2.2-1
TOPOGRAPHIC MAP



Disclaimer: Representations on this map or illustration are intended only to indicate locations of project parameters reported in the legend. Project parameter information supplied by others (see layer credits) may not have been independently verified for accuracy by UltraSystems Environmental, Inc. This map or illustration should not be used for, and does not replace, final grading plans or other documents that should be professionally certified for development purposes.

Path: \\GIS\Projects\71212_WCovina_Envision_Dealership_ISMND\MXDs\71212_WCovina_4_5_Topo_2024_04_18.mxd
Service Layer Credits: Sources: Esri, HERE, Garmin, USGS, Intermap, INCREMENT P, NRCan, Esri Japan, METI, Esri China (Hong Kong), Esri Korea, Esri (Thailand), NGCC, (c) OpenStreetMap contributors, and the GIS User Community, Copyright © 2013 National Geographic Society, i-cubed, California Department of Conservation, 2019; UltraSystems Environmental, Inc., 2024.

April 18, 2024



**Figure 2.2-2
PROJECT SITE PHOTOGRAPHS**



PHOTO 1: View looking at the northern portion of the project site along the I-10 freeway.



PHOTO 2: View looking at the eastern portion of the project site along East Garvey Avenue.



PHOTO 3: View looking at the southern portion of the project site along East Garvey Avenue.



PHOTO 4: View looking at the western portion of the project site along North Azuza Avenue.



2.3 Existing Characteristics of the Site

2.3.1 Climate and Air Quality

The project site is located within the South Coast Air Basin (SCAB), a 6,600-square-mile area encompassing all of Orange County and the non-desert portion of Los Angeles, Riverside, and San Bernardino Counties. A persistent high-pressure area that commonly resides over the eastern Pacific Ocean largely dominates regional meteorology. The distinctive climate of this area is determined primarily by its terrain and geographic location. Local climate is characterized by warm summers, mild winters, infrequent rainfall, moderate daytime onshore breezes, and moderate humidity. Ozone (O₃) and pollutant concentrations tend to be lower along the coast, where the onshore breeze disperses pollutants toward the inland valley of the SCAB and adjacent deserts. However, as a whole, the SCAB fails to meet National Ambient Air Quality Standards (NAAQS) for O₃ and fine particulate matter (PM_{2.5}), and is classified as a “nonattainment area” for those pollutants (ARB, 2024).

2.3.2 Geology and Soils

Topography within the project site is relatively flat. The project site is not located within a landslide, liquefaction, or Alquist-Priolo zone. However, the project site is located within a regionally active area for seismic activity (Norcal Engineering, 2024).

2.3.3 Hydrology

Surface topography is generally flat to slightly sloping with elevations ranging from approximately 442 to 456 feet above mean sea level (amsl). The project site is in the Main San Gabriel Valley Groundwater Basin. The Basin covers approximately 255 square miles underlying most of the San Gabriel Valley. The project site is within the service area of Suburban Water Systems (Suburban). Suburban’s water supplies consist of groundwater from the Main San Gabriel Basin and the Central Subbasin of the Coastal Plain of Los Angeles Groundwater Basin; water imported from northern California and the Colorado River; and recycled water purchased from the Upper San Gabriel Valley Municipal Water District. Groundwater is forecast to comprise about 54 percent of Suburban’s water supplies over the 2025-2045 period (Suburban, 2021, pp. 3-1 and 3-30).

2.3.4 Biology

The project site is built-out with a car dealership and a gas station and is in completely developed urban surroundings. Only minor amounts of ornamental landscaping are present onsite currently, in addition to street trees along the site perimeter along Azusa Avenue and East Garey Avenue. No natural habitat suitable for special-status species, and no sensitive natural communities, are present onsite.

2.3.5 Public Services

The West Covina Fire Department (WCFD) provides fire protection and emergency medical services to the City of West Covina. The West Covina Police Department (WCPD) provides police protection to the City. The project site is in the West Covina Unified School District (WCUSD). The West Covina Library is part of the Los Angeles County Library System, which is made up of 72 branch libraries.



2.3.6 Utilities

Suburban Water Systems (SWS) provides water to the project site. The Los Angeles County Flood Control District (LACFCD) is in charge of designing and maintaining the lined washes and underground stormwater systems within the City of West Covina. Southern California Edison (SCE) provides electric power for the project site (City of West Covina, 2016a). Southern California Gas Company (SoCalGas) supplies natural gas service to the City of West Covina (City of West Covina, 2016a). Telecommunication services, including internet, telephone, and television, on and near the project site are provided by AT&T, Spectrum, and Frontier Communications (InMyArea, 2024).



3.0 PROJECT DESCRIPTION

Project Location

The project site is at 1800 East Garvey South Avenue in the city of West Covina. The project site is bounded by East Garvey Avenue to the south and east; Azusa Avenue to the west; and the Interstate 10 (I-10) freeway to the north. Regional access to the site is from the I-10 via Azusa Avenue. The 3.54-acre project site consists of three parcels: assessor's parcel numbers (APNs) 8478-007-025; -031; and -042.

Project Setting

The north and central parts of the project site are developed with an auto dealership (currently Envision Toyota of West Covina), and the southwest part with a Valero-branded gas station. The site is surrounded by an auto dealership to the east and south opposite East Garvey Avenue; a restaurant and a gas station to the west opposite Azusa Avenue; and the I-10 freeway to the north.

General Plan and Zoning Designations

Parcels 8478-007-025 and -031 are zoned Service Commercial Mixed Use (SMU) within the Auto Plaza Overlay Zone, with General Plan land use designations of Commercial; parcel -042 is zoned Neighborhood Commercial Mixed Use (NMU) within the Auto Plaza Overlay Zone, and has General Plan land use designation of Commercial (City of West Covina, 2024).


Project Overview

The proposed project would involve demolition of the existing auto dealership and the operating Valero gas station, and construction of a new two-story automotive sales and dealership building housing Envision Motors Mercedes Benz, selling four related brands – Mercedes Benz, Maybach, AMG and Sprinter – as well as associated surface parking, landscaping, and facilities for EV charging. EV charging would be available for the public during the dealership's hours of 8:30 am to 8:30 pm every day of the week.

The proposed building would be in the north-central part of the site. The balance of the site would be developed with surface parking and landscaping (see **Figure 3.4-1**).


The first floor would consist of a pre-owned car showroom; a Sprinter showroom; five new vehicle delivery bays; eight detail bays; reception space; office space; a lunchroom; restrooms; and mechanical and electrical rooms. **Figure 3.4-2** shows the first-floor plan. The second floor would contain three showrooms; office spaces; a training room; a conference room; an employee lounge; restrooms; and storage rooms. **Figure 3.4-3** shows the second-floor plan. The building would total 86,642 square feet building area consisting of 42,500 square feet on the first floor and 44,142 square feet on the second floor. Eight roll-up doors would be installed on the first floor of the building. One vehicle elevator would be provided on the east side of the building. **Figure 3.4-4** shows elevations of the proposed building, and **Figures 3.4-5** and **3.4-6** show renderings of the proposed building. Square feet by use inside the building is summarized in **Table 3.4-1**.

Figure 3.4-1
SITE PLAN



Envision Motors
West Covina Mercedes Benz
Site Plan


Figure 3.4-2
FIRST FLOOR PLAN



Envision Motors
West Covina Mercedes Benz
First Floor Plan



**Figure 3.4-3
SECOND FLOOR PLAN**




**Envision Motors
West Covina Mercedes Benz**
Second Floor Plan



ELEVATIONS

Figure 3.4-4



Disclaimer: Illustration provided by Dennis J. Flynn Architects, Inc., who has indicated that the information is true and correct. No other warranties are expressed or implied.

Source: Dennis J. Flynn Architects, Inc., April 30, 2024.

Envision Motors
West Covina Mercedes Benz
 Elevations



Figure 3.4-5
RENDERINGS (1 of 2)



CUSTOMER ENTRY - SOUTH SIDE



OFF RAMP VIEW - WEST SIDE



EAST SIDE - DAY



EAST SIDE - NIGHT

Disclaimer: Illustration provided by Dennis J. Flynn Architects, Inc., who has indicated that the information is true and correct. No other warranties are expressed or implied.

Source: Dennis J. Flynn Architects, Inc., April 16, 2024.

Figure 3.4-6
RENDERINGS (2 of 2)



NORTH - FREEWAY VIEW - DAY



NORTH - FREEWAY - NIGHT



EAST SIDE



EAST SIDE

Disclaimer: Illustration provided by Dennis J. Flynn Architects, Inc., who has indicated that the information is true and correct. No other warranties are expressed or implied.

Source: Dennis J. Flynn Architects, Inc., April 16, 2024.



Table 3.4-1
SQUARE FEET BY USE IN PROPOSED BUILDING

Use	Square Feet
First Floor	
Showroom and Delivery	36,297
Office	500
Service (detail bays, etc.)	2,395
Other (lunchrooms, restrooms, mechanical, engineering, plumbing, and storage)	3,308
Subtotal	42,500
Second Floor	
Showroom and Delivery	28,336
Office	12,989
Other (lunchrooms, restrooms, mechanical, engineering, plumbing, and storage)	2,817
Subtotal	44,142
Total	86,642

¹ Source: Beltran, 2024

At project completion, about 144,000 square feet, or about 94 percent of the site, would be impervious land cover (hardscape/parking) or the proposed building; the remaining site area would be pervious landscaping.

3.1.1 Access, Circulation, and Parking

Four vehicular entrances would be provided from surrounding streets: three from East Garvey South Avenue along the south and east site perimeter; and one from Azusa Avenue on the southwest side of the project site. The main entrance would be from East Garvey Avenue on the south site boundary. Access via the driveway to and from Azusa Avenue would be right-in-right-out only, as that segment of Azusa Avenue is a divided road. As shown in **Figure 3.4-1**, driveways would extend around the southern, western, and northern sides of the building.

Surface parking would consist of 232 spaces including display spaces, customer parking, employee parking, and electric vehicle charging stations. Parking spaces inside the building would consist of two showrooms, new vehicle delivery bays, and detail bays on the first floor totaling 125 spaces; and 42 showroom spaces on the second floor, totaling 167 spaces. The total parking onsite would be 399 spaces.

The project site does not contain a loading/unloading zone. The cars would be loaded/unloaded at the Mercedes service facility across the street at 1829 East Garvey Avenue within the City of West Covina. Cars would then be individually driven to the site.

3.1.2 Trash

Trash would be picked up on the northern portion of the site as depicted in **Figure 3.4-1**, Site Plan.



3.1.3 Landscaping

Landscaping would consist of trees along the site perimeter and lining both sides of the main entrance driveway in the southern part of the site; landscaped areas would total 10,076 square feet, or about 6.6 percent of the project site (see **Figures 3.4-1** and **3.4-7**).



Site Plan Details:

- Building:** A large rectangular building footprint.
- Parking Lot:** 20 spaces, located to the west of the building.
- Landscaping:** Various plants and trees are indicated by symbols and codes. A legend on the right side of the plan provides details for these symbols.
- Streets:** South Azusa Avenue (North) and E. Carvey Avenue South (South).

PLANT LEGEND

SYMBOL	PLANT NAME	COMMON NAME	SIZE	QUANTITY	WATER USE
	WASHINGTONIA ROBUSTA	MEXICAN FAN PALM	10' BT	01	1,000
	L. DESERTI	DESERT LILY	10' BT	01	1,000
	R. ELAEAGNIFOLIA	ARGENT-LEAFED OLIVE	10' BT	01	1,000
	A. AMERICANA	AGAVE AMERICANA	10' BT	01	1,000
	C. ELAEAGNIFOLIA	CELESTINE	10' BT	01	1,000
	R. ELAEAGNIFOLIA	ARGENT-LEAFED OLIVE	10' BT	01	1,000
	A. AMERICANA	AGAVE AMERICANA	10' BT	01	1,000
	C. ELAEAGNIFOLIA	CELESTINE	10' BT	01	1,000
	R. ELAEAGNIFOLIA	ARGENT-LEAFED OLIVE	10' BT	01	1,000
	A. AMERICANA	AGAVE AMERICANA	10' BT	01	1,000
	C. ELAEAGNIFOLIA	CELESTINE	10' BT	01	1,000
	R. ELAEAGNIFOLIA	ARGENT-LEAFED OLIVE	10' BT	01	1,000
	A. AMERICANA	AGAVE AMERICANA	10' BT	01	1,000
	C. ELAEAGNIFOLIA	CELESTINE	10' BT	01	1,000
	R. ELAEAGNIFOLIA	ARGENT-LEAFED OLIVE	10' BT	01	1,000
	A. AMERICANA	AGAVE AMERICANA	10' BT	01	1,000
	C. ELAEAGNIFOLIA	CELESTINE	10' BT	01	1,000
	R. ELAEAGNIFOLIA	ARGENT-LEAFED OLIVE	10' BT	01	1,000
	A. AMERICANA	AGAVE AMERICANA	10' BT	01	1,000
	C. ELAEAGNIFOLIA	CELESTINE	10' BT	01	1,000
	R. ELAEAGNIFOLIA	ARGENT-LEAFED OLIVE	10' BT	01	1,000
	A. AMERICANA	AGAVE AMERICANA	10' BT	01	1,000
	C. ELAEAGNIFOLIA	CELESTINE	10' BT	01	1,000
	R. ELAEAGNIFOLIA	ARGENT-LEAFED OLIVE	10' BT	01	1,000
	A. AMERICANA	AGAVE AMERICANA	10' BT	01	1,000
	C. ELAEAGNIFOLIA	CELESTINE	10' BT	01	1,000
	R. ELAEAGNIFOLIA	ARGENT-LEAFED OLIVE	10' BT	01	1,000
	A. AMERICANA	AGAVE AMERICANA	10' BT	01	1,000
	C. ELAEAGNIFOLIA	CELESTINE	10' BT	01	1,000
	R. ELAEAGNIFOLIA	ARGENT-LEAFED OLIVE	10' BT	01	1,000
	A. AMERICANA	AGAVE AMERICANA	10' BT	01	1,000
	C. ELAEAGNIFOLIA	CELESTINE	10' BT	01	1,000
	R. ELAEAGNIFOLIA	ARGENT-LEAFED OLIVE	10' BT	01	1,000
	A. AMERICANA	AGAVE AMERICANA	10' BT	01	1,000
	C. ELAEAGNIFOLIA	CELESTINE	10' BT	01	1,000
	R. ELAEAGNIFOLIA	ARGENT-LEAFED OLIVE	10' BT	01	1,000
	A. AMERICANA	AGAVE AMERICANA	10' BT	01	1,000
	C. ELAEAGNIFOLIA	CELESTINE	10' BT	01	1,000
	R. ELAEAGNIFOLIA	ARGENT-LEAFED OLIVE	10' BT	01	1,000
	A. AMERICANA	AGAVE AMERICANA	10' BT	01	1,000
	C. ELAEAGNIFOLIA	CELESTINE	10' BT	01	1,000
	R. ELAEAGNIFOLIA	ARGENT-LEAFED OLIVE	10' BT	01	1,000
	A. AMERICANA	AGAVE AMERICANA	10' BT	01	1,000
	C. ELAEAGNIFOLIA	CELESTINE	10' BT	01	1,000
	R. ELAEAGNIFOLIA	ARGENT-LEAFED OLIVE	10' BT	01	1,000
	A. AMERICANA	AGAVE AMERICANA	10' BT	01	1,000
	C. ELAEAGNIFOLIA	CELESTINE	10' BT	01	1,000
	R. ELAEAGNIFOLIA	ARGENT-LEAFED OLIVE	10' BT	01	1,000
	A. AMERICANA	AGAVE AMERICANA	10' BT		

Disclaimer: Illustration provided by Emerald Design and Dennis J. Flynn Architects, Inc., who has indicated that the information is true and correct. No other warranties are expressed or implied.

Source: Emerald Design and Dennis J. Flynn Architects, Inc., April 22, 2024.

**Envision Motors
West Covina Mercedes Benz**

Preliminary Landscape Plan





3.2 Employment

During project operation, company management estimates that the project would have 49 employees (Beltran, 2024). All employees would park along East Garvey Avenue.

3.3 Construction

3.3.1 Demolition

All existing structures on the project site would be demolished before construction of the proposed buildings.

- Area of demolition (Toyota Dealership): 23,754 square feet
- Area of demolition (Gas Station): 2,485 square feet
- Total area of demolition: 26,239 square feet

3.3.2 Hazardous Materials Assessment and Remediation

In June 2004, piping and dispensers at the former Shell station were upgraded. As part of the project, nine soil samples were collected beneath dispensers and piping. Total petroleum hydrocarbons in the gasoline range (TPH-g) was detected in three samples at concentrations ranging from 0.44 mg/kg to 6.4 mg/kg. TPH in the diesel range (TPH-d) was detected in two samples at 19,000 mg/kg and 48 mg/kg. Methyl tert-butyl ether (MTBE, a gasoline oxygenate) was detected in two samples at 390 ug/kg and 45 ug/kg. Based on these results, the northwest dispenser islands, adjacent product trench and southern dispenser island were excavated on 18 June 2004 to remove the contaminated soil.

Following the excavation of 146 tons of soil, confirmatory soil samples were collected. One sample contained TPH-g at 45 mg/kg, TPH-d at 5.7 mg/kg, MTBE at 1,100 ug/kg and tertiary butyl alcohol (TBA, a gasoline additive) at 7,300 ug/kg. One additional piping excavation sample contained TBA at 46 ug/kg. The soil was transported to TPS Technologies in Adelanto, CA for recycling. Based on the results, Los Angeles County Public Works (LADPW) requested a workplan to assess the vertical and lateral extent of the impacted soil in a letter from February 2007. No work was completed and in May 2013, the LADPW referred the case to the Regional Water Quality Control Board (SWRCB).

SWRCB Order WQ 2014-0158-UST, issued on 06 October 2014, indicates that the remaining contaminants fall under the Low Threat Closure Policy. On 03 March 2015, the Regional Water Quality Control Board issued a case closure letter. Celly Services (CSI) compared the results of the impacted soil left in place to the current residential Environmental Screening Levels (ESLs), established by the Regional Water Quality Control Board in 2019. The concentrations of TPH-d, MTBE and TBA fall below residential screening levels and therefore are considered an historical recognized environmental condition (HREC; CSI, 2024b, p. iii).⁵

⁵ An historical REC (HREC) is a previous release of hazardous substances or petroleum products affecting the subject property that has been addressed to the satisfaction of the applicable regulatory authority or authorities and meeting



❖ SECTION 3.0 – PROJECT DESCRIPTION ❖

The Phase I Environmental Site Assessment (ESA) for the Valero Station noted that hydrocarbon impacted soil is present on the subject property and will be encountered during future grading operations. Impacted soil may also be encountered near the clarifier/hoists in the repair area. CSI recommends that any impacted soil that is encountered be segregated, sampled for waste profiling purposes, and transported to a licensed disposal or recycler facility (CSI, 2024b, p. iv).

Additional assessment for hazardous materials is expected to be needed during site grading; such assessment is discussed further in **Section 4.9, Hazards and Hazardous Materials**.

3.3.3 Construction Phasing

The schedule, construction equipment, and number of construction workers for each construction phase are listed below in **Table 3.4-1**. As shown below, overall construction is forecast to last about 14 months, from June 2025 to July 2026.

Table 3.4-1
CONSTRUCTION PHASING AND EQUIPMENT

Construction Phase	Beginning Month	Ending Month	Duration, Months	Construction Equipment		Construction Workers
				Type	Number	
Demolition	June 2025	July 2025	2	Bulldozer	2	10
Site Preparation	June 2025	July 2025	2	Bulldozer	2	8
Grading	June 2025	July 2025	2	Skiploader	3	5
Utilities Installation	June 2025	July 2025	2	Trench Digger	2	12
Building Construction	July 2025	July 2026	12	Power Tools	25	25
Paving	June 2026	July 2026	2	Concrete Trucks	15	16
Landscaping Installation	June 2026	July 2026	2	Skiploader	1	8

¹ Source: Beltran, 2024

3.3.4 Grading

The site is expected to balance, and therefore no soil import or export is anticipated.

unrestricted use criteria established by the applicable regulatory authority or authorities without subjecting the subject property to any controls (CSI, 2024, p.ii).



Required Approvals

The following entitlements are required for the proposed development:

- Site and Design Review
- Zone Change to change the portion of the project site zoned Neighborhood Commercial Mixed Use (SMU) to Service Commercial Mixed Use (SMU) within the Auto Plaza Overlay Zone.
- Administrative lot merger Approval by the Engineering Division.

Other Public Agencies Whose Approval is Required

- The Los Angeles Regional Water Quality Control Board would approve the water quality management plan for the project
- The South Coast Air Quality Management District would issue a permit to construct
- California Department of Motor Vehicles would issue a Vehicle Dealer License



4.0 ENVIRONMENTAL CHECKLIST

Environmental Factors Potentially Affected

The environmental factors checked below would be potentially affected by this project, involving at least one impact that is a "Potentially Significant Impact" or as a "Potentially Significant Unless Mitigation Incorporated," as indicated by the checklist on the following pages.

- | | | |
|--|--|--|
| ☐ Aesthetics | ☐ Agricultural and Forest Resources | ☐ Air Quality |
| ☒ Biological Resources | ☒ Cultural Resources | ☐ Energy |
| ☒ Geology / Soils | ☐ Greenhouse Gas Emissions | ☒ Hazards & Hazardous Materials |
| ☐ Hydrology / Water Quality | ☐ Land Use / Planning | ☐ Mineral Resources |
| ☐ Noise | ☐ Population / Housing | ☐ Public Services |
| ☐ Recreation | ☐ Transportation | ☒ Tribal Cultural Resources |
| ☐ Utilities/Service Systems | ☐ Wildfire | ☒ Mandatory Findings of Significance |

Determination (To Be Completed by the Lead Agency)

On the basis of this initial evaluation:

☐ I find that the proposed project COULD NOT have a significant effect on the environment, and a NEGATIVE DECLARATION will be prepared.

☒ I find that although the proposed project could have a significant effect on the environment, there will not be a significant effect in this case because revisions in the project have been made by or agreed to by the project proponent. A MITIGATED NEGATIVE DECLARATION will be prepared.

☐ I find that the proposed project MAY have a significant effect on the environment, and an ENVIRONMENTAL IMPACT REPORT is required.

☐ I find that the proposed project MAY have a "potentially significant impact" or "potentially significant unless mitigated" impact on the environment, but at least one effect (1) has been adequately analyzed in an earlier document pursuant to applicable legal standards, and (2) has been addressed by mitigation measures based on the earlier analysis as described on attached sheets. An ENVIRONMENTAL IMPACT REPORT is required, but it must analyze only the effects that remain to be addressed.

☐ I find that although the proposed project could have a significant effect on the environment, because all potentially significant effects (a) have been analyzed adequately in an earlier EIR or NEGATIVE DECLARATION pursuant to applicable standards, and (b) have been avoided or mitigated pursuant to that earlier EIR or NEGATIVE DECLARATION, including revisions or mitigation measures that are imposed upon the proposed project, nothing further is required.

Signature

Jo-Anne Burns

Printed Name

Date

10/24/24

City of West Covina



Evaluation of Environmental Impacts

- (1) A brief explanation is required for all answers except “No Impact” answers that are adequately supported by the information sources a lead agency cites in the parentheses following each question. A “No Impact” answer is adequately supported if the referenced information sources show that the impact simply does not apply to projects like the one involved (e.g., the project falls outside a fault rupture zone). A “No Impact” answer should be explained where it is based on project-specific factors, as well as general standards (e.g., the project would not expose sensitive receptors to pollutants, based on a project-specific screening analysis).
- (2) All answers must take into account the whole action involved, including offsite as well as onsite, cumulative as well as project-level, indirect as well as direct, and construction as well as operational impacts.
- (3) Once the lead agency has determined that a particular physical impact may occur then the checklist answers must indicate whether the impact is potentially significant, less than significant with mitigation, or less than significant. “Potentially Significant Impact” is appropriate if there is substantial evidence that an effect may be significant. If there are one or more “Potentially Significant Impact” entries when the determination is made, an EIR is required.
- (4) “Negative Declaration: Less than Significant with Mitigation Incorporated” applies where the incorporation of mitigation measures has reduced an effect from “Potentially Significant Impact” to a “Less than Significant Impact.” The lead agency must describe the mitigation measures and briefly explain how they reduce the effect to less than significant level.
- (5) Earlier analyses may be use where, pursuant to the tiering, Program EIR, or other CEQA process, an affect has been adequately analyzed in an earlier EIR or negative declaration. (See Section 15063(c)(3)(D) of the CEQA Guidelines. In this case, a brief discussion should identify the following:
 - (a) Earlier Analyses Used. Identify and state where the earlier analysis available for review.
 - (b) Impacts Adequately Addressed. Identify which effects from the above checklist were within the scope of and adequately analyzed in an earlier document pursuant to applicable legal standards, and state whether such effects were addressed by mitigation measures based on the earlier analysis.
 - (c) Mitigation Measures. For effects that are “Less than Significant with Mitigation Measures Incorporated,” describe the mitigation measures that were incorporated or refined from the earlier document and the extent to which they address site-specific conditions for the project.
- (6) Lead agencies are encouraged to incorporate into the checklist references to information sources for potential impacts (e.g., general plans, zoning ordinances). Reference to a previously prepared or outside document should, where appropriate, include a reference



❖ SECTION 4.0 – ENVIRONMENTAL CHECKLIST ❖

to the page or pages where the statement is substantiated. A source list should be attached and other sources used or individuals contacted should be cited in the discussion.

- (7) Supporting Information Sources: A source list should be attached, and other sources used or individuals contacted should be cited in the discussion.
- (8) This is only a suggested form, and lead agencies are free to use different formats; however, lead agencies should normally address the questions from this checklist that are relevant to a project's environmental effects in whatever format is selected.
- (9) The explanation of each issue should identify:
 - (a) The significance criteria or threshold, if any, used to evaluate each question; and
 - (b) The mitigation measure identified, if any, to reduce the impact to less than significant.



4.1 Aesthetics

Would the project:	Potentially Significant Impact	Less than Significant Impact with Mitigation Incorporated	Less than Significant Impact	No Impact
a) Have a substantial adverse effect on a scenic vista?				X
b) Substantially damage scenic resources, including, but not limited to, trees, outcroppings, and historic buildings within a state scenic highway?				X
c) In non-urbanized areas, substantially degrade the existing visual character or quality of public views of the site and its surroundings? (Public views are those that are experienced from publicly accessible vantage point). If the project is in an urbanized area, would the project conflict with applicable zoning and other regulations governing scenic quality?			X	
d) Create a new source of substantial light or glare which would adversely affect day or nighttime views in the area?			X	

A “visual environment” includes the built environment (development patterns, buildings, parking areas and circulation elements) and the natural environment (such as hills, vegetation, rock outcroppings, drainage pathways and soils) features. Visual quality, viewer groups, and sensitivity, duration, and visual resources characterize the views. Visual quality refers to the general aesthetic quality of a view, such as vividness, intactness, and unity. Viewer groups identify who is most likely to experience the view. High-sensitivity land uses include residences, schools, playgrounds, religious institutions, and passive outdoor spaces such as parks, playgrounds, and recreation areas. Duration of a view is the amount of time a particular view can be seen by a specific viewer group. Visual resources refer to unique views, and views identified in local plans, from scenic highways, or of specific unique structures or landscape features.

a) Would the project have a substantial adverse effect on a scenic vista?

No Impact

Scenic vistas generally include extensive panoramic views of natural features, unusual terrain, or unique urban or historic features, for which the field of view can be wide and extend into the distance, and focal views that focus on a particular object, scene, or feature of interest. West Covina is situated in the middle of San Gabriel Watershed, nestled between the San Gabriel Mountains and the San Jose Hills. West Covina benefits from and relies on natural resources, which includes the San Jose Hills that provides an important visual backdrop that frames the City. The hills provide residents and visitors with scenic vistas and are part of a larger integrated ecosystem that provides a habitat for plant and animal life (Rincon, 2016, p. 36). The project site has partial views of the hills due to the large distance and intervening development between the project site and the hills.



The project site currently has an existing automotive dealership and an operating automotive fueling station with convenience store. The project proposes the construction of a two-story automotive sales and dealership building to house the Envision Motors Mercedes Benz dealership, as well as associated surface parking, landscaping, charging facilities for EV, and a car wash tunnel.

The site is currently within the Auto Plaza Overlay Zone consisting of Service-Commercial Mixed Use zoned properties located south of San Bernardino Freeway (Interstate 10), north of Norma Avenue, west of Baymar Street, and east of Azusa Avenue. The project site is directly adjacent to a similar automotive dealership on the south and east, Azusa Avenue to the west, and Interstate 10 on the north.

The proposed site plan is shown in **Figure 3.1-1**. Proposed floor plans are shown in **Figures 3.1-2** and **3.1-3**. **Figure 3.1-4** shows elevations of the proposed building. The maximum height of the building would be, and **Figures 3.1-5** and **3.1-6** shows renderings of the proposed building

The proposed new building would be consistent with the general character and of the surrounding neighborhood in terms of architectural style, density, height, bulk, footprint, and setback. The proposed development would not obstruct views of distant mountains and hills for motorists traveling along nearby roadways. Therefore, the project would have no impact on scenic vistas.

- b) Would the project substantially damage scenic resources, including, but not limited to, trees, rock outcroppings, and historic buildings within a state scenic highway?**

No Impact

The California Department of Transportation (Caltrans) provides information on official designated or eligible state scenic highways, designated as part of the California scenic highway program. As discussed in the 2016 update of the City of West Covina's General Plan and the final environmental impact report, there are currently no officially designated scenic roads within the City of West Covina (City of Covina, 2016a, p. 51).

As shown in **Figure 4.1-1**, the closest officially designated state scenic highway is State Route 2 (Angles Crest Highway), which begins approximately 10 miles northwest of the project site on the northern edge of La Canada. The nearest eligible scenic highway is State Route 39 (San Gabriel Canyon Road) approximately five miles north of the project site.

Given that there are no existing or proposed State scenic highways located within the City of West Covina, the project does not have the potential to damage scenic resources, including, but not limited to, trees, rocks, outcroppings, and historic buildings within a state scenic highway. Therefore, the project would not have an impact on trees, rock outcroppings, and historic buildings within a state scenic highway.

- c) In non-urbanized areas, would the project substantially degrade the existing visual character or quality of public views of the site and its surroundings? (Public views are those that are experienced from publicly accessible vantage point). If the project is in an urbanized area, would the project conflict with applicable zoning and other regulations governing scenic quality?**



Less than Significant Impact

The project site is located in an urbanized area. Although West Covina does not have officially designated state scenic highways, several areas within the city are identified as scenic in the 1985 General Plan and the City Municipal Code.



**Figure 4.1-1
STATE SCENIC HIGHWAYS**



Path: \\GIS\envr\gis\Projects\7212_WCovina_Envision_Dealership_ISMND\MXD\7212_WCovina_4_1_Scenic_Hwyrs_2024_05_23.mxd
Service Layer Credits: Sources: Esri, HERE, Garmin, USGS, Intermap, INCREMENT P, NRCan, Esri Japan, METI, Esri China (Hong Kong), Esri Korea, Esri (Thailand), NGCC,
(c) OpenStreetMap contributors, and the GIS User Community; Caltrans, 2021; UltraSystems Environmental, Inc., 2024.

May 23, 2024

Scale: 1:253,440



0 2 4 Miles

0 2 4 Kilometers

Legend

- Project Location
- Officially Designated State Scenic Highway
- Eligible State Scenic Highway
- National Scenic Byway

**Envision Motors
West Covina Mercedes Benz**
Scenic Highways





The 1985 General Plan discusses the desire of the City to designate several sections of the road as scenic city highways. Azusa Avenue is one of these roadways (City of West Covina, 2016a, p. 56). The project site abuts Azusa Avenue on the western side, which is a primary north-south highway through the city. The City sets minimum standards for these roadways, including a 10-foot-wide landscaped median strip, distinctive street lighting, specially designed bus stop areas, and an incorporated theme for sidewalk treatment, landscaping, and crosswalks (City of West Covina, 2016a, p. 57). The proposed project would not encroach on or impose any alterations along Azusa Avenue, so existing visual resources along the section of the roadway would remain unchanged.

Additionally, the proposed project does not intend to change land use and complies with the general plan, zoning, and other regulations that govern the scenic quality of the proposed project, as detailed in **Table 4.1-1**. Therefore, the project would have a less than significant impact.

Table 4.1-1

PROJECT COMPLIANCE WITH APPLICABLE CITY OF WEST COVINA GENERAL PLAN POLICIES REGARDING SCENIC QUALITY

General Plan Policy	Compliance
Policy 1.9: During the review of public and private development projects, analyze potential impacts to views of natural areas from public streets, parks, trails, and community facilities.	Project Compliance: The project will not impact the views of natural areas from public streets, parks, trails, and community facilities. The project will be required to comply with all regulations regarding public streets, including those specifically directed at the scenic quality of the area.
Policy 1.11: Plant to maximize the social, economic, and environmental benefits of trees.	Project Compliance: The project will be required to submit a compliant architectural landscape plan in compliance with City and State regulations.

Source: City of West Covina, 2016, p. 29

Based on the analysis above, the project would not conflict with the applicable General Plan policies governing scenic quality. Therefore, the impact would be less than significant.

- d) Would the project create a new source of substantial light or glare which would adversely affect day- or night-time views in the area?**

Less Than Significant Impact

The construction of the project would not generate substantial glare that would adversely affect daytime or nighttime views in the area. Construction equipment consists of low-glare materials. Construction would occur between the hours of sunset and 9:00 pm, and thus would not involve longer durations of nighttime work. The proposed exterior building materials, such as sand-colored exterior plaster and stone veneer, would not be highly reflective. The impact of the construction glare would be less than significant, and no mitigation is required.

West Covina is primarily built-out; therefore, a substantial amount of ambient light from urban uses already exists. Similar to other developed urban areas, sources of light and glare include neon signs, glass building façades, streetlights, parking lot lighting and automotive headlights (Rincon, 2016, p51). Streetlights, traffic on local streets, and exterior lighting in surrounding developments are the main sources of light that contribute to the ambient light levels in the project area.



❖ SECTION 4.1 – AESTHETICS ❖

The operation of the project proposes new exterior lighting throughout the site. The installation of exterior lighting would be necessary for safety and visibility at night throughout the proposed development per City Municipal Code Section 26-739, Security Lighting Requirement for Auto Plaza Overlay Zones (City of West Covina Municipal Code, 2024). The new project lighting would be visible from the surrounding area. Therefore, the proposed exterior lighting of the project is expected to contribute to the ambient illumination at night near the project.

Per City Municipal Code Section 26-739, Security Lighting Requirement for Auto Plaza Overlay Zones and Section 26-570, Lighting in Non-residential areas, the project would comply with all regulations regarding lighting while using light colored building materials without using highly reflective building materials. Therefore, the impact of new sources of substantial light or glare would be less than significant (City of West Covina Municipal Code, 2024).

**4.2 Agriculture and Forestry Resources**

Would the project:	Potentially Significant Impact	Less than Significant Impact with Mitigation Incorporated	Less than Significant Impact	No Impact
a) Convert Prime Farmland, Unique Farmland, or Farmland of Statewide Importance (Farmland), as shown on the maps prepared pursuant to the Farmland Mapping and Monitoring Program of the California Resources Agency, to non-agricultural use?				X
b) Conflict with existing zoning for agricultural use, or a Williamson Act contract?				X
c) Conflict with existing zoning for, or cause rezoning of, forest land (as defined in Public Resources Code § 12220(g)), timberland (as defined by Public Resources Codes § 4526), or timberland zoned Timberland Production (as defined by Government Code § 51104(g))?				X
d) Result in the loss of forest land or conversion of forest land to non-forest use?				X
e) Involve other changes in the existing environment which, due to their location or nature, could result in conversion of Farmland, to non-agricultural use or conversion of forest land to non-forest use?				X

- a) **Would the project convert Prime Farmland, Unique Farmland, or Farmland of Statewide Importance (Farmland), as shown on the maps prepared pursuant to the Farmland Mapping and Monitoring Program of the California Resources Agency, to non-agricultural use?**


No Impact

The project site and surrounding uses are designated by the Division of Land Resource Protection (DLRP) as “Urban and Built-Up Land” and the nearest Unique Farmland is 21 miles southeast of the project site (DOC, 2022; see **Figure 4.2-1** below). Therefore, no farmland would be converted to non-agricultural use and no impacts would occur.




❖ SECTION 4.2 – AGRICULTURE AND FORESTRY RESOURCES ❖

Figure 4.2-1
IMPORTANT FARMLAND CATEGORIES



Path: \\GIS\rr\gis\Projects\7212_WCovina_Environ_Dealshp_ISMND\MXDs\7212_WCovina_4_2_Important_Farmlands_2024_05_23.mxd
Service Layer Credits: Sources: Esri, HERE, Garmin, USGS, InMap, INCREMENT P, NRCan, Esri Japan, METI, Esri China (Hong Kong), Esri Korea, Esri (Thailand), NGCC, (c) OpenStreetMap contributors, and the GIS User Community, Esri, HERE, Garmin, (c) OpenStreetMap contributors, Source: Esri, Maxar, Earthstar Geographics, and the GIS User Community, CA Dept. of Conservation, 2022; UltraSystems Environmental, Inc., 2024. May 23, 2024





❖ SECTION 4.2 – AGRICULTURE AND FORESTRY RESOURCES ❖

- b) **Would the project conflict with existing zoning for agricultural use, or a Williamson Act contract?**

No Impact

The project site is zoned Service Commercial Mixed Use (SMU) and Neighborhood Commercial Mixed Use (NMU) within the Auto Plaza Overlay Zone, and is not zoned for agricultural use. Williamson Act contracts restrict the use of privately-owned land to agriculture and compatible open space uses under contract with local governments; in exchange, the land is taxed based on actual use rather than potential market value. Williamson Act contracts are made only on land within agricultural reserves; the project site is not within an agricultural reserve. Therefore, the project would not conflict with existing zoning for agricultural use or a Williamson Act contract and no impact would occur.

- c) **Would the project conflict with existing zoning for, or cause rezoning of, forest land (as defined in Public Resources Code § 12220(g)), timberland (as defined by Public Resources Codes § 4526), or timberland zoned Timberland Production (as defined by Government Code § 51104(g))?**

No Impact

The project site is zoned Service Commercial Mixed Use (SMU) and Neighborhood Commercial Mixed Use (NMU) within the Auto Plaza Overlay Zone; the site is not zoned for forest, timberland, or timberland production use. Therefore, project development would not conflict with zoning for forest land or timberland, and no impact would occur.

- d) **Would the project result in the loss of forest land or conversion of forest land to non-forest use?**

No Impact

The project site and surroundings are not cultivated for forest resources. Therefore, project development would not result in the loss of forest land or conversion of forest land to non-forest use, and no impact would occur.

- e) **Would the project involve other changes in the existing environment which, due to their location or nature, could result in conversion of Farmland, to non-agricultural use or conversion of forest land to non-forest use?**

No Impact

The project site is a commercial use and is surrounded by commercial to the east, to the west opposite Azusa Avenue and to the north by Interstate 10. No important farmland is near the project site; the nearest such farmland is Unique Farmland approximately 21 miles to the southeast. No forest land is present on or near the project site.

Therefore, project development would not indirectly cause conversion of farmland to non-agricultural use or conversion of forest land to non-forest use, and no impacts would occur.



4.3 Air Quality

Would the project:	Potentially Significant Impact	Less than Significant Impact with Mitigation Incorporated	Less than Significant Impact	No Impact
a) Conflict with or obstruct implementation of the applicable air quality plan?			X	
b) Result in a cumulatively considerable net increase of any criteria pollutant for which the project region is nonattainment under an applicable federal or state ambient air quality standard?			X	
c) Expose sensitive receptors to substantial pollutant concentrations?			X	
d) Result in other emissions (such as those leading to odors) adversely affecting a substantial number of people?			X	

4.3.1 Pollutants of Concern

Criteria pollutants are air pollutants for which acceptable levels of exposure can be determined and an ambient air quality standard has been established by the U.S. Environmental Protection Agency (USEPA) and/or the California Air Resources Board (ARB). The criteria air pollutants of concern are nitrogen dioxide (NO₂), carbon monoxide (CO), particulate matter (PM₁₀ and PM_{2.5}), sulfur dioxide (SO₂), lead (Pb), and ozone, and their precursors, such as reactive organic gases (ROG) (which are ozone precursors). Since the Envision Mercedes Benz Dealership Project (project) would not generate appreciable SO₂ or Pb emissions,⁶ the analysis did not include those two pollutants.

The project is in the Los Angeles County portion of the South Coast Air Basin (SCAB), for whose air pollution control the South Coast Air Quality Management District (SCAQMD) is substantially responsible. **Table 4.3-1** shows the attainment status of the SCAB for each criteria pollutant for both the National Ambient Air Quality Standards (NAAQS) and California Ambient Air Quality Standards (CAAQS). Presented below is a description of the air pollutants of concern and their known health effects.

Nitrogen oxides (NO_x) serve as integral participants in the process of photochemical smog production and are precursors for certain particulate compounds that are formed in the atmosphere and for ozone. A precursor is a directly emitted air contaminant that, when released into the atmosphere, forms, causes to be formed, or contributes to the formation of a secondary air contaminant for which an ambient air quality standard (AAQS) has been adopted, or for which presence in the atmosphere will contribute to the violation of one or more AAQs. When NO_x and

⁶ Sulfur dioxide emissions will be below 0.16 pounds per day during construction and operations.



ROG are released into the atmosphere, they can chemically react with one another in the presence of sunlight to form ozone. The two major forms of NO_x are nitric oxide (NO) and nitrogen dioxide (NO_2). NO is a colorless, odorless gas formed from atmospheric nitrogen and oxygen when combustion takes place under high temperature and/or high pressure. NO_2 is a reddish-brown pungent gas formed by the combination of NO and oxygen. It acts as an acute respiratory irritant and eye irritant and increases susceptibility to respiratory pathogens (USEPA, 2011).

Table 4.3-1
FEDERAL AND STATE ATTAINMENT STATUS

Pollutants	Federal Classification	State Classification
Ozone (O_3)	Nonattainment (Extreme)	Nonattainment
Particulate Matter (PM_{10})	Maintenance (Serious)	Nonattainment
Fine Particulate Matter ($\text{PM}_{2.5}$)	Nonattainment (Serious)	Nonattainment
Carbon Monoxide (CO)	Maintenance (Serious)	Attainment
Nitrogen Dioxide (NO_2)	Maintenance (Primary)	Attainment
Sulfur Dioxide (SO_2)	Unclassified/Attainment	Attainment
Sulfates	No Federal Standards	Attainment
Lead (Pb)		Attainment
Hydrogen Sulfide (H_2S)		Unclassified
Visibility Reducing Particles		Unclassified

Sources: ARB, 2022a; USEPA, 2024d

Carbon monoxide (CO) is a colorless, odorless non-reactive pollutant produced by incomplete combustion of fossil fuels. CO is emitted almost exclusively from motor vehicles, power plants, refineries, industrial boilers, ships, aircraft, and trains. In urban areas, such as the project location, automobile exhaust accounts for most CO emissions. CO is a non-reactive air pollutant that dissipates relatively quickly; therefore, ambient CO concentrations generally follow the spatial and temporal distributions of vehicular traffic. CO concentrations are influenced by local meteorological conditions: primarily wind speed, topography, and atmospheric stability. CO from motor vehicle exhaust can become locally concentrated when surface-based temperature inversions are combined with calm atmospheric conditions, a typical situation at dusk in urban areas between November and February. The highest levels of CO typically occur during the colder months of the year when inversion conditions are more frequent. In terms of health, CO competes with oxygen, often replacing it in the blood, thus reducing the blood's ability to transport oxygen to vital organs. The results of excess CO exposure can be dizziness, fatigue, and impairment of central nervous system functions. High concentrations are lethal (USEPA, 2023).

Particulate matter (PM) consists of finely divided solids or liquids, such as soot, dust, aerosols, fumes, and mists. Primary PM is emitted directly into the atmosphere from activities such as agricultural operations, industrial processes, construction and demolition activities, and the entrainment of road dust into the air. Secondary PM is formed in the atmosphere from predominantly gaseous combustion by-product precursors, such as sulfur oxides, NO_x , and ROG.



Particle size is a critical characteristic of PM that primarily determines the location of PM deposition along the respiratory system (and associated health effects) as well as the degradation of visibility through light scattering. In the United States, federal and state agencies have focused on two types of PM. PM₁₀ corresponds to the fraction of PM no greater than 10 micrometers in aerodynamic diameter and is commonly called respirable particulate matter, while PM_{2.5} refers to the subset of PM₁₀ of aerodynamic diameter smaller than 2.5 micrometers, which is commonly called fine particulate matter.

PM₁₀ and PM_{2.5} deposition in the lungs results in irritation that triggers a range of inflammation responses, such as mucus secretion and bronchoconstriction, and exacerbates pulmonary dysfunctions, such as asthma, emphysema, and chronic bronchitis. Sufficiently small particles may penetrate the bloodstream and impact functions such as blood coagulation, cardiac autonomic control, and mobilization of inflammatory cells from the bone marrow. Individuals susceptible to higher health risks from exposure to PM₁₀ airborne pollution include children, the elderly, smokers, and people of all ages with low pulmonary/cardiovascular function. For these individuals, adverse health effects of PM₁₀ pollution include coughing, wheezing, shortness of breath, phlegm, bronchitis, and aggravation of lung or heart disease, leading, for example, to increased risks of hospitalization and mortality from asthma attacks and heart attacks (USEPA, 2024b).

Reactive organic gases (ROG) are defined as any compound of carbon, excluding CO, carbon dioxide, carbonic acid, metallic carbides or carbonates, and ammonium carbonate, that participates in atmospheric photochemical reactions. It should be noted that there are no state or national ambient air quality standards for ROG because ROG are not classified as criteria pollutants. They are regulated, however, because a reduction in ROG emissions reduces certain chemical reactions that contribute to the formation of ozone. ROG are also transformed into organic aerosols in the atmosphere, which contribute to higher PM₁₀ and lower visibility. The term “ROG” is used by the ARB for this air quality analysis and is defined the same as the federal term “volatile organic compound” (VOC).

Ozone is a secondary pollutant produced through a series of photochemical reactions involving ROG and NO_x. Ozone creation requires ROG and NO_x to be available for approximately three hours in a stable atmosphere with strong sunlight. Because of the long reaction time, peak ozone concentrations frequently occur downwind of the sites where the precursor pollutants are emitted. Thus, ozone is considered a regional, rather than a local, pollutant. The health effects of ozone include eye and respiratory irritation, reduction of resistance to lung infection and possible aggravation of pulmonary conditions in persons with lung disease. Ozone is also damaging to vegetation and untreated rubber (USEPA, 2020).

4.3.2 Climate/Meteorology

Air quality is affected by both the rate and location of pollutant emissions, and by meteorological conditions that influence the movement and dispersal of pollutants. Atmospheric conditions such as wind speed, wind direction, and air temperature gradients, along with local topography, provide the link between air pollutant emissions and air quality.

The project site is located wholly within the SCAB, which includes all of Orange County, as well as the non-desert portions of Los Angeles, Riverside, and San Bernardino Counties. The distinctive climate of the SCAB is determined by its terrain and geographical location. The SCAB is in a coastal plain with connecting broad valleys and low hills, bounded by the Pacific Ocean in the southwest quadrant with high mountains forming the remainder of the perimeter. The general region lies in the semi-



permanent high-pressure zone of the eastern Pacific. Thus, the climate is mild, tempered by cool sea breezes. This usually mild climatological pattern is interrupted infrequently by periods of extremely hot weather, winter storms, or Santa Ana winds (SCAQMD, 1993).

The annual average temperature varies little throughout the 6,600-square-mile SCAB, ranging from the low 60s to the high 80s. However, with a less pronounced oceanic influence, the inland portion shows greater variability in the annual maximum and minimum temperatures. The mean annual maximum and minimum temperatures in the project area – as determined from the nearest weather station in San Gabriel Canyon, California (047776) (WRCC, 2016a), which has a period of record from 1939 to 2016 – are 78.2 degrees Fahrenheit (°F) and 52.8°F, respectively. The hottest month is August, with an average maximum temperature of 91.7°F, and the coldest months are December and January, with an average minimum temperature of 68.5°F.

The nearest station to the project site that measures precipitation is Covina City, California (COOP ID: 042090) (WRCC, 2016b), which has a period of record from 1929 to 2016. The average rainfall is 18.08 inches, which occurs mostly during the winter and relatively infrequently during the summer. Monthly precipitation averages approximately 3.57 inches during the winter (December, January, and February), approximately 1.49 inches during the spring (March, April, and May), approximately 0.90 inch during the fall (September, October, and November), and approximately 0.08 inch during the summer (June, July, and August).

4.3.3 Local Air Quality

The SCAQMD has divided the SCAB into source receptor areas (SRAs), based on similar meteorological and topographical features. The project site is in SCAQMD's South San Gabriel Valley air monitoring area (SRA 11), and is served by the SCAQMD's Pasadena station, 4.63 miles north at 752 North Loren Avenue in Azusa, CA (SCAQMD, 2022b). This station monitors ozone, PM₁₀, PM_{2.5}, and NO₂. All stations in the SCAB ceased monitoring CO in 2012. The ambient air quality data in the project vicinity as recorded from 2020 through 2022, along with applicable standards, are shown in **Table 4.3-2**.

Table 4.3-2
AMBIENT AIR QUALITY MONITORING DATA

Air Pollutant	Standard/Exceedance	2020	2021	2022
Ozone	Max. 1-hour Concentration (ppm)	0.168	0.187	0.111
	Max. 8-hour Concentration (ppm)	0.125	0.086	0.080
	# Days > Federal 8-hour Std. of 0.070 ppm	62	21	11
	# Days > California 1-hour Std. of 0.09 ppm	53	20	6
	# Days > California 8-hour Std. of 0.070 ppm	65	22	11
PM ₁₀	Max. 24-hour Concentration (µg/m ³)	152.3	79.4	98.2
	Est. # Days > Fed. 24-hour Std. of 150 µg/m ³	ND	0	ND
	Federal Annual Arithmetic Mean (12 µg/m ³)	40.4	33.4	38.3
PM _{2.5}	Max. 24-hour Concentration (µg/m ³)	102.7	61.9	18.4
	# Days > Fed. 24-hour Std. of 35 µg/m ³	15	8.9	ND
	State Annual Average (12 µg/m ³)	13.6	12	ND
NO ₂	Max. 1-hour Concentration (ppm)	0.070	0.070	0.070
	State Annual Average (0.030 ppm)	0.013	0.014	ND
	# Days > California 1-hour Std. of 0.18 ppm	0	0	0



Source: ARB, 2024.

ND - There were insufficient (or no) data available to determine the value.

4.3.4 Air Quality Management Plan (AQMP)

The SCAQMD is required to produce plans to show how air quality would be improved in the region. The California Clean Air Act (CCAA) requires that these plans be updated triennially to incorporate the most recent available technical information.⁷ A multi-level partnership of governmental agencies at the federal, state, regional, and local levels implements the programs contained in these plans. Agencies involved include the USEPA, ARB, local governments, Southern California Association of Governments (SCAG), and SCAQMD. The SCAQMD and the SCAG are responsible for formulating and implementing the Air Quality Management Plan (AQMP) for the SCAB. The SCAQMD updates its AQMP every three years.

The 2022 AQMP (SCAQMD, 2022a) was adopted by the SCAQMD Board on December 2, 2022. It focuses on reducing ozone by limiting the emissions of NO_x, which is a key reactant in ozone formation. The NO_x reductions are through extensive use of zero-emission technologies across all stationary and mobile source categories. The majority of NO_x emissions are from heavy-duty trucks, ships, and other state and federally regulated mobile sources that are mostly beyond the SCAQMD's control. The SCAQMD's primary authority is over stationary sources, which account for approximately 20 percent of the SCAB's NO_x emissions.

The AQMP incorporates updated emission inventory methodologies for various source categories and incorporates the 2020-2045 Regional Transportation Plan/Sustainable Communities Strategy (RTP/SCS) prepared by SCAG (2020). The 2020-2045 RTP/SCS was determined to conform to the federally mandated State Implementation Plan for the attainment and maintenance of the NAAQS. county and city general plans.

4.3.5 Sensitive Receptors

Some people, such as individuals with respiratory illnesses or impaired lung function because of other illnesses, persons over 65 years of age, and children under 14, are particularly sensitive to certain pollutants. Facilities and structures where these sensitive people live or spend considerable amounts of time are known as sensitive receptors. For a CEQA analysis, the SCAQMD considers a sensitive receptor to be a receptor such as a residence, hospital, or convalescent facility where it is possible that an individual could remain for 24 hours (Chico and Koizumi, 2008, p. 3-2). Commercial and industrial facilities are not included in the definition of sensitive receptor, because employees typically are present for shorter periods, such as eight hours. Therefore, applying a 24-hour standard for PM₁₀ is appropriate not only because the averaging period for the state standard is 24 hours, but because the sensitive receptor could be present at the location for the full 24 hours

The nearest sensitive receptor to the project site is a single-family residence 60 meters (197 feet) south of the project site, located at 220 South Azusa Avenue in the city of West Covina. One school, Huffman Options for Learning Center, is located 95 meters (312 feet) southwest of the project site. Additionally, UEI College - West Covina is located at 339 North Azusa Avenue in the city of West Covina, 0.3 mile from the project site (Google Maps, 2024).

⁷ CCAA of 1988.



4.3.6 Applicable South Coast Air Quality Management District Rules

4.3.6.1 Rule 403 (Fugitive Dust Rule)

During construction, the project would be subject to SCAQMD Rule 403 (fugitive dust). SCAQMD Rule 403 does not require a permit for construction activities, per se; rather, it sets forth general and specific requirements for all construction sites (as well as other fugitive dust sources) in the SCAB. The general requirement prohibits a person from causing or allowing emissions of fugitive dust from construction (or other fugitive dust source) such that the presence of such dust remains visible in the atmosphere beyond the property line of the emissions source. SCAQMD Rule 403 also prohibits construction activity from causing an incremental PM₁₀ concentration impact, as the difference between upwind and downwind samples, at the property line of more than 50 micrograms per cubic meter as determined through PM₁₀ high-volume sampling. The concentration standard and associated PM₁₀ sampling do not apply if specific measures identified in the rules are implemented and appropriately documented.

Other requirements of Rule 403 include no track-out extending 25 feet or more in cumulative length and all track-outs to be removed after each workday; and using the applicable best available control measures included in Table 1 of Rule 403.

4.3.6.2 Rule 1113 (Architectural Coatings)

Construction of this project will include the application of architectural coatings and be subject to SCAQMD Rule 1113 (Architectural Coatings). Rule 1113 requires those who apply, store at a worksite, or solicit the application of architectural coatings to use coatings that contain VOC less than or equal to the VOC limits specified in Table 1 of the rule.

4.3.7 Impact Analysis

- a) **Would the project conflict with or obstruct the implementation of the applicable air quality plan?**

Less than Significant Impact

The South Coast 2022 AQMP, discussed above, incorporates land use assumptions from local general plans and regional growth projections developed by SCAG to estimate stationary and mobile air emissions associated with projected population and planned land uses. If the proposed land use is consistent with the local general plan, then the impact of the project is presumed to have been accounted for in the AQMP. This is because the land use and transportation control sections of the AQMP are based on the SCAG regional growth forecasts, which incorporate projections from local general plans. The project site is bounded by East Garvey Avenue to the south and east; Azusa Avenue to the west; and the Interstate 10 (I-10) freeway to the north. Regional access to the site is from the I-10 via Azusa Avenue. The 3.54-acre project site consists of three parcels: assessor's parcel numbers (APNs) 8478-007-025; -031; and -042. Parcels 8478-007-025 and -031 are zoned Service Commercial (S-C) with General Plan land use designations of Commercial; parcel -042 is zoned Neighborhood Commercial (N-C) and has General Plan land use designation of Commercial (City of West Covina, 2024). The land use and zoning would continue to be consistent with the local plans and the impacts of the project are still accounted for in the AQMP.



Another measurement tool for evaluating consistency with the AQMP is to determine whether a project would generate population and employment growth and, if so, whether that growth would exceed the growth rates forecasted in the AQMP and how the project would accommodate the expected increase in population or employment. In this case, the project is expected to result in an increase in the number of jobs onsite, and thus, it will not contribute to an increase in population or employment (Francis and Reicher, Personal Communication, 2024).

Furthermore, to help implement the AQMP, projects must not create regionally significant emissions of regulated pollutants from either short-term construction or long-term operations. The SCAQMD (2019) has developed criteria in the form of emissions thresholds for determining whether emissions from a project are regionally significant. They are useful for estimating whether a project is likely to result in a violation of the NAAQS and/or whether the project conforms with plans to achieve attainment. SCAQMD's significance thresholds for criteria pollutant emissions during construction activities and project operation are summarized in **Table 4.3-3**. A project is considered to have a regional air quality impact if emissions from its construction and/or operational activities exceed the corresponding SCAQMD significance thresholds.

Table 4.3-3
SCAQMD THRESHOLDS OF SIGNIFICANCE

Pollutant	Construction Thresholds (lbs/day)	Operational Thresholds (lbs/day)
Volatile Organic Compounds (VOC)	75	55
Nitrogen Oxides (NO _x)	100	55
Carbon Monoxide (CO)	550	550
Sulfur Oxides (SO _x)	150	150
Particulate Matter (PM ₁₀)	150	150
Fine Particulate Matter (PM _{2.5})	55	55

Note: lbs = pounds.
Source: SCAQMD, 2023.

Regional Construction Emissions

Construction activities for the project consist of demolition of an existing auto dealership (Envision Motors Toyota) and an operating Valero gas station, and construction of a new two-story automotive sales and dealership building housing Envision Motors Mercedes Benz that will sell four related brands – Mercedes Benz, Maybach, AMG and Sprinter – as well as associated surface parking, landscaping, and facilities for EV charging.

Construction is anticipated to last 14 months, beginning in June 2025 and ending in July 2026. There would be eight subphases:

- Demolition.
- Site Preparation.
- Grading.
- Utilities Installation.
- Building Construction.
- Paving.
- Architectural Coating.



- Landscaping Installation.

The Client provided information which was used to create an approximate schedule on CalEEMod for modeling purposes (Francis and Reicher, Personal Communication, 2024). **Table 4.3-4** shows the project schedule used for the air quality, GHG emissions, and noise analyses.

Table 4.3-4
CONSTRUCTION SCHEDULE

Construction Phase	Start	End
Demolition	June 2, 2025	July 31, 2025
Site Preparation	June 26, 2025	July 31, 2025
Grading	June 30, 2025	July 31, 2025
Utilities Installation	June 30, 2025	July 31, 2025
Building Construction	July 1, 2025	July 1, 2026
Paving	June 1, 2026	July 31, 2026
Architectural Coating	June 20, 2026	July 31, 2026
Landscaping Installation	June 20, 2026	July 31, 2026

Source: Estimated by UltraSystems with CalEEMod (Version 2022.1.1.25) (CAPCOA, 2023).

These construction activities would temporarily create emissions of dust, fumes, equipment exhaust, and other air contaminants. Mobile sources (such as diesel-fueled equipment onsite and traveling to and from the project site) would primarily generate NO_x emissions. The quantity of emissions generated daily would vary, depending on the amount and types of construction activities occurring at the same time.

Estimated criteria pollutant emissions from the project's onsite and offsite project construction activities were calculated using the California Emissions Estimator Model (CalEEMod), Version 2022.1.1.25 (CAPCOA, 2023). CalEEMod is a planning tool for estimating emissions related to land use projects. Model-predicted project emissions are compared with applicable thresholds to assess regional air quality impacts. Offroad construction equipment information was supplied by the client but CalEEMod defaults were used for onroad construction traffic inputs.

As shown in **Table 4.3-5**, construction emissions would not exceed SCAQMD regional thresholds. Therefore, the project's short-term regional air quality impacts would be less than significant. Refer to **Appendix B** of this document for air quality calculations.

Table 4.3-5
MAXIMUM DAILY REGIONAL CONSTRUCTION EMISSIONS

Construction Activity	Maximum Emissions (lbs/day)				
	ROG	NO _x	CO	PM ₁₀	PM _{2.5}
Maximum Emissions, 2025	5.65	50.6	56.4	6.53	3.65



Construction Activity	Maximum Emissions (lbs/day)				
	ROG	NO _x	CO	PM ₁₀	PM _{2.5}
Maximum Emissions, 2026	9.25	28.2	39.4	2.02	1.17
SCAQMD Significance Thresholds	75	100	550	150	55
Significant? (Yes or No)	No	No	No	No	No

Source: Calculated by UltraSystems with CalEEMod (Version 2022.1.1.25) (CAPCOA, 2023).

Regional Operational Emissions

The proposed project consists of the demolition of an existing auto dealership (Envision Motors Toyota) and an operating Valero gas station, and the construction of a new two-story automotive sales and dealership building housing Envision Motors Mercedes Benz. Operational emissions generated by area sources, motor vehicles and energy demand would result from normal day-to-day activities of the project. The trip rates developed by CalEEMod were adjusted with data provided in the Trip Generation Assessment Memorandum (RK Engineering, 2024). In the traffic memorandum, RK Engineering calculated the number of trips by comparing the existing and new project sites. They assessed the difference between the existing Toyota dealership and Valero gas station and the new project, a Mercedes dealership. Similarly, operational emissions were calculated by comparing the emissions from the old project site to those of the new project site.

The operational emissions for the existing land uses – the Toyota dealership and the Valero gas station – are presented in **Table 4.3-6**. The projected operational emissions for the proposed West Covina Envision Mercedes Benz Dealership Project are shown in **Table 4.3-7**. The net operational emissions were calculated by comparing the operational emissions of the existing land use with those of the proposed project. The results of these calculations are presented in **Table 4.3-8**. The net negative emissions show that the project's emissions are less than the existing operational emissions. As seen in the table, for each criteria pollutant, operational emissions would be below the pollutant's SCAQMD significance threshold. Therefore, regional operational emissions would be less than significant.



Table 4.3-6
MAXIMUM DAILY EXISTING OPERATIONAL EMISSIONS

Emission Source	Pollutant (lbs/day)				
	ROG	NO _x	CO	PM ₁₀	PM _{2.5}
Area Source Emissions	0.83	0.01	1.14	0.005	0.005
Energy Source Emissions	0.01	0.19	0.16	0.01	0.01
Mobile Source Emissions	9.58	8.3	84.6	16.7	4.32
Total Operational Emissions	10.42	8.5	85.9	16.715	4.335
<i>SCAQMD Significance Thresholds</i>	<i>55</i>	<i>55</i>	<i>550</i>	<i>150</i>	<i>55</i>
Significant? (Yes or No)	No	No	No	No	No

Source: Calculated by UltraSystems with CalEEMod (Version 2022.1.1.25) (CAPCOA, 2023).

Table 4.3-7
MAXIMUM DAILY PROJECT OPERATIONAL EMISSIONS

Emission Source	Pollutant (lbs/day)				
	ROG	NO _x	CO	PM ₁₀	PM _{2.5}
Area Source Emissions	1.14	0.03	3.77	0.01	0.01
Energy Source Emissions	0.01	0.16	0.14	0.01	0.01
Mobile Source Emissions	7.81	6.44	67.9	14.9	3.87
Total Operational Emissions	8.96	6.63	71.81	14.92	3.89
<i>SCAQMD Significance Thresholds</i>	<i>55</i>	<i>55</i>	<i>550</i>	<i>150</i>	<i>55</i>
Significant? (Yes or No)	No	No	No	No	No

Source: Calculated by UltraSystems with CalEEMod (Version 2022.1.1.25) (CAPCOA, 2023).



Table 4.3-8
MAXIMUM DAILY NET CHANGE IN OPERATIONAL EMISSIONS

Emission Source	Pollutant (lbs/day)				
	ROG	NO _x	CO	PM ₁₀	PM _{2.5}
Area Source Emissions	0.31	0.02	2.63	0.005	0.005
Energy Source Emissions	0	(0.03)	(0.02)	0	0
Mobile Source Emissions	(1.77)	(1.86)	(16.7)	(1.8)	(0.45)
Total Operational Emissions⁸	(1.46)	(1.87)	(14.09)	(1.795)	(0.445)
<i>SCAQMD Significance Thresholds</i>	<i>55</i>	<i>55</i>	<i>550</i>	<i>150</i>	<i>55</i>
Significant? (Yes or No)	No	No	No	No	No

Source: Calculated by UltraSystems with CalEEMod (Version 2022.1.1.25) (CAPCOA, 2023).

- b) Would the project result in a cumulatively considerable net increase of any criteria pollutant for which the project region is non-attainment under an applicable federal or state ambient air quality standard?**

Less Than Significant Impact

Since the SCAB is currently in nonattainment for ozone and PM_{2.5}, related projects may exceed an air quality standard or contribute to an existing or projected air quality exceedance. The SCAQMD neither recommends quantified analyses of construction and/or operational emissions from multiple development projects nor provides methodologies or thresholds of significance to be used to assess the cumulative emissions generated by multiple cumulative projects. Instead, the District recommends that a project's potential contribution to cumulative impacts be assessed by utilizing the same significance criteria as those for project-specific impacts. Furthermore, the SCAQMD states that if an individual development project generates less-than-significant construction or operational emissions impacts, then the development project would not contribute to a cumulatively considerable increase in emissions for those pollutants for which the Basin is in nonattainment.

As discussed above, the maximum daily construction and net maximum operational emissions generated by the project would not exceed any of the SCAQMD's significance thresholds. Also, as discussed below, localized emissions generated by the project would not exceed the SCAQMD's Localized Significance Thresholds (LSTs). Therefore, the project would not contribute a cumulatively considerable increase in emissions for the pollutants that the SCAB is in nonattainment. Thus, cumulative air quality impacts associated with the project would be less than significant.

⁸ Net negative emissions indicate that the proposed project will generate fewer emissions than the current use.



- c) **Would the project expose sensitive receptors to substantial pollutant concentrations?**

Less than Significant Impact

Construction of the project would generate short-term and intermittent emissions. Following the SCAQMD's Final Localized Significance Threshold Methodology (Chico and Koizumi, 2008), only onsite construction emissions were considered in the localized significance analysis. The nearest sensitive receptor to the project site is the single-family residence 60 meters (197 feet) south of the project site, located at 220 South Azusa Avenue in the city of West Covina. LSTs for projects in Source Receptor Area 11 (South San Gabriel Valley) were obtained from tables in Appendix C of the aforementioned methodology⁹. **Table 4.3-9** shows the results of the localized significance analysis for the project. Localized short-term air quality impacts from the construction of the project would be less than significant.

Table 4.3-9
RESULTS OF UNMITIGATED LOCALIZED SIGNIFICANCE ANALYSIS

Nearest Sensitive Receptor	Maximum Onsite Construction Emissions (pounds/day)			
	NO _x	CO	PM ₁₀	PM _{2.5}
Maximum daily unmitigated emissions	19.7	18.7	3.0	1.7
<i>SCAQMD LST for 3.54 acres @ 60 meters</i>	<i>149.37</i>	<i>1672.72</i>	<i>35.88</i>	<i>11.16</i>
Significant (Yes or No)	No	No	No	No

- d) **Would the project result in other emissions (such as those leading to odors) adversely affecting a substantial number of people?**

Less than Significant Impact

A project-related significant adverse effect could occur if the construction or operation of the proposed project would result in the generation of odors that would be perceptible in adjacent sensitive areas. According to the SCAQMD CEQA Air Quality Handbook (SCAQMD, 1993), land uses and industrial operations that are associated with odor complaints include agricultural uses, wastewater treatment plants, food processing plants, chemical plants, composting, refineries, landfills, dairies, and fiberglass molding. Potential sources that may emit odors during construction activities include equipment exhaust. Odors from these sources would be localized and generally confined to the immediate area surrounding the project. The project would use typical construction techniques, and the odors would be typical of most construction sites and temporary in nature. The project would not create substantial objectionable odors and this impact would be less than significant.

⁹ Double interpolation was conducted from SCAQMD Localized Significance Thresholds (LST) for sites of 2 acres and 5 acres, and distances of 50 meters and 100 meters, to estimate the LST for the project site of 3.54 acres at a distance of 60 meters.



4.4 Biological Resources

Would the project:	Potentially Significant Impact	Less than Significant with Mitigation Incorporated	Less than Significant Impact	No Impact
a) Have a substantial adverse effect, either directly or through habitat modifications, on any species identified as a candidate, sensitive, or special status species in local or regional plans, policies, or regulations, or by the California Department of Fish and Wildlife or U.S. Fish and Wildlife Service?		X		
b) Have a substantial adverse effect on any riparian habitat or other sensitive natural community identified in local or regional plans, policies, regulations or by the California Department of Fish and Wildlife or US Fish and Wildlife Service?				X
c) Have a substantial adverse effect on state or federally protected wetlands (including, but not limited to, marsh, vernal pool, coastal, etc.) through direct removal, filling, hydrological interruption, or other means?				X
d) Interfere substantially with the movement of any native resident or migratory fish or wildlife species or with established native resident or migratory wildlife corridors, or impede the use of native nursery sites?		X		
e) Conflict with any local policies or ordinances protecting biological resources, such as a tree preservation policy or ordinance?		X		
f) Conflict with the provisions of an adopted Habitat Conservation Plan, Natural Community Conservation Plan, or other approved local, regional, or state habitat conservation plan?				X

The project site is built-out with a car dealership and a gas station and is located in completely developed urban surroundings. Only minor amounts of ornamental landscaping are present onsite currently, in addition to street trees along the site perimeter along Azusa Avenue and East Garey Avenue. No natural habitat suitable for special-status species, and no sensitive natural communities, are present onsite. A California Natural Diversity Database (CNDDB) search was run for the project site and a 10-mile radius surrounding the site. Species Occurrence Potential (SOP) tables for the project are included in **Appendix C**.



4.4.1 Discussion of Impacts

- a) **Would the project have a substantial adverse effect, either directly or through habitat modifications, on any species identified as a candidate, sensitive, or special status species in local or regional plans, policies, or regulations, or by the California Department of Fish and Wildlife or U.S. Fish and Wildlife Service?**

Less Than Significant with Mitigation Incorporated

Plant and wildlife species listed under the federal Endangered Species Act (ESA) or under the California Endangered Species Act (CESA) are referred to collectively as “listed species” in this section. Plant and wildlife species not listed under ESA or CESA but still protected by federal agencies, state agencies, local or regional plans, and/or nonprofit resource organizations, such as the California Native Plant Society (CNPS), are collectively referred to as “sensitive species” in this section. The term “special-status species” is used when collectively referring to both listed and sensitive species.

As stated above, SOP tables were prepared for the project based on the CNDDDB 10-mile radius species search conducted (see **Appendix C**). Due to the project site and surrounding area being fully developed, species listed are not expected to occur on the project site. However, trees onsite could provide foraging, nesting, and cover habitats to support multiple bird species. Most bird species occurring in California are protected by the federal Migratory Bird Treaty Act (MBTA) and by California Fish and Game Code § 3503, § 3503.5, and § 3513. Mitigation measure **BIO-1** would reduce potential project impacts to bird species.

Mitigation Measure

BIO-1: Pre-Construction Breeding Bird Survey

To be in compliance with the MBTA and Fish and Game Code, and to avoid impacts or take of migratory non-game breeding birds, their nests, young, and eggs, the following measures will be implemented. The measures below will help to reduce direct and indirect impacts caused by construction on migratory non-game breeding birds to less than significant levels.

- Project activities that will remove or disturb potential nest sites, such as open ground, trees, shrubs, grasses, or burrows, during the breeding season would be a potential significant impact if migratory non-game breeding birds are present. Project activities that will remove or disturb potential nest sites will be scheduled outside the breeding bird season to avoid potential direct impacts on migratory non-game breeding birds protected by the MBTA and Fish and Game Code. The breeding bird nesting season is typically from February 15 through September 15, but can vary slightly from year to year, usually depending on weather conditions. Removing all physical features that could potentially serve as nest sites will also help to prevent birds from nesting within the project site during the breeding season and during construction activities.
- If project activities cannot be avoided during February 15 through September 15, a qualified biologist will conduct a pre-construction breeding bird survey for breeding birds and active nests or potential nesting sites within the limits of project disturbance. The survey will be conducted at least seven days prior to the onset of scheduled activities, such as mobilization and staging. It will end no more than three days prior to vegetation, substrate, and structure removal and/or disturbance.



❖ SECTION 4.4 – BIOLOGICAL RESOURCES ❖

- If no breeding birds or active nests are observed during the pre-construction survey or they are observed and will not be impacted, project activities may begin and no further mitigation will be required.
- If a breeding bird territory or an active bird nest is located during the pre-construction survey and will potentially be impacted, the site will be mapped on engineering drawings and a no activity buffer zone will be marked (fencing, stakes, flagging, orange snow fencing, etc.) a minimum of 100 feet in all directions or 500 feet in all directions for listed bird species and all raptors. The biologist will determine the appropriate buffer size based on the type of activities planned near the nest and the type of bird that created the nest. Some bird species are more tolerant than others of noise and activities occurring near their nest. This no-activity buffer zone will not be disturbed until a qualified biologist has determined that the nest is inactive, the young have fledged, the young are no longer being fed by the parents, the young have left the area, or the young will no longer be impacted by project activities. Periodic monitoring by a biologist will be performed to determine when nesting is complete. Once the nesting cycle has finished, project activities may begin within the buffer zone.
- If listed bird species are observed within the project site during the pre-construction survey, the biologist will immediately map the area and notify the appropriate resource agency to determine suitable protection measures and/or mitigation measures and to determine if additional surveys or focused protocol surveys are necessary. Project activities may begin within the area only when concurrence is received from the appropriate resource agency.
- Birds or their active nests will not be disturbed, captured, handled or moved. Active nests cannot be removed or disturbed; however, nests can be removed or disturbed if determined inactive by a qualified biologist.

Level of Significance After Mitigation

With implementation of mitigation measure **BIO-1**, the proposed project would have less than significant impacts on nesting birds.


- b) Would the project have a substantial adverse effect on any riparian habitat or other sensitive natural community identified in local or regional plans, policies, regulations or by the California Department of Fish and Wildlife or U.S. Fish and Wildlife Service?**

No Impact

The project site is built out and no streams, rivers or sensitive natural communities are present onsite. The nearest riparian habitat to the project site mapped on the National Wetlands Mapper is about 0.5 miles to the south, as shown on **Figure 4.4-1** (USFWS, 2024). No impact would occur.



Figure 4.4-1
NATIONAL WETLANDS INVENTORY





- c) **Would the project have a substantial adverse effect on state or federally protected wetlands (including, but not limited to, marsh, vernal pool, coastal, etc.) through direct removal, filling, hydrological interruption, or other means?**

No Impact

The project site is built out with commercial uses. The nearest stream to the project site mapped on the National Wetlands Mapper is Walnut Creek, a constructed channel about 0.25 mile south of the project site (USFWS, 2024). Therefore, the project would not result in the direct removal, filling, hydrological interruption, or other direct impacts. No impact would occur.

- d) **Would the project interfere substantially with the movement of any native resident or migratory fish or wildlife species or with established native resident or migratory wildlife corridors, or impede the use of native wildlife nursery sites?**

Less Than Significant Impact with Mitigation Incorporated.

The project site and surroundings are built out with urban uses, and the site is not available as a wildlife movement corridor. Trees onsite could be used for nesting by birds. This impact would be significant without mitigation.

Mitigation Measure

Implementation of mitigation measure **BIO-1**.

Level of Significance After Mitigation

Impacts would be less than significant after implementation of mitigation measure BIO-1.

- e) **Would the project conflict with any local policies or ordinances protecting biological resources, such as a tree preservation policy or ordinance?**

No Impact

One mature tree, a Callery pear tree (*Pyrus calleryana*), is present onsite (Tollett, 2024). City of West Covina Municipal Code §§ 26-288 et seq. protect heritage trees and significant trees, on both private and public properties. Heritage trees are trees that are historically significant as defined in Municipal Code Section 26-289(6); and Southern California black walnut tree species (*Juglans californica*) in the San Jose Hills within the city of West Covina (Municode.com, 2024). Significant trees are trees of certain sizes of any of several oak species or two sycamore species (Municode.com, 2024). The tree onsite is not a historic tree; it is part of the landscaping on the existing development. The southern part of the Envision Toyota property was developed with a building containing a liquor store and delicatessen in 1957; that building was demolished at the end of the 1980's. Garvey Avenue South bisected the property in the late 1950's and 1960's. The existing auto dealership buildings were built in 1977-79 (CSI 2024a, p. 6). The gas station property has been developed as a gas station since 1957 (CSI 2024b, p. 6). Project development would not conflict with City of West Covina municipal code provisions protecting trees, and no impact would occur.



- f) **Would the project conflict with the provisions of an adopted Habitat Conservation Plan, Natural Community Conservation Plan, or other approved local, regional, or state habitat conservation plan?**

No Impact

The project site is not in a habitat conservation plan or natural community conservation plan, and no impact to such plans would occur.



4.5 Cultural Resources

Would the project:	Potentially Significant Impact	Less than Significant Impact with Mitigation Incorporated	Less than Significant Impact	No Impact
a) Cause a substantial adverse change in the significance of a historical resource pursuant to § 15064.5?				X
b) Cause a substantial adverse change in the significance of an archaeological resource pursuant to § 15064.5?		X		
c) Disturb any human remains, including those interred outside of formal cemeteries?		X		

Information from UltraSystems' Cultural Resources Inventory Report, dated June 7, 2024 (see **Appendix D**), prepared for the Envision Motors Mercedes Benz of West Covina Project, City of West Covina has been included within this section.

4.5.1 Methodology


A cultural resources inventory was requested on March 22, 2024 for the Envision Motors Mercedes Benz of West Covina Project site (**Figure 4.5-1, Topographic Map**). This study included a California Historic Resources Inventory System (CHRIS) records and literature search at the South Central Coastal Information Center (SCCIC) at the California State University Fullerton. A request was made to the Native American Heritage Commission (NAHC) to conduct a search of their Sacred Lands File (SLF) for potential traditional cultural properties as well as to provide a list of local Native American tribal organizations to contact. The NAHC request was made on April 19, 2024, and a reply was received on May 10, 2024; letters were sent to the listed tribes on May 16, 2024 and follow-up telephone calls were conducted following the response period on June 7, 2024. A pedestrian field survey of the project site was conducted on May 10, 2024.

4.5.2 Existing Conditions

Based on the cultural resources records search, it was determined that no historic cultural resources or prehistoric archeological sites have been recorded previously within the project site boundary, the area of potential affect (APE). Within the 0.5-mile buffer zone of the APE there were 12 previously recorded historic-era cultural resources, but no prehistoric archaeological sites have been recorded (see **Appendix D**, Section 4.1). No historic or prehistoric resources were observed during the field survey.



Figure 4.5-1
TOPOGRAPHIC MAP



Disclaimer: Representations on this map or illustration are intended only to indicate locations of project parameters reported in the legend. Project parameter information supplied by others (see layer credits) may not have been independently verified for accuracy by UltraSystems Environmental, Inc. This map or illustration should not be used for, and does not replace, final grading plans or other documents that should be professionally certified for development purposes.

Path: V:\GIS\GIS\Projects\7212_WCovina_Environ_Dealership_ISMND\MXDs\7212_WCovina_4_5_Topo_2024_04_18.mxd
Service Layer Credits: Sources: Esri, HERE, Garmin, USGS, Intermap, INCREMENT P, NRCan, Esri Japan, METI, Esri China (Hong Kong), Esri Korea, Esri (Thailand), NGCC, (c) OpenStreetMap contributors, and the GIS User Community. Copyright © 2013 National Geographic Society, I-cubed, California Department of Conservation, 2010; UltraSystems Environmental, Inc., 2024.

April 18, 2024



Envision Motors
West Covina Mercedes Benz

Topographic Map
USGS Quadrangle: Baldwin Park
Township: 1S Range: 10W
Section: 23





4.5.3 Impact Analysis

- g) **Would the project cause a substantial adverse change in the significance of a historical resource pursuant to § 15064.5?**

No Impact

A historical resource is defined in § 15064.5(a)(3) of the *CEQA Guidelines* as any object, building, structure, site, area, place, record, or manuscript determined to be historically significant or significant in the architectural, engineering, scientific, economic, agricultural, educational, social, political, military, or cultural annals of California. Historical resources are further defined as being associated with significant events, important persons, or distinctive characteristics of a type, period or method of construction; representing the work of an important creative individual; or possessing high artistic values. Resources listed in or determined eligible for the California Register, included in a local register, or identified as significant in a historic resource survey are also considered as historical resources under CEQA.

Similarly, the National Register criteria (contained in Code of Federal Regulations Title 36 § 60.4) are used to evaluate resources when complying with Section 106 of the National Historic Preservation Act. Specifically, the National Register criteria state that eligible resources comprise districts, sites, buildings, structures, and objects that possess integrity of location, design, setting, materials, workmanship, feeling, and association, and that (a) are associated with events that have made a significant contribution to the broad patterns of our history; or (b) that are associated with the lives of persons significant in our past; or (c) that embody the distinctive characteristics of a type, period, or method of construction, or that possess high artistic values, or that represent a significant distinguishable entity whose components may lack individual distinction; or (d) that have yielded or may be likely to yield, information important to history or prehistory.

A substantial adverse change in the significance of an historical resource, as a result of a project or development, is considered a significant impact on the environment. Substantial adverse change is defined as physical demolition, relocation, or alteration of a resource or its immediate surroundings such that the significance of the historical resource would be materially impaired. Direct impacts are those that cause substantial adverse physical change to a historic property. Indirect impacts are those that cause substantial adverse change to the immediate surroundings of a historic property, such that the significance of a historical resource would be materially impaired.

The cultural resources records search conducted at the SCCIC determined that no historic-era resources have been recorded within the APE. Within the 0.5-mile radius of the project boundary there are 12 previously recorded historic-era cultural resources. None of these resources are adjacent to or visible from the APE. No prehistoric archaeological sites have been recorded (Table 4.1-1 in **Appendix D**).

According to records at the SCCIC, no previous cultural resource surveys have included a portion of the project site (APE), but there have been three surveys conducted within the 0.5-mile radius project buffer (**Appendix D**).

As a result of the project site's field survey, no historic buildings were identified within the project site. No other cultural resources were observed during the survey.



Based on the results of the records search and the onsite field survey there would be no substantial adverse change in the significance of a historical resource pursuant to in § 15064.5, and therefore the project would have no impact in this regard.

h) Would the project cause a substantial adverse change in the significance of an archaeological resource pursuant to § 15064.5?

Less than Significant Impact with Mitigation Incorporated

An archaeological resource is defined in § 15064.5(c) of the CEQA Guidelines as a site, area or place determined to be historically significant as defined in § 15064(a) of the CEQA Guidelines, or as a unique archaeological resource defined in § 21083.2 of the Public Resources Code as an artifact, object, or site that contains information needed to answer important scientific research questions of public interest or that has a special and particular quality such as being the oldest or best example of its type, or that is directly associated with a scientifically-recognized important prehistoric or historic event or person. The project parcel has been highly disturbed by several decades of urban development. It is highly unlikely that undisturbed unique archeological resources exist on the project site as determined by the cultural resources investigation conducted by UltraSystems, which included a CHRIS records search of the project site and 0.5-mile radius around the site, a search of the SLF by the NAHC, and pedestrian field survey.

The cultural resources records search conducted at the SCCIC determined that there are no known prehistoric cultural resource sites or isolates recorded within the APE or in the 0.5-mile radius of the project boundary (Table 4.1-1 in **Appendix D**).

A NAHC SLF search was conducted for the project site region. The NAHC letter of May 10, 2024 was negative for the presence of a traditional cultural property within this area. The NAHC provided a list of 13 contacts representing seven tribes. These were all contacted via letter and email requesting a reply if they have knowledge of cultural resources in the area that they wished to share and asking if they had any questions or concerns regarding the project. These tribes included:

- Gabrielino Band of Mission Indians – Kizh Nation
- Gabrielino/Tongva San Gabriel Band of Mission Indians
- Gabrielino Tongva Indians of California Tribal Council
- Gabrielino/Tongva Nation
- Gabrielino -Tongva Tribe
- Santa Rosa Band of Mission Indians
- Soboba Band of Luiseño Indians

There have been three responses to the outreach contacts from the seven tribes. The Administrative Specialist for the Gabrielino Band of Mission Indians – Kizh Nation replied by email on May 17, 2024 requested the lead agency's contact information. Assistant Project Archaeologist Megan B. Doukakakis responded that contact information was not available as the project has not yet been submitted to the City at that time. Christina Conley, Cultural Resource Administrator for the Gabrielino Tongva Indians of California Tribal Council responded by email on May 16, 2024 indicating that the tribe does not have any concerns about the project. Vanesse Minott, Tribal Administrator for the Santa Rosa Band of Cahuilla Indians responded by email on May 20, 2024 stating that the tribe has no comments on the project. Steven Estrada, Tribal Chairman for the Santa Rosa Band of Cahuilla Indians responded by email on May 17, 2024 stating that the tribe defers any consultation and monitoring efforts to the Soboba Band of Luiseno Indians.



Following up on the initial letter and email contacts, telephone calls were conducted by Ms. Doukakis on June 7, 2024 to the eight tribal contacts who had not previously replied by email or letter. Five of the telephone calls were placed with no answer and messages were left describing the project and requesting a response. These were to Sam Dunlap, Cultural Resource Director with the Gabrielino-Tongva Tribe; Anthony Morales, Chairperson of the Gabrielino / Tongva San Gabriel Band of Mission Indians; Joseph Ontiveros, Cultural Resources Director, Isaiah Vivanco, Chairperson, and Jessica Valdez, Cultural Resource Specialist for the Soboba Band of Luiseño Indians. In the call to Charles Alvarez with the Gabrielino-Tongva Tribe the phone line was found to be disconnected and so no message could be left. In the call to Sandonne Goad, Chairperson of the Gabrielino / Tongva Nation there was no answer and the mailbox was full; no message could be left. There has been no response to date from these contacts.

On the call to Andrew Salas, Chairperson for the Gabrieleno Band of Mission Indians – Kizh Nation the tribal receptionist indicated that Secretary Martinez and Chairperson Salas were not in the office. A message was left with the receptionist (See contact record table in Attachment C, **Appendix D**).

A pedestrian field survey of the project site was conducted on May 10, 2024. The main project parcel, occupied by the current Envision Motors Toyota car dealership, is situated at 1800 East Garvey Avenue South (APNs 8478-007-025 and -031); a smaller associated parcel is the former Shell (now Valero) service station on the northeast corner of E. Garvey Avenue and South Azusa Avenue (APN 8478-007-042). The survey consisted of walking along and over the several landscape beds surrounding the periphery of the project site. Along the northwest and west periphery of the property bordering the Azusa Avenue onramp to the east-bound I-10 freeway and along Azusa Avenue itself there is a 4' wide and approximately 310' long landscape bed. This was covered with dry grass and weeds. This bed was observed with a single transect walk north to south. At the southern end of the bed is a small plot approximately 10' x 20' also covered with dry grass and weeds. In the middle of the parcel is a stand-alone car repair building with a 12' long hedge of boxwood on the north side with no ground visible. The front outer edge of the parcel to the east along East Garvey Avenue has a landscape bed 5' wide and approximately 550' long containing well-maintained grass and a row of palm trees that was observed by walking along its edge south to north. At the north end of the bed, which is the main entrance to the property, is a hedge of boxwood with open ground below. The smaller parcel containing the service station has three small landscape beds along E. Garvey Avenue and South Azusa Avenue. These are covered with well maintain grass and some shrubbery with no ground surface visible. Visibility of the surface throughout the project site was poor with an average of approximately 10 percent. The result of the pedestrian survey was negative for both prehistoric and historic sites, features and isolates.

The cultural resources study findings suggest that there is a low potential for the presence of prehistoric cultural resources. The project site is disturbed by several decades of urban development. It is not recommended that an archaeological monitor be present during ground-disturbing activities. However, if prehistoric and/or historic items are observed during subsurface activities, work should be stopped in that area and a qualified archaeologist and Native American monitor be retained to assess the finding(s) and retrieve the material.

Mitigation Measure

MM CUL-1 If archaeological resources are discovered during construction activities, the contractor will halt construction activities in a 50-foot diameter and notify the City of West Covina. The project applicant shall retain an archaeologist who meets the Secretary of the Interior's Professional Qualifications Standards for Archaeology who



will be notified and afforded the necessary time to recover, analyze, and curate the find(s). The qualified archaeologist will recommend the extent of archaeological monitoring necessary to ensure the protection of any other resources that may be in the area. Any identified cultural resources shall be recorded on the appropriate DPR 523 (A-L) form and filed with the South Central Coastal Information Center. Construction activities may continue on other parts of the project site while evaluation and treatment of prehistoric archaeological resources takes place.

Level of Significance After Mitigation

With implementation of Mitigation Measures **MM CUL-1** above, the project would result in less than significant impacts to archeological resources.

i) Would the project disturb any human remains, including those interred outside of formal cemeteries?

Less than Significant Impact with Mitigation Incorporated

As previously discussed in **Section 4.5.b)** above, the project would be built on disturbed land due to several decades of urban development. No human remains have been previously identified or recorded onsite. The project proposes trench digging and some grading activities for the installation of infrastructure including water, sewer, and utility lines; and for construction of the proposed buildings. Trenching would involve new subsurface disturbance and could result in the unanticipated discovery of unknown human remains, including those interred outside of formal cemeteries. In the unlikely event of an unexpected discovery, implementation of mitigation measure **CUL-2** would ensure that impacts related to the accidental discovery of human remains would be less than significant.

California Health and Safety Code § 7050.5 specifies the procedures to follow during the unlikely discovery of human remains. CEQA § 15064.5 describes determining the significance of impacts on archeological and historical resources. California Public Resources Code § 5097.98 stipulates the notification process during the discovery of Native American human remains, descendants, disposition of human remains, and associated grave goods.

Mitigation Measure

MM CUL-2 If human remains are encountered during excavations associated with this project, all work will stop within a 30-foot radius of the discovery and the Los Angeles County Coroner will be notified (§ 5097.98 of the Public Resources Code). The Coroner will determine whether the remains are recent human origin or older Native American ancestry. If the coroner, with the aid of the supervising archaeologist, determines that the remains are prehistoric, they will contact the NAHC. The NAHC will be responsible for designating the Most Likely Descendant (MLD). The MLD (either an individual or sometimes a committee) will be responsible for the ultimate disposition of the remains, as required by § 7050.5 of the California Health and Safety Code. The MLD will make recommendations within 24 hours of their notification by the NAHC. These recommendations may include scientific removal and nondestructive analysis of human remains and items associated with Native American burials (§ 7050.5 of the Health and Safety Code).



Level of Significance After Mitigation

With adherence to applicable codes and regulations protecting cultural resources and with implementation of Mitigation Measure **MM CUL-2** above, the proposed project would result in less than significant impacts to human remains.



4.6 Energy

Would the project:	Potentially Significant Impact	Less than Significant Impact with Mitigation Incorporated	Less than Significant Impact	No Impact
a) Result in potentially significant environmental impact due to wasteful, inefficient, or unnecessary consumption of energy resources, during project construction or operation?			X	
b) Conflict with or obstruct a state or local plan for renewable energy or energy efficiency?			X	

As part of the air quality and greenhouse gas emissions analyses (refer to **Section 4.3** and **Section 4.8**), the California Emissions Estimator Model (CalEEMod) was used to estimate the electric energy demand for the proposed project.

- a) **Would the project result in potentially significant environmental impact due to wasteful, inefficient, or unnecessary consumption of energy resources, during project construction or operation?**

Electricity

Construction Use

Southern California Edison (SCE) will provide electric power for the proposed project. Temporary electric power for as-necessary lighting and electronic equipment would be provided by SCE. The amount of electricity used during construction would be temporary and minimal, as demand would primarily stem from use of electrically powered hand tools. Therefore, project construction would not result in wasteful, inefficient, or unnecessary consumption of electricity, and impacts would be less than significant.

Operational Use

Project operation would require electricity for multiple purposes including, but not limited to, building heating and cooling, lighting, appliances, and electronics. Additionally, the supply, conveyance, treatment, and distribution of water used by the project would indirectly result in electricity usage. The operational energy consumption for the existing land uses, the Toyota dealership and Valero gas station, which together have 60 employees (Beltran, 2024b), are shown in **Table 4.6-1**.



Table 4.6-1
ESTIMATED EXISTING OPERATIONAL ENERGY USE

Energy Type	Units	Value	Per Capita ^a
Onroad Motor Vehicle Travel (Fuel) ^b	Gallons gasoline/year	309,598	5,160
	Gallons diesel/year	93,230	1,554
Electricity Use	Kilowatt-hours per year	530,593	8,843
Natural Gas Use	1,000 BTU per year	708,443	11,807

^a Based upon estimated employee population of 60; see **Section 3.5**. The per capita value for the on-road motor vehicle fuel consumption is calculated from fuel consumption by passenger vehicles (automobiles and light-duty trucks).

^b Onroad Motor Vehicle Fuel Consumption calculated by UltraSystems using EMFAC2021(v1.0.2) emissions inventory web platform tool (ARB, 2022c) and CalEEMod (2022.1.1.25) (CAPCOA, 2023); see **Appendix B**.
Electricity use calculated by UltraSystems with CalEEMod (2022.1.1.25).

Projected operational energy use by only the proposed West Covina Envision Mercedes Benz Dealership Project is shown in **Table 4.6-2**. The per capita project values are based on an estimated employee population of 49, which was provided by the applicant (Beltran, 2024b). Net operational energy uses were calculated by comparing the energy uses from the present land uses with those of the proposed new land uses.

Table 4.6-2
ESTIMATED PROPOSED PROJECT OPERATIONAL ENERGY USE

Energy Type	Units	Value	Per Capita ^a
Onroad Motor Vehicle Travel (Fuel) ^b	Gallons gasoline/year	266,509	5,439
	Gallons diesel/year	83,640	1,707
Electricity Use	Kilowatt-hours per year	685,194	13,984
Natural Gas Use	1,000 BTU per year	599,656	12,238

^a Based upon estimated employee population of 49; see **Section 3.5**. The per capita value for the on-road motor vehicle fuel consumption is calculated from fuel consumption by passenger vehicles (automobiles and light-duty trucks).

^b Onroad Motor Vehicle Fuel Consumption calculated by UltraSystems using EMFAC2021(v1.0.2) emissions inventory web platform tool (ARB, 2022c) and CalEEMod (2022.1.1.25) (CAPCOA, 2023); see **Appendix B**.
Electricity use calculated by UltraSystems with CalEEMod (2022.1.1.25).

The results of these calculations are presented in **Table 4.6-3**. The negative values show that the proposed project's fuel consumption and natural gas use will be less than that of the existing



operations. The proposed project's electricity use and all per-capita values will increase slightly; however, this energy use will not be wasteful, inefficient, or unnecessary and impacts would be less than significant.

Table 4.6-3
ESTIMATED NET CHANGE IN OPERATIONAL ENERGY USE

Energy Type	Units	Value	Per Capita
Onroad Motor Vehicle Travel	Gallons gasoline/year	(43,089)	279
(Fuel) ^a	Gallons diesel/year	(9,590)	153
Electricity Use	Kilowatt-hours per year	154,600	5,141
Natural Gas Use	1,000 BTU per year	(108,786)	430

^a Onroad Motor Vehicle Fuel Consumption calculated by UltraSystems using EMFAC2021(v1.0.2) emissions inventory web platform tool (ARB, 2022c) and CalEEMod (2022.1.1.25) (CAPCOA, 2023); see **Appendix B**.
Electricity use calculated by UltraSystems with CalEEMod (2022.1.1.25).

Natural Gas

Construction Use

Southern California Gas Company (SoCalGas) will provide natural gas for the proposed project. Construction activities, including the construction of new buildings and facilities, typically do not involve the consumption of natural gas. Any minor amounts of natural gas that may be consumed as a result of project construction would be temporary and negligible and would not have an adverse effect; therefore, construction would not result in wasteful, inefficient, or unnecessary consumption of natural gas. Therefore, impacts would be less than significant.

Operational Use

Natural gas consumption during operation would be required for various purposes, including building heating and cooling. As part of the air quality and greenhouse gas emissions analyses (refer to **Section 4.3** and **Section 4.8**), the California Emissions Estimator Model (CalEEMod), was used to estimate natural gas demand for the proposed project, which is presented above in **Table 4.6-3**. The negative values show that the proposed project's natural gas use would be less than that of the existing operations while per-capita values would increase slightly; however, this energy use would not be wasteful, inefficient, or unnecessary and impacts would be less than significant.



Petroleum

Construction Use

Petroleum-based fuel consumed by construction equipment would be the primary energy resource expended during construction. Transportation of construction materials and construction workers would also result in petroleum consumption. Heavy-duty construction equipment, vendor trucks, and haul trucks would use diesel fuel. Construction workers would likely travel to and from the project area in gasoline-powered vehicles. Construction for the proposed project is anticipated to take 13 months, from June 2025 to July 2026. Because of the short-term nature of construction and relatively small scale of the project, the project's petroleum consumption would be negligible when compared to California's daily total use of approximately 1.8 million barrels of petroleum.

During project construction, trucks and construction equipment would be required to comply with the ARB's anti-idling regulations. ARB's In-Use Off-Road Diesel Fueled Fleets regulation would also apply (ARB, 2023). Vehicles driven to or from the project site (delivery trucks, construction employee vehicles, etc.) are subject to fuel efficiency standards established by the federal government. Therefore, project construction activities regarding fuel use would not result in wasteful, inefficient, or unnecessary consumption, and impacts would be less than significant.

Operational Use

During operations, the majority of fuel consumption resulting from the project would involve the use of motor vehicles traveling to and from the project site, as well as fuels used for alternative modes of transportation that may be used by employees and visitors to the project site. Annual project operation petroleum usage from on-road motor vehicle fuel consumption was estimated using the California Air Resources Board Emission Factor model (EMFAC2021). As part of the air quality and greenhouse gas emissions analyses (refer to **Section 4.3** and **Section 4.8**), the California Emissions Estimator Model (CalEEMod), was used to estimate the project's vehicle miles travelled (VMT) which was included in the EMFAC analysis to predict annual diesel and gasoline fuel consumption.

The project would comply with all applicable regulations and codes that require achievement of various levels of energy efficiency in building operation. These include (1) the 2022 California Energy Efficiency Standards for Nonresidential Buildings (California Code of Regulations Title 24, Part 6), and (2) the 2022 California Green Building Standards Code (CalGreen; California Code of Regulations Title 24 Part 11).

As shown in **Table 4.6-2** above, the project would consume 350,149 gallons of petroleum-based fuel per year during operation, which is less than the fuel consumption of the existing land uses. By comparison, approximately 13.82 billion gallons of petroleum were consumed in California in 2021 (CEC, 2022a). The anticipated fuel consumption associated with one year of project operation is 0.0023 percent of the statewide use. Implementation of the project would result in a decrease in petroleum use during operation and, over time, vehicles would use less petroleum due to advances in fuel economy.

The project would consume approximately 685,194 kilowatt-hours (kWh) of electricity per year, which is an increase of 154,600 kWh/year compared to existing land uses. The project would consume 599,656 thousand British thermal units (kBtu) of natural gas per year which is a decrease of 108,786 kBtu/year compared to existing land uses. By comparison, in 2022, the latest year for which data are available, approximately 68,484 gigawatt hours of electricity were consumed by SCE



residential and nonresidential customers in Los Angeles County (CEC, 2023a). SoCalGas supplied approximately 282 trillion British thermal units (MMBtu) in 2022 for the residential and nonresidential customer service area in that same year (CEC, 2023b). The usage of electricity and natural gas demand at the project site would be negligible relative to the use in SCE's and SoCalGas's service areas.

Continued use of energy resources is consistent with the anticipated growth within the City and the general vicinity and would not result in energy consumption that would require a significant increase in energy production for the energy provider. Based on the information provided above, the proposed project would have a less than significant impact regarding wasteful, inefficient, or unnecessary consumption of energy resources during project construction or operation.

b) Would the project conflict with or obstruct a state or local plan for renewable energy or energy efficiency?

Less than Significant Impact

Title 24 Building Energy Efficiency Standards

The initial Energy Efficiency Standards for Residential and Nonresidential Buildings (Title 24, Part 6, of the California Code of Regulations) were established in 1978 in response to a legislative mandate to reduce California's energy consumption. The standards are updated periodically to allow consideration and possible incorporation of new energy efficiency technologies and methods. Compliance with Title 24 will result in a decrease in GHG emissions.

The Title 24 standards are updated on a three-year schedule, with the most current 2022 standards adopted on August 11, 2021. In December 2021, the 2022 standards were approved by the California Building Standards Commission for inclusion into the California Building Standards Code. The Building Energy Efficiency Standards (Energy Code) apply to newly constructed buildings, additions, and alterations. They are a vital pillar of California's climate action plan. The 2022 Energy Code will produce benefits to support the state's public health, climate, and clean energy goals by encouraging implementation of efficient electric heat pumps, establishing electric-ready requirements for new homes, expanding solar photovoltaic and battery storage standards, strengthening ventilation standards, and more. Buildings with permit applications applied for on or after January 1, 2023, must comply with the 2022 Energy Code. Public Resources Code §§ 25402 subdivisions (a)-(b) and § 25402.1 emphasize the importance of building design and construction flexibility by requiring the California Energy Commission (CEC) to establish performance standards, in the form of an "energy budget" in terms of the energy consumption per square foot of floor space (CEC, 2022b).

The provisions of Title 24, Part 6 apply to all buildings for which an application for a building permit or renewal of an existing permit is required by law. They regulate design and construction of the building envelope, space-conditioning and water-heating systems, indoor and outdoor lighting systems of buildings, and signs located either indoors or outdoors. Title 24, Part 6 specifies mandatory, prescriptive and performance measures, all designed to optimize energy use in buildings and decrease overall consumption of energy to construct and operate residential and nonresidential buildings. Mandatory measures establish requirements for manufacturing, construction, and installation of certain systems, equipment, and building components that are installed in buildings.



Title 24 California Green Building Standards Code

The California Green Building Standards Code (Title 24, Part 11 code) commonly referred to as the CALGreen Code, is a statewide mandatory construction code developed and adopted by the California Building Standards Commission and the Department of Housing and Community Development. The CALGreen standards require new residential and commercial buildings to comply with mandatory measures under the topics of planning and design, energy efficiency, water efficiency/conservation, material conservation and resource efficiency, and environmental quality. CALGreen also provides voluntary tiers and measures that local governments may adopt that encourage or require additional measures in the five green building topics.

The proposed project would be designed with energy-efficient features, including insulated and glazed windows and low-E coating on windows, and will be built in compliance with the California Green Building Standards (CAL Green) Code (California Code of Regulations, Title 24, Part 11). Therefore, energy impacts would be less than significant.

**4.7 Geology and Soils**

Would the project:	Potentially Significant Impact	Less than Significant Impact with Mitigation Incorporated	Less than Significant Impact	No Impact
a) Directly or indirectly cause potential substantial adverse effects, including the risk of loss, injury, or death involving:				
i) Rupture of a known earthquake fault, as delineated on the most recent Alquist-Priolo Earthquake Fault Zoning Map issued by the State Geologist for the area or based on other substantial evidence of a known fault? Refer to Division of Mines and Geology Special Publication 42.			X	
ii) Strong seismic ground shaking?			X	
iii) Seismic-related ground failure, including liquefaction?			X	
iv) Landslides?				X
b) Result in substantial soil erosion or the loss of topsoil?			X	
c) Be located on a geologic unit or soil that is unstable, or that would become unstable as a result of the project, and potentially result in on or off-site landslide, lateral spreading, subsidence, liquefaction or collapse?			X	
d) Be located on expansive soil, as defined in Table 18-1 B of the Uniform Building Code (1994), creating substantial direct or indirect risks to life or property?			X	
e) Have soils incapable of adequately supporting the use of septic tanks or alternative waste water disposal systems where sewers are not available for the disposal of waste water?				X
f) Directly or indirectly destroy a unique paleontological resource or site or unique geologic feature?		X		

The information in this section is based on the following two technical reports:

- Geotechnical Engineering Investigation, Proposed Envision Mercedes-Benz of West Covina Automotive Dealership 1800 E Garvey Avenue South, West Covina, California. Prepared by



NorCal Engineering, dated May 17, 2024. A complete copy of this report is included as **Appendix E1** to this IS/MND.

- Paleontological Records Search for the Envision Motors Mercedes Project. Prepared by Natural History Museum of Los Angeles County, dated April 28, 2024. A complete copy of this report is included as **Appendix E2** to this IS/MND.

a) **Would the project directly or indirectly cause potential substantial adverse effects, including the risk of loss, injury, or death involving:**

- i) **Rupture of a known earthquake fault, as delineated on the most recent Alquist-Priolo Earthquake Fault Zoning Map issued by the State Geologist for the area or based on other substantial evidence of a known fault? Refer to Division of Mines and Geology Special Publication 42.**

No Impact

The Alquist-Priolo Zones Special Studies Act defines active faults as those that have experienced surface displacement or movement during the last 11,000 years. As shown in **Figure 4.7-1**, the nearest Alquist-Priolo Earthquake Fault Zone to the project site is along the Duarte Fault about four miles to the north. The nearest active fault to the project site is the Sierra Madre Fault Zone, also about four miles to the north, as shown in **Figure 4.7-2**. Project development would not exacerbate hazards related to surface rupture of a known active fault, and no impact would occur.

- ii) **Strong seismic ground shaking?**

Less than Significant Impact

As shown in **Figure 4.7-2** above, the project is located within a seismically active region of Southern California, and all structures in the region are susceptible to collapse, buckling of walls, and damage to foundations from strong ground shaking. The strength of earthquakes is measured in terms of *moment*, that is, the distance a fault moved multiplied by the force required to move it. Moment is described using the moment magnitude scale (M_w), where each one-point increase represents a 10-fold increase in moment (USGS, 2021). The Sierra Madre Fault Zone can produce a magnitude 7.0 earthquake (NorCal, 2024, p. 4).

Project design and construction would comply with the 2022 California Building Code (CBC), adopted as § 7-16 of the City of West Covina Municipal Code. The CBC contains provisions for earthquake safety based on factors including occupancy type, the types of soil and rock onsite, and the strength of ground motion with specified probability of occurring at the site. The geotechnical engineering investigation report sets forth seismic design parameters to be used in project design pursuant to CBC requirements (see **Appendix E1**). Thus, impacts from strong ground shaking would be less than significant and mitigation is not proposed.



Figure 4.7-1
ALQUIST PRIOLO FAULT ZONES



Path: \\GIS\enviro\Projects\7212_WCovina_Envision_Dealership_ISMND\04\7212_WCovina_4_7_Alquist_Priolo_2024_05_23.mxd
Service Layer Credits: Sources: Esri, HERE, Garmin, USGS, Intelmap, INCREMENT P, NRCan, Esri Japan, METI, Esri China (Hong Kong), Esri Korea, Esri (Thailand), NGCC, (c) OpenStreetMap contributors, and the GIS User Community, Seismic Hazards Program, California Geological Survey, California Department of Conservation, Sources: Esri, HERE, Garmin, Intelmap, INCREMENT P Corp., GEBCO, USGS, FAO, NPS, NRCAN, GeoBase, IGN, Kadaster NL, Ordnance Survey, Esri Japan, METI, Esri China (Hong Kong), (c) OpenStreetMap contributors, and the GIS User Community, CA Dept. of Conservation, September 2021; UltraSystems Environmental, Inc., 2024.

May 23, 2024

Scale: 1:95,040



0 0.75 1.5 Miles

0 0.75 1.5 Kilometers

Legend

- Project Location
- Alquist Priolo Special Study Zone Boundary
- Alquist Priolo Potentially Active Fault

**Envision Motors
West Covina Mercedes Benz**

Alquist Priolo Earthquake
Fault Zones





**Figure 4.7-2
REGIONALLY ACTIVE FAULTS**



Path: \\G:\envision\Projects\7212_WCovina_Envision_Dealership_ISMND\MXDs\7212_WCovina_4.7_Active_Faults_2024_05_23.mxd
Service Layer Credits: Sources: Esri, HERE, Garmin, USGS, Intermap, INCREMENT P, NRCan, Esri Japan, METI, Esri China (Hong Kong), Esri Korea, Esri (Thailand), NGCC, (c) OpenStreetMap contributors, and the GIS User Community. Sources: Esri, HERE, Garmin, Intermap, INCREMENT P Corp., GEBCO, USGS, FAO, NPS, NRCAN, GeoBase, IGN, Kadaster NL, Ordnance Survey, Esri Japan, METI, Esri China (Hong Kong), (c) OpenStreetMap contributors, and the GIS User Community; U.S./California Geological Survey, 2006; UltraSystems Environmental, Inc., 2024.

May 23, 2024

Scale: 1:95,040



0 0.75 1.5 Miles

0 0.75 1.5 Kilometers

Legend

- Project Location
- Active Faults
- Older Quaternary Faults
- Class B, Unspecified Quaternary, Undifferentiated Quaternary

**Envision Motors
West Covina Mercedes Benz**
Regionally Active Faults





iii) **Seismic-related ground failure, including liquefaction?**

Less than Significant Impact

General types of ground failures that might occur due to severe ground shaking typically include landslides, ground subsidence, ground lurching and shallow ground rupture. The probability of occurrence of each type of ground failure depends on the severity of the earthquake, distance from the faults, topography, subsoils and relatively shallow groundwater tables (approximately 50 feet or less below ground surface), in addition to other factors.

Liquefaction typically occurs when saturated or partially saturated soils behave like a liquid, due to losses in strength and stiffness in response to ground shaking. The project site is not in a zone of required investigation for liquefaction (see **Figure 4.7-3**).

Groundwater was not encountered in subsurface exploration of the project site to a depth of 20 feet below ground surface (bgs). A nearby groundwater monitoring well located approximately 1.5 miles to the west from the subject site noted a groundwater depth of 170 feet below ground surface last measured in July 2023 (NorCal, 2024, p. 6).

The subject site is not in an area of historic occurrence of liquefaction, or local geological, geotechnical and groundwater conditions to indicate a potential for permanent ground displacement. Thus, design of the proposed construction in conformance with the latest Building Code provisions for earthquake design is expected to minimize ground shaking hazards that are typical in Southern California (NorCal, 2024, p. 5). Impacts would be less than significant.

Landslides?

No Impact

The project site is flat; therefore, project development would not exacerbate landslide hazards and no impact would occur.



**Figure 4.7-3
LANDSLIDES AND LIQUEFACTION**



Path: \\Gissvrgis\Projects\7212_WCovina_Envision_Dealership_ISMND\MXDs\7212_WCovina_4_7_Landslides_Liquefaction_2024_05_24.mxd
Service Layer Credits: Sources: Esri, HERE, Garmin, USGS, Intermap, INCREMENT P, NRCan, Esri Japan, METI, Esri China (Hong Kong), Esri Korea, Esri (Thailand), NGCC, (c) OpenStreetMap contributors, and the GIS User Community. Sources: Esri, HERE, Garmin, Intermap, increment P Corp., GEBCO, USGS, FAO, NPS, NRCAN, GeoBase, IGN, Kadaster NL, Ordnance Survey, Esri Japan, METI, Esri China (Hong Kong), (c) OpenStreetMap contributors, and the GIS User Community. U.S./California Geological Survey, 2021-April 2022; UltraSystems Environmental, Inc., 2024.

May 24, 2024

Scale: 1:24,000



0 1,000 2,000 Feet

0 300 600 Meters

Legend



Project Boundary



Landslide Zone



Liquefaction Zone

**Envision Motors
West Covina Mercedes Benz**

Landslides and Liquefaction
Hazard Zones



UltraSystems
environmental management planning



b) Would the project result in substantial soil erosion or the loss of topsoil?

Less than Significant Impact

Construction

Erosion is the detaching of soil particles from the soil surface; sedimentation is the transport of soil offsite, such as by water. Site clearance, grading, and construction would disturb and expose large amounts of soil, leaving the soil vulnerable to erosion.

The project proponent is required by the California State Water Resources Control Board (SWRCB) to obtain coverage under a General Permit for Discharges of Storm Water Associated with Construction Activity (Construction General Permit Order 2022-0057-DWQ, as authorized by § 402 CWA, NPDES for projects which will disturb one or more acres of soil during construction). The Construction General Permit requires potential dischargers of pollutants into Waters of the U.S. to prepare a site-specific Stormwater Pollution Prevention Plan (SWPPP). The SWPPP prescribes several categories of best management practices (BMPs), including BMPs for erosion control, wind erosion control, sediment control, and tracking control (that is, tracking soil offsite by vehicles). Because the project is required by the SWRCB to comply with all applicable conditions of Construction General Permit Order 2022-0057-DWQ, impacts related to soil erosion during project construction would be less than significant.

Operation

As designed, the project would be developed with a mix of impervious surfaces, such as concrete and pavement, and grass/landscaped areas, including landscaping along the site boundary. This combination of impervious surfaces and landscaped areas would reduce the potential of the project for soil erosion to a negligible level during project operations. The Landscape Plan is shown in **Figure 3.4-7** and included in **Appendix A**. The project Low-Impact Development (LID) Plan also includes two treatment control BMPs, hydrodynamic separators and an infiltration basin, that would remove sediment from runoff before the runoff was discharged offsite (CDR, 2024b, p. 8).

With the implementation of soil erosion and sedimentation BMPs during the construction phase and the proposed combination of impervious and landscaped surfaces during the operational phase, the project would have less than significant impacts related to soil erosion or loss of topsoil and mitigation is not proposed.

c) Would the project be located on a geologic unit or soil that is unstable, or that would become unstable as a result of the project, and potentially result in on or off-site landslide, lateral spreading, subsidence, liquefaction or collapse?

Less than Significant Impact

The project site is underlain by fill soil consisting of brown, fine to medium grained, silty sand to depths ranging from 1.5 to 6.0 feet bgs, which is underlain by alluvium described as a brown, fine to medium grained, silty sand (NorCal 2024, pp. 2-3). Impacts related to liquefaction and landslides are discussed above in **Section 4.7 a)**.



Lateral Spreading

Lateral spreading is the downslope movement of surface sediment due to liquefaction in a subsurface layer. For the reasons discussed in **Section 4.7 a)** above, the potential for lateral spread on the project site would be less than significant (NorCal 2024, p. 6).

Collapsible Soils

Collapsible soils shrink upon being wetted and/or being subject to a load. The geotechnical engineering report for the project found that shallow soils onsite are not suitable for supporting the proposed building, and recommended removal of the existing fill soil plus soils to a depth of two feet below all proposed foundations (NorCal, 2024, p. 8). Project site preparation and grading would comply with recommendations of the geotechnical investigation report, and project development would not exacerbate hazards arising from collapsible soils.

Subsidence

The major cause of ground subsidence is the excessive withdrawal of groundwater. Soils with high silt or clay content are particularly susceptible to subsidence. The project site is not in an area of subsidence mapped by the USGS (USGS, 2024). The project site is over the Main San Gabriel Groundwater Basin. The Main Basin Watermaster (“Watermaster”) regulates groundwater extractions and recharge pursuant to two court judgments. The Watermaster establishes an operating safe yield of extractions and determines rights to extract water for each groundwater producer, each year. Producers who pump water exceeding their extraction rights are required to purchase imported water to recharge the groundwater basin, replacing the excess water they produced (Suburban Water Systems, 2021, p. 3-17). Therefore, ground subsidence in the project region due to excessive groundwater withdrawal is considered unlikely. Project development would not exacerbate hazards related to ground subsidence and impacts would be less than significant.

- d) Would the project be located on expansive soil, as defined in Table 18-1 B of the Uniform Building Code (1994), creating substantial direct or indirect risks to life or property?**

Less than Significant Impact

Expansive soils shrink and swell with changes in soil moisture. Soil moisture may change from landscape irrigation, rainfall, and utility leakage. A measurement of expansion index in one subsurface soil sample conducted as part of the geotechnical engineering investigation yielded an expansion index of 3, indicating very low expansion potential (NorCal, 2024, p. 25). Project development would not exacerbate hazards arising from expansive soils, and impacts would be less than significant.



- e) **Would the project have soils incapable of adequately supporting the use of septic tanks or alternative wastewater disposal systems where sewers are not available for the disposal of waste water?**

No Impact

The project site would connect to the City of West Covina's existing sewer system; therefore, the project would not use septic tanks or alternative wastewater disposal systems. Therefore, no impacts associated with septic tanks or alternative wastewater disposal systems would occur.

- f) **Would the project directly or indirectly destroy a unique paleontological resource or site or unique geologic feature?**

Less than Significant Impact with Mitigation Incorporated

The project site is underlain by the Younger undivided alluvial fan and valley deposits (Qyfa) (11,650 years before present [ybp] to present). This deposit consists of unconsolidated sand and dates to the Holocene period (11,650 years before present [ybp] to present) (Tan, 2000). Several paleontological resources have been discovered in the region. While no localities have been recorded within the project boundary itself, there are "fossil localities nearby from the same sedimentary deposits that occur in the proposed project area, either at surface or at depth" (Bell 2024:1). These resources are presented in **Table 4.7-2** below.

Table 4.7-2
FOSSIL LOCALITIES IN THE PROJECT REGION

Locality No.	Location	Depth	Formation	Taxa
LACM VP 2027	1600 block, Bridgen Rd., Pasadena	Unknown	Unknown formation (Pleistocene)	Mammoth (<i>Mammuthus</i>)
LACM VP 7701, 7702	Intersection of 26th St and Atlantic Blvd, Bell Gardens	30 feet bgs	Unknown formation (Pleistocene; silt)	Fish (<i>Gasterosteus</i>); Snake (<i>Colubridae</i>), Rodents (<i>Thomomys</i> , <i>Microtus</i> , <i>Reithrodontomys</i>); Rabbit (<i>Sylvilagus</i>)
LACM VP 3363	W of Monterey Pass Road in Coyote Pass; E of the Long Beach Freeway & S of the N boundary of Section 32; Monterey Park	Unknown	Unknown formation (Pleistocene; sand and silt)	Horse (<i>Equus</i>)
LACM VP 1728	W of intersection of English Rd & Peyton Dr, Chino	15-20 feet bgs	Unknown (light brown shale with interbeds of very coarse brown sand; Pleistocene)	Horse (<i>Equus</i>), camel (<i>Camelops</i>)

Source: Bell, 2024

Excavations or grading that extend into the uppermost layers of soil and deeper excavation into the late Pleistocene sediments in the proposed project area may encounter significant fossil vertebrate remains. Any substantial excavations below the uppermost layers should be closely monitored to



quickly and professionally collect any specimens. Grading and excavation activities associated with development of the proposed project would cause new subsurface disturbance and could result in the unanticipated discovery of paleontological resources, for which mitigation is required.

In the event of an unexpected discovery, implementation of mitigation measure **GEO-1** would ensure paleontological resources or unique geologic features are not significantly affected. Impacts in this regard would be mitigated to less than significant levels, with implementation of required mitigation measures.

Mitigation Measure

MM GEO-1 Prior to the issuance of the grading permit, the applicant shall provide a letter to the City of West Covina Planning Division, or designee, from a qualified paleontologist stating that the paleontologist has been retained to provide services for the project. The paleontologist shall develop, as needed, a Paleontological Resources Impact Mitigation Plan (PRIMP) to mitigate the potential impacts to unknown buried paleontological resources that may exist onsite for the review and approval by the City. The PRIMP shall require that the paleontologist perform paleontological monitoring of any ground disturbing activities within undisturbed native sediments during mass grading, site preparation, and underground utility installation. The project paleontologist may reevaluate the necessity for paleontological monitoring after 50 percent or greater of the excavations have been completed. In the event paleontological resources are encountered, ground-disturbing activity within 50 feet of the area of the discovery shall cease. The paleontologist shall examine the materials encountered, assess the nature and extent of the find, and recommend a course of action to further investigate and protect or recover and salvage those resources that have been encountered. Criteria for discard of specific fossil specimens will be made explicit. If the qualified paleontologist determines that impacts to a sample containing significant paleontological resources cannot be avoided by project planning, then recovery may be applied. Actions may include recovering a sample of the fossiliferous material prior to construction, monitoring work and halting construction if a significant fossil needs to be recovered, and/or cleaning, identifying, and cataloging specimens for curation and research purposes. Recovery, salvage and treatment shall be done at the Applicant's expense. All recovered and salvaged resources shall be prepared to the point of identification and permanent preservation by the paleontologist. Resources shall be identified and curated into an established accredited professional repository. The paleontologist shall have a repository agreement in hand prior to initiating recovery of the resource.

Level of Significance After Mitigation

With implementation of **MM GEO-1**, potential impacts to paleontological resources would be reduced to a less than significant level.



4.8 Greenhouse Gas Emissions

Would the project:	Potentially Significant Impact	Less than Significant Impact with Mitigation Incorporated	Less than Significant Impact	No Impact
a) Generate greenhouse gas emissions, either directly or indirectly, that may have a significant impact on the environment?			X	
b) Conflict with an applicable plan, policy or regulation adopted for the purpose of reducing the emissions of greenhouse gases?			X	

4.8.1 Background Information on Greenhouse Gas Emissions

Life on earth depends on energy coming from the sun. About half the light reaching Earth's atmosphere passes through the air and clouds to the surface, where it is absorbed and then radiated upward in the form of infrared heat. About 90 percent of this heat is then absorbed by carbon dioxide (CO₂) and other greenhouse gases (GHGs) and radiated back toward the surface, which is warmed to a life-supporting average of 59 degrees Fahrenheit (°F) (NASA, 2018).

Human activities are changing the natural greenhouse. Over the last century, the burning of fossil fuels such as coal and oil has increased the concentration of atmospheric CO₂. This happens because the coal or oil burning process combines carbon in the fuel with oxygen in the air to make CO₂. To a lesser extent, the clearing of land for agriculture, industry, and other human activities has increased concentrations of GHGs (NASA, 2018).

GHGs are defined under the California Global Warming Solutions Act of 2006 as CO₂, methane (CH₄), nitrous oxide (N₂O), hydrofluorocarbons (HFCs), perfluorocarbons (PFCs) and sulfur hexafluoride (SF₆) (AB 32, chapter 488). HFCs, PFCs, and SF₆ would not be emitted in significant amounts by the new activities in the proposed project, so they will not be discussed further.

Associated with each GHG species is a “global warming potential” (GWP), which is a value used to compare the abilities of different GHGs to trap heat in the atmosphere. GWPs are based on the heat-absorbing ability of each gas relative to that of CO₂, as well as the decay rate of each gas (the amount removed from the atmosphere over a given number of years). The GWPs of CO₂, CH₄ and N₂O are 1, 25 and 298, respectively (GMI, 2019). “Carbon dioxide equivalent” (CO₂e) emissions are calculated by weighting each GHG compound’s emissions by its GWP and then summing the products.

Carbon Dioxide (CO₂). Carbon dioxide is a colorless, odorless gas consisting of molecules made up of two oxygen atoms and one carbon atom. CO₂ is produced when an organic carbon compound (such as wood) or fossilized organic matter (such as coal, oil, or natural gas) is burned in the presence of oxygen. Since the industrial revolution began in the mid-1700s, industrial activities have increased in scale and distribution. Prior to the industrial revolution, CO₂ concentrations were stable at a range of 275 to 285 parts per million (ppm) (IPCC, 2007a). The National Oceanic and Atmospheric Administration’s Earth System Research Laboratory indicates that the global concentration of CO₂



was 419.3 ppm in 2023 (NOAA, 2024). These concentrations of CO₂ exceed by far the natural range over the last 650,000 years (180 to 300 ppm) as determined from ice cores.

Methane (CH₄). Methane is a colorless, odorless non-toxic gas consisting of molecules made up of four hydrogen atoms and one carbon atom. CH₄ is combustible, and is the main constituent of natural gas, a fossil fuel. CH₄ is released when organic matter decomposes in low oxygen environments. Natural sources include wetlands, swamps and marshes, termites, and oceans. Anthropogenic sources include the mining of fossil fuels and transportation of natural gas, digestive processes in ruminant animals such as cattle, rice paddies, and the buried waste in landfills. Over the last 50 years, human activities such as growing rice, raising cattle, using natural gas, and mining coal have added to the atmospheric concentration of CH₄. Other anthropogenic sources include fossil-fuel combustion and biomass burning.

Nitrous Oxide (N₂O). Nitrous oxide is a colorless, non-flammable gas with a sweetish odor, commonly known as “laughing gas,” and sometimes used as an anesthetic. N₂O is naturally produced in the oceans and in rainforests (USEPA, 2019b). Manmade sources of N₂O include the use of fertilizers in agriculture, nylon and nitric acid production, cars with catalytic converters and the burning of organic matter. Atmospheric concentrations of N₂O also began to rise at the beginning of the industrial revolution.

4.8.2 Regulatory Setting

GHGs are regulated at the national, state, and air basin level; each agency has a different degree of control. The United States Environmental Protection Agency (USEPA) regulates at the national level; the California Air Resources Board (ARB) regulates at the state level; and the South Coast Air Quality Management District (SCAQMD) regulates at the air basin level in the Envision Mercedes Benz Dealership project area.

4.8.2.1 Federal Regulations

The USEPA collects several types of GHG emissions data. These data help policy makers, businesses, and the USEPA track GHG emissions trends and identify opportunities for reducing emissions and increasing efficiency. The USEPA has been maintaining a national inventory of GHG emissions since 1990 and in 2009 established mandatory reporting of GHG emissions from large GHG emissions sources.

EPA is also obtaining GHG reductions through partnerships and initiatives, evaluating policy options, costs, and benefits, advancing the science, partnering internationally and with states, localities, and tribe, and helping communities adapt.

Corporate Average Fuel Economy (CAFE) Standards

In May 2010, the USEPA finalized the first-ever national GHG emissions standards under the Clean Air Act, and the National Highway Traffic Safety Administration (NHTSA) finalized Corporate Average Fuel Economy (CAFE) standards under the Energy Policy and Conservation Act (USEPA, 2022g). The CAFE Standards for model years 2017-2025 introduce new ways to comply, such as improving air conditioning efficiency and increasing production of electric and alternative fuel vehicles. Passenger cars and light-duty trucks are defined in the Code of Federal Regulations (CFR) under 49 CFR part 523. These definitions include two distinct “footprint” categories based on vehicle size, which determine the specific CAFE requirements for each vehicle. The required average fuel



economy for model years 2017-2025 is projected from the 2010 model year baseline. Looking ahead, CAFE Standards for model years 2027-2032 will see annual increases of 2% for passenger cars (model years 2027-2031) and 2% for light trucks (model years 2029-2031)(USDE, 2024).

Safer Affordable Fuel-Efficient (SAFE) Vehicles Rule

On September 27, 2019, the USEPA and the NHTSA published the Safer Affordable Fuel-Efficient (SAFE) Vehicles Rule Part One: One National Program (USDOT, 2022), revoked California's authority to set its own GHG emissions standards and set zero emission vehicle (ZEV) mandates in California. The loss of the ZEV sales requirements would likely result in additional gasoline-fueled vehicles being sold in the State and criteria pollutant emissions increasing. On April 30, 2020, USEPA and NHTSA issued the Final SAFE Rule (ARB, 2020), which relaxed the federal GHG emissions and CAFE standards and would probably have resulted in increased CO₂ emissions. However, this regulation was repealed on December 21, 2021 by the Biden administration (NHTSA, 2021).

State Regulations

Executive Order S 3-05

On June 1, 2005, the governor issued EO S 3-05, which set the following GHG emission reduction targets:

- By 2010, reduce GHG emissions to 2000 levels;
- By 2020, reduce GHG emissions to 1990 levels;
- By 2050, reduce GHG emissions to 80 percent below 1990 levels.

To meet these targets, the Climate Action Team (CAT)¹⁰ prepared a report to the Governor in 2006 that contains recommendations and strategies to help ensure that the targets in EO S-3-05 were met.

Assembly Bill 32 (AB 32)

In 2006, the California State Legislature enacted the California Global Warming Solutions Act of 2006, also known as AB 32. AB 32 focuses on reducing GHG emissions in California. GHGs, as defined under AB 32, include CO₂, CH₄, N₂O, HFCs, PFCs, and SF₆. AB 32 required that GHGs emitted in California be reduced to 1990 levels by the year 2020. The ARB is the state agency charged with monitoring and regulating sources of emissions of GHGs that cause global warming. AB 32 also required that by January 1, 2008, the ARB determine what the statewide GHG emissions level was in 1990, and that it had to approve a statewide GHG emissions limit, so it could be applied to the 2020 benchmark. The ARB approved a 1990 GHG emissions level of 427 million metric tons of CO₂e (MMTCO₂e), on December 6, 2007, in its Staff Report. Therefore, in 2020, emissions in California were required to be at or below 427 MMTCO₂e.

Under the "business as usual or (BAU)¹¹" scenario established in 2008, statewide emissions were increasing at a rate of approximately one percent per year, as noted below. It was estimated that the

¹⁰ The Climate Action Team (CAT) members are state agency secretaries and the heads of agencies, boards, and departments, led by the Secretary of the California Environmental Protection Agency (Cal/EPA). They coordinate statewide efforts to implement global warming emission reduction programs and the state's Climate Adaptation Strategy.

¹¹ A business-as-usual (BAU) scenario assumes that none of the Scoping Plan measures are implemented (ARB, 2024b).



2020 estimated BAU of 596 MMTCO₂e would have required a 28 percent reduction to reach the 1990 level of 427 MMTCO₂e.

As part of the 2014 update, the ARB revised the 2020 Statewide limit to 431 million MT of CO₂e, an approximately one percent increase from the original estimate. The 2020 business as usual forecast in the update is 509 million MT of CO₂e. The state would need to reduce those emissions by 15.3% to meet the 431 million MT of CO₂e 2020 limit.

Climate Change Scoping Plan

The first AB 32 Scoping Plan (ARB, 2008) contained the main strategies to achieve the 2020 emissions cap. The strategies included direct regulations, alternative compliance mechanisms, monetary and non-monetary incentives, voluntary actions, and market-based mechanisms such as a cap-and-trade system. In August 2011, the Scoping Plan was reapproved by the Board and included the Final Supplement to the Scoping Plan Functional Equivalent Document (ARB, 2011). The 2011 Scoping Plan expanded the list of nine Early Action Measures into a list of 39 Recommended Actions contained in Appendices C and E of the Plan. In May 2014, ARB developed, in collaboration with the CAT, the First Update to California's Climate Change Scoping Plan (Update) (ARB, 2014), which showed that California was on track to meet the near-term 2020 GHG limit and was well positioned to maintain and continue reductions beyond 2020 as required by AB 32. In November 2017, ARB published the 2017 Scoping Plan (ARB, 2017) which builds upon the former Scoping Plan and Update by outlining priorities and recommendations for the state to achieve its target of a 40 percent reduction in GHGs by 2030, compared to 1990 levels.

In December 2022, the ARB approved its Final 2022 Scoping Plan Update (ARB, 2022b), which adds carbon neutrality to the former Scoping Plan. The 2022 Plan identifies a technologically feasible, cost-effective path to reduce GHG emissions by 85 percent below 1990 levels and achieve carbon neutrality by 2045 or earlier. Through the lens of carbon neutrality, the 2022 Plan expands the scope to more meaningfully consider how our natural and working lands (NWL) contribute to our long-term climate goal through carbon capture. The 2022 Plan focuses on efforts to shift away from fossil fuels, resulting in a 94 percent decrease in liquid petroleum demand, a 71 percent decrease in smog-related pollutants, a job increase of 4 million, and \$200 billion of health cost savings for Californians (ARB, 2022b).

Renewables Portfolio Standard (Scoping Action E-3)

The California Energy Commission estimates that in 2000 about 12 percent of California's retail electric load was met with renewable resources. Renewable energy includes (but is not limited to) wind, solar, geothermal, small hydroelectric, biomass, anaerobic digestion, and landfill gas. California's current Renewables Portfolio Standard (RPS) was intended to increase that share to 33 percent by 2020. It was reported that in 2021, over 37 percent of California's retail electricity sales were provided by RPS-certified renewables (CEC, 2021). Increased use of renewables will decrease California's reliance on fossil fuels, thus reducing emissions of GHGs from the electricity sector. In October 2015, Governor Brown signed into law Senate Bill (SB) 350, which requires retail sellers and publicly owned utilities to procure 50 percent of their electricity from eligible renewable energy resources by 2030. Signed in 2018, SB 100 requires an increase in the RPS to 60 percent by 2030, along with a long-term goal of 100 percent of RPS and zero-carbon energy by 2045 (CEC, 2021).



Senate Bill 375 (SB 375)

Senate Bill (SB) 375 passed the Senate on August 30, 2008, and was signed by the governor on September 30, 2008. Per SB 375, the transportation sector is the largest contributor of GHG emissions and contributes approximately 45 percent of the GHG emissions in California, with automobiles and light trucks alone contributing almost 30 percent. SB 375 indicates that GHGs from automobiles and light trucks can be reduced by new vehicle technology. However, significant reductions from changed land use patterns and improved transportation also are necessary. SB 375 states, “Without improved land use and transportation policy, California will not be able to achieve the goals of AB 32.” SB 375 does the following: (1) requires metropolitan planning organizations to include sustainable community strategies (SCS) in their regional transportation plans for reducing GHG emissions, (2) aligns planning for transportation and housing, and (3) creates specified incentives for the implementation of the strategies.

Executive Order B-30-15

On April 29, 2015, Governor Brown issued EO B-30-15, which added an interim target of GHG emissions reductions to help ensure that the State meets its 80 percent reduction by 2050, as set in EO S-3-05. The interim target is to reduce GHG emissions by 40 percent by 2030. It also directs State agencies to update the Scoping Plan, update the Adaptation Strategy every three years, and take climate change into account in their planning and investment strategies. Additionally, it requires the State’s Five-Year Infrastructure Plan to take current and future climate change impacts into account in all infrastructure projects.

Title 24

Although not originally intended to reduce GHGs, California Code of Regulations Title 24 Part 6: California’s Building Energy Efficiency Standards for Residential and Nonresidential Buildings, was first adopted in 1978 in response to a legislative mandate to reduce California’s energy consumption. Energy-efficient buildings require less electricity; therefore, increased energy efficiency reduces fossil fuel consumption and decreases GHG emissions. The California Energy Commission updates the standards every three years, to allow consideration and possible incorporation of new energy-efficient technologies and methods. The 2016 standards became effective July 1, 2017. The 2019 Standards improve upon the 2016 Standards for new construction of, and additions and alterations to, residential and non-residential buildings. Buildings whose permit applications are dated on or after January 1, 2020, must comply with the 2019 Standards. The 2019 Standards are a major step towards meeting the Zero Net Energy goal by the year 2030 and are the last of three updates to move California towards achieving that goal. The 2022 standard, effective January 1, 2023, encourages efficient electric heat pumps, establishes electric-ready requirements for new homes, expands solar photovoltaic and battery storage standards, strengthens ventilation standards, and more (CEC, 2024).

South Coast Air Quality Management District (SCAQMD)

In the process of fulfilling its mandate to reduce local air pollution, the SCAQMD has promoted a few programs to combat climate change, e.g., energy conservation, low-carbon fuel technologies, renewable energy, vehicle miles traveled (VMT) reduction programs and market incentive programs.



Air Quality-Related Energy Policy

In 2011, the SCAQMD Board adopted an Air Quality-Related Energy Policy (SCAQMD, 2011) that integrates air quality, energy, and climate change issues in a coordinated and consolidated manner. The Energy Policy presents policies to guide and coordinate SCAQMD efforts and actions to support the policies.

4.8.2.2 Local Regulations

City of West Covina General Plan

The City of West Covina's 2016 General Plan (General Plan) and 2016 General Plan Update and Downtown Plan & Code Final EIR, which were adopted on December 20, 2016, includes policies and actions that guide the City to comply with requirements of AB 32, SB 375 and SCS with the goal of addressing issues that contribute to GHG emissions:

- **P1.1 & A1.1:** Allocate federal, state, and local transportation funds towards initiatives and infrastructure enhancements that encourage the use of alternative transportation methods such as walking, cycling, and public transit to lower emissions associated with vehicle travel.
- **P1.2 & A1.2:** Monitor and decrease air pollution emissions from City-owned vehicles and municipal operations and facilities by increasing the integration of alternative fuel, electric, and hybrid vehicles into City fleets.
- **P1.3 & A1.3:** Develop and implement a strategy to decrease greenhouse gas emissions within the Environmental Impact Report (approved alongside the West Covina General Plan). This plan aims to meet state requirements and align with the Regional Transportation Plan/Sustainable Community Strategy. The goal is to streamline approval processes, promote development, and enhance air quality.
- **P4.8 & A4.8:** Implement “green” streetscape elements to enhance aesthetics, reduce carbon emissions, and manage stormwater runoff. Within the green infrastructure framework, establish a plan to boost tree coverage along current main roads by 25 percent as a strategic goal.
- **P3.6 & A3.6:** Implement crucial land use adaptation strategies aimed at reducing greenhouse gas emissions, such as promoting transit-oriented infill development and offering incentives for high-performance buildings and infrastructure.

City of West Covin Energy Action Plan

The City of West Covina approved an Energy Action Plan (EAP) on September 6, 2011 which included conservation goals aimed at reducing greenhouse gas emissions within the community. These goals include:

- Exceed energy efficiency requirements set by the California Building Code for both new and existing municipal buildings and facilities.
- Offer online guidance and support accessible via the Internet to homeowners and builders, ensuring that compliance with updated Title 24 energy standards is as streamlined and effective as possible.



- Enhance the City's Residential Solar Power permit-waiver initiative to include additional alternative energy initiatives and consider fee modifications or rebates for local businesses and residents.
- Update the City's lighting standards which will prevent excessive and spill-over lighting.
- Create an ordinance to incentivize energy efficiency upgrades in existing buildings, encouraging real estate professionals and stakeholders to engage in financial incentives and energy retrofit opportunities before property sales.
- Incorporate energy and water conservation features in all significant renovation and development projects.
- Promote the use of pool covers and solar heating systems for residential swimming pools instead of traditional heating methods.
- Support water efficiency and minimize urban runoff by promoting natural drainage, drought-tolerant landscaping, and efficient irrigation systems in new development and major renovation projects.
- Facilitate collaboration between landscapers and residential solar power contractors to improve on shading design and reduce heat buildup in both existing and new homes.
- Expand the City's vehicle fleet with hybrid vehicles that are cleaner and more energy-efficient.
- Explore and implement additional energy conservation programs and measures beneficial to both the economy and environment of West Covina.

4.8.3 GHG Emissions

4.8.3.1 National Emissions

The United States is the second largest emitter of GHGs globally (behind China) and emitted approximately 5.3 billion MTCO_{2e} in 2020 (WRI, 2024), not including GHG absorbed by forests and agricultural land. The largest source of GHG in the United States (86.18 percent) is the energy sector (WRI, 2020). The agriculture sector accounted for 6.94 percent of GHG emissions in the United States, followed by industrial processes accounting for 4.42 percent of GHG emissions, and the waste sector accounted for 2.46 percent. Land use change and forestry in the United States is a carbon sink, sequestering 3.92 percent of GHG emissions (WRI, 2020).

4.8.3.2 State Emissions

In 2021, emissions from GHG emitting activities statewide were 381.3 million metric tons of carbon dioxide equivalent (MMTCO_{2e}), 35.3 MMTCO_{2e} lower than 2019 levels and 49.7 MMTCO_{2e} below the 2020 GHG target of 431 MMTCO_{2e}. The 2019 to 2020 decrease in emissions is likely due in large part to the impacts of the COVID-19 pandemic. Economic recovery from the pandemic may result in emissions increases over the next few years. The transportation sector showed the largest decline in emissions, 27 MMTCO_{2e} (16 percent) compared to 2019 (ARB, 2021).

GHG Thresholds

To provide guidance to local lead agencies on determining the significance of GHG emissions in their CEQA documents, the South Coast Air Quality Management District (SCAQMD) Board adopted an Interim CEQA GHG Significance Threshold for Stationary Sources, Rules, and Plans (SCAQMD, 2008).



The Interim Guidance uses a tiered approach to determining significance. Although this Interim Guidance was developed primarily to apply to stationary source industrial projects where the SCAQMD is the lead agency under CEQA, in the absence of more directly applicable policy, the SCAQMD's Interim Guidance is often used as general guidance by local agencies to address the long-term adverse impacts associated with global climate change. The guidance is described in detail in **Section 4.8.5**.

4.8.4 Impact Thresholds

The following thresholds of significance are based on criteria in Appendix G of the State CEQA Guidelines. A project has the potential to create a significant environmental impact if it would:

- Generate GHG emissions, either directly or indirectly, that may have a significant impact on the environment; or
- Conflict with an applicable plan, policy or regulation adopted for the purpose of reducing emissions of GHG.

4.8.5 Impact Analysis

4.8.5.1 Methodology

Short-term construction GHG emissions and long-term operational GHG emissions were assessed using the California Environmental Emissions Estimator Model (CalEEMod) Version 2022.1.1.25 (CAPCOA, 2023). This analysis focused upon emissions of CO₂, CH₄, and N₂O only. HFCs, PFCs, and SF₆ would be emitted in negligible quantities by the proposed project's sources, so they are not discussed further.

- a) Would the project generate GHG emissions, either directly or indirectly, that may have a significant impact on the environment?**

Less than Significant Impact

California has enacted several pieces of legislation that relate to GHG emissions and climate change, much of which set aggressive goals for GHG reductions within the state. Per Senate Bill 97, the California Natural Resources Agency adopted amendments to the CEQA Guidelines, which address the specific obligations of public agencies when analyzing GHG emissions under CEQA to determine a project's effects on the environment. However, neither a threshold of significance nor any specific mitigations are included or provided in these CEQA Guideline amendments.

GHG Significance Threshold

Neither the City of West Covina, the SCAQMD, nor the State CEQA Guidelines Amendments has adopted quantitative thresholds of significance for addressing a project's GHG emissions. Nonetheless, § 15064.4 of the CEQA Guidelines serves to assist lead agencies in determining the significance of the impacts of GHGs. As required in § 15064.4 of the CEQA Guidelines, this analysis includes an impact determination based on (1) an estimate of the amount of GHG emissions resulting from the proposed project; (2) a qualitative analysis or performance-based standards; (3) a quantification of the extent to which the proposed project increases GHG emissions as compared to the existing environmental setting; and (4) the extent to which the proposed project complies with



regulations or requirements adopted to implement a statewide, regional, or local plan for the reduction or mitigation of GHG emissions.

SCAQMD's guidance (SCAQMD, 2008) uses a tiered approach rather than a single numerical emissions threshold. If a project's GHG emissions "fail" the non-significance of a given tier, then one goes to the next tier.

The threshold selected for this analysis is Tier 3, which establishes a screening significance threshold level to determine significance using a 90 percent emission capture rate. For Tier 3, the SCAQMD estimated that at a threshold of approximately 3,000 metric tons CO₂e per year emissions would capture 90 percent of the GHG emissions from new commercial and residential projects. Although this is not a residential project, it is in a residential area and, as will be seen below, operational GHG emissions from the project will be negligible. Thus, this analysis uses 3,000 MTCO₂e per year as the significance threshold under the first impact criterion in **Section 4.8.3**.

Construction GHG Emissions

Construction is an episodic, temporary source of GHG emissions. Emissions are generally associated with the operation of construction equipment and the disposal of construction waste. To be consistent with the guidance from the SCAQMD for calculating emissions of criteria pollutants from construction activities, only GHG emissions from onsite construction activities and offsite hauling and construction worker commuting are considered as project-generated. As explained by the CAPCOA in its 2008 white paper (CAPCOA, 2008), the information needed to characterize GHG emissions from the manufacture, transport, and end-of-life of construction materials would be speculative at the CEQA analysis level. CEQA does not require an evaluation of speculative impacts (*CEQA Guidelines* § 15145). Therefore, the construction analysis does not consider such GHG emissions, but does consider non-speculative onsite construction activities, and offsite hauling, and construction worker trips. All GHG emissions are identified on an annual basis.

Estimated criteria pollutant emissions from the West Covina Envision Mercedes Benz Dealership Project's onsite and offsite project construction activities were calculated using CalEEMod, Version 2022.1.1.25, which was described in **Section 4.3.6**. The results of this analysis are presented in **Table 4.8-2**. The increase in GHG emissions from West Covina Envision Mercedes Benz Dealership Project's construction activities would be 314 metric tons in 2025 and 358.55 metric tons in 2026. Consistent with SCAQMD recommendations (SCAQMD, 2008, p. 3-10) and to ensure that construction emissions are assessed in a quantitative sense, construction GHG emissions have been amortized over a 30-year period. The amortized value, **22.42 MTCO₂e**, has been added to the West Covina Envision Mercedes Benz Dealership Project's annual operational GHG emissions. Modeling results are in **Appendix B**.



Table 4.8-2
PROJECT CONSTRUCTION-RELATED GHG EMISSIONS

Year/Phase	Annual Emissions (MT)			
	CO ₂	CH ₄	N ₂ O	CO ₂ e
2025	311.09	0.01	0.01	314.00
2026	355.90	0.01	0.01	358.55
Total	666.99	0.03	0.02	672.55

Operational GHG Emissions

The operational GHG emissions for the existing land uses, the Toyota dealership and Valero gas station, are shown in **Table 4.8-3**. Projected operational GHG emissions by only the proposed West Covina Envision Mercedes Benz Dealership Project is shown in **Table 4.8-4**. Net operational GHG emissions were calculated by comparing the GHG emissions from the present land uses with those of the proposed new land uses. The results of these calculations are presented in **Table 4.8-5**. The negative values show that the proposed project's operational GHG emissions from mobile sources and water demand will be less than those of the existing operations. The proposed project's operational GHG emissions from area sources, energy demand, and solid waste generation will increase slightly, and will include amortized construction emissions. However, the net change of total annual unmitigated emissions would be negative.¹²

Table 4.8-3
EXISTING OPERATIONAL GHG EMISSIONS

Emissions Source	Estimated Project Generated CO ₂ e Emissions (Metric Tons per Year)
Mobile (Motor Vehicles)	3,116.90
Area Sources	0.53
Energy Demand (Electricity & Natural Gas)	166.21
Water Demand	12.91
Solid Waste Generation	7.74
Total	3,304.29

¹² Calculations are provided in **Appendix B**.



Table 4.8-4
PROJECT OPERATIONAL GHG EMISSIONS

Emissions Source	Estimated Project Generated CO ₂ e Emissions (Metric Tons per Year)
Mobile (Motor Vehicles)	2,685.17
Area Sources	1.76
Energy Demand (Electricity & Natural Gas)	197.87
Water Demand	11.35
Solid Waste Generation	8.55
Construction Emissions ^a	22.42
Total	2,927

^a Total construction GHG emissions were amortized over 30 years and added to those resulting from the operation of the project.

Table 4.8-5
NET CHANGE OF OPERATIONAL GHG EMISSIONS

Emissions Source	Estimated Project Generated CO ₂ e Emissions (Metric Tons per Year)
Mobile (Motor Vehicles)	(431.73)
Area Sources	1.23
Energy Demand (Electricity & Natural Gas)	31.66
Water Demand	(1.55)
Solid Waste Generation	0.81
Construction Emissions ^a	22.42
Total	(377)

^a Total construction GHG emissions were amortized over 30 years and added to those resulting from the operation of the project.

Therefore, under the first significance criterion, GHG emissions would be less than significant, and no mitigation is necessary.

- b) **Would the project conflict with an applicable plan, policy or regulation adopted for the purpose of reducing the emissions of GHG?**



Less than Significant Impact

The City of West Covina has identified actions in the General Plan and EAP that the City can take to reduce GHG emissions from City operations and from development in its jurisdiction. While none of these policies and actions are directly relevant to the project, the project does not conflict with any of them and the impact would be less than significant. As was demonstrated in **Section 4.11**, the proposed project would have less than significant impacts in relation to consistency with local land use policies or regulations. Therefore, the project would not hinder the GHG emission reductions of the West Covina General Plan and EAP.

4.9 Hazards and Hazardous Materials

Would the project:	Potentially Significant Impact	Less than Significant Impact with Mitigation Incorporated	Less than Significant Impact	No Impact
a) Create a significant hazard to the public or the environment through the routine transport, use, or disposal of hazardous materials?		X		
b) Create a significant hazard to the public or the environment through reasonably foreseeable upset and accident conditions involving the release of hazardous materials into the environment?			X	
c) Emit hazardous emissions or handle hazardous or acutely hazardous materials, substances, or waste within one quarter mile of an existing or proposed school?		X		
d) Be located on a site which is included on a list of hazardous materials sites compiled pursuant to Government Code Section 65962.5 and, as a result, would it create a significant hazard to the public or the environment?			X	
e) For a project located within an airport land use plan or, where such a plan has not been adopted, within two miles of a public airport or public use airport, would the project result in a safety hazard or excessive noise for people residing or working in the project area?				X
f) Impair implementation of or physically interfere with an adopted emergency response plan or emergency evacuation plan?			X	
g) Expose people or structures, either directly or indirectly, to a significant risk of loss, injury or death involving wildland fires?				X

The analysis for this section is based on the following technical reports:

- Phase I Environmental Site Assessment (referred to as Phase I ESA), Envision Toyota, 1800 – 1820 East Garvey Avenue S, West Covina, California, by Celly Services, Inc. (CSI) dated June 12, 2024.

❖ SECTION 4.9 – HAZARDS AND HAZARDOUS MATERIALS ❖

- Asbestos Sampling and Testing Records for the Envision Toyota property completed by McKenna Environmental in October 2022.
- Phase I Environmental Site Assessment (referred to as Phase I ESA) for the Former Shell Station (Valero), 200 South Azusa Avenue, West Covina, California by CSI dated June 13, 2024.

Complete copies of these reports are included as **Appendices F1, F2, and F3**, respectively.

- a) **Would the project create a significant hazard to the public or the environment through the routine transport, use, or disposal of hazardous materials?**

Less than Significant with Mitigation Incorporated

Construction

Envision Toyota Property

The Phase I ESA for the Envision Toyota property (**Appendix F1**) did not identify any recognized environmental conditions (RECs) on the Envision Toyota property. An REC is defined as (1) the presence of hazardous substances or petroleum products in, on, or at the subject property due to a release to the environment; (2) the likely presence of hazardous substances or petroleum products in, on, or at the subject property due to release or likely release to the environment; or (3) the presence of hazardous substances or petroleum products in, on, or at the subject property under conditions that pose a material threat of a future release to the environment (CSI, 2024, p. i).

An historical REC (HREC) is a previous release of hazardous substances or petroleum products affecting the subject property that has been addressed to the satisfaction of the applicable regulatory authority or authorities and meeting unrestricted use criteria established by the applicable regulatory authority or authorities without subjecting the subject property to any controls (CSI, 2024, p.ii). The Phase I ESA for the Envision Toyota property identified four HRECs on the property:

- A 2,000-gallon gasoline underground storage tank (UST) was removed from the property in November 1986. Soil samples were collected following the removal did not contain any hydrocarbon contamination and is therefore an HREC.
- Five USTs, including a 2,000-gallon gasoline, a 500-gallon waste oil, a 500-gallon gear oil, a 1,000-gallon waste oil and split 1,500-gallon new oil/waste oil tanks were removed in August 1992. Trace concentrations of total recoverable petroleum hydrocarbons were detected under the gear oil and waste oil tanks. Elevated concentrations of petroleum hydrocarbons were detected under the removed gasoline UST. In October 1992, the contaminated soil associated with the gasoline tank was excavated to a depth of 23 feet. A mobile laboratory was on site to analyze samples until the non-detectable concentrations were obtained. A total of 117 tons of impacted soil were transported off-site for disposal. On 18 February 1993, the Los Angeles County Department of Public Works (LADPW) issued a case closure letter for the five former USTs. Based on the analytical results, the USTs are considered an HREC.

- In January 2019, borings were drilled at each of the 20 hydraulic lifts. No total petroleum hydrocarbons (TPH) or VOCs were detected in the analyzed samples indicating no release had occurred from the lifts and is therefore an HREC.
- In January 2019, four borings were drilled near the two clarifiers, one boring was drilled near the former waste oil tank excavation (located west of building B) and three additional borings were drilled west of Building B. Soil samples were collected at varying depths with 2 to 3 samples collected from each boring and analyzed. TPH and VOCs were not detected in any of the samples and California Administrative Manual (CAM) 17 metals were either not detected or below their total threshold limit concentration (TTLC) as well as below 10x the soluble threshold limit concentration (STLC) and is therefore considered an HREC.

The Phase I ESA did not recommend additional investigation of the site. Project development would not cause substantial hazards to people or the environment related to the HRECs, and impacts from construction of the project would be less than significant.

Sampling and testing of paint, drywall, siding, and flooring from the Envision Toyota property were tested for asbestos-containing materials (ACM) by McKenna Environmental in October 2022 (**Appendix F3**); no ACM were found. Demolition and clearance of the Envision Toyota property would not cause substantial hazards relating to ACM.

Former Shell Station (Valero)

The Phase I ESA for the former Shell Station, presently Valero, (**Appendix F3**) did not identify RECs on the property. The Phase I ESA identified two HRECs on the property:

- The LADPW had a permit on file for the removal of two 5,000-gallon steel, two 8,000-gallon steel and one 10,000-gallon fiberglass USTs from August 1986. Apparently, results had not been provided to the LADPW and they were requesting that just the laboratory report needed to be submitted. Attached to the letter was a letter report from Geo-Etka, Inc. dated 25 August 1986. Five soil samples had been collected by Geo-Etka and analyzed by Anaheim Test Laboratory. The samples were analyzed for total hydrocarbons, BTE&X (benzene, toluene, ethylbenzene, and xylenes; volatile organic compounds that are found in petroleum and petroleum products); and total lead. All analytes in the samples were below detectable limits and are therefore considered an HREC (CSI, 2024b, p. ii).
- In June 2004, piping and dispensers were upgraded. As part of the project, nine soil samples were collected beneath dispensers and piping. TPH-g (gas range) was detected in three samples at concentrations ranging from 0.44 mg/kg to 6.4 mg/kg. TPH-d (diesel range) was detected in two samples at 19,000 mg/kg and 48 mg/kg. methyl tert-butyl ether (MTBE, a gasoline oxygenate) was detected in two samples at 390 ug/kg and 45 ug/kg. Based on these results, the northwest dispenser islands, adjacent product trench and southern dispenser island were excavated on 18 June 2004 to remove the hydrocarbon impacted soil. Following the excavation of 146 tons of soil, confirmatory soil samples were collected. One sample contained TPH-g at 45 mg/kg, TPH-d at 5.7 mg/kg, MTBE at 1,100 ug/kg and tertiary butyl alcohol (TBA, a gasoline additive) at 7,300 ug/kg. One additional piping excavation sample contained TBA at 46 ug/kg. The soil was transported to TPS Technologies in Adelanto, CA for recycling. Based on the results, the LADPW requested a workplan to assess the vertical and lateral extent of the impacted soil in a letter from February 2007. No work was completed and in May 2013, the LADPW referred the case to the Regional Water Quality Control Board. The case was reviewed by the State Water Resources Control Board (SWRCB). SWRCB Order WQ 2014-0158-

UST, issued on 06 October 2014, indicates that the remaining contaminants falls under the Low Threat Closure Policy and as such requires the issuance of a uniform closure letter. On 03 March 2015, the Regional Water Quality Control Board issued a case closure letter. CSI compared the results of the impacted soil left in place to the current residential Environmental Screening Levels (ESLs), established by the Regional Water Quality Control Board in 2019. The concentrations of TPH-d, MTBE and TBA fall below residential screening levels and therefore are considered an HREC (CSI, 2024b, p. iii).

The Phase I ESA for the former Shell Station (presently Valero) noted that hydrocarbon impacted soil is present on the subject property and would be encountered during future grading operations. Impacted soil may also be encountered near the clarifier/hoists in the repair area. CSI recommends that any impacted soil that is encountered be segregated, sampled for waste profiling purposes, and transported to a licensed disposal or recycler facility (CSI, 2024b, p. iv). Impacts related to contaminated soil under the former Shell station (presently Valero) would be potentially significant without mitigation. Implementation of Mitigation Measure **HAZ-1** would reduce this impact to less than significant.

Mitigation Measure HAZ-1

During project site grading on the Valero gas station site the project proponent shall periodically have soil samples tested for TPH-g, TH-d, MTBE, and TBA. Upon finding samples with concentrations of any of the contaminants at concentrations over environmental screening levels (ESLs) for commercial use, the project proponent shall: halt grading operations; shall retain a qualified environmental assessor to conduct soil sampling and testing to determine the extent of soil contaminated with concentrations over ESLs; and shall then retain an environmental remediation company to remediate and/or remove the contaminated soil.

Level of Significance After Mitigation

Construction impacts regarding contaminants that may be present in soils onsite would be less than significant after implementation of mitigation measure **HAZ-1**.

Operation

Project operation would involve the use, storage, transport, and disposal of hazardous materials used in servicing cars, including solvents, lubricants, and degreasers, as well as other chemicals used in operation and maintenance of the building and landscaping such as cleansers, paints, fertilizers, and pesticides. These materials would be stored, handled, and disposed of in accordance with applicable regulations. Therefore, hazardous materials impacts from project operation would be less than significant.

- b) **Would the project create a significant hazard to the public or the environment through reasonably foreseeable upset and accident conditions involving the release of hazardous materials into the environment?**

Less than Significant Impact

Construction

Project construction would involve transport, storage, and use of chemical agents, solvents, paints, and other hazardous materials commonly associated with construction activities. Chemical transport, storage, and use would comply with Resource Conservation and Recovery Act (RCRA); Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA); Occupational Safety and Health Administration (OSHA); California hazardous waste control law (California Health and Safety Code, Division 20, Chapter 6.5, Hazardous Waste Control); California Division of Safety and Health (DOSH); SCAQMD; and Los Angeles County Department of Public Health (LADPH) requirements. The construction contractor would maintain equipment and supplies onsite for containing and cleaning up small spills of hazardous materials; and in the event of a release of hazardous materials of quantity and/or toxicity that onsite workers could not safely contain and clean up, would notify Los Angeles County Fire Department Health Hazardous Materials Division which manages the Los Angeles County Certified Unified Program Agency (CUPA)¹³. Therefore, compliance with applicable laws and regulations during project construction would reduce the potential for accidental releases of hazardous materials, and construction hazards impacts would be less than significant.

Operation

Project operation would involve the handling and storage of materials such as commercial cleansers, solvents and other janitorial or industrial-use materials, paints, and landscape fertilizers/pesticides during project operations. However, these materials would be stored, handled, and disposed of in accordance with applicable regulations and would not be stored in amounts that would create a significant hazard to the public or the environment through accidental release. The project would have a less than significant impact in this regard.

- c) **Would the project emit hazardous emissions or handle hazardous or acutely hazardous materials, substances, or waste within one-quarter mile of an existing or proposed school?**

Less than Significant Impact with Mitigation Incorporated

Options for Learning facility is within 0.25 mile of the project site. Although the project site contains a gas station that may contain contaminated soils, the project would implement **MM HAZ-1**, which would periodically test soils during construction and require remediation if required. As mentioned above, the project would adhere to applicable regulations regarding the transportation, handling, storage and use of hazardous materials during construction and operation. Therefore, there would be less than significant impacts with mitigation incorporated.

¹³ A Certified Unified Program Agency (CUPA) is a local agency certified by CalEPA to implement and enforce six state hazardous waste and hazardous materials regulatory management programs (CACUPA, 2024).

- d) **Would the project be located on a site which is included on a list of hazardous materials sites compiled pursuant to Government Code Section 65962.5 and, as a result, would it create a significant hazard to the public or the environment?**

Less than Significant Impact

Government Code § 65962.5 requires the Department of Toxic Substances Control (DTSC) to compile and update, at least annually, lists of the following:

- Hazardous waste and substances sites from the DTSC EnviroStor database.
- Leaking Underground Storage Tank (LUST) sites by county and fiscal year in the SWRCB GeoTracker database.
- Solid waste disposal sites identified by SWRCB with waste constituents above hazardous waste levels outside waste management units.
- SWRCB Cease and Desist Orders (CDOs), and Cleanup and Abatement Orders (CAOs).
- Hazardous waste facilities subject to corrective action pursuant to § 25187.5 of the Health and Safety Code, identified by DTSC.

These lists are collectively referred to as the “Cortese List.” The project site is not included on the Cortese List. HRECs identified during the two Phase I ESAs for the project site are described above in Section 4.9.a. Seven Cortese List sites, listed below, were identified within 0.5 mile of the project site (see **Figure 4.9-1**):

- SAS C-Stores, Inc. - West Covina Valero, 200 S. Azusa Avenue (on project site), GeoTracker leaking underground storage tank (LUST) site, gasoline release affected soil, case closed 2015.
- Penske Motor Group, Inc., 2010 East Garvey Avenue, GeoTracker LUST site, release of waste oil / motor / hydraulic / lubricating oil affected soil, case closed 2007
- Mobil #17-M51V, 201 S Azusa Avenue, GeoTracker LUST site, gasoline release affected soil, case closed 1986
- Mobil Oil Corp S/S #18-M51, 201 S Azusa Avenue, GeoTracker LUST site, contaminants and media affected unspecified, case closed 2018.
- Unocal # 4550, 245 Azusa Ave N, GeoTracker LUST cleanup site, diesel release affected soil, case closed 1996
- Arco #1276, 300 N Azusa Ave, GeoTracker LUST site, gasoline release, media affected unspecified, case closed 2010
- Arco #1276, 300 N Asuza Ave, GeoTracker LUST site, release of waste oil / motor / hydraulic / lubricating oil affected soil, case closed 1992

None of those sites are considered environmental concerns for the proposed project because all seven sites are closed cases, and due to the distances of six of the sites from the project site. Impacts would be less than significant.

- e) **For a project located within an airport land use plan or, where such a plan has not been adopted, within two miles of a public airport or public use airport, would the**

project result in a safety hazard or excessive noise for people residing or working in the project area?

No Impact

The nearest public-use airports to the project site are San Gabriel Valley Airport, approximately seven miles to the west at 4233 Santa Anita Avenue in the City of El Monte, and Brackett Field Airport, approximately seven miles to the east at 1615 McKinley Avenue in the City of La Verne (see **Figure 4.9-2**). The project site is outside of zones around San Gabriel Valley Airport and Brackett Field Airport where land uses are regulated to minimize aviation-related hazards to persons on the ground, and outside of noise compatibility contours for the airports (County of Los Angeles, 2024a). Project development would not cause airport-related hazards, or excessive noise, to persons at the project site. No impact would occur, and no mitigation is required.

**Figure 4.9-1
CORTESE LIST SITES**






Figure 4.9-2
AIRPORTS IN THE PROJECT REGION



- f) **Would the project impair implementation of or physically interfere with an adopted emergency response plan or emergency evacuation plan?**

Less than Significant Impact

Construction

The County of Los Angeles All-Hazards Mitigation Plan (AHMP) was adopted by the County of Los Angeles in 2020. As further detailed in **Section 4.17**, Transportation, project construction within the public right-of-way next to the project site could temporarily impact street traffic. Project construction could temporarily reduce the number of lanes or temporarily close a portion of East Garvey Avenue S. The city requires that projects conducting construction work in City roadway rights-of-way get Engineering Permit Application approved by the Engineering Division. Emergency access must be maintained. Compliance with city requirements for traffic management during construction in the public right-of-way would ensure that the project would have a less than significant impact.

Operation

Project operation would not block traffic on East Garvey Avenue S or other local roadways. The project would provide emergency access to the proposed buildings compliant with California Fire Code Section 503. Therefore, impacts would be less than significant.

- g) **Would the project expose people or structures, either directly or indirectly, to a significant risk of loss, injury or death involving wildland fires?**

No Impact

The California Department of Forestry and Fire Protection (CAL FIRE) developed Fire Hazard Severity Zones (FHSZ) for State Responsibility Areas (SRA) and Local Responsibility Areas (LRA).

Very High Fire Hazard Severity Zone (VHFHSZ) designation refers to either:

wildland areas supporting high-to-extreme fire behavior resulting from climax fuels typified by well-developed surface fuel profiles (e.g., mature chaparral) or forested systems where crown fire is likely. Additional site elements include steep and mixed topography and climate/fire weather patterns that include seasonal extreme weather conditions of strong winds and dry fuel moistures. Burn frequency is typically high and should be evidenced by numerous historical large fires in the area. Firebrands from both short- (<200 yards) and long-range sources are often abundant.

OR


developed/urban areas typically with high vegetation density (>70% cover) and associated high fuel continuity, allowing for frontal flame spread over much of the area to progress impeded by only isolated non-burnable fractions. Often where tree cover is abundant, these areas look very similar to adjacent wildland areas. Developed areas may have less vegetation cover

❖ SECTION 4.9 – HAZARDS AND HAZARDOUS MATERIALS ❖


and still be in this class when in the immediate vicinity (0.25 mile) of wildland areas zoned as Very High (see above).

The project site is not in or near a fire hazard severity zone (FHSZ) mapped by CAL FIRE within a State Responsibility Area (SRA, where the state is responsible for the costs of wildfire prevention and suppression) or within a Local Responsibility Area (LRA, where cities and counties are responsible)(see **Figures 4.9-3** and **4.9-4**, respectively). The project site is bounded on three sides by urban development; the nearest FHSZ to the site is in LRA approximately 1.6 miles to the southeast. Project development would not expose people or structures to substantial hazards from wildfire, and impacts would be less than significant.

Figure 4.9-3
FIRE HAZARD SEVERITY ZONES – STATE RESPONSIBILITY AREA




July 24, 2024





❖ SECTION 4.10 – HYDROLOGY AND WATER QUALITY ❖

Figure 4.9-4
FIRE HAZARD SEVERITY ZONES – LOCAL RESPONSIBILITY AREA



Path: \\Gissvringis\Projects\7212_WCovina_Envision_Dealership_ISMND\MXDs\7212_WCovina_4_20_Fire_Hazard_LRA_2024_05_24.mxd
Service Layer Credits: Sources: Esri, HERE, Garmin, USGS, Intermap, INCREMENT P, NRCan, Esri Japan, METI, Esri China (Hong Kong), Esri Korea, Esri (Thailand), NGCC, (c) OpenStreetMap contributors, and the GIS User Community; Cal Fire, June 2022; UltraSystems Environmental, Inc., 2024.

Scale: 1:30,000



0 1,250 2,500 Feet

0 300 600 Meters

Legend

● Project Location

Fire Hazard Severity Zones in LRA

Very High

Envision Motors West Covina Mercedes Benz

Fire Hazard Severity Zone
Local Responsibility Area (LRA)





4.10 Hydrology and Water Quality

Would the project:	Potentially Significant Impact	Less than Significant Impact with Mitigation Incorporated	Less than Significant Impact	No Impact
a) Violate any water quality standards or waste discharge requirements or otherwise substantially degrade surface or ground water quality?			X	
b) Substantially decrease groundwater supplies or interfere substantially with groundwater recharge such that the project may impede sustainable groundwater management of the basin?			X	
c) Substantially alter the existing drainage pattern of the site or area, including through the alteration of the course of a stream or river or through the addition of impervious surfaces, in a manner which would:			X	
i) result in substantial erosion or siltation on or offsite;			X	
ii) substantially increase the rate or amount of surface runoff in a manner which would result in flooding on- or offsite;			X	
iii) create or contribute runoff water which would exceed the capacity of existing or planned stormwater drainage systems or provide substantial additional sources of polluted runoff; or			X	
iv) impede or redirect flood flows?				X
d) In flood hazard, tsunami, or seiche zones, risk release of pollutants due to project inundation?				X
e) Conflict with or obstruct implementation of a water quality control plan or sustainable groundwater management plan?				X

The analysis for this section includes information from the following technical reports:

- Preliminary Hydrology Study for West Covina Mercedes, 1800 E Garvey Ave S, West Covina, CA 91791, APN: 8478-007-031, -025 prepared by Commercial Development Resources (CDR) on May 10, 2024 (CDR, 2024a) (see **Appendix G1**).



❖ SECTION 4.10 – HYDROLOGY AND WATER QUALITY ❖

- Low Impact Development (LID) Plan for Mercedes-Benz West Covina, 1800 East Garvey Ave South, West Covina, CA 91791, APN: 8478-007-031, 8478-007-025 prepared by CDR on May 10, 2024 (CDR, 2024b) (see **Appendix G2**).

a) Would the project violate any water quality standards or waste discharge requirements or otherwise substantially degrade surface or ground water quality?

Less than Significant Impact


The California State Water Resources Control Board requires its nine Regional Water Quality Control Boards (RWQCBs) to develop water quality control plans (Basin Plans) designed to preserve and enhance water quality and protect the beneficial uses of all regional waters. Specifically, Basin Plans designate beneficial uses for surface waters and groundwater, set narrative and numerical objectives that must be attained or maintained to protect the designated beneficial uses and conform to the State antidegradation policy, and describe implementation programs to protect all waters in the Regions (RWQCB, 2011). In addition, Basin Plans incorporate by reference all applicable State and Regional Board plans and policies, and other pertinent water quality policies and regulations. The project site is located within the Los Angeles River Watershed under the authority of the Los Angeles Regional Water Quality Control Board (Region 4)(CDR, 2024a, p. 2).

As shown in **Figure 4.10-1**, the project site is located within the Big Dalton Wash Subwatershed, which spans about 81 square miles in the northeast San Gabriel Valley and south-central San Gabriel Mountains. Walnut Creek, the major stream in the subwatershed, flows into the San Gabriel River in the city of Baldwin Park about 5.7 miles west of the project site. Existing site drainage flows to inlets for storm drains in Garvey Avenue and Azusa Avenue on the southeast and west sides of the project site, respectively; those storm drains discharge into Walnut Creek Channel (CDR, 2024a, p. 5). The storm drain in Azusa Avenue next to the project site is an 84-inch reinforced concrete pipe (LACPW, 2024). The LACFCD storm drain system eventually discharges all project site runoff to the Walnut Creek Channel and ultimately discharges to the Pacific Ocean (CDR, 2024a, p. 2).

Development of the project has the potential to result in two types of water quality impacts: (1) short-term impacts due to construction-related discharges; and (2) long-term impacts from operation. Temporary soil disturbance would occur during project construction, due to earth-moving activities such as excavation and trenching for foundations and utilities, soil compaction and moving, cut and fill activities, and grading. Disturbed soils are susceptible to high rates of erosion from wind and rain, resulting in sediment transport via stormwater runoff from the project area. Erosion and sedimentation affect water quality of receiving waters through interference with photosynthesis, oxygen exchange, and respiration, growth, and reproduction of aquatic species. Runoff from construction sites may include sediments and contaminants such as oils, fuels, paints, and solvents. Additionally, other pollutants such as nutrients, trace metals, and hydrocarbons can attach to sediment and be carried by stormwater into storm drains which discharge eventually to the Pacific Ocean.

Spills and mishandling of construction materials and waste may also potentially leave the project site and negatively impact water quality. The use of construction equipment and machinery may potentially result in contamination from petroleum products, hydraulic fluids, and heavy metals. Contamination from building preparation materials such as paints and solvents, and landscaping materials such as fertilizers, pesticides, and herbicides may also potentially degrade water quality during project construction. Trash and demolition debris may also be carried into storm drains and discharged into receiving waters.

Figure 4.10-1
USGS SURFACE WATERS AND WATERSHEDS





Construction Pollutants Control

The project proponent is required by the California State Water Resources Control Board (SWRCB) to obtain coverage under a General Permit for Discharges of Storm Water Associated with Construction Activity (Construction General Permit Order 2022-0057-DWQ, as authorized by § 402 CWA, NPDES for projects which will disturb one or more acres of soil during construction). The Construction General Permit requires potential dischargers of pollutants into Waters of the United States (WOUS) to prepare a site-specific Stormwater Pollution Prevention Plan (SWPPP), which establishes enforceable limits on discharges, requires effluent monitoring, designates reporting requirements, and requires construction best management practices (BMPs) to reduce or eliminate point and non-point source discharges of pollutants. Additionally, BMPs must be maintained, inspected before and after each precipitation event, and repaired or replaced as necessary. Because the project is required by the SWRCB to comply with all applicable conditions of Construction General Permit Order 2022-0057-DWQ, potential violations of water quality standards or waste discharge requirements during project construction would be less than significant.

Operational Pollutant Controls

The Municipal Stormwater Permit for the Coastal Watersheds of Los Angeles County (Los Angeles Regional Water Quality Control Board Order No. R4-2021-0105) regulates the discharge of pollutants into WOUS through stormwater and urban runoff conveyance systems, including flood control facilities. These conveyance systems are commonly referred to as municipal separate storm sewer systems (MS4s), or storm drains, and thus the Municipal Stormwater Permit is also referred to as an MS4 Permit.

Pursuant to the MS4 Permit, Principal Permittees (i.e., the Los Angeles County Flood Control District) and Co-Permittees (the City of West Covina is a Co-Permittee) must regulate discharges of pollutants in urban runoff from man-made sources into storm water conveyance systems within their jurisdiction.

New development and redevelopment can significantly increase pollutant loads in stormwater and urban runoff, because increased population density results in proportionately higher levels of vehicle emissions, vehicle maintenance wastes, municipal sewage wastes, household hazardous wastes, fertilizers, pet waste, trash, and other pollutants (RWQCB, 2021).

A Low-Impact Development Plan (LID Plan; CDR, 2024b) has been prepared for the proposed project site and is included herein as **Appendix G2**. The use of LID best management practices (BMPs) in project planning and design is intended to preserve a site's predevelopment hydrology by minimizing the loss of natural hydrologic processes such as infiltration, evapotranspiration, and runoff detention. LID BMPs try to offset these losses by introducing structural and non-structural design components that restore these water quality functions into the project's land plan (LACPW, 2014, p. 1-5).

The LID Plan incorporates BMPs in two categories, site design BMPs and treatment control BMPs. Site Design BMPs reduce or eliminate post project runoff. Two site design BMPs are prescribed for the project:

- **Minimize Impervious Area/Maximize Permeability:** landscape areas are incorporated wherever possible within the project.



❖ SECTION 4.10 – HYDROLOGY AND WATER QUALITY ❖

- Minimize Directly Connected Impervious Areas (DCIAs): DCIAs are minimized by limiting sidewalks and patios to the minimal necessary for proper use. Yard areas will be provided with only minimal concrete walkways to the door.

Treatment Control BMPs remove pollutants from contaminated stormwater before the water is discharged offsite. Two treatment control BMPs, hydrodynamic separators (two) and infiltration basin (one), are prescribed for the project. Hydrodynamic separators remove suspended solids, debris, floatables, and free-floating oil from stormwater (CDR, 2024a, p. 46). With implementation of construction and operational BMPs, potential impacts to water quality would be less than significant and mitigation is not proposed.

- b) Would the project substantially decrease groundwater supplies or interfere substantially with groundwater recharge such that the project may impede sustainable groundwater management of the basin?**

Less than Significant Impact

The project site is in the Main San Gabriel Valley Groundwater Basin. The Basin covers approximately 255 square miles underlying most of the San Gabriel Valley (see **Figure 4.10-2**). The project site is within the service area of Suburban Water Systems (Suburban). Suburban's water supplies consist of groundwater from the Main San Gabriel Basin and the Central Subbasin of the Coastal Plain of Los Angeles Groundwater Basin; water imported from northern California and the Colorado River; and recycled water purchased from the Upper San Gabriel Valley Municipal Water District. Groundwater is forecast to comprise about 54 percent of Suburban's water supplies over the 2025-2045 period (Suburban, 2021, pp. 3-1 and 3-30).

The project proposes installation of an underground stormwater detention chamber that would have capacity for an 85th-percentile, 24-hour storm (that is, a 24-hour storm more intense than 85 percent of the 24-hour storms in the area). The detention chamber, plus a gravel pit the chamber would be installed in, would have total capacity of 11,203 cubic feet or 83,798 gallons. Water within the detention chamber would infiltrate into soil within 48 hours (CDR, 2024a, p. 28). Project development would not cause a substantial adverse impact to groundwater supplies or groundwater recharge, and impacts would be less than significant.

- c) Would the project substantially alter the existing drainage pattern of the site or area, including through the alteration of the course of a stream or river or through the addition of impervious surfaces, in a manner which would:**

- i) Result in substantial erosion or siltation on or offsite;**


Less Than Significant Impact

The project site is relatively flat, with elevations ranging from approximately 442 to 456 feet above mean sea level (amsl) [Google Earth Pro, 2024]. There is no evidence that ephemeral, intermittent, or perennial streams or rivers occur in the Biological Study Area (BSA). As detailed in Section **4.10 a)**, the project owner would be required to develop a SWPPP by a certified qualified SWPPP developer. The required SWPPP would be project specific and would prescribe site specific stormwater BMPs which would be intended to minimize or avoid having soil leave the project site, through either stormwater or wind, and thus minimize or avoid soil erosion onsite and siltation in receiving waters.




❖ SECTION 4.10 – HYDROLOGY AND WATER QUALITY ❖

**Figure 4.10-2
GROUNDWATER BASINS MAP**



Path: \\Gissrvr\gis\Projects\7212_WCovina_Envision_Dealership_ISMND\MXDs\7212_WCovina_4_10_Groundwater_Basins_Recharge_2024_05_24.mxd
Service Layer Credits: Sources: Esri, HERE, Garmin, USGS, Intermap, INCREMENT P, NRCan, Esri Japan, METI, Esri China (Hong Kong), Esri Korea, Esri (Thailand), NGCC, (c) OpenStreetMap contributors, and the GIS User Community, Esri, HERE, Garmin, (c) OpenStreetMap contributors, and the GIS user community, Sources: Esri, HERE, Garmin, Intermap, increment P Corp., GEBCO, USGS, FAO, NPS, NRCAN, GeoBase, IGN, Kadaster NL, Ordnance Survey, Esri Japan, METI, Esri China (Hong Kong), (c) OpenStreetMap contributors, and the GIS User Community; California Department of Water Resources 2021-(Bulletin 118, 2021); UltraSystems Environmental, Inc., 2024.

May 24, 2024





❖ SECTION 4.10 – HYDROLOGY AND WATER QUALITY ❖

With implementation of a project specific SWPPP and proper maintenance and replacement of required stormwater BMPs (as necessary), potential impacts resulting in substantial erosion or siltation on- or offsite would be minimized or avoided, and impacts would be less than significant. No mitigation is proposed.

Construction

As described in **Section 4.10 a)**, temporary soil disturbance would occur during project construction, due to earth-moving activities such as excavation and trenching for foundations and utilities, soil compaction and moving, cut and fill activities, and grading. Disturbed soils are susceptible to high rates of erosion from wind and rain, resulting in sediment transport via stormwater runoff from the project area.

Implementation of the required SWPPP BMPs, including installation, maintenance, and replacement of BMPs, as discussed in **Section 4.10 a)**, would minimize or avoid potential impacts resulting from on- or offsite erosion and siltation impacts to a level that is less than significant.

Operation

As detailed in **Section 4.10 a)**, the LID BMPs proposed as part of project design would minimize or avoid on- or offsite erosion and siltation by a combination of maintaining drainage patterns, installation of landscaping, and installation of hydrodynamic separators and a detention basin, which would prevent erosion and prevent siltation-laden stormwater from leaving the site. Applicable regulations (e.g., the MS4 permit, and installation of LID BMPs, including site design and infiltration BMPs), would limit pollutant discharges from development of the project. The project's adherence to existing requirements would reduce erosion and siltation during operation; therefore, impacts resulting from operation of the project would be less than significant.

- ii) **Substantially increase the rate or amount of surface runoff in a manner which would result in flooding on- or offsite;**
- iii) **Create or contribute runoff water which would exceed the capacity of existing or planned stormwater drainage systems or provide substantial additional sources of polluted runoff?**

Less than Significant Impact

The proposed project site plan is divided into 15 drainage areas (DAs). Seven DAs are comprised of asphalt concrete (ac) pavement, concrete hardscape and commercial landscaping. Runoff from these drainage areas will sheet flow to a proposed curb and gutter before being routed to an onsite drainage basin. Two DAs are comprised of roof, ac pavement, commercial landscaping, and concrete hardscape runoff. Runoff from these drainage areas will sheet flow to a proposed area drain to be routed to the onsite storm drain network. Three DAs are comprised of roof, concrete hardscape, ac pavement, and commercial landscaping runoff. Runoff from these drainage areas will sheet flow to a curb and gutter to be routed to catch basin and the onsite drainage network. Three DAs are comprised of ac pavement, concrete hardscape, and commercial landscaping runoff. Runoff from these areas will sheet flow to onsite trench drains before entering the onsite storm drainage network (CDR, 2024b, p. 5). Peak stormwater flow rates in cubic feet per second are listed below in **Table 4.10-1**.



Table 4.10-1
HYDROLOGY ANALYSIS SUMMARY FOR EXISTING AND PROPOSED CONDITIONS

Condition	Area, acres	% Impervious	Cubic feet per second			
			Q ₂ ¹	Q ₁₀	Q ₅₀	Q ₁₀₀
Existing	3.547	96%	3.84	8.35	12.15	14.27
Proposed	3.547	94%	4.87	9.54	13.42	15.07
% Change	0	-2%	+27%	+14%	+10%	+6%

¹ Q₂ is the peak stormwater flow rate from a two-year, 24-hour storm; that is, the storm intensity likely to recur once every two years on average, with a duration of 24 hours.

Source: CDR 2024a

The project site stormwater runoff will be pre-treated via two hydrodynamic separators and will be detained for onsite infiltration via a detention tank (CDR, 2024b, p. 6). The conditions after entering the public storm drain system will remain unchanged from the existing conditions.

Therefore, upon adherence to existing state water quality requirements, including MS4 requirements, the proposed project would minimize or avoid causing a substantial increase in the rate or amount of surface runoff in a manner which would: (1) result in flooding on- or offsite; (2) would not create or contribute runoff water which would exceed the capacity of existing or planned stormwater drainage systems, or provide substantial additional sources of polluted runoff; or (3) create or contribute runoff water which would exceed the capacity of existing or planned stormwater drainage systems or provide substantial additional sources of polluted runoff. Impacts would be less than significant, and no mitigation is proposed.

iv) Impede or redirect flood flows?

No Impact

The project site is in flood hazard zone X, that is, in a 500-year flood zone; or a 100-year flood zone with average depths less than one foot or drainage area less than one square mile; and areas protected by levees from 100-year floods (FEMA, 2024); see **Figure 4.10-3**. The project site is outside of 100-year flood zones, and project development would not impede or redirect flood flows. No impact would occur, and mitigation is not required.

d) In flood hazard, tsunami, or seiche zones, would the project risk release of pollutants due to project inundation?

No Impact

The project site is in the dam inundation area of Puddingstone Dam, which is about six miles east of the project site (DWR, 2024a). The project site is approximately 36 miles inland from the Pacific Ocean and is not in a tsunami inundation zone. A seiche is a surface wave created when an inland water body is shaken, usually by an earthquake. No waterbodies are close enough to the project site to pose a flood hazard to the site due to a seiche.

The proposed project would not be at risk of inundation by flood hazards, tsunami, or seiche, and would therefore not be at risk of release of pollutants due to inundation. No impact would occur, and mitigation is not required.



❖ SECTION 4.10 – HYDROLOGY AND WATER QUALITY ❖

**Figure 4.10-3
FEMA FLOOD INSURANCE RATE MAP**



**Envision Motors
West Covina Mercedes Benz**

FEMA FIRM Map



- e) **Would the project conflict with or obstruct implementation of a water quality control plan or sustainable groundwater management plan?**



❖ SECTION 4.10 – HYDROLOGY AND WATER QUALITY ❖

No Impact

As discussed in **Section 4.10 a)**, the proposed project would comply with the Construction General Permit by developing and implementing a site-specific SWPPP and construction stormwater BMPs throughout the construction phase. The proposed project would also comply with the MS4 Permit by incorporating LID BMPs into project design, which would avoid or minimize the amount and type of pollutants leaving the project, entering receiving waters, and impacting water quality and beneficial uses defined for these waters by the Basin Plan (RWQCB, 2021). In addition, the LID BMPs would allow stormwater infiltration into the local aquifer, similar to existing conditions and minimize or avoid impacts to groundwater quality. The Main San Gabriel Valley Groundwater Basin is not subject to a groundwater sustainability plan (DWR, 2024b), and project development would not cause adverse impacts to such a plan.



4.11 Land Use and Planning

Would the project:	Potentially Significant Impact	Less than Significant Impact with Mitigation Incorporated	Less than Significant Impact	No Impact
a) Physically divide an established community?				X
b) Cause a significant environmental impact due to a conflict with any land use plan, policy, or regulation adopted for the purpose of avoiding or mitigating an environmental effect?			X	

a) Would the project physically divide an established community?

No Impact

The project site consists of an existing car dealership and gas station. The project would not expand into surrounding rights-of-way (ROWs) or surrounding properties. Therefore, there would be no impact.


b) Would the project cause a significant environmental impact due to a conflict with any land use plan, policy, or regulation adopted for the purpose of avoiding or mitigating an environmental effect?

Less than Significant Impact

As shown in **Figures 4.11-1** and **4.11-2** below, the project site has a General Plan land use designation of Commercial (C) and zoning designations of Service Commercial (S-C) and Neighborhood Commercial (N-C) (City of West Covina, 2024). Commercial land uses could be developed but not limited to automobile dealerships and retail stores (City of West Covina, 2016, p. 33). The purpose of the service-commercial (S-C) zone is to classify and set standards for those retail and service commercial, recreational, and business office land uses which by their nature are of a relative high intensity; are unique in that their success depends upon direct motorist exposure and excellent access; require special traffic circulation patterns that will not unduly restrict rapid traffic flow and extraordinary physical treatments in order to create compatibility with adjacent zoning and the development thereon. The purpose of the neighborhood-commercial (N-C) zone is to classify and set standards for those retail and service commercial uses which by their nature are of moderate intensity; are necessary in order to provide convenient daily shopping facilities to residential home and apartment dwellers; and are generally adjacent to or within close proximity to residential zoning or development and, therefore, require extraordinary physical treatment in order to guarantee compatibility with and protection to surrounding properties and their values (City of West Covina Municipal Code, 2024).



Figure 4.11-1
GENERAL PLAN LAND USE DESIGNATION



Sources: City of West Covina, 2016-2021.




Envision Motors
West Covina Mercedes Benz

General Plan Land Use Designation



**Figure 4.11-2
ZONING DESIGNATION**



Sources: City of West Covina, August 22, 2023.



Envision Motors
West Covina Mercedes Benz
Zoning Designation



❖ SECTION 4.11 – LAND USE AND PLANNING ❖

As mentioned above, the project site consists of a car dealership and a gas station. The car dealership is zoned S-C and the gas station is zoned N-C. The Project Applicant requests a zoning amendment to change the portion of the site zoned as N-C to S-C. With the approval of the zoning amendment, the project would be consistent with the General Plan land use and zoning designations of the project site.

A consistency analysis of the proposed project with relevant City of West Covina General Plan land use policies and actions is provided below in **Table 4.11-1**.

Table 4.11-1
CONSISTENCY ANALYSIS: PROPOSED PROJECT COMPARED TO APPLICABLE CITY OF WEST COVINA GENERAL PLAN LAND USE, POLICIES AND ACTIONS

Policies and Actions	Consistency Analysis
Policy 3.3: New growth will complete, enhance, and reinforce the form and character of the unique West Covina neighborhoods, districts, and corridors.	
Action 3.3: Adjust regulations for the neighborhoods, districts and corridors to reflect the nature of intended change	Consistent: The proposed project would allow the city to develop a luxury car dealership with high-quality materials that would strengthen the City's identity as a regional commercial supplier. The project requires an adjustment in regulations with a zoning amendment to allow the development of the project. With approval of the zoning amendment, the project would be consistent with this policy and action.

Source: City of West Covina, 2016, p. 55

As detailed above, with the approval of the zoning amendment, the project would result in less than significant impacts regarding applicable land use and zoning regulations.



4.12 Mineral Resources

Would the project:	Potentially Significant Impact	Less than Significant Impact with Mitigation Incorporated	Less than Significant Impact	No Impact
a) Result in the loss of availability of a known mineral resource that would be of value to the region and the residents of the state?				X
b) Result in the loss of availability of a locally-important mineral resource recovery site delineated on a local general plan, specific plan or other land use plan?				X

a) **Would the project result in the loss of availability of a known mineral resource that would be of value to the region and the residents of the state?**

and

b) **Would the project result in the loss of availability of a locally important mineral resource recovery site delineated on a local general plan, specific plan, or other land use plan?**

No Impact

The project site is mapped as Mineral Resource Zone 3 (MRZ-3) by the California Geological Survey (CGS) as shown on **Figure 4.12-1**. The MRZ-3 is described as areas containing mineral deposits and the significance of these deposits can't be determined from available data (Miller, Russel V., 1994). Additionally, the project site is currently developed, is not zoned for mineral excavation, and is not compatible for mineral excavation given the surrounding land uses. Therefore, the project would not impact mineral resources on the project site.


The nearest active mine to the project site mapped by the Division of Mines Reclamation (DMR) is the Olive Pit Mine (Mine ID 91-19-0052), located approximately two miles to the northwest at 4407 Azusa Canyon Road, City of Irwindale. This is an open pit sand and gravel mine and the lead agency is the City of Irwindale (DMR, 2024).

As shown on **Figure 4.12-2**, The nearest active oil and gas well is located approximately 3.5 miles to the southwest of the project site. **Figure 4.12-3** shows the closest active geothermal well is located 35 miles to the east.

The project site is surrounded by commercial development and rights-of-way. Thus, any aggregate onsite is unavailable for mining. Given the distance of active mines, oil wells, and geothermal wells from the project site, project development would not cause a loss of availability of known mineral resources valuable to the region, and no impact would occur. Furthermore, the proposed project would not result in the loss of availability of a locally important mineral resource recovery site delineated on a local general plan, specific plan, or other land use plan. No impact would occur.



Figure 4.12-1
DESIGNATED MINERAL RESOURCE ZONE





**Figure 4.12-2
OIL AND GAS WELLS AND FIELDS**



Path: \\Gis\enviro\Projects\7212_WCovina_Envision_Dealership_ISMIND\UXDn\7212_WCovina_4_12_Oil_Gas_2024_05_24.mxd
Service Layer Credits: Sources: Esri, HERE, Garmin, USGS, Intermap, INCREMENT P, NRCan, Esri Japan, METI, Esri China (Hong Kong), Esri Korea, Esri (Thailand), NGCC,
(c) OpenStreetMap contributors, and the GIS User Community; CalGEM WellSTAR 2021; UltraSystems Environmental, Inc., 2024

May 24, 2024

Scale: 1:95,040



0 0.75 1.5 Miles

0 0.75 1.5 Kilometers

Legend

- Project Location
- Oil and Gas Field
- Oil and Gas Well Status:
 - Active
 - Idle
 - Plugged

**Envision Motors
West Covina Mercedes Benz**

Oil & Gas Wells
and Fields



**Figure 4.12-3
GEOTHERMAL WELLS**



Scale: 1:950,400



0 7.5 15 Miles

0 7.5 15 Kilometers

Legend

- Project Location
- County Boundary
- Geothermal Well Status:**
 - Active
 - Idle

**Envision Motors
West Covina Mercedes Benz**

Geothermal Wells





4.13 Noise

Would the project result in:	Potentially Significant Impact	Less than Significant Impact with Mitigation Incorporated	Less than Significant Impact	No Impact
a) Generation of a substantial temporary or permanent increase in ambient noise levels in the vicinity of the project in excess of standards established in the local general plan or noise ordinance, or applicable standards of other agencies?			X	
b) Generation of excessive groundborne vibration or groundborne noise levels?			X	
c) For a project located within the vicinity of a private airstrip or an airport land use plan or, where such a plan has not been adopted, within two miles of a public airport or public use airport, would the project expose people residing or working in the project area to excessive noise levels?				X

4.13.1 Characteristics of Sound

Sound is a pressure wave transmitted through the air. It is described in terms of loudness or amplitude (measured in decibels), frequency or pitch (measured in hertz or cycles per second), and duration (measured in seconds or minutes). The decibel (dB) scale is a logarithmic scale that describes the physical intensity of the pressure vibrations that make up any sound. The pitch of the sound is related to the frequency of the pressure vibration. Because the human ear is not equally sensitive to all frequencies, a special frequency-dependent rating scale is used to relate noise to human sensitivity. The A-weighted decibel scale (dBA) provides this compensation by discriminating against upper and lower frequencies in a manner approximating the sensitivity of the human ear. The scale is based on a reference pressure level of 20 micropascals (zero dBA). The scale ranges from zero (for the average least perceptible sound) to about 130 (for the average human pain level).

4.13.2 Noise Measurement Scales

Several rating scales have been developed to analyze adverse effects of community noise on people. Since environmental noise fluctuates over time, these scales consider that the effect of noise on people depends largely upon the total acoustical energy content of the noise, as well as the time of day when the noise occurs. Those that are applicable to this analysis are as follows:

- L_{eq} , the equivalent noise level, is an average of sound level over a defined time period (such as 1 minute, 15 minutes, 1 hour or 24 hours). Thus, the L_{eq} of a time-varying noise and that of a steady noise are the same if they deliver the same acoustic energy to the ear during exposure.
- L_{90} is a noise level that is exceeded 90 percent of the time at a given location; it is often used as a measure of “background” noise.



- $L_{\max}$ is the root mean square (RMS) maximum noise level during the measurement interval. This measurement is calculated by taking the RMS of all peak noise levels within the sampling interval. $L_{\max}$ is distinct from the peak noise level, which only includes the single highest measurement within a measurement interval.
- CNEL, the Community Noise Equivalent Level, is a 24-hour average L_{eq} with a 4.77-dBA “penalty” added to noise during the hours of 7:00 p.m. to 10:00 p.m., and a 10-dBA penalty added to noise during the hours of 10:00 p.m. to 7:00 a.m. to account for noise sensitivity in the evening and nighttime (Hendriks, 2013). The logarithmic effect of these additions is that a 60-dBA 24-hour L_{eq} would result in a calculation of 66.7 dBA CNEL.
- L_{dn} , the day-night average noise, is a 24-hour average L_{eq} with an additional 10-dBA “penalty” added to noise that occurs between 10:00 p.m. and 7:00 a.m. The L_{dn} metric yields values within 1 dBA of the CNEL metric. As a matter of practice, L_{dn} and CNEL values are considered to be equivalent and are treated as such in this assessment.

4.13.3 Existing Noise

The City of West Covina’s General Plan does not explicitly define sensitive receivers. In this document, sensitive receivers are defined as locations where human populations (especially children, senior citizens, and sick persons) are present, and where there is a reasonable expectation of lower levels of human exposure to noise. Sensitive receivers located within the City of West Covina include residential uses, schools, hospitals, churches, and parks. Additionally, the City’s Municipal Code has applicable noise standards in regard to construction noise, interior noise, and exterior noise (City of West Covina Municipal Code, 2023). The closest sensitive receivers to the project site include the single-family residential neighborhood directly south of the project site, and the single-family homes and Options For Learning childcare facility west of the project site (Google Earth Pro, 2024). Sensitive receivers are summarized in **Table 4.13-1**, while **Figure 4.13-1** shows their locations.

Table 4.13-1
SENSITIVE RECEIVERS IN PROJECT AREA

Description	Location	Distance From Site Boundary (feet) ^a	Nearest Ambient Sampling Point ^b
Single-family residence	220 South Azusa Avenue	198	1
Options For Learning	203 South Azusa Avenue	319	2
Single-family residence	132 South Homerest Avenue	339	3
Single-family residence	1828 East Norma Avenue	237	4

^aThese distances were not used for the noise or vibration calculations.

^bSee **Figure 4.13-2** for locations of ambient noise sampling points.




Figure 4.13-1
SENSITIVE RECEIVERS NEAR THE PROJECT SITE



Path: \\GIS\SVR\gis\Projects\212_WCovina_Environ_Dealership_JSMIND\MAXDeV212_WCovina_4_13_Noise_Receivers_2024_06_17.mxd
Service Layer Credits: Sources: Esri, HERE, Garmin, USGS, Intermap, INCREMENT P, NRCan, Esri Japan, METI, Esri China (Hong Kong), Esri Korea, Esri (Thailand), NGCC, (c) OpenStreetMap contributors, and the GIS User Community, Source: Esri, Maxar, Earthstar Geographics, and the GIS User Community UltraSystems Environmental, Inc. 2024

June 18, 2024





Freeway traffic (passenger vehicles and trucks) and traffic on heavily traveled surface streets are the largest contributors to ambient noise levels in West Covina. City roadways that generate the most traffic noise include the major east-west trending I-10 Freeway, due to its higher traffic volumes and vehicle speeds. Major arterials that generate significant noise include Azusa Avenue, Sunset Avenue, Valinda Avenue and Glendora Avenue (City of West Covina, 2016b). The project site is adjacent to two of the major arterials – the I-10 Freeway and South Azusa Avenue (Google Earth Pro, 2024).

On April 24, 2024, UltraSystems obtained 15-minute ambient noise samples at four locations in the general area of the project. Sampling locations are shown in **Figure 4.13-2**. Measurements were made between 11:06 a.m. and 12:57 p.m. As shown in **Table 4.13-2**, average short-term ambient noise levels (L_{eq}) ranged from 52.0 to 66.8 dBA L_{eq} . The 66.8-dBA noise level was along South Azusa Avenue, in front of a single-family home. All monitored noise levels were within the range considered typical for the nearby land uses.

Table 4.13-2
AMBIENT NOISE MEASUREMENT RESULTS

Point	Data Set	Sampling Time	Address	Sound Level (dBA)			Notes
				L_{eq}	L_{max}	L_{90}	
1	S007	1106-1121	220 South Azusa Avenue	66.8	79.6	56.9	In front of a single-family residence south of the project site.
2	S008	1142-1157	203 South Azusa Avenue	61.1	79.2	51.7	In front of Options for Learning, west of the project site.
3	S009	1214-1229	132 South Homcrest Avenue	52.0	64.6	48.5	In front of a single-family residence west of the project site.
4	S010	1242-1257	1828 East Norma Avenue	52.5	68.2	47.0	In front of a single-family residence southeast of the project site.
Source: UltraSystems, 2024.							



**Figure 4.13-2
AMBIENT NOISE MEASUREMENT LOCATIONS**



Path: \\GIS\SVR\GIS\Projects\7212_WCovina_Envision_Dealership_ISMND\MXDA\7212_WCovina_4.13_Noise_Sampling_2024_06_17.mxd
Service Layer Credits: Sources: Esri, HERE, Garmin, USGS, Intermap, INCREMENT P, NRCan, Esri Japan, METI, Esri China (Hong Kong), Esri Korea, Esri (Thailand), NGCC, (c) OpenStreetMap contributors, and the GIS User Community. Source: Esri, Maxar, Earthstar Geographics, and the GIS User Community UltraSystems Environmental, Inc., 2024.

June 17, 2024

Scale: 1:2,400



0 100 200 Feet

0 30 60 Meters

Legend



Project Boundary



Noise Sampling Locations

**Envision Motors
West Covina Mercedes Benz**

Ambient Noise
Measurement Locations



UltraSystems
Environmental Consulting & Engineering



4.13.4 Regulatory Setting

State of California

The now-defunct California Department of Health Services (DHS) Office of Noise Control studied the correlation of noise levels with effects on various land uses. The most current guidelines prepared by the state noise officer are contained in the “General Plan Guidelines” issued by the Governor’s Office of Planning and Research in 2003 and reissued in 2017 (Governor’s Office of Planning and Research, 2017). These guidelines establish four categories for judging the severity of noise intrusion on specified land uses:

- **Normally Acceptable:** Is generally acceptable, with no mitigation necessary.
- **Conditionally Acceptable:** May require some mitigation, as established through a noise study.
- **Normally Unacceptable:** Requires substantial mitigation.
- **Clearly Unacceptable:** Probably cannot be mitigated to a less-than-significant level.

The types of land uses addressed by the state standards, and the acceptable noise categories for each, are presented in **Table 4.13-3**. There is some overlap between categories, which indicates that some judgment is required in determining the applicability of the numbers in a given situation.

Title 24 of the California Code of Regulations requires performing acoustical studies before constructing dwelling units in areas that exceed 60 dBA L_{dn} . Given the calculation described in **Section 4.13.3**, the siting would be conditionally acceptable. In addition, the California Noise Insulation Standards identify an interior noise standard of 45 dBA CNEL for new multi-family residential units. Local governments frequently extend this requirement to single-family housing.

Table 4.13-3
CALIFORNIA LAND USE COMPATIBILITY FOR COMMUNITY NOISE SOURCES

Land Use Category	Noise Exposure (dBA, CNEL)					
	55	60	65	70	75	80
Residential – Low-Density Single-Family, Duplex, Mobile Homes						
Residential – Multiple Family						
Transient Lodging – Motel, Hotels						
Schools, Libraries, Churches, Hospitals, Nursing Homes						
Auditoriums, Concert Halls, Amphitheaters						



Land Use Category	Noise Exposure (dBA, CNEL)
Sports Arena, Outdoor Spectator Sports	
Playgrounds, Neighborhood Parks	
Golf Courses, Riding Stables, Water Recreation, Cemeteries	
Office Buildings, Business Commercial and Professional	
Industrial, Manufacturing, Utilities, Agriculture	
	Normally Acceptable: Specified land use is satisfactory, based upon the assumption that any buildings involved are of normal conventional construction without any special noise insulation requirements.
	Conditionally Acceptable: New construction or development should be undertaken only after a detailed analysis of the noise reduction requirements is made and needed noise insulation features included in the design. Conventional construction, but with closed windows and fresh air supply system or air conditioning will normally suffice.
	Normally Unacceptable: New construction or development should generally be discouraged. If new construction or development does proceed, a detailed analysis of the noise reduction requirements must be made and needed noise insulation features included in the design.
	Clearly Unacceptable: New construction or development should generally not be undertaken.

Source: Governor's Office of Planning and Research, 2017.

City of West Covina General Plan Noise Element

The Noise Element of the City of West Covina General Plan (City of West Covina, 2016b) identifies sources of noise in the city and provides objectives and policies that ensure that noise from various sources would not create an unacceptable noise environment. As shown in **Table 4.13-3**, for an automotive dealership such as the proposed project, exterior noise levels of 70 dBA CNEL or less are desirable.

The General Plan Noise Element has the following applicable policies (P) and actions (A) for addressing noise issues in the community (City of West Covina, 2016b):

P6.24: *Ensure that new development does not expose surrounding land uses to excessive noise.*

A6.24 Through the environmental review process, require applicants for new development proposals to analyze potential noise impacts on nearby noise-sensitive receivers before project approval. As feasible, require appropriate noise mitigation to address any identified significant noise impacts).



P6.25: *Minimize noise conflicts between local noise generators and sensitive receivers.*

A6.25a Continue to enforce the City's existing Noise Ordinance.

A6.25b Track noise complaints to determine areas of potential problems, and work proactively with the noise generators and the affected parties to reduce the impacts of such noise.

P6.26: *Strive to reduce potential noise impacts in the City's own operations.*

A6.26a Incorporate noise reduction features for items such as, but not limited to, parking and loading areas, ingress/egress point, HVAC units, and refuse collection areas, during site planning to mitigate anticipated noise impacts on affected noise sensitive land uses.

A6.26b Purchase any equipment that produces high noise levels with all necessary and feasible noise abating equipment installed.

To the extent that the foregoing applies to the proposed project, the project design and operational characteristics are compatible with the Noise Element's goal, objectives and policies.

City of West Covina Municipal Code

The City of West Covina regulations with respect to noise are included in Article IV – Noise Regulations within the City's Municipal Code.

Article IV. - Noise Regulations

Division 2. - Specific Noise Sources

Sec. 15-95. - Construction and building projects.

- A. **Regulation.** Between the hours of 8:00 p.m. of one day and 7:00 a.m. of the next day, it shall be unlawful for any person within a residential zone, or within a radius of five hundred (500) feet therefrom, to operate equipment or perform any outside construction or repair work on buildings, structures, or projects or to operate any pile driver, steam shovel, pneumatic hammer, derrick, steam or electric hoist, or other construction type device in such manner as to create any noise which causes the noise level at the property line to exceed the ambient noise level by more than five (5) decibels unless a permit therefor has been duly obtained in accordance with paragraph (b) of this section. No permit shall be required to perform emergency work as defined in section 15-83 of this article.
- B. **Permit procedure.** A permit may be issued authorizing noises prohibited by this section whenever it is found that the public interest will be served thereby. Applications for permits shall be in writing, shall be accompanied by an application fee in the amount of five dollars (\$5.00), and shall set forth in detail facts showing that the public interest will be served by the issuance of such permit. Applications shall be made to the building director; provided, however, that, with respect to work upon or involving the use of a public street, alley, building, or other public place under the jurisdiction of the engineering department,



applications shall be made to the city engineer. Anyone dissatisfied with the denial of a permit may appeal to the council.

- C. **Unloading and Loading.** Between the hours of 8:00 p.m. of one day and 6:00 a.m. of the next day, it shall be unlawful for any person within the radius of five hundred (500) feet of generally occupied residences to unload, load or otherwise perform duties preparatory to the commencement of construction or repair work on buildings or structures. Generally occupied residences shall include, but not be limited to, areas in which there is a reasonable probability of occupancy within the area.

(Code 1960, § 4611; Ord. No. 1826, § 2, 11-13-89)

4.13.5 Significance Thresholds

Two criteria were used for judging noise impacts. First, noise levels generated by the proposed project must comply with all applicable relevant federal, state, and local standards and regulations. Noise impacts on the surrounding community are limited by local noise ordinances, which are implemented through investigations in response to nuisance complaints. It is assumed that all existing regulations for the construction and operation of the proposed project will be enforced. In addition, the proposed project should not produce noise levels that are incompatible with adjacent noise-sensitive land uses.

The second measure of impact used in this analysis is a significant increase in noise levels above existing ambient noise levels because of the introduction of a new noise source. An increase in noise level due to a new noise source has a potential to adversely impact people. The proposed project would have a significant noise impact if it would:

- Expose persons to or generate noise levels in excess of standards prescribed by the City of West Covina Municipal Code; or
- Include construction activities within the hours prohibited by the Municipal Code, without a permit; or
- Result in total noise exposures (construction plus ambient) at sensitive receivers during construction of 80 dBA L_{eq} or more (Federal Transit Administration [FTA], 2018); or
- Contribute, with other local construction projects, to a significant cumulative noise impact; or
- Increase operational exposures at sensitive receivers (mainly because of an increase in traffic flow) by 5 dBA CNEL or more.



4.13.6 Impact Analysis

- a) Would the project result in generation of substantial temporary or permanent increase in ambient noise levels in the vicinity of the project in excess of standards established in the local general plan or noise ordinance, or applicable standards of other agencies?

Less than Significant Impact

Noise impacts associated with automotive dealership projects include short-term and long-term impacts. Construction activities, especially heavy equipment operation, would create noise effects on and adjacent to the construction site. Long-term noise impacts include project-generated onsite and offsite operational noise sources. Onsite (stationary) noise sources from the automotive dealership would include operation of mechanical equipment such as air conditioners and building maintenance. Offsite noise would be attributable to project-induced traffic, which would result in an incremental decrease in noise levels within and near the project vicinity due to the demolition of the gas station currently on the project site.

Construction

Noise impacts from construction activities are a function of the noise generated by the operation of construction equipment and onroad delivery and worker commuter vehicles, the location of equipment, and the timing and duration of the noise-generating activities. For the purpose of this analysis, it was estimated that the proposed project would be built in the eight phases listed in **Table 4.13-4**. Construction is anticipated to run approximately one year, from early June 2025 to July 2026.

The types and numbers of pieces of equipment to be deployed during each construction phase were determined as part of the air quality and greenhouse gas emissions analyses for this project.¹⁴ For each equipment type, **Table 4.13-4** shows the number of equipment pieces to be used, an average noise emission level (in dB at 50 feet, unless otherwise specified) and a “usage factor,” which is an estimated percentage of operating time that the equipment would be producing noise at the stated level. Equipment use was matched to phases of the construction schedule. The last column of the table shows the composite noise at 50 feet for each phase; i.e., the total noise if all of each phase’s equipment were to operate simultaneously.

Table 4.13-4
CONSTRUCTION EQUIPMENT CHARACTERISTICS

Construction Phase	Equipment Type	No. of Pieces	Maximum Sound Level (dBA @50 feet)	Usage Factor	Composite Noise (dBA @ 50 Feet)
1 - Demolition	Concrete/Industrial Saws	1	90.0	0.73	89.00
	Rubber-Tired Dozers	2	79.0	0.40	
2 – Site Preparation	Rubber Tired Dozers	2	79.0	0.40	78.03

¹⁴ See **Section 4.3** and **Section 4.8**.



Construction Phase	Equipment Type	No. of Pieces	Maximum Sound Level (dBA @50 feet)	Usage Factor	Composite Noise (dBA @ 50 Feet)
3- Grading	Graders	1	85.0	0.41	86.82
	Tractor/Loader/Backhoes	3	85.0	0.37	
4 – Building Construction	Cranes	1	83.0	0.08	85.94
	Forklift	3	67.0	0.30	
	Generator Sets	1	73.0	0.50	
	Welders	1	74.0	0.45	
	Tractor/Loader/Backhoes	3	85.0	0.37	
5 - Paving	Cement and Mortar Mixers	2	85.0	0.40	86.42
	Off-Highway Trucks	5	75.0	0.40	
	Rollers	2	74.0	0.10	
	Tractor/Loader/Backhoes	1	85.0	0.37	
6 – Architectural Coating	Air Compressors	1	81.0	0.48	77.81
7 – Utilities Installation	Trenchers	2	83.0	0.30	80.78
8 – Landscaping Installation	Rollers	1	85.0	0.37	80.68

Using calculation methods published by the Federal Transit Administration,¹⁵ UltraSystems estimated the average hourly exposures at the nearest sensitive receiver for each construction phase. The receivers evaluated included single-family residences south and southeast of the project site and single-family residences along East Garvey Avenue, across from the project site (see **Figure 4.13-1**). The distances used for the calculation were measured from the receivers to the approximate center of activity of each construction phase, since that would be the average location of construction equipment most of the time. **Table 4.13-5** shows the relationships between the receivers, the noise sources, and the nearest ambient measurement points. South of the project site, an approximately seven-foot-high brick wall partially shields the single-family residences from onsite noise. Another approximately seven-foot-high brick wall shields single-family residences west of the project site from onsite noise.

Table 4.13-5
NOISE ANALYTICAL FRAMEWORK

Sensitive Receiver	Construction Phase(s) ^a	Nearest Ambient Sampling Point(s)
Single-family residence	All Construction Phases	1
Options For Learning	All Construction Phases	2

¹⁵ Transit Noise and Vibration Impact Assessment Manual. Federal Transit Administration, Office of Planning and Environment, Washington, DC, FTA Report No. 0123. September 2018. Internet: https://www.transit.dot.gov/sites/fta.dot.gov/files/docs/research-innovation/118131/transit-noise-and-vibration-impact-assessment-manual-fta-report-no-0123_0.pdf.



Sensitive Receiver	Construction Phase(s) ^a	Nearest Ambient Sampling Point(s)
Single-family residence	All Construction Phases	3
Single-family residence	All Construction Phases	4

Table 4.13-6 summarizes the estimated maximum construction-related short-term noise exposures for each construction phase. In no cases were there intervening buildings between a noise source and a receiver. Residential noise exposures due to construction activities would be about 67.0 to 71.4 dBA L_{eq} . These are conservative values, since sound attenuation from the aforementioned seven-foot-high brick walls were not taken into account.

**Table 4.13-6
ESTIMATED MAXIMUM CONSTRUCTION NOISE EXPOSURES**

Phase	Receiver ^a	Distance (feet)	Ambient (dBA L_{eq})	Construction (dBA L_{eq}) ^b	New Total (dBA L_{eq})	Increase (dBA L_{eq})
Demolition	SF	470	66.8	69.5	71.4	4.6
Site Preparation	SF	470	66.8	58.6	67.4	0.6
Grading	SF	470	66.8	67.4	70.1	3.3
Building Construction	SF	470	66.8	66.5	69.7	2.9
Paving	SF	470	66.8	67.0	69.9	3.1
Architectural Coating	SF	470	66.8	58.4	67.4	0.6
Utilities Installation	SF	470	66.8	61.3	67.9	1.1
Landscaping Installation	SF	470	66.8	61.2	67.9	1.1
^a Sensitive Receiver at 220 South Azusa Avenue.						

Noise exposure from construction of the proposed project would not exceed the FTA's 80 dBA threshold. Impacts would be less than significant.

Operational Noise

Onsite

Onsite noise sources from the proposed automotive dealership project would include operation of mechanical equipment such as air conditioners and building maintenance equipment; and motor vehicles accessing, driving on, and exiting the parking lot. Noise levels are expected to decrease from the current condition due to the demolition of the gas station on the project site. Noise levels associated with operation of the project are expected to be comparable to those of nearby residential areas. Therefore, noise from onsite sources would be less than significant.



Mobile Sources

The VMT analysis prepared for this project (RK Engineering, 2024a) estimates that the existing trip generation is 2,649 trips per day, while the development will generate 2,337 trips per day. This would constitute a decrease of 272 trips per day. Given the logarithmic nature of the decibel, traffic volume needs to be doubled in order for the noise level to increase by 3 dBA (ICF Jones & Stokes, 2009), the minimum level perceived by the average human ear. A doubling is equivalent to a 100 percent increase. Because the maximum increase in traffic on any road segment would be far below 100 percent, the increase in roadway noise experienced at sensitive receivers would not be perceptible to the human ear. Therefore, roadway noise associated with project operation would not expose a land use to noise levels that are considered incompatible with or in excess of adopted standards, and impacts would be less than significant.

b) Would the project result in generation of excessive groundborne vibration or groundborne noise levels?

Less than Significant Impact

Vibration is sound radiated through the ground. Vibration can result from a source (e.g., subway operations, vehicles, machinery equipment, etc.) causing the adjacent ground to move, thereby creating vibration waves that propagate through the soil to the foundations of nearby buildings. This effect is referred to as groundborne vibration. The peak particle velocity (PPV) or the RMS velocity is usually used to describe vibration levels. PPV is defined as the maximum instantaneous peak of the vibration level, while RMS is defined as the square root of the average of the squared amplitude of the level. PPV is typically used for evaluating potential building damage, while RMS velocity in dB is typically more suitable for evaluating human response.

The background vibration velocity level in residential areas is usually around 50 vibration decibels (VdB). The vibration velocity level threshold of perception for humans is approximately 65 VdB. A vibration velocity level of 75 VdB is the approximate dividing line between barely perceptible and distinctly perceptible levels for most people. Most perceptible indoor vibration is caused by sources within buildings such as operation of mechanical equipment, movement of people, or the slamming of doors. Typical outdoor sources of perceptible groundborne vibration are construction equipment, steel-wheeled trains, and traffic on rough roads. If a roadway is smooth, the groundborne vibration from traffic is rarely perceptible. The range of interest is from approximately 50 VdB to 100 VdB, which is the general threshold where minor damage can occur in fragile buildings.

Construction Vibration

Construction activities for the project have the potential to generate low levels of groundborne vibration. The operation of construction equipment generates vibrations that propagate through the ground and diminish in intensity with distance from the source. Vibration impacts can range from no perceptible effects at the lowest vibration levels, to low rumbling sounds and perceptible vibration at moderate levels, to slight damage of buildings at the highest levels. The construction activities associated with the project could have an adverse impact on both sensitive structures (i.e., building damage) and populations (i.e., annoyance).

The FTA (2018) has published standard vibration levels, at a distance of 25 feet, for construction equipment operations. The construction-related vibration levels for the nearest sensitive receivers



for major construction phases are shown in **Table 4.13-7**. These calculations were based on the distances from the construction activity to the closest sensitive receivers.

Table 4.13-7
VIBRATION LEVELS OF TYPICAL CONSTRUCTION EQUIPMENT

Equipment	PPV at 25 feet (in/sec)	Vibration Decibels at 25 feet (VdB)	PPV at 222 feet (in/sec) ^a	Vibration Decibels at 222 feet (VdB) ^a	PPV at 64 feet (in/sec) ^b	Vibration Decibels at 64 feet (VdB) ^b
Loaded Trucks	0.076	86			0.027	74
Jackhammer	0.035	79	0.0032	51		
Small bulldozer	0.003	58	0.00027	30		
Large bulldozer	0.089	87	0.0081	59		

Source: Calculated by UltraSystems.

Note: PPV = peak particle velocity, VdB = vibration decibels, in/sec = inches per second.

^aApplies to onsite construction activities.

^bApplies to onroad truck activities.

As shown in **Table 4.13-7**, the PPV of construction equipment at the nearest sensitive receiver (64 feet) is at most 0.027 inch per second, which is less than the FTA damage threshold of 0.12 inch per second PPV for fragile historic buildings. The maximum VdB are 74 VdB, which are below the FTA threshold for human annoyance of 80 VdB. Unmitigated vibration impacts would therefore be less than significant.

Operational Vibration

The automotive dealership is not the type of facility that creates operational vibration. The project would not involve the use of stationary equipment that would result in high vibration levels, which are more typical for large manufacturing and industrial projects. Groundborne vibrations at the project site and immediate vicinity currently result from heavy-duty vehicular travel (e.g., refuse trucks and transit buses) on the nearby local roadways, and the project would not result in a substantive increase of these heavy-duty vehicles on the public roadways. Therefore, vibration impacts associated with operation of the project would be less than significant.

- c) For a project located within the vicinity of a private airstrip or an airport land use plan or, where such a plan has not been adopted, within two miles of a public airport or public use airport, would the project expose people residing or working in the project area to excessive noise levels?**

No Impact

The closest active public airport is the Brackett Field Airport, located approximately 6.8 miles northeast of the project site (Google Earth Pro, 2024). The project site is located outside of the airport's influence area boundary and noise contours (LA County ALUC, 2015). Therefore, no impact related to the exposure of people residing or working in the proposed project area to excessive airport-related noise levels is anticipated.



4.14 Population and Housing

Would the project:	Potentially Significant Impact	Less than Significant Impact with Mitigation Incorporated	Less than Significant Impact	No Impact
a) Induce substantial unplanned population growth in an area, either directly (for example, by proposing new homes and businesses) or indirectly (for example, through extension of roads or other infrastructure)?			X	
b) Displace substantial numbers of existing people or housing, necessitating the construction of replacement housing elsewhere?				X

- a) **Would the project induce substantial unplanned growth in an area either directly (for example, by proposing new homes and business) or indirectly (for example, through extension of roads or other infrastructure)?**

Less than Significant Impact

The project does not propose the development of any residential uses that would cause direct population growth. The proposed project would involve the demolition of an existing auto dealership and an operating gas station, and the construction of a new two-story automotive sales and dealership building, as well as associated surface parking, landscaping, and charging facilities for electric vehicles. The project does not involve the extension of roads or other infrastructure and would not be of the scale to induce indirect unplanned population growth in the project area. Therefore, there would be a less than significant impact.

- b) **Would the project displace substantial numbers of existing people or housing, necessitating the construction of replacement housing elsewhere?**

No Impact

The project site is currently occupied exclusively by commercial use and structures and does not have existing residents or residential uses. Therefore, the project would not displace any housing or people and the project would not necessitate the construction of replacement housing. There would be no impact.



4.15 Public Services

Would the project:	Potentially Significant Impact	Less than Significant Impact with Mitigation Incorporated	Less than Significant Impact	No Impact
Would the project result in substantial adverse physical impacts associated with the provision of new or physically altered governmental facilities, the need for new or physically altered governmental facilities, construction of which could cause significant environmental impacts, in order to maintain acceptable service ratios, response times or other performance objectives for any of the public services:				
a) Fire protection?			X	
b) Police protection?			X	
c) Schools?				X
d) Parks?			X	
e) Other public facilities?			X	

a) Fire protection?

Less than Significant Impact

The West Covina Fire Department (WCFD) provides fire protection and emergency medical services to the City of West Covina. WCFD operates five fire stations throughout the city. Each station has a designated district to which it responds. The nearest existing fire station to the project site is Station No. 2 at 2441 E. Cortez Street, approximately one mile to the southeast.

WCFD operations are funded mostly through property taxes and sales taxes. The City also receives one-time fees on new development to be used to cover the costs of capital equipment, and infrastructure required to serve new growth via Fund 165 - Fire Impact Fees of \$0.38 per square foot for nonresidential development (City of West Covina, 2023b, p. 31). However, project development is not expected to generate an increase in calls for fire protection and emergency medical services and, therefore, would not require the city to build a new or expanded fire station. Additionally, the demand for fire protection depends on population increase. The project would not increase the population and would pay the applicable fees. Therefore, the impact would be less than significant.

b) Police protection?

Less than Significant Impact

The West Covina Police Department (WCPD) provides police protection to the City. The WCPD station is located at 1444 West Garvey Avenue, approximately 1.75 miles west of the project site. WCPD consists of the police department that has an authorized full-time workforce of 100 sworn officers and 66 civilians. In addition, there are about 55 part-time positions that include reserve officers and clerical staff. The Department also uses volunteer programs (City of West Covina, 2024d).

WCPD operations are funded mostly through property taxes and sales taxes. The City also receives one-time fees on new development to be used to cover the costs of capital equipment, and



infrastructure required to serve new growth via Fund 164 - Police Impact Fees of \$0.32 per square foot for nonresidential development (City of West Covina, 2023b, p. 31).

The WCPD does not anticipate that project development would require the construction or expansion of a new or expanded police facility or adversely affect WCPD operations. Additionally, the demand for police service depends on an increase in population. The project would not increase the population and would pay the applicable fees. The impact of the project on police services would be less than significant and mitigation is not required.

c) Schools?

No Impact

The project site is in the West Covina Unified School District (WCUSD). WCUSD currently serves more than 14,000 students in 15 local area schools and two charter schools. District-wide enrollment in the 2019-2020 school year was 23,470 (WCUSD, 2024a).

The demand for school facilities is generated by the number of residential properties and school-age children within the attendance limits of schools. The project involves commercial development and does not propose the creation of new housing or increase the demand for additional housing. Additionally, the project is subject to pay the appropriate amount in developer fees. The West Covina Unified School District is authorized by the Government Code §65995 to collect a development fee of \$0.66 per square foot for the development of a new commercial development (WCUSD, 2024b).

Under Government Code §65995, the WCUSD is authorized to collect a development fee of \$0.66 per square foot of development for new commercial ventures. This fee serves as a source of funding for the school district, allowing it to adequately address any potential impact that might arise from such development. Therefore, there would be no impact on schools.

d) Parks?

Less Than Significant Impact

Recreational services in the City of West Covina are managed by the Community Services Division of the Public Services Department of the City, which maintains 23 city-operated recreational facilities, including 16 parks (City of West Covina, 2024e).

The nearest city park to the project is Cortez Park, located approximately 0.75 miles east of the project site. The project does not propose residential land use and is not anticipated to add new residents to the city. Additionally, park development depends on population increases. The project would not increase the population and would pay the applicable fees. Employees at the project site can visit nearby parks, but the potential impact of these visits to the parks would be less than significant.



e) Other Public Facilities?

Less Than Significant Impact

Library

The West Covina Library is part of the Los Angeles County Library System, which is made up of 72 branch libraries. The West Covina Library is the only public library within the City of West Covina and is located at 1601 West Covina Parkway (County of Los Angeles, 2024c). Additionally, libraries depend on population increases. The project is not of the scope or scale to induce any population growth. Therefore, the project would not have an impact on libraries or other public facilities.

Hospitals

The nearest hospital to the project site is the West Covina Medical Center at 725 S Orange Avenue, approximately two miles west of the project site. West Covina Medical Center provides 24-hour urgent care, physical therapy services, a wound care center, a medical imaging center, and gastrointestinal and urology services (WCMC, 2024). Additionally, the demand for hospital services depends in part on the increase in population. The project would not increase the population and would pay the applicable fees. Adequate hospital facilities are present in the project region for project residents, and project development would not require the construction of new or expanded hospitals. The impacts would be less than significant.

**4.16 Recreation**

Would the project:	Potentially Significant Impact	Less than Significant Impact with Mitigation Incorporated	Less than Significant Impact	No Impact
a) Would the project increase the use of existing neighborhood and regional parks or other recreational facilities such that substantial physical deterioration of the facility would occur or be accelerated?			X	
b) Does the project include recreational facilities or require the construction or expansion of recreational facilities which might have an adverse physical effect on the environment?				X

- a) **Would the project increase the use of existing neighborhood and regional parks or other recreational facilities such that substantial physical deterioration of the facility would occur or be accelerated?**

Less than Significant Impact

The City offers a range of park types that include two small pocket parkettes, eight neighborhood parks, three community parks, two wilderness areas, specialized sports facilities, paseos, and conservation areas (Rincon, 2016, p. 244). Impacts to recreation are based on whether the project would increase the population of the City with project buildout. As detailed in **Section 4.14**, Population and Housing, the proposed project would develop a commercial dealership that would not increase the population in the city. Employees for the project are expected to come from the local workforce. Although project employees may potentially use parks and recreational facilities, impacts would be less than significant.

- b) **Does the project include recreational facilities or require the construction or expansion of recreational facilities which might have an adverse physical effect on the environment?**

No Impact

The proposed project would not include recreational facilities as part of the project. Therefore, there would be no impact.



4.17 Transportation

Would the project:	Potentially Significant Impact	Less than Significant Impact with Mitigation Incorporated	Less than Significant Impact	No Impact
a) Conflict with a program plan, ordinance or policy addressing the circulation system, including transit, roadway, bicycle and pedestrian facilities?			X	
b) Would the project conflict or be inconsistent with CEQA Guidelines section 15064.3, subdivision (b)?			X	
c) Substantially increase hazards due to a geometric design feature (e.g., sharp curves or dangerous intersections) or incompatible uses (e.g., farm equipment)?		X		
d) Result in inadequate emergency access?		X		

The project site is located along East Garvey Avenue S, a two-lane meandering street designated a Minor Arterial Roadway in the City of West Covina General Plan (City of West Covina, 2016a, p. 60). There are sidewalks near the project site on both sides of East Garvey Avenue S.

Existing public transit service in West Covina is provided by Foothill Transit and by the City of West Covina, operating as Go West. Foothill Transit is the regional bus service provider for the eastern San Gabriel Valley. The Go West system, meanwhile, consists of three shuttle routes, labeled Red, Blue, and Green (City of Covina, 2016a, p. 63).

Foothill Transit is a public transit provider in the region, including the City of West Covina, with more than 30 local and express routes and operating a fleet of more than 300 buses, fueled by low-emission compressed natural gas and zero-emission electric batteries and hydrogen fuel cells serving more than 300 square miles of the San Gabriel and Pomona Valleys of Southern California (Foothill Transit, 2024).

In 2014, the City of West Covina unveiled its Go West Transit fleet. The fleet includes seven alternative fuel, environmentally-friendly vehicles, which is utilized for both the City's fixed-route shuttle service and the dial-a-ride service. The nearest transit stop to the project site is Azusa Avenue and S Garvey Avenue N on the western edge of the project site (City of Covina, 2024f).

The City of West Covina has not adopted a bicycle master plan. Chapter 22, Article III of the Municipal Code defines standards for Class I Bike Paths, Class II Bike Lanes, and Class III Shared Routes. There are bike routes along Walnut Creek Wash east of Glendora, continuing to Azusa, approximately 1,800 feet south of the project site (City of West Covina, 2016a, p. 66).



- a) **Would the project conflict with a program plan, ordinance, or policy addressing circulation system, including transit, roadway, bicycle, and pedestrian facilities?**

Less than Significant Impact

The project site currently has four entrance/exit driveways for the existing gas station and one entrance and one exit for the existing dealership (Google Earth Pro, 2024). The proposed project would reduce the total number of driveways from six to four. As described in **Section 3.4.1**, four vehicular entrances would be provided from surrounding streets: three from East Garvey South Avenue along the south and east site perimeter; and one from Azusa Avenue on the southwest side of the project site. The main entrance would be from East Garvey Avenue on the south site boundary. Access via the driveway to and from Azusa Avenue would be right-in-right-out only, as that segment of Azusa Avenue is a divided road. As shown in **Figure 3.4-1**, driveways would extend around the southern, western, and northern sides of the building. The proposed project would not make any changes to the surrounding roadways.

City of West Covina General Plan

The circulation element of the City has several goals and policies that are applicable to the proposed project. Refer to **Table 4.17-1** below, which lists the applicable policies and how the proposed project would comply.

Table 4.17-1
PROJECT COMPLIANCE WITH CITY OF WEST COVINA GENERAL PLAN POLICIES
REGARDING MOBILITY AND TRANSPORTATION

General Plan Element	Project Compliance
Circulation Goal P5.1: Promote fine-grained network of complete streets in new and redevelopment projects.	The proposed project does not propose altering public roads and plans to maintain the existing frontages on Garvey Avenue and Azusa Avenue. However, it does propose reducing vehicular right-of-way access points from six to four; restricting vehicular access from North Azusa Avenue and completely removing two access points on either side of the northbound transit stop. This would reduce potential conflict points between pedestrians and public transit users with automobiles, a primary goal of the Complete Streets concept.
Policy A5.1: Adjust development regulations and review processes to require new development and redevelopment projects to provide a fine-grained, interconnected, multimodal transportation network with a balance of motor vehicle, pedestrian, bike, and transit amenities.	
Transportation Goal P5.5: Implement a Complete Streets Policy for the city to ensure that the right of way will provide safe access for all users.	
Policy A5.5: Publish a Complete Streets Manual that provides engineering and design guidelines for different street typologies to better accommodate a mix of modes, including cars, public transportation, cyclists, and pedestrians; apply the standards in the manual to projects whenever possible.	

Source: (City of West Covina, 2016d, pp. 138-139)



❖ SECTION 4.18 – TRIBAL CULTURAL RESOURCES ❖

As detailed above, the proposed project would not conflict with any applicable policies of the city's General Plan addressing the circulation system, including transit, roadway, bicycle, and pedestrian facilities. Therefore, the project would have a less than significant impact in this regard.

City of West Covina Municipal Code § 26-751.1100

The Transportation Demand Management ordinance has a set of transportation management requirements for development projects in the city. The proposed project has a total building area of 82,000 square feet; therefore, § 26-751.1100(d)(2)(a & b) would be applicable with requirements that apply to (a) non-residential development of 25,000 square feet or more and (b) non-residential development of 50,000 square feet or more. Through the required compliance with the aforementioned Municipal Code Sections, the proposed project would not conflict with an applicable plan, ordinance, or policy establishing measures of effectiveness for the performance of the circulation system. Impacts would be less than significant.

Project Trip Generation - Vehicle Miles Traveled (VMT)

A Vehicle Miles Traveled (VMT) Screening Analysis by RK Engineering Group, Inc. was completed on September 27, 2024 (RK Engineering, 2024) for the proposed project. This analysis is presented in **Appendix I**. The purpose of this analysis is to determine whether the proposed project will require a detailed VMT modeling analysis. The project operation is estimated to generate 300 fewer trips per day than currently achieved, as shown in **Table 4.17-2**.

Table 4.17-2
NET PROJECT TRIP GENERATION

Land Use	ITE Code	Qty.	Units	AM Peak Hour			PM Peak Hour			Daily
ITE Trip-Generation Rates										
Auto Sales (New)	840	-	TSF ¹	73%	27%	1.86	40%	60%	2.42	27.84
Conv. Store/Gas Station	945	-	VFP ²	50%	50%	16.06	50%	50%	18.42	265.12
EV Charging Station ³	-	-	Positions	53%	47%	1.70	49%	51%	1.89	33.43
Existing Trip Generation										
Auto Sales (New)	840	23.754	TSF	32	12	44	23	34	57	661
Conv. Store/Gas Station	945	10	VFP	80	81	161	92	92	184	2,651
Existing Trip Generation Subtotal (A)				112	93	205	115	126	241	3,312
Proposed Trip Generation										
Auto Sales (New)	840	85.390	TSF	116	43	159	83	124	207	2,377
EV Charging Station	-	19	Positions	17	15	32	18	18	36	635
Proposed Trip Generation Subtotal (B)				133	58	191	101	142	234	3,012
Net Trip Generation (A) - (B)				21	-35	-14	-14	16	2	-300

Source: RK Engineering, 2024, Table 1 (*Institute of Transportation Engineers (ITE) Trip Generation Manual (11th Edition, 2021)*)

1. TSF = Thousand Square Feet

2. VFP = Vehicle Fueling Position

3. Trip rates based on surveys of the following three EV charging facilities on August 29–31, 2023: (1) Fountain Valley (9380 Warner Avenue), (2) Westminster (1025 Westminster Mall), and (3) Santa Monica (1425 Santa Monica Boulevard).

Note: The ITE Trip Generation Manual (11th Edition, 2021) provides the following pass-by reductions for ITE Land Use 945: 76% for the AM Peak Hour & 75% for the PM peak hour. A 25% daily pass-by reduction has been assumed.



The purpose of VMT Screening Analysis was to determine whether the proposed project will require a detailed VMT modeling analysis. The analysis utilized the City of West Covina Transportation Study Guidelines for Vehicle Miles Traveled and Level of Service Assessment, dated September 2020, which establishes uniform analysis methodologies and thresholds of significance for determining VMT impacts under the CEQA (RK Engineering, 2024).

As specified in the City's Guidelines, projects generating less than 110 daily trips are presumed to have a less than significant impact absent substantial evidence to the contrary. Comparing the existing/entitled and proposed land uses, the project is expected to generate 300 fewer daily trips. The VMT Screening Analysis concluded that the proposed project is screened out based on Step 3: Project Type Screening (i.e., the project will generate less than 110 net new daily vehicle trips). Therefore, no further VMT analysis is required, and the project would have a less than significant impact on VMT under CEQA (RK Engineering, 2024, p. 6). RK Engineering also concluded in their VMT analysis memo that since the project trips would be below the threshold, it is determined that the project does not have the potential to significantly affect roadway operations compared to existing land uses..

b) Would the project conflict or be inconsistent with CEQA Guidelines section 15064.3, subdivision (b)

Less than Significant Impact

CEQA Guidelines § 15064.3(b) pertains to the use of VMT as a method of determining the significance of transportation impacts. The VMT analysis presented above in **Section 4.17.a** satisfies the requirements under CEQA Guidelines § 15064.3(b). As described above, the project trip generation would be less than the existing land use trip generation. Therefore, the proposed project's impact on VMT would be less than significant.

c) Would the project substantially increase hazards due to a geometric design feature (e.g., sharp curves or dangerous intersections) or incompatible uses (e.g., farm equipment)?

Less than Significant Impact with Mitigation Incorporated

As detailed in the VMT and Site Access Report the project's circulation system, including driveways and parking areas, would be designed to meet city development standards and would allow adequate circulation throughout the project site (RK Engineering, 2024, p. 7). Vehicular access to the project would be provided by three driveways from East Garvey Avenue S and one driveway from Azusa Avenue. The report found that multiple driveways could potentially be affect driver's line of site. However, the report found that if the project implemented the corner sight distance recommendations detailed in the report, all potential corner sight impacts would be reduced to less than significant (RK Engineering, 2024, p. 10-11). Therefore, the project would implement **MM TRANS-1**, which would ensure that the project incorporate all corner sight distance recommendations that are listed in the report. Therefore, there would be a less than significant impact due to the geometric design features or incompatible uses with mitigation measures incorporated.

Mitigation Measure

TRANS-1: Corner Sight Distance Measures



Several of the project's driveway could have potentially significant corner sight impacts. However, the project would incorporate all the corner sight distance recommendations in the Vehicle Miles Traveled Screening Analysis and Site Access Assessment Report created for the proposed project by RK Engineering (**Appendix I**).

Level of Significance After Mitigation

With implementation of mitigation measure TRANS-1, the proposed project would have less than significant impacts regarding design features.

d) Would the project result in inadequate emergency access?

Less than Significant Impact with Mitigation Incorporated

Construction

Project construction could involve temporary closure of a segment of a lane on East Garvey Avenue S or an entire segment of the road. Any plans for construction activity on the right-of-way would require an encroachment permit from the City of West Covina. The City Public Works/Engineering Department would review any encroachment permit applications to ensure that such construction did not impede emergency response to the project site or nearby properties; and did not create traffic hazards. Compliance with any conditions set forth in an encroachment permit is a condition of the permit. The impacts would be less than significant after the City review and after the conformance of the project to the conditions set forth in any encroachment permit.

Operation

The project would comply with applicable city regulations, such as the requirement to comply with the City's fire code to provide adequate emergency access, as well as the California Building Standards Code. Before the issuance of building permits, the City of West Covina would review the project site plans, including the location of all buildings, fences, access driveways, and other features that can affect emergency access. The design of the site includes access and fire lanes that would accommodate emergency ingress and exit by fire trucks, police units, and ambulance/paramedic vehicles. As detailed above, the project would have deficit corner sight views at several driveways. However, with implementation of **MM TRANS-1**, there would be less than significant design features and site access. Therefore, with implementation of **MM TRANS-1**, the project would not result in inadequate emergency access and there would be less than significant impacts with mitigation incorporated.

Mitigation Measure

TRANS-1: See above.

Level of Significance After Mitigation

With implementation of mitigation measure **TRANS-1**, the proposed project would have less than significant impacts regarding emergency access.



4.18 Tribal Cultural Resources

Would the project:	Potentially Significant Impact	Less than Significant Impact with Mitigation Incorporated	Less than Significant Impact	No Impact
a) Cause a substantial adverse change in the significance of a tribal cultural resource that is listed or eligible for listing in the California Register of Historical Resources or in a local register of historical resources as defined in Public Resources Code § 5020.1(k)?				X
b) Cause a substantial adverse change in the significance of a tribal cultural resource that is determined to be a significant resource to a California Native American tribe pursuant to the criteria set forth in subdivision (c) of Public Resource Code § 5024.1(c)?		X		

Information from UltraSystems' Phase I Cultural Resources Inventory, dated June 10, 2024 for the proposed project (refer to **Appendix D**) is included in the analysis below.

- a) **Would the project cause a substantial adverse change in the significance of a tribal cultural resource that is listed or eligible for listing in the California Register of Historical Resources or in a local register of historical resources as defined in Public Resources Code § 5020.1(k)?**

No Impact

No resources as defined by Public Resources Code § 21074 have been identified. Additionally, the project site has not been recommended for historic designation for prehistoric and tribal cultural resources (TCRs). No specific tribal resources have been identified by local tribes responding to inquiries for the Cultural Resources Inventory study. A records search by the Native American Heritage Commission's (NAHC) of their Sacred Lands File (SLF) did not find a traditional cultural site within the project area (see Section 4.2 and Attachment C in **Appendix D** of this IS/MND).

No prehistoric archaeological resources were observed during the archaeological field survey conducted March 3, 2024 by Stephen O'Neil, M.A., RPA as part of the cultural resources investigation (Section 4.3 in **Appendix D**). The results of the pedestrian assessment indicate that it is unlikely that prehistoric resources will be adversely affected by construction of the project; due to the extensive disturbance to the site by prior construction activities. The cultural resource records search at the South Central Coastal Information Center (SCCIC, the local California Historical Resources Information System [CHRIS] facility) did not identify any prehistoric resources either within the project site or the 0.5-mile buffer surrounding it. (Refer to Section 4.1 in **Appendix D**).



❖ SECTION 4.18 – TRIBAL CULTURAL RESOURCES ❖

No tribal cultural resources onsite are listed or eligible for listing in the California Register of Historical Resources or in a local register of historical resources as defined in Public Resources Code § 5020.1(k). Therefore, the project would have no impact in this regard.

- b) Would the project cause a substantial adverse change in the significance of a tribal cultural resource that is determined to be a significant resource to a California Native American tribe pursuant to the criteria set forth in subdivision (c) of Public Resource Code § 5024.1(c)?**

Less than Significant Impact with Mitigation Incorporated

Assembly Bill 52 (AB 52) and Senate Bill 18 (SB 18) require meaningful consultation with California Native American Tribes on potential impacts on TCRs, as defined in Public Resources Code § 21074. TCRs are sites, features, places, cultural landscapes, sacred places, and objects with cultural value to a California Native American tribe that are either eligible or listed in the California Register of Historical Resources or local register of historical resources (CNRA, 2007).

As part of the AB 52 process, Native American tribes must submit a written request to the lead agency to be notified of projects within their traditionally and culturally affiliated area. The lead agency must provide written, formal notification to those tribes within 14 days of deciding to undertake a project. The tribe must respond to the lead agency within 30 days of receiving this notification if they want to engage in consultation on the project, and the lead agency must begin the consultation process within 30 days of receiving the tribe's request. Consultation concludes when either (1) the parties agree to mitigation measures to avoid a significant effect on a tribal cultural resource, or (2) a party, acting in good faith and after reasonable effort, concludes mutual agreement cannot be reached.

Senate Bill (SB) 18 consultation is initiated with California Native American tribes under Government Code § 65352.3(a) when there will be either General Plan and/or Specific Plan amendments for a project. The consultation process is similar to that for AB 52 and may be conducted concurrently. The tribe must respond to the lead agency within 90 days of receiving notification if they want to engage in consultation on the project, and the lead agency must begin the consultation process within 30 days of receiving the tribe's request.

The City of West Covina (the lead agency) would initiated AB 52 and SB 18 consultation to local tribes for the Envision Motors Mercedes Benz Dealership project following submittal of the project to the City's Planning Division (personal communication, Jo-Anne Burns, Deputy Community Development Director, City of West Covina; via email to S. O'Neil, May 7, 2024). On May 22, 2024, the City received a request from the Gabrielino – Kizh Nation requesting AB 52 consultation (personal communication J. Burns, via email to S. O'Neil, May 22, 2024), but as the project had not been filed with City, at this point consultation was postponed.

Miriam Machado, Associate Planner with the City Planning Division sent letters on September 5, 2024 to the 13 contacts representing seven tribes on the NAHC list provided by UltraSystems informing them of the project and asking if they wished to participate in AB 52 and SB 18 consultation. The letters conveyed that the recipient has 30 days from the receipt of the letter to request AB 52 consultation regarding the project and 90-days for SB 18 consultation (M. Machado, personal communication to S. O'Neil; September 5, 2024). The letters were sent via certified mail to:

- Andrew Salas, Chairperson: Gabrieleno Band of Mission Indians - Kizh Nation,
- Christina Martinez, Secretary: Gabrieleno Band of Mission Indians - Kizh Nation,



❖ SECTION 4.18 – TRIBAL CULTURAL RESOURCES ❖

- Anthony Morales, Chairperson: Gabrieleno/Tongva San Gabriel Band of Mission Indians,
- Sandonne Goad, Chairperson: Gabrieleno/Tongva,
- Robert Dorame, Chairperson: Gabrieleno Tongva Indians of California Tribal Council,
- Christina Conley, Cultural Resources Administrator: Gabrieleno Tongva Indians of California Tribal Council,
- Sam Dunlap, Cultural Resources Director: Gabrieleno-Tongva Tribe,
- Charles Alvarez, Chairperson: Gabrieleno-Tongva Tribe,
- Steven Estrada, Chairperson: Santa Rosa Band of Cahuilla Indians,
- Vanessa Minott, Tribal Administrator: Santa Rosa Band of Cahuilla Indians,
- Jessica Valdez, Cultural Resource Specialist: Soboba Band of Luiseño Indians,
- Isaiah Vivanco, Chairperson: Soboba Band of Luiseño Indians,
- Joseph Ontiveros, THPO: Soboba Band of Luiseño Indians.

There has been one response to the letters to date. The Administrative Specialist for the Gabrieleno Band of Mission Indians – Kizh Nation replied by email on September 5, 2024, and followed up the following day September 6, 2024 requesting consultation (M. Machado, personal communication to S. O'Neil; September 10, 2024.) The Kizh Nation informed Ms. Machado that the project area is in an area with a high potential to impact Tribal Cultural resources due to being in the area of the traditional community of *Wininga* as well as sacred water ways and traditional trade routes. In place of a meeting the Kizh Nation sent Ms. Machado attachments providing information of the Tribe's history, traditional territory, maps and excerpts from published sources providing their history, cultural background and settlements. The Kizh Nation also submitted two recommended mitigation measures. These measures were adopted following approval by the applicant and Ms. Machado informed the tribe October 8, 2024 that they had been adopted (M. Machado, personal communication to S. O'Neil; October 7, 2024; October 8, 2024). On October 11 the Kizh Nation acknowledged that their mitigation measures had been adopted and at the tribe's request on October 14th Ms. Machado confirmed the use of their mitigation measures. With this consultation was concluded (M. Machado, personal communication to S. O'Neil; October 15, 2024).

The Native American Heritage Commission's SLF search was negative for recorded traditional sites in the project region. No resources as defined by Public Resources Code § 21074 have been identified (refer to Attachment C: "Native American Heritage Commission Records Search and Native American Contacts" in **Appendix D** to this IS/MND). Additionally, the project site has not been recommended for historic designation for prehistoric and TCRs. No specific tribal resources have been identified.

No prehistoric or archaeological resources were observed during the field survey. The SCCIC CHRIS records search was negative for prehistoric resources either in the project site or the surrounding 0.5-mile buffer zone.

Land at the project site has extensively disturbed due to road and freeway on-ramp construction surrounding the property and development of the car dealership itself. No human remains have been previously identified or recorded onsite. Therefore, the potential for subsurface prehistoric cultural deposits is considered to be low.

The project proposes demolition of several buildings and shallow grading. Grading activities associated with development of the project would involve new subsurface disturbance and could result in the unanticipated discovery of unknown human remains, including those interred outside of formal cemeteries. Implementation of mitigation measures **TCR-1** provides for tribal monitoring of subsurface construction work; in the event of an unexpected discovery implementation of **TCR-2**



provides for dealing with the findings by the tribe, and **TCR-3** deals with the unanticipated discovery of human remains and associated funerary objects. (**MM CR-3** in **Section 4.5 Cultural Resources** above also deals with human remains.) These three **TCR MMs** are recommended to ensure that impacts related to the accidental discovery of cultural resources and human remains would be less than significant.

Mitigation Measures

MM-TCR-1: Retain a Native American Monitor Prior to Commencement of Ground-Disturbing Activities

- A. The project applicant/lead agency shall retain a Native American Monitor from or approved by the Gabrieleño Band of Mission Indians – Kizh Nation. The monitor shall be retained prior to the commencement of any “ground-disturbing activity” for the subject project at all project locations (i.e., both on-site and any off-site locations that are included in the project description/definition and/or required in connection with the project, such as public improvement work). “Ground disturbing activity” shall include, but is not limited to, demolition, pavement removal, potholing, auguring, grubbing, tree removal, boring, grading, excavation, drilling, and trenching.
- B. A copy of the executed monitoring agreement shall be submitted to the lead agency prior to the earlier of the commencement of any ground-disturbing activity, or the issuance of any permit necessary to commence a ground-disturbing activity.
- C. The monitor will complete daily monitoring logs that will provide descriptions of the relevant ground-disturbing activities, the type of construction activities performed, locations of ground disturbing activities, soil types, cultural-related materials, and any other facts, conditions, materials, or discoveries of significance to the Tribe. Monitor logs will identify and describe any discovered TCRs, including but not limited to, Native American cultural and historical artifacts, remains, places of significance, etc., (collectively, tribal cultural resources, or “TCR”), as well as any discovered Native American (ancestral) human remains and burial goods. Copies of monitor logs will be provided to the project applicant/lead agency upon written request to the Tribe.
- D. On-site tribal monitoring shall conclude upon the latter of the following (1) written confirmation to the Kizh from a designated point of contact for the project applicant/lead agency that all ground-disturbing activities and phases that may involve ground-disturbing activities on the project site or in connection with the project are complete; or (2) a determination and written notification by the Kizh to the project applicant/lead agency that no future, planned construction activity and/or development/construction phase at the project site possesses the potential to impact Kizh TCRs.

MM-TCR-2: Unanticipated Discovery of Tribal Cultural Resource Objects (Non-Funerary/Non-Ceremonial)

- A. Upon discovery of any TCRs, all construction activities in the immediate vicinity of the discovery shall cease (i.e., not less than the surrounding 50 feet) and shall not resume until the discovered TCR has been fully assessed by the Kizh monitor and/or Kizh archaeologist. The Kizh will recover and retain all discovered TCRs in the form and/or manner the Tribe deems appropriate, in the Tribe’s sole



❖ SECTION 4.18 – TRIBAL CULTURAL RESOURCES ❖

discretion, and for any purpose the Tribe deems appropriate, including for educational, cultural and/or historic purposes.

MM-TCR-3: Unanticipated Discovery of Human Remains and Associated Funerary or Ceremonial Objects

- A. Native American human remains are defined in PRC 5097.98 (d)(1) as an inhumation or cremation, and in any state of decomposition or skeletal completeness. Funerary objects, called associated grave goods in Public Resources Code Section 5097.98, are also to be treated according to this statute.
- B. If Native American human remains and/or grave goods are discovered or recognized on the project site, then Public Resource Code 5097.9 as well as Health and Safety Code Section 7050.5 shall be followed.
- C. Human remains and grave/burial goods shall be treated alike per California Public Resources Code section 5097.98(d)(1) and (2).
- D. Preservation in place (i.e., avoidance) is the preferred manner of treatment for discovered human remains and/or burial goods.
- E. Any discovery of human remains/burial goods shall be kept confidential to prevent further disturbance.

Level of Significance After Mitigation

With implementation of mitigation measures **TCR-1** through **TCR-3**, the proposed project would have less than significant impacts regarding Tribal Cultural Resources.



Level of Significance After Mitigation

With implementation of **MM TCR-1**, potential project impacts on TCRs would be less than significant. With implementation of Mitigation Measures **MM TCR-2** and **MM TCR-3** above, the proposed project would result in less than significant impacts to human remains and associated funerary objects.

**4.19 Utilities and Service Systems**

Would the project:	Potentially Significant Impact	Less than Significant Impact with Mitigation Incorporated	Less than Significant Impact	No Impact
a) Require or result in the relocation or construction of new or expanded water wastewater treatment or storm water drainage, electric power, natural gas, or telecommunications facilities, the construction or relocation of which could cause significant environmental effects?			X	
b) Have sufficient water supplies available to serve the project and reasonably foreseeable future development during normal, dry and multiple dry years?			X	
c) Result in a determination by the wastewater treatment provider which serves or may serve the project that it has adequate capacity to serve the project's projected demand in addition to the provider's existing commitments?			X	
d) Generate solid waste in excess of State or local standards, or in excess of the capacity of local infrastructure, or otherwise impair the attainment of solid waste reduction goals?			X	
e) Comply with federal, state, and local management and reduction statutes and regulations related to solid waste?			X	

- a) **Would the project require or result in the relocation or construction of new or expanded water, wastewater treatment or storm water drainage, electric power, natural gas, or telecommunications facilities, the construction or relocation of which could cause significant environmental effects?**

Less than Significant Impact

Domestic Water - As detailed in Threshold 4.19 b) below, the project would have sufficient water supplies available to serve it for reasonably foreseeable future development during normal, dry, and multiple dry years. Additionally, no off-site improvements are proposed for the needed utilities. Therefore, impacts would be less than significant.

Wastewater Treatment and Conveyance - As detailed in Threshold 4.19 c) below, the current wastewater conveyance and treatment system servicing the project site would serve the proposed



project adequately. Therefore, impacts would be less than significant.

Storm Water – The project includes the demolition of the existing parking lot and buildings with the subsequent construction of a new automotive dealership building with onsite parking. The proposed utilities will connect to the existing utilities at the property line. Other enhancements include the installation of an underground basin to retain water, the addition of commercial landscaping, and the installation of the necessary utilities (CDR, 2024a, p. 2).

The project area will be regraded to manage stormwater on site. The excess water from the project will be released and directed into an underground basin for infiltration on the premises. If there is an overflow of the runoff, it will be discharged into the public catch basin located along Garvey Avenue. From there, it will be guided into the existing public storm drain system underneath Azusa Avenue (CDR, 2024a, p. 2).

The project site is situated in the Los Angeles River Watershed, which falls under the jurisdiction of the Los Angeles Regional Water Quality Control Board (LARWCB). The existing curb inlets that collect runoff and channel it towards E Garvey Avenue are owned by LACFCD. Eventually, the LACFCD storm drain system directs all runoff from the project site to the Walnut Creek Channel, which then ultimately discharges to the Pacific Ocean (CDR, 2024a, p. 5).

The City of West Covina has a Watershed Management-focused Stormwater Management Program Plan in accordance with Order R4-2012-0175, NPDES Permit No. CAS4001 (NPDES/MS4 Permit), Waste Discharge Requirements for Municipal Separate Storm Sewer System Discharges within the Coastal Watersheds of Los Angeles County. The West Covina has been a permittee to the Los Angeles County MS4 program since 1993. It has been a permittee designated under the 1990, 1996, and 2001 MS4 permits. The program regulates, through Order No. R4-2012-0175, the discharge of pollutants into the Waters of the U.S. through stormwater and urban runoff conveyance systems, including flood control facilities. (City of West Covina, 2014).

The NPDES/MS4 Permit requires that the Los Angeles County Flood Control District, the County of Los Angeles, and 84 other municipalities (including West Covina) within the County of Los Angeles comply with the prescribed elements of the MS4 Permit. Compliance with the MS4 Permit requires that new developments and significant redevelopment projects incorporate post-construction low impact development (LID) BMPs into the project design to minimize the amount of stormwater discharged from the project site (CDR, 2024a, p. 6).

According to the Los Angeles County Low Impact Development Standards Manual (LACPW, 2014), the project falls under 'Designated Project' because the project proposes more than 10,000 square feet of additional impervious surface area. Designated Projects are required to retain 100 percent of the stormwater quality design volume onsite through infiltration, evapotranspiration, stormwater runoff harvest, and use, or a combination thereof (LACPW, 2014, p 1-8).

As discussed in **Section 4.10**, a Low-Impact Development Plan (LID Plan; CDR, 2024b) has been prepared for the proposed project site and is included as **Appendix G2**. The use of LID BMPs in project planning and design is intended to preserve a site's predevelopment hydrology by minimizing the loss of natural hydrologic processes such as infiltration, evapotranspiration, and runoff detention. LID BMPs try to offset these losses by introducing structural and non-structural design components that restore this water quality functions into the project's land plan (LACPW, 2014, p. 1-5). With the implementation of construction and operational BMPs, the potential impacts on stormwater drainage would have a less than significant impact.



Electric Power - Southern California Edison (SCE) provides electric power for the project site (City of West Covina, 2016a). The project site is located in a developed area and the infrastructure for providing electric power to the area is well established. The proposed project would connect to existing electrical lines on the property. The project would be constructed in accordance with all applicable California Code of Regulations Title 24 provisions and would not require the construction or relocation of electric power facilities. Therefore, any impact would be less than significant.

Natural Gas: Southern California Gas Company (SoCalGas) supplies natural gas service to the City of West Covina (Rincon, 2016). In its 2022 California Gas Report, SoCalGas analyzed a 16-year demand period from 2022 to 2035, to determine its ability to meet the projected demand. Under the base case, gas demand for the entire state is projected to average 5,298 million cubic feet of gas per day (MMcf/d) in 2022, decreasing to 4,857 MMcf/d by 2035, a decline of 0.67 percent per year (CGEU, 2022, p. 7). Therefore, the expected natural gas supply is adequate to meet demand in the SoCalGas region, and the proposed project is not expected to impact this determination. Thus, no natural gas facilities would have to be constructed or relocated and would have a less than significant impact.

Telecommunications Facilities: Telecommunication services, including internet, telephone, and television, on and near the project site are provided by AT&T, Spectrum, and Frontier Communications (InMyArea, 2024). The development of the project would not interfere with the operation of telecommunications facilities and would have a less than significant impact.

- b) **Would the project have sufficient water supplies available to serve the project and reasonably foreseeable future development during normal, dry and multiple dry years?**

Less than Significant

Multiple water agencies provide water service in the City. Most areas, including the project site, are served by Suburban Water Systems (Suburban), an investor-owned water utility under the Southwest Water Company (SWC). Groundwater accounts for around 80 percent of Suburban's water supply, with additional sources including imported surface water, local surface water supplies, and recycled water (Rincon, 2016, p. 265). Suburban Water Systems serves a population of about 300,000 through a water distribution system that includes 20 wells, 34 reservoirs, and more than 870 miles of pipeline with a network of facilities and pumps that distributes approximately 45,000 acre-feet of water annually (SWC, 2024).

The Suburban service area is currently divided into two main service areas: the San Jose Hills service area and the Whittier/La Mirada service area. The project is located within the San Jose Hills service area (Suburban, 2021, p. 1-8). The San Jose Hills service area encompasses approximately 24.17 square miles (15,470 acres) and is the successor of the former San Jose Hills Water Company. The service area is located primarily along the south and east sides of the San Gabriel Valley, from just north of the San Bernardino Freeway (I-10) to south of the Pomona Freeway (I-60). The Service Area has a total of approximately 42,700 service connections within the cities of Glendora, Covina, West Covina, La Puente, and Walnut, as well as unincorporated areas of Los Angeles County (Suburban, 2021, p. 1-8).

Groundwater - The City of West Covina receives groundwater from Suburban and other agencies from the Main San Gabriel Groundwater Basin and Central Basin (Rincon, 2016, p. 265). The main San Gabriel Basin measures 167 square miles and contains an estimated 8.6 million acre-feet of water. The Central Basin spans 278 square miles and has a capacity to store 13 million acre-feet of



❖ SECTION 4.19 – UTILITIES AND SERVICE SYSTEMS ❖

water (Suburban, 2021, p. 3-10)

Surface Water - West Covina receives its local surface water supply from the San Gabriel River, which originates in the San Gabriel Mountains north of the city. This water is diverted by Azusa Light and Water and the Covina Irrigation District. The Covina Irrigation District sells water to the City of Covina, Suburban Water Systems, Valencia Heights Water Company, and the Valley County Water District (Rincon, 2016, p. 265).

Imported Water - Water agencies in West Covina receive their imported water from the Metropolitan Water District of Southern California (MWD). MWD moves water from the Colorado River through the Colorado River Aqueduct and from the State Water Project through the California Aqueduct. Before supplying the city, imported water is treated at MWD's Weymouth Treatment Plant. Rather than buying directly from MWD, Suburban Water Systems purchases its imported water from local agencies such as the Upper San Gabriel Valley Municipal Water District, Covina Irrigation Company, City of Glendora, and Walnut Valley Water District Walnut Creek (Suburban, 2021, p. 2-2).

Projected supplies during single and multiple dry-year scenarios indicate that MWD's projected supply will exceed its projected single and multiple dry-year demand in all years. Likewise, for normal years, MWD supply exceeds the projected demand for all years (Suburban, 2021, p. 5-1).

As shown in **Table 4.19-1**, it is estimated that the project would have a daily water demand of approximately 2,599 gallons per day (gpd) or an annual demand of 2.9 acre-feet based on the projection that customers within Suburban's service area generate wastewater based on 80 percent of potable water demand (Suburban, 2021, p. 6-1). The Retail Area (less than 100,000 SF) of the Sewage Generation Factors Chart from the Los Angeles Bureau of Sanitation was used as the closest option to the proposed automotive dealership.

Table 4.19-1
ESTIMATE PROJECT WATER DEMAND

Land Use	Quantity (sq. ft.)	Wastewater Generation Rate (gpd/1,000 sf)	Daily Demand (gpd)	Annual Demand (afy)
Retail Area (<100,000 sf)	86,642	25	2,599	2.9

Note: sf. ft. = square feet; gpd = gallons per day; afy=acre-feet per year

Note: Daily Demand = $((86,642 \div 1,000) * 25) * 1.2$ (120 percent) = 2,599.26

Sources: Los Angeles Bureau of Sanitation, Sewage Generation Factors, April 2012 (City of Los Angeles, 2021);

Suburban Water Systems 2020 Urban Water Management Plan, June 2021 (Suburban, 2021).

The San Jose Hills Service Area is projected to have an average excess of 11,242 acre-feet per year (afy) between 2025 and 2045 as shown in **Table 4.19-2**. **Tables 4.19-3** through **4.19-5** summarize the supply and demand comparisons during the normal, single-dry, and multiple-dry year scenarios for San Jose Hills Service Area.

Table 4.19-2
SUPPLY & DEMAND PREDICTIONS FOR THE SAN JOSE HILLS SERVICE AREA BY SOURCE (afy)

Supply Source	2025	2030	2035	2040	2045
Potable Water, Raw, Other Non-potable	24,089	24,328	24,570	24,815	25,062
Recycled Water Demand	700	700	700	700	700
Total Water Demand	24,789	25,028	25,270	25,515	25,762



❖ SECTION 4.19 – UTILITIES AND SERVICE SYSTEMS ❖

Groundwater	16,715	16,715	16,715	16,715	16,715
Recycled Water Demand	700	700	700	700	700
Imported Water	18,200	18,200	18,200	18,200	18,200
Total Water Supply	35,615	35,615	35,615	35,615	35,615
Difference	10,826	10,587	10,345	10,100	9,853
Potential Impact	0.02%	0.02%	0.02%	0.02%	0.02%

Source: Suburban, 2021, p. 2-24 and p. 3-31

Table 4.19-3

SAN JOSE HILLS SERVICE AREA NORMAL YEAR SUPPLY & DEMAND COMPARISON (afy)

	2025	2030	2035	2040	2045
Supply totals	35,615	35,615	35,615	35,615	35,615
Demand totals	24,789	25,028	25,270	25,515	25,762
Difference	10,826	10,587	10,345	10,100	9,853
Potential Impact	0.02%	0.02%	0.02%	0.02%	0.02%

Source: Suburban, 2021, p. 5-2

Table 4.19-4

SAN JOSE HILLS SERVICE AREA SINGLE DRY YEAR SUPPLY & DEMAND COMPARISON (afy)

	2025	2030	2035	2040	2045
Supply totals	29,579	29,579	29,579	29,579	29,579
Demand Totals	25,535	25,782	26,032	26,285	26,538
Difference	4,044	3,797	3,547	3,294	3,041
Potential Impact	0.06 percent	0.06 percent	0.07 percent	0.07 percent	0.08 percent

Source: Suburban, 2021, p. 5-2

Table 4.19-5

SAN JOSE HILLS SERVICE AREA MULTIPLE DRY YEAR SUPPLY & DEMAND COMPARISON (afy)

	2025	2030	2035	2040	2045
First Year					
Supply totals	33,945	33,945	33,945	33,945	33,945
Demand totals	24,374	24,610	24,848	25,088	25,331
Difference	9,571	9,335	9,097	8,857	8,614
Potential Impact	0.03%	0.03%	0.03%	0.03%	0.03%
Second Year					
Supply totals	32,893	32,893	32,893	32,893	32,893
Demand totals	24,374	24,610	24,848	25,088	25,331
Difference	8,519	8,283	8,045	7,805	7,562
Potential Impact	0.03%	0.03%	0.03%	0.03%	0.03%
Third Year					
Supply totals	32,481	32,481	32,481	32,481	32,481
Demand totals	24,374	24,610	24,848	25,088	25,331
Difference	8,107	7,871	7,633	7,393	7,150
Potential Impact	0.03%	0.03%	0.03%	0.03%	0.03%
Fourth Year					
Supply totals	29,579	29,579	29,579	29,579	29,579
Demand totals	24,374	24,610	24,848	25,088	25,331
Difference	5,205	4,969	4,731	4,491	4,248
Potential Impact	0.05%	0.05%	0.05%	0.05%	0.06%



❖ SECTION 4.19 – UTILITIES AND SERVICE SYSTEMS ❖

	2025	2030	2035	2040	2045
Fifth Year					
Supply totals	36,662	36,662	36,662	36,662	36,662
Demand totals	24,374	24,610	24,848	25,088	25,331
Difference	12,288	12,052	11,814	11,574	11,331
Potential Impact	0.02%	0.02%	0.02%	0.02%	0.02%

Source: Suburban, 2021, p. 5-3.

The project would require approximately 0.02 percent of the average water distributed by the water sources of the San Jose Hills service area through 2045. The impact of the project on excess water supply in normal, single, and multiple dry years would have projected demand of from a low of 0.02 percent during normal years to a high of 0.08 percent for a single dry year in 2045.

The project would not require or result in the construction of new water treatment facilities or the expansion of existing facilities and would have sufficient water supply available for the reasonably foreseeable future during normal, dry and multiple dry years. Furthermore, the project applicant would be obliged to implement the applicable requirements of the 2022 California Green Building Standards Code (CALGreen) that would further reduce water demand. The impact on water supply would be less than significant.

- c) **Would the project result in a determination by the wastewater treatment provider which serves or may serve the project that it has adequate capacity to serve the project's projected demand in addition to the provider's existing commitments?**

Less than Significant Impact

The City of West Covina Public Works Department operates and maintains sewers within the City of West Covina, including the project site (City of West Covina, 2017, p. 15). The wastewater from the project site is transferred through the municipal wastewater infrastructure maintained by the Los Angeles Bureau of Sanitation to the San Jose Creek Water Reclamation Plant (WRP), a public facility subject to the requirements of the Los Angeles Regional Water Quality Control Board (RWQCB). The San Jose Creek Water Reclamation Plant consists of two hydrologically interconnected facilities located on the east and west side of the San Gabriel River (I-605) highway. Currently, it provides primary, secondary, and tertiary treatment with a design capacity of 100 million gallons of wastewater per day (MGD).

The City of West Covina sewers receive and transport approximately 14.1 MGD of wastewater. This waste flows to the regional trunk sewer and wastewater treatment plant. The City service area covers 17 square miles, and its wastewater collection system consists of 227 miles of community sewer facilities, with 31 miles of regional trunk sewer (owned and operated by Los Angeles County) also located within the city area (City of West Covina, 2017).

Los Coyotes Water Reclamation Plant has a capacity of 37.5 MGD; Average effluent flows in 2021 were 17.52 mgd (LACSD, 2022a, p. 1-1), for a residual capacity of approximately 19.98 MGD. Auto sales are estimated to generate 100 gallons per day (gpd) of wastewater per 1,000 square feet (LACSD, 2022b). The proposed project would develop an automotive dealership of approximately 86,642 square feet. The project operation is estimated to generate 8,664 gpd of wastewater. In the region, there is sufficient wastewater treatment capacity for project-generated wastewater, and project development would not require the construction of new or expanded wastewater treatment facilities. Impacts would be less than significant.



- d) **Would the project generate solid waste in excess of State or local standards, or in excess of the capacity of local infrastructure, or otherwise impair the attainment of solid waste reduction goals?**

Less than Significant Impact

The City of West Covina is contracted with Athens Services to provide trash, recycling, and special pickup services throughout the City. Details regarding waste haulers, transfer stations, and landfills are provided below (Rincon, 2016, p. 271).

Waste Haulers - Athens Services offers waste management and recycling services to households, as well as commercial, governmental, and industrial establishments located in West Covina. Athens Services has entered into an agreement with the City for the provision of these services.

Transfer Stations - Transfer stations are facilities that move waste from small vehicles to larger transfer trailers or railway cars, which are then used to transport the waste to a remote landfill. A Materials Recovery Facility (MRF) serves as both a transfer station for waste and a location for sorting and categorizing mixed materials, such as glass, plastic, cardboard, and more. Once these materials are separated, they are sent to recycling firms for further processing.

In contrast, a "dirty" MRF specializes in sorting and retrieving recyclables from the waste stream. Following collection, the waste is transported to the Athens Services MRF situated in the City of Industry. This particular MRF boasts a processing capability of 5,000 tons of mixed materials per day (Rincon, 2016, p. 271).

Landfills. The remaining waste, which is not recycled, is routed to a remote landfill. After the waste is sorted at the Athens MRF, the material that cannot be recycled is sent to the Victorville Sanitary Landfill. **Table 4.19-6** summarizes the permitted daily throughput, estimated average waste quantities disposed, and remaining capacity for the Victorville Landfill.

Table 4.19-6
LANDFILLS SERVING WEST COVINA

Landfill	Remaining Capacity (cubic yards)	Daily Permitted Disposal Capacity (tons)	Actual Daily Disposal, (tons) ¹	Residual Daily Disposal Capacity (tons)	Estimated Closing Date
Victorville Landfill	79,400,000	3,000	1,294	1706	10/1/2047

1. Daily disposal calculated based on annual disposal tonnage assuming 300 operating days per year: 6 days/week less holidays.

Sources: CalRecycle. 2024a/b.

Construction - Construction of the project would generate solid waste that would be disposed of in local landfills. Materials generated during the construction of the project would include paper, cardboard, metal, plastics, glass, concrete, lumber scrap, and other materials. Section 4.408 of the 2022 California Green Building Standards Code (CALGreen; California Code of Regulations, Title 24, Part 11) requires that at least 65 percent of non-hazardous construction and demolition waste from residential construction operations be recycled and/or salvaged for reuse. Project construction would include recycling and/or salvaging at least 65 percent of construction and demolition waste according to the 2022 CALGreen.



Operation

The CalRecycle Solid Waste Generation Rates estimate an auto dealer has a generation rate of 0.9 pounds per 100 square feet per day (CalRecycle, 2024c). The project proposes a 85,390 square foot building area. The proposed auto dealer would generate an estimated 768.51 pounds of solid waste per day as shown in **Table 4.19-7**. The estimated project operational solid waste disposal of 140.25 tons per year is approximately 0.08 percent of the remaining annual disposal capacity at Victorville Landfill. Sufficient landfill capacity is available in the region for estimated project solid waste generation, and the impact of the project on solid waste disposal capacity would be less than significant.

Table 4.19-7
ESTIMATED PROJECT-GENERATED SOLID WASTE

Land Use	Generation Rate*	Approximate Waste	Approximate Waste
Auto Dealer / Service Station	0.9 lbs. / 100 sq. ft. / day	768.51 lbs./day	140.25 tons/yr.

*CalRecycle, 2024c

- e) **Would the project comply with federal, state, and local management and reduction statutes and regulations related to solid waste?**

Less Than Significant Impact

State - In 1989, the California Legislature enacted the California Integrated Waste Management Act (AB 939), to address solid waste problems and capacity comprehensively. The law required each city and county to divert 50 percent of its waste from landfills by the year 2000.

Assembly Bill 1826 (AB 1826; California Public Resources Code § 42649.8 et seq.) requires the recycling of organic matter by businesses and multifamily residences of five or more units, generating such waste in amounts over certain thresholds. Organic waste means food waste, green waste, landscape and pruning waste, nonhazardous wood waste, and food-soiled paper waste that is mixed in with food waste.

Senate Bill 1383 (SB 1383; California Health and Safety Code § 39730.5 et seq.) set targets to achieve a 50 percent reduction in the level of statewide disposal of organic waste from the 2014 level by 2020 and a 75 percent reduction by 2025. The law is intended to reduce the emissions of methane, a short-lived climate pollutant, from the decomposition of organic waste in landfills, for the protection of people in at-risk communities as well as to reduce GHG emissions.

Section 5.408 (Construction Waste Reduction, Disposal, and Recycling) of the 2022 California Green Building Standards Code (CALGreen; Title 24, California Code of Regulations, Part 11) requires that at least 65 percent of the nonhazardous construction and demolition waste from nonresidential construction operations be recycled and/or salvaged for reuse.

Assembly Bill 341 (AB 341; Chapter 476, Statutes of 2011) increases the statewide waste diversion goal to 75 percent by 2020 and mandates recycling for commercial and multifamily residential land uses. The project would include storage areas for recyclable materials according to AB 341.



❖ SECTION 4.19 – UTILITIES AND SERVICE SYSTEMS ❖

Local - Los Angeles Countywide Integrated Waste Management Plan. The Los Angeles Countywide Integrated Waste Management Plan (CIWMP), adopted by the Los Angeles County Board of Supervisors in January 1998 and approved by CalRecycle in June 1999, outlines a means of addressing the County's long-term refuse disposal needs in compliance with AB 939. The CIWMP is composed of the Los Angeles Countywide Summary Plan, the Source Reduction and Recycling Element (SRRE) for the County, the Nondisposal Facility Element (NDFE) for the County, the Household Hazardous Waste Element (HHWE) for the County, and the Los Angeles Countywide Siting Element. (Rincon, 2016, pp. 276-277).

The proposed project would comply with applicable local, state, and federal solid waste disposal standards; therefore, the impacts would be less than significant.

**4.20 Wildfire**

If located in or near state responsibility areas or lands classified as very high fire hazard severity zones, would the project:	Potentially Significant Impact	Less than Significant Impact with Mitigation Incorporated	Less than Significant Impact	No Impact
a) Substantially impair an adopted emergency response plan or emergency evacuation plan?				X
b) Due to slope, prevailing winds, and other factors, exacerbate wildfire risks, and thereby expose project occupants to, pollutant concentrations from a wildfire or the uncontrolled spread of a wildfire?				X
c) Require the installation or maintenance of associated infrastructure (such as roads, fuel breaks, emergency water sources, power lines or other utilities) that may exacerbate fire risk or that may result in temporary or ongoing impacts to the environment?				X
d) Expose people or structures to significant risks, including downslope or downstream flooding or landslides, as a result of runoff, post-fire slope instability, or drainage changes?				X

- a) **If located in or near state responsibility areas or lands classified as very high fire hazard severity zones, would the project substantially impair an adopted emergency response plan or emergency evacuation plan?**

No Impact

As shown in **Figure 4.9-3** in **Section 4.9** of this Initial Study, the project site is not located in or near an State Responsibility Area (SRA), i.e., where the State is responsible for the costs of wildfire prevention and suppression. The nearest SRA is approximately 2.4 miles southeast of the project site. The project site is also not located in or near a Very High Fire Hazard Severity Zone (VHFHSZ) within a Local Responsibility Area (LRA), that is, where cities or counties are responsible for the costs of wildfire prevention and suppression. As shown in **Figure 4.9-4**, the nearest VHFHSZ in an LRA to the project site is about 1.6 miles southeast of the project site. Therefore, the project would not substantially impair an adopted emergency response plan or emergency evacuation plan concerning fire hazard severity zones and no impact would occur.

- b) **If located in or near state responsibility areas or lands classified as very high fire hazard severity zones, would the project due to slope, prevailing winds, and other factors, exacerbate wildfire risks, and thereby expose project occupants to, pollutant concentrations from a wildfire or the uncontrolled spread of a wildfire?**



No Impact

The project site is not located in or near a VHFHSZ. The project site is not located on or near a slope that could exacerbate the risks of wildfires. The Santa Ana winds can cause extreme winds in the San Gabriel Valley and the western portions of Los Angeles County. These winds can occur at any time of the year, but are most known for bringing hot, dry weather and low humidity, typically between October and March (NWS, 2024). Being situated roughly the middle of the San Gabriel Valley, West Covina would be no more susceptible to the Santa Ana winds than most of the San Gabriel Valley. Therefore, the project would not expose the project occupants to pollutant concentrations from a wildfire or the uncontrolled spread of a wildfire and would have no impact in this regard.

- c) **If located in or near state responsibility areas or lands classified as very high fire hazard severity zones, would the project require the installation or maintenance of associated infrastructure (such as roads, fuel breaks, emergency water sources, power lines or other utilities) that may exacerbate fire risk or that may result in temporary or ongoing impacts to the environment?**

No Impact

The project site is not located in or near an SRA, nor is the project site in or near a VHFHSZ. The project would not require the installation or maintenance of infrastructure that can improve fire risk. Therefore, the proposed project would have no impact in this regard.

- d) **If located in or near state responsibility areas or lands classified as very high fire hazard severity zones, would the project expose people or structures to significant risks, including downslope or downstream flooding or landslides, as a result of runoff, post-fire slope instability, or drainage changes?**

No Impact

As discussed above, the project site is not located in or near an SRA or land classified as VHFHSZ. The proposed project would not expose people or structures to significant risks, including downslope or downstream flooding or landslides, as a result of runoff, post-fire slope instability, or drainage changes. As detailed in **Section 4.7** of this Initial Study, the project site is relatively flat, is not in an area with high slopes or unstable ground conditions and is not within a landslide hazard zone (refer to **Figure 4.7-3**). Therefore, the project would have no impact in this regard.

**4.21 Mandatory Findings of Significance**

Would the project have:	Potentially Significant Impact	Less than Significant Impact with Mitigation Incorporated	Less than Significant Impact	No Impact
a) Does the project have the potential to substantially degrade the quality of the environment, substantially reduce the habitat of a fish or wildlife species, cause a fish or wildlife population to drop below self-sustaining levels, threaten to eliminate a plant or animal community, substantially reduce the number or restrict the range of a rare or endangered plant or animal or eliminate important examples of the major periods of California history or prehistory?		X		
b) Does the project have impacts that are individually limited, but cumulatively considerable? ("Cumulatively considerable" means that the incremental effects of a project are considerable when viewed in connection with the effects of past projects, the effects of other current projects, and the effects of probable future projects)?			X	
c) Does the project have environmental effects which will cause substantial adverse effects on human beings, either directly or indirectly?		X		

- a) **Would the project have the potential to substantially degrade the quality of the environment, substantially reduce the habitat of a fish or wildlife species, cause a fish or wildlife population to drop below self-sustaining levels, threaten to eliminate a plant or animal community, substantially reduce the number or restrict the range of a rare or endangered plant or animal or eliminate important examples of the major periods of California history or prehistory?**

Less Than Significant Impact with Mitigation Incorporated

Section 4.4 of this Initial Study discusses Biological Resources. As noted, the project site is currently built-out with a car dealership and a gas station and is located in completely developed urban surroundings. On the site, minor amounts of ornamental landscaping are present, in addition to street trees along the perimeter of the site along Azusa Avenue and East Garey Avenue. There is no natural habitat suitable for special-status species and there are no sensitive natural communities on site. The trees on site could provide foraging, nesting, and cover habitats to support multiple species of birds. Most bird species occurring in California are protected by the federal Migratory Bird Treaty Act



❖ SECTION 4.21 – MANDATORY FINDINGS OF SIGNIFICANCE ❖

(MBTA) and by California Fish and Game Code § 3503, § 3503.5, and § 3513. Mitigation measure **BIO-1** would reduce potential project impacts on wildlife to a less than significant level.

As examined in **Section 4.5**, Cultural Resources, it was determined that no historical cultural resources or prehistoric archeological sites have been previously recorded within the project site boundary. The findings of the cultural resources study suggest that there is a low potential for the presence of prehistoric cultural resources. The project site is disturbed by several decades of urban development. However, if prehistoric and/or historic items are observed during subsurface activity or during the unlikely discovery of human remains, mitigation measures **CUL-1** and **CUL-2** are recommended.

As detailed in **Section 4.18**, Tribal Cultural Resources, activities associated with the development of the project would involve new subsurface disturbance and could result in the unanticipated discovery of unknown human remains, including those interred outside of formal cemeteries. In the unlikely event of an unexpected discovery, the implementation of mitigation measures **TCR-1** and **TCR-2** dealing tribal monitoring and the unanticipated discovery of TCRs, and **TCR-3** dealing with human remains and associated funerary objects is recommended.

As per **Section 4.7**, Geology and Soils, excavation or grading associated with the proposed project that goes beyond the surface soil layers and deeper into late Pleistocene sediments in the project area can uncover vertebrate fossil remains. The impacts resulting from the unexpected discovery of paleontological resources that may be related to major periods of California history or prehistory would be less than significant with the implementation of the mitigation measure **GEO-1**.

The implementation of mitigation measures **BIO-1**, **CUL-1**, **CUL-2**, **TCR-1**, **TCR-2**, **TCR-3** and **GEO-1** would reduce the potential impacts on plants, animals, and important examples of the major periods of California history or prehistory to a less than significant level.

- b) Would the project have impacts that are individually limited, but cumulatively considerable? ("Cumulatively considerable" means that the incremental effects of a project are considerable when viewed in connection with the effects of past projects, the effects of other current projects, and the effects of probable future projects)?**

Less than Significant Impact

The proposed project would be consistent with regional plans and programs that address environmental factors such as air quality, water quality, and other applicable regulations that have been adopted by public agencies with jurisdiction over the project for avoiding or mitigating environmental effects. In **Sections 4.1** through **4.20**, all impacts are less than significant with mitigation incorporated. Therefore, without significant impacts, the proposed project would not be cumulatively significant and would have a less than significant impact.

- c) Would the project have environmental effects which will cause substantial adverse effects on human beings, either directly or indirectly?**

Less than Significant Impact with Mitigation Incorporated

Archaeological resources may be buried in site soils and could be damaged by project ground-disturbing activities. This impact would be significant without mitigation. Implementing the mitigation measure **CUL-1** would reduce this impact to less than significant. Impacts on human remains that can be buried in the soils of the site were determined to be significant without



❖ SECTION 4.21 – MANDATORY FINDINGS OF SIGNIFICANCE ❖

mitigation. Implementing the mitigation measure **CUL-2** would reduce this impact to less than significant.

As mentioned above, excavation or grading that penetrates into late Pleistocene sediments within the project area may come across vertebrate fossil remains, potentially resulting in unexpected paleontological resource findings which could cause substantial adverse effects on human beings. The impacts related to the unanticipated discovery of paleontological resources would be less than significant after the implementation of the mitigation measure **GEO-1**.

Tribal cultural resources could be buried in site soils. The grading of the project site and the construction of the project could damage such resources. Implementing mitigation measures **TCR-1**, **TCR-2** and **TCR-3** would reduce these impacts to less than significant.

The implementation of mitigation measures **CUL-1**, **CUL-2**, **TCR-1**, **TCR-2**, **TCR-3**, and **GEO-1** would reduce the environmental effects which could potentially cause adverse effects on human beings to a less than significant level.



5.0 REFERENCES

- ARB, 2008. Climate Change Scoping Plan: a framework for change. California Air Resources Board. December 2008.
- ARB, 2011. Final Supplement to the AB 32 Scoping Plan Functional Equivalent Document. California Air Resources Board. August 19, 2011.
- ARB, 2014. First Update to the Climate Change Scoping Plan, Building on the Framework. California Air Resources Board. May 2014.
- ARB, 2021. GHG Emission Inventory Graphs. Available at <https://ww2.arb.ca.gov/ghg-inventory-graphs>, Accessed online on May 7, 2024.
- ARB, 2022a. Maps of State and Federal Area Designations. Accessed online at <https://ww2.arb.ca.gov/resources/documents/maps-state-and-federal-area-designations>, accessed online on May 3, 2024.
- ARB, 2022b. CARB approves unprecedented climate action plan to shift world's 4th largest economy from fossil fuels to clean and renewable energy. Accessed Online at <https://ww2.arb.ca.gov/news/carb-approves-unprecedented-climate-action-plan-shift-worlds-4th-largest-economy-fossil-fuels>, on May 7, 2024
- ARB, 2022c. Emission FACTor (EMFAC). EMFAC2021 (v1.0.2) Emissions Inventory. Accessed online at <https://arb.ca.gov/emfac/emissions-inventory/c46d1155de837ac643abe44873185afed98bf886>, on July 18, 2024.
- ARB, 2024. iADAM Air Quality Data Statistics. California Air Resources Board. Accessed online at <http://www.arb.ca.gov/adam>, on May 3, 2024.
- Bell, Alyssa (Los Angeles County Museum of Natural History). 2024. Paleontological Records Search Results Letter. Dated April 28, 2024.
- Beltran, Peter (Project Manager), 2024. Email sent to Michael Milroy May 28, 2024. Dennis Flynn Architects.
- Beltran, Peter (Project Manager), 2024b. Email sent to Bob Reicher July 2, 2024. Dennis Flynn Architects.
- CAL FIRE (California Department of Forestry and Fire Protection), 2024. GIS Mapping and Data Analytics, GIS Layers, PDF Maps, Interactive Viewers and More. Accessed online at <https://www.fire.ca.gov/what-we-do/fire-resource-assessment-program/gis-mapping-and-data-analytics> in June 2024.
- CALCUPA, 2024. What is a CUPA. Accessed online at <https://calcupa.org/about/mission.html> on May 20, 2024.
- CalRecycle, 2024a. SWIS Facility Detail: Victorville Sanitary Landfill (36-AA-0045). Accessed online at



- <https://www2.calrecycle.ca.gov/SolidWaste/Site/Summary/2652https://www2.calrecycle.ca.gov/SWFacilities/Directory/30-AB-0035/Detail/> on June 18, 2024.
- CalRecycle, 2024b. Landfill Tonnage Reports. Accessed online at <https://www2.calrecycle.ca.gov/LandfillTipFees> on June 18, 2024.
- CalRecycle, 2024c. Estimated Solid Waste Generation Rates. Accessed online at <https://www2.calrecycle.ca.gov/wastecharacterization/general/rates> on June 18, 2024.
- Caltrans, 2024. California Department of Transportation, California Scenic Highway Mapping System. Accessed online at http://www.dot.ca.gov/hq/LandArch/16_livability/scenic_highways on April 24, 2024.
- CalRecycle, 2019. Estimated Solid Waste Generation Rates. Accessed online at <https://www2.calrecycle.ca.gov/WasteCharacterization/General/Rates>, accessed on March 24, 2022.
- CAPCOA, 2023. California Emissions Estimator Model®, Version 2022.1.1.25. California Air Pollution Control Officers Association. July 2024.
- CASGEM (California Statewide Groundwater Elevation Monitoring Program), 2022. Well Details for State Well Number 01N05W32N001S. Available at <https://www.casgem.water.ca.gov/>. Accessed on March 8, 2022.
- CBWCD (Chino Basin Water Conservation District), 2022. Where Does Our Water Come From? <https://www.cbwcd.org/386/Where-Does-Our-Water-Come-From>
- CDR (Commercial Development Resources), 2024a. Preliminary Hydrology Study for West Covina Mercedes, 1800 E Garvey Ave S, West Covina, CA 91791, APN: 8478-007-031, -025. Dated May 10, 2024.
- CDR (Commercial Development Resources), 2024b. Low Impact Development (LID) Plan for Mercedes-Benz West Covina, 1800 East Garvey Ave South, West Covina, CA 91791. Dated May 10, 2024.
- CEMA, CGS, and USC (California Emergency Management Agency, California Geological Survey, and University of Southern California). 2009. Tsunami Inundation Map for Emergency Planning: County of Los Angeles, California. Scale 1:24,000. Available at <https://www.conservation.ca.gov/cgs/tsunami/maps>.
- CGEU (California Gas & Electric Utilities), 2022. Joint Utility Biennial Comprehensive California Gas Report 2022. Accessed online at https://www.socalgas.com/sites/default/files/Joint_Utility_Biennial_Comprehensive_California_Gas_Report_2022.pdf on June 18, 2024.
- CEC (California Energy Commission), 2022a. What Drives California's Gasoline Prices?. Accessed online at <https://www.energy.ca.gov/data-reports/energy-insights/what-drives-californias-gasoline-prices#:~:text=California%20Consumption,12.4%20billion%20gallons%20during%202021,> on July 17, 2024.



- CEC, 2022b. 2022 Building Energy Efficiency Standards for Residential and Nonresidential Buildings: For the 2022 Building Energy Efficiency Standards Title 24, Part 6, and Associated Administrative Regulations in Part 1. Accessed online at <https://www.energy.ca.gov/publications/2022/2022-building-energy-efficiency-standards-residential-and-nonresidential>, on July 18, 2024.
- CEC, 2023a. Electricity Consumption by County. Accessed online at <https://ecdms.energy.ca.gov/elecbycounty.aspx>, on July 10, 2024.
- CEC, 2023b. Gas Consumption by County Accessed online at <https://ecdms.energy.ca.gov/gasbycounty.aspx>, July 10, 2024.
- Chico, T. and Koizumi, J., 2008. Final Localized Significance Threshold Methodology. South Coast Air Quality Management District, Diamond Bar, California. June 2003. Revised July 2008. Accessed online at <http://www.aqmd.gov/docs/default-source/ceqa/handbook/localized-significance-thresholds/final-lst-methodology-document.pdf?sfvrsn=2>, on July 18, 2024.
- City of Los Angeles, 2012. Bureau of Sanitation Sewerage Generation Factors. Dated April 6, 2012. Accessed online at <https://engpermitmanual.lacity.org/sewer-s-permits/technical-procedures/sewage-generation-factors-chart> on June 18, 2024.
- City of West Covina, 2016a. West Covina General Plan. Dated December 2016. Accessed online at <https://www.westcovina.org/home/showpublisheddocument/17689/637109880132000000> on April 22, 2024.
- City of West Covina, 2016b. West Covina Interactive General Plan Housing Element Revision. Dated. Adopted October 1, 2013, Amended October 20, 2016. Accessed online at <https://www.westcovina.org/home/showpublisheddocument/18140/637232598134970000> on April 22, 2024.
- City of West Covina, 2017. Sewer System Management Plan. Accessed online at <https://www.westcovina.org/departments/community-development/engineering-division/sewer-system-management-plan> June 18, 2024.
- City of West Covina, 2014. Stormwater and Watershed Management Program. Dated June 28, 2024. https://www.waterboards.ca.gov/losangeles/water_issues/programs/stormwater/municipal/watershed_management/west_covina/WC_IWMP.pdf on July 25, 2024.
- City of West Covina, 2023a. West Covina Police Department 2022 Annual Review. Accessed online at <https://www.wcpd.org/wp-content/uploads/2023/03/2022-Annual-Review-Text.pdf> on April 25, 2024.
- City of West Covina. 2023b. Master Fee Schedule. Accessed online at <https://www.westcovina.org/departments/fee-schedule> on May 17, 2024.
- City of West Covina, 2024a. West Covina Interactive Zoning Map. Accessed online at <https://www.arcgis.com/apps/webappviewer/index.html?id=eab40ffbe9b944dfa9195f75342d4986> on April 24, 2024.



❖ SECTION 5.0 - REFERENCES ❖

- City of West Covina, 2024b. City of West Covina Fire Department Map. Accessed online at <https://www.westcovina.org/departments/fire> on April 25, 2024.
- City of West Covina, 2024c. West Covina Fire Department Stations. Accessed online at <https://www.arcgis.com/home/item.html?id=8a49ad0faf044689bdb6d29a205bae35> on April 25, 2024.
- City of West Covina, 2024d. Police Department: About. Accessed online at <https://www.wcpd.org/> on May 17, 2024.
- City of West Covina, 2024e. Parks and Community Center Facilities, Accessed online at <https://www.westcovina.org/departments/public-services-department/community-services-division/parks-and-community-center-facilities> on May 17, 2024.
- City of West Covina, 2024f. Transit Services, Accessed online at <https://www.westcovina.org/residents/transit-programs> on May 20, 2024.
- County of Los Angeles, 2020. All Hazards Mitigation Plan. Approved May 2020. Accessed online at <https://ceo.lacounty.gov/wp-content/uploads/2023/08/County-of-Los-Angeles-All-Hazards-Mitigation-Plan-APPROVED-05-2020.pdf> on May 20, 2024.
- County of Los Angeles, 2024a. Congestion Management Program for Los Angeles County. Accessed online at <https://libraryarchives.metro.net/dpgtl/programs/congestion-management-program-lacmta/congestion-management-program-for-los-angeles-county-index-page.html> on May 20, 2024.
- County of Los Angeles, 2024b. LA County Airport Land Use Commission Site. <https://planning.lacounty.gov/public-hearings-and-meetings/airport-land-use-commission/> on May 20, 2024.
- County of Los Angeles, 2024c. West Covina Library – LA County Library. <https://lacountylibrary.org/location/west-covina-library> on May 17, 2024.
- CSI, 2024a. Phase I Environmental Site Assessment (referred as Phase I or Phase I ESA), Envision Toyota, 1800 – 1820 East Garvey Avenue S, West Covina, California, by Celly Services, Inc. dated June 12, 2024.
- CSI, 2024b. Phase I Environmental Site Assessment (referred as Phase I or Phase I ESA) for the Former Shell Station (Valero), 200 South Azusa Avenue, West Covina, California by Celly Services, Inc. dated June 13, 2024.
- Digalert.com. 2024. Utilities contact lookup. Accessed online at: <https://newtinb.digalert.org/direct/>, on June 18, 2024.
- DOC, 2022. California Important Farmland Finder. Accessed online at: <https://maps.conservation.ca.gov/DLRP/CIFF/>. Accessed on June 07, 2024.
- DMR (Division of Mine Reclamation), 2024. Mines Online, Division of Mine Reclamation, California Department of Conservation. Accessed online at: <https://maps.conservation.ca.gov/mol/index.html>, on July 22, 2024.



❖ SECTION 5.0 - REFERENCES ❖

- DWR (Department of Water Resources), 2024a. Dam Breach Inundation Map Web Publisher. Accessed online at: https://fmds.water.ca.gov/webgis/?appid=dam_prototype_v2, on July 19, 2024.
- DWR (Department of Water Resources), 2024b. SGMA [Sustainable Groundwater Management Act] Data Viewer. Accessed online at: <https://sgma.water.ca.gov/webgis/?appid=SGMADataViewer#boundaries>, on July 19, 2024.
- FEMA (Federal Emergency Management Agency), 2024. National Flood Hazard Layer (NFHL) Viewer. Available at: <https://www.fema.gov/flood-maps/national-flood-hazard-layer>, Accessed on July 18, 2024.
- Foothill Transit, 2024. Wo We Are. Accessed online at <https://www.foothilltransit.org/> on June 18, 2024.
- Francis and Reicher, Personal Communication, 2024. 7212 - Envision Motors Mercedes West Covina Project: Plans Submittal Status - AB 52 at Outlook, on July 22, 2024.
- FTA, 2018. Transit Noise and Vibration Impact Assessment. Accessed online at https://www.transit.dot.gov/sites/fta.dot.gov/files/docs/research-innovation/118131/transit-noise-and-vibration-impact-assessment-manual-fta-report-no-0123_0.pdf, on July 10, 2024.
- GMI, 2019. What is a Global Warming Potential? And Which One Do I Use? GHG Management Institute. <https://ghginstitute.org/2010/06/28/what-is-a-global-warming-potential/>. Accessed July 2024.
- Google Earth Pro, 2024. Google Earth Pro Version 7.3.6.9796 (Build Date: February 22, 2024). City of West Covina, Los Angeles County, California, U.S.A.
- Google Maps, 2024. Accessed online at <https://www.google.com/maps>, on July 18, 2024.
- Governor's Office of Planning and Research, 2017. State of California General Plan Guidelines. Accessed online at https://opr.ca.gov/docs/OPR_COMPLETE_7.31.17.pdf, on July 9, 2024.
- ICF Jones & Stokes, 2009. Technical Noise Supplement. Prepared by ICF Jones & Stokes, Sacramento, California for California Department of Transportation, Division of Environmental Analysis, Sacramento, California. November 2009.
- InMyArea, 2024. Top Providers in West Covina, California. Accessed online at <https://www.inmyarea.com/internet-in-my-area?zip=91791&product=internet&vh=c0> on July 5, 2024.
- LA County ALUC (Los Angeles County Airport Land Use Commission), 2015. Brackett Field Airport Land Use Compatibility Plan. Accessed online at <https://planning.lacounty.gov/wp-content/uploads/2022/10/Brackett-Field-Airport-Land-Use-Compatibility-Plan.pdf>, on July 11, 2024.
- Los Angeles County Department of Public Works (LACPW). 2014. Low Impact Development Standards Manual. Accessed online at:



- <http://dpw.lacounty.gov/ldd/lib/fp/Hydrology/Low%20Impact%20Development%20Standards%20Manual.pdf>, on July 15, 2024.
- LACPW (Los Angeles County Public Works), 2024. Los Angeles County Storm Drain System. Accessed online at: <https://pw.lacounty.gov/fcd/StormDrain/index.cfm>, on July 18, 2024.
- LACSD (Los Angeles County Sanitation District) 2021. Wastewater Revenue Program Report. Dated January 2012. Accessed online at <https://www.lacsd.org/services/wastewater-programs-permits/wastewater-revenue-program/revenue-program-rates-on-july-25>, 2024.
- LACPW (Los Angeles County Public Works), 2021. 2020 Urban Water Management Plan for Los Angeles County Waterworks. Dated October 21, 2021. Accessed online at https://dpw.lacounty.gov/wwd/web/Documents/D40_AV2020_UWMP%20FINAL.pdf on July 25, 2024.
- LSA, 2024. Trip Generation and Vehicle Miles Traveled Analysis for 18005 Garvey Avenue, West Covina, California. Memorandum from Arthur Black, Principal Transportation Planner, LSA, to Sanjay Datta, Director of Franchise Operations, Envision Motors. July 1, 2024.
- Machado, Miriam, 2024a. Personal Communication to Stephen O'Neil. Associate Planner, City of West Covina AB 52 Consultation; September 5, 2024.
- Machado, Miriam, 2024b. Personal Communication to Stephen O'Neil. Associate Planner, City of West Covina AB 52 Consultation. On September 10, 2024.
- Machado, Miriam, 2024c. Personal Communication to Stephen O'Neil. Associate Planner, City of West Covina AB 52 Consultation; October 7, 2024.
- Machado, Miriam, 2024d. Personal Communication to Stephen O'Neil. Associate Planner, City of West Covina AB 52 Consultation; October 8, 2024.
- Miller, Russel V., 1994. Generalized Mineral Land Classification Map of Los Angeles County-South Half, Aggregate Resources Only. California Department of Conservation (DOC), Division of Mines and Geology (DMG), Open-File Report (OFR) 94-14, Plate 1B. Accessed online at: <https://maps.conservation.ca.gov/cgs/informationwarehouse/mlc/> (Surface Mining and Reclamation Act [SMARA] CGS Information Warehouse: Mineral Land Classification), on June 11, 2024.
- Municode.com, 2024. City of West Covina Municipal Code §§ 26-288 et seq. Accessed online at: https://library.municode.com/ca/west_covina/codes/code_of_ordinances?nodeId=MUCO_CH26ZO_ARTVIPRHENOFECA_DIV9PRPRRETR_S26-288PU, on July 22, 2024.
- NASA, 2018. Global Climate Change: Vital Signs of the Planet. National Air and Space Administration. Accessed online at: <https://climate.nasa.gov/evidence/>. Accessed in July 2024
- NOAA Research, 2024. No sign of greenhouse gases increases slowing in 2023. Accessed online at <https://research.noaa.gov/2024/04/05/no-sign-of-greenhouse-gases-increases-slowing-in-2023/> on July 16, 2024.



❖ SECTION 5.0 - REFERENCES ❖

- NorCal Engineering. 2024. Geotechnical Engineering Investigation, Proposed Envision Mercedes-Benz of West Covina Automotive Dealership 1800 E Garvey Avenue South, West Covina, California. Dated May 17, 2024
- NWS (National Weather Service), 2024. Damaging Downslope Wind Events in the San Gabriel Valley of Southern California. Accessed online at https://www.weather.gov/media/wrh/online_publications/TAs/TA1602.pdf on July 24, 2024.
- Rincon, 2016. City of West Covina General Plan Final EIR. Dated December 2016. Accessed online at <https://www.westcovina.org/home/showpublisheddocument/18142/637232598667300000> on April 22, 2024.
- RK Engineering (RK Engineering Group, Inc.), 2024. Mercedes-Benz of West Covina Project Vehicle Miles Traveled (VMT) Screening Analysis, City of West Covina, CA. Dated May 31, 2024.
- RWQCB (Los Angeles Regional Water Quality Control Board). 2014. Basin Plan for the Coastal Watersheds of Los Angeles and Ventura Counties. Accessed online at: https://www.waterboards.ca.gov/losangeles/water_issues/programs/basin_plan/basin_plan_documentation.html, on July 24, 2024.
- RWQCB (Los Angeles Regional Water Quality Control Board). 2021. Waste Discharge Requirements and National Pollutant Discharge Elimination System (NPDES) Permit for Municipal Separate Storm Sewer System (MS4) Discharges Within the Coastal Watersheds of Los Angeles And Ventura Counties. Accessed online at: chrome-extension://efaidnbmnnnibpcajpcglclefindmkaj/https://www.waterboards.ca.gov/losangeles/water_issues/programs/stormwater/municipal/public_docs/2022/1_Order(ACC-RPSignature).pdf, on July 25, 2024.
- Screening Analysis, City of West Covina, CASCAQMD, 1993. CEQA Air Quality Handbook. Diamond Bar, CA. November. July 18, 2024.
- SCAQMD, 2008. Draft Guidance Document – Interim CEQA Greenhouse Gas (GHG) Significance Threshold. South Coast Air Quality Management District. October 2008. [http://www.aqmd.gov/docs/default-source/ceqa/handbook/greenhouse-gases-\(ghg\)-ceqa-significance-thresholds/ghgattachmente.pdf](http://www.aqmd.gov/docs/default-source/ceqa/handbook/greenhouse-gases-(ghg)-ceqa-significance-thresholds/ghgattachmente.pdf). On May , 2024.
- SCAQMD, 2011. Final AQMD Air Quality-Related Energy Policy. September 9, 2011. Internet URL: <http://www.aqmd.gov/nav/about/policies/aqmd-air-quality-related-energy-policy>. Accessed May 7, 2024.
- SCAQMD, 2022a. 2022 Air Quality Management Plan. Accessed online at <https://www.aqmd.gov/docs/default-source/clean-air-plans/air-quality-management-plans/2022-air-quality-management-plan/final-2022-aqmp/final-2022-aqmp.pdf?sfvrsn=16>, on July 18, 2024.
- SCAQMD, 2022b. South Coast AQMD Site Survey Report for Azusa. Accessed online at <https://www.aqmd.gov/docs/default-source/clean-air-plans/air-quality-monitoring-network-plan/aaqmnp-azusa.pdf>, on July 18, 2024.



- SCAQMD, 2023. SCAQMD Air Quality Significance Thresholds. South Coast Air Quality Management District. Revision: May, 2023. <https://www.aqmd.gov/docs/default-source/ceqa/handbook/south-coast-aqmd-air-quality-significance-thresholds.pdf?sfvrsn=25>. Accessed July 18, 2024.
- SDLAC (Sanitation District of Los Angeles County), 2024a. Whittier Narrows Water Reclamation Plant. Accessed online at <https://www.lacsd.org/services/wastewater-sewage/facilities/whittier-narrows-water-reclamation-plant> on June 18, 2024.
- SDLAC (Sanitation District of Los Angeles County), 2024b. San Jose Creek Water Reclamation Plant. Accessed online at <https://www.lacsd.org/services/wastewater-sewage/facilities/san-jose-creek-water-reclamation-plant> on June 18, 2024.
- Tollett, Michelle (certified arborist), 2024. Email dated July 18, 2024.
- Suburban (Suburban Water Systems), 2021. 2020 Urban Water Management Plan, Suburban Water Systems. Accessed online at: https://wuedata.water.ca.gov/public/uwmp_attachments/3851880729/Suburban%20Final%202020%20UWMP%5F2021%2D06%2D30.pdf, on July 19, 2024.
- Suburban (Suburban Water Systems), 2024. About Our Water - Your Local Utility. Accessed online at <https://www.swwc.com/suburban/> on June 18, 2024.
- Tan, S. S. 2000. Geologic map of the Baldwin Park 7.5 quadrangle, Los Angeles County, California. California Division of Mines and Geology. Accessed online at: https://ngmdb.usgs.gov/Prodesc/proddesc_44880.htm, on July 17, 2024.
- Transtech, 2024. Memo from Transtech to JoAnn Burns regarding the Traffic Impact Study Scoping. Dated May 14, 2024.
- USDE (U.S. Department of Energy), 2024. Maps and Data - Vehicle Fuel Efficiency (CAFE) Requirements by Year. Accessed online at <https://afdc.energy.gov/data/10562>, on July 22, 2024.
- USEPA (U.S. Environmental Protection Agency), 2011. Air Quality Guide for Nitrogen Dioxide. Office of Air and Radiation. EPA-456/F-11-003. Accessed online at <https://document.airnow.gov/air-quality-guide-for-nitrogen-dioxide.pdf>, on July 18, 2024.
- USEPA, 2019b. Overview of Greenhouse Gases. U.S. Environmental Protection Agency. <https://www.epa.gov/ghgemissions/overview-greenhouse-gases>. Accessed May 7, 2024.
- USEPA, 2020. Integrated Science Assessment for Ozone and Related Photochemical Oxidants. Center for Public Health and Environmental Assessment, Office of Research and Development, U.S. Environmental Protection Agency, Research Triangle Park, NC. EPA/600/R-20/012. April. Accessed online at <https://cfpub.epa.gov/ncea/isa/recordisplay.cfm?deid=348522>, on July 18, 2024.
- USEPA, 2023. Indoor Air Quality (IAQ). What is Carbon Monoxide? Accessed online at <https://www.epa.gov/indoor-air-quality-iaq/what-carbon-monoxide>, on July 18, 2024.



- USEPA, 2024a. WATERS GeoViewer. Available at <https://www.epa.gov/waterdata/waters-geoviewer>. Accessed on March 27, 2024.
- USEPA, 2024b. Particulate Matter (PM) Pollution. Accessed online at <https://www.epa.gov/pm-pollution>, on July 18, 2024.
- USEPA, 2024c. The Safer Affordable Fuel Efficient (SAFE) Vehicles Proposed Rule for Model Years 2021-2026. Accessed online at <https://www.epa.gov/regulations-emissions-vehicles-and-engines/safer-affordable-fuel-efficient-safe-vehicles-proposed>, on May 7, 2024.
- USEPA, 2024d. Current Nonattainment Counties for All Criteria Pollutants. Accessed online at <https://www3.epa.gov/airquality/greenbook/ancl.html>, on July 18, 2024.
- USFWS (US Fish and Wildlife Service), 2024. National Wetlands Mapper. Accessed online at: <https://fwsprimary.wim.usgs.gov/wetlands/apps/wetlands-mapper/>, on July 18, 2024.
- USGS (U.S. Geological Survey), 2021. The Severity of an Earthquake. Accessed online at: <https://pubs.usgs.gov/gip/earthq4/severitygip.html>, on July 2, 2024
- USGS (US Geological Survey), 2024. Areas of Land Subsidence in California. Accessed online at: https://ca.water.usgs.gov/land_subsidence/california-subsidence-areas.html, on July 22, 2024.
- WCUSD (West Covina Unified School District), 2024. West Covina Unified School District – About Us. Accessed online at <https://www.wcusd.org/about/about-us> on April 25, 2024.
- WCMC (West Covina Medical Center), 2024. West Covina Medical Center - Our Services. Accessed online at <https://westcovinamc.com/our-services.html> on May 17, 2024.
- WCPD (West Covina Police Department), 2024. 2023 Annual Review - West Covina Police Department. Accessed online at <https://www.wcpd.org/annualreview/> on May 17, 2024.
- WCUSD (West Covina Unified School District), 2024a. About Us - West Covina Unified School District. Accessed online at <https://www.wcusd.org/about/about-us> on May 17, 2024.
- WCUSD (West Covina Unified School District), 2024b. Developer Fees, Accessed online at <https://www.wcusd.org/departments/business-services/fiscal-services> on May 17, 2024.
- WRCC, 2016a. Western U.S. Climate Historical Summaries, Western Regional Climate Center. Accessed online at <https://wrcc.dri.edu/cgi-bin/cliMAIN.pl?ca7776>, on July 18, 2024
- WRCC, 2016b. Western U.S. Climate Historical Summaries, Western Regional Climate Center. Accessed online at <https://wrcc.dri.edu/cgi-bin/cliMAIN.pl?ca2090>, on July 18, 2024



6.0 LIST OF PREPARERS

6.1 CEQA Lead Agency

Jo-Anne Burns, Deputy Community Development Director

City of West Covina

1444 West Garvey Avenue S. #208

West Covina, CA 91790

Email Address: jburns@westcovina.org

6.2 Project Applicant

Boyd Sumner, Director of Franchise Operations

Envision Motors

2010 East Garvey Avenue S.

West Covina, CA 91791

Phone: (818) 512-7009

Email Address: boyd.sumner@envisionmotors.com

6.3 UltraSystems Environmental, Inc.

6.3.1 Environmental Planning Team

Betsy Lindsay, MURP, ENV SP, Project Director

Robert Reicher, MBA, B.S., ENV SP, Project Manager

Victor Paitimusa, B.A., ENV SP, Assistant Project Manager

6.3.2 Technical Team

Allison Carver, B.S., B.A., Senior Biologist

Andrew Soto, B.A., Word Processing/Technical Editing

Billye Jean Breckenridge, B.S., GIS Manager

Erik Segura, B.S., ENV SP, Associate Planner

Gulben Kaplan, M.S., GIS Analyst

Isha Shah, M.S., Staff Engineer/Scientist

Marissa Kasssieh, B.A., Assistant Planner

Megan Doukakis, M.A., Assistant Project Archaeologist

Michael Milroy, B.S., M.S., Senior Planner

Patricia Haigh, B.S., B.A., Staff Scientist

Rodrigo Jacobo, M.A., Cultural Resources Specialist

Stephen O'Neil, M.A., RPA, Cultural Resources Manager

Steve Borjeson, B.A., Senior Planner

Zach Neider, B.S., ISA, Senior Biologist



7.0 MITIGATION MONITORING AND REPORTING PROGRAM

The Mitigation Monitoring and Reporting Program (MMRP) has been prepared in conformance with § 21081.6 of the Public Resources Code and § 15097 of the CEQA Guidelines, which requires all state and local agencies to establish monitoring or reporting programs whenever approval of a project relies upon a Mitigated Negative Declaration (MND) or an Environmental Impact Report (EIR). The MMRP ensures implementation of the measures being imposed to mitigate or avoid the significant adverse environmental impacts identified through the use of monitoring and reporting. Monitoring is generally an ongoing or periodic process of project oversight; reporting generally consists of a written compliance review that is presented to the decision-making body or authorized staff person.

It is the intent of the MMRP to: (1) provide a framework for document implementation of the required mitigation; (2) identify monitoring/reporting responsibility; (3) provide a record of the monitoring/reporting; and (4) ensure compliance with those mitigation measures (MM) that are within the responsibility of the City and/or Applicant to implement.

The following table lists the impacts and mitigation measures adopted by the City of West Covina in connection with approval of the proposed project, level of significance after mitigation, responsible and monitoring parties, and the project phase in which the measures are to be implemented.

Only those environmental topics for which mitigation is required are listed in this Mitigation Monitoring and Reporting Program.



❖ SECTION 7.0 - MITIGATION MONITORING & REPORTING PROGRAM ❖

Table 7.0-1
MITIGATION MONITORING AND REPORTING PROGRAM

TOPICAL AREA IMPACT	MITIGATION MEASURE	RESPONSIBLE PARTY	MONITORING ACTION	1. ENFORCEMENT AGENCY 2. MONITORING AGENCY 3. MONITORING PHASE
4.4 Biological Resources				
Threshold 4.4 a) Would the project have a substantial adverse effect, either directly or through habitat modifications, on any species identified as a candidate, sensitive, or special status species in local or regional plans, policies, or regulations, or by the California Department of Fish and Game or U.S. Fish and Wildlife Service?	MM BIO-1: Pre-Construction Breeding Bird Survey To be in compliance with the MBTA and Fish and Game Code, and to avoid impacts or take of migratory non-game breeding birds, their nests, young, and eggs, the following measures will be implemented. The measures below will help to reduce direct and indirect impacts caused by construction on migratory non-game breeding birds to less than significant levels. Project activities that will remove or disturb potential nest sites, such as open ground, trees, shrubs, grasses, or burrows, during the breeding season would be a potential significant impact if migratory non-game breeding birds are present. Project activities that will remove or disturb potential nest sites will be scheduled outside the breeding bird season to avoid potential direct impacts on migratory non-game breeding birds protected by the MBTA and Fish and Game Code. The breeding bird nesting season is typically from February 15 through September 15, but can vary slightly from year to year, usually depending on weather conditions. Removing all physical features that could potentially serve as nest sites will also help to prevent birds from nesting within the project site during the breeding season and during construction activities.	- Project Applicant - Qualified Biologist	Field Verification	- City of West Covina - City of West Covina - Before Construction



❖ SECTION 7.0 – MITIGATION MONITORING AND REPORTING PROGRAM ❖

TOPICAL AREA IMPACT	MITIGATION MEASURE	RESPONSIBLE PARTY	MONITORING ACTION	1. ENFORCEMENT AGENCY 2. MONITORING AGENCY 3. MONITORING PHASE
	• If project activities cannot be avoided during February 15 through September 15, a qualified biologist will conduct a pre-construction breeding bird survey for breeding birds and active nests or potential nesting sites within the limits of project disturbance. The survey will be conducted at least seven days prior to the onset of scheduled activities, such as mobilization and staging. It will end no more than three days prior to vegetation, substrate, and structure removal and/or disturbance. • If no breeding birds or active nests are observed during the pre-construction survey or they are observed and will not be impacted, project activities may begin, and no further mitigation will be required. • If a breeding bird territory or an active bird nest is located during the pre-construction survey and will potentially be impacted, the site will be mapped on engineering drawings and a no activity buffer zone will be marked (fencing, stakes, flagging, orange snow fencing, etc.) a minimum of 100 feet in all directions or 500 feet in all directions for listed bird species and all raptors. The biologist will determine the appropriate buffer size based on the type of activities planned near the nest and the type of bird that created the nest. Some bird species are more tolerant than others of noise and activities occurring near their nest. This no-activity buffer zone will not be disturbed until a qualified biologist has determined that the nest is inactive, the young have			



❖ SECTION 7.0 – MITIGATION MONITORING AND REPORTING PROGRAM ❖

TOPICAL AREA IMPACT	MITIGATION MEASURE	RESPONSIBLE PARTY	MONITORING ACTION	1. ENFORCEMENT AGENCY 2. MONITORING AGENCY 3. MONITORING PHASE
	fledged, the young are no longer being fed by the parents, the young have left the area, or the young will no longer be impacted by project activities. Periodic monitoring by a biologist will be performed to determine when nesting is complete. Once the nesting cycle has finished, project activities may begin within the buffer zone. - If listed bird species are observed within the project site during the pre-construction survey, the biologist will immediately map the area and notify the appropriate resource agency to determine suitable protection measures and/or mitigation measures and to determine if additional surveys or focused protocol surveys are necessary. Project activities may begin within the area only when concurrence is received from the appropriate resource agency. - Birds or their active nests will not be disturbed, captured, handled or moved. Active nests cannot be removed or disturbed; however, nests can be removed or disturbed if determined inactive by a qualified biologist.			
Threshold 4.4 d) Would the project interfere substantially with the movement of any native resident or	Refer to Threshold 4.4 a) MM BIO-1 above.	Refer to above	Refer to above	Refer to above



❖ SECTION 7.0 – MITIGATION MONITORING AND REPORTING PROGRAM ❖

TOPICAL AREA IMPACT	MITIGATION MEASURE	RESPONSIBLE PARTY	MONITORING ACTION	1. ENFORCEMENT AGENCY 2. MONITORING AGENCY 3. MONITORING PHASE
migratory fish or wildlife species or with established native resident or migratory wildlife corridors, or impede the use of native wildlife nursery sites?				
Threshold 4.4 e) Conflict with the provisions of an adopted Habitat Conservation Plan, Natural Community Conservation Plan, or other approved local, regional, or state habitat conservation plan?	Refer to Threshold 4.4 a) MM BIO-1 above.	• Refer to above	• Refer to above	• Refer to above
4.5 Cultural Resources				
Threshold 4.5 b) Cause a substantial adverse change in the significance of an archaeological	MM CUL 1: If archaeological resources are discovered during construction activities, the contractor will halt construction activities within a 50-foot diameter and notify the City of West Covina. The project applicant shall retain an archaeologist who meets the Secretary of the Interior's Professional Qualifications Standards for Archaeology who will be notified and afforded the necessary time	• Project Contractor • Qualified Archaeologist	• Field Verification	1. City of West Covina 2. City of West Covina



❖ SECTION 7.0 – MITIGATION MONITORING AND REPORTING PROGRAM ❖

TOPICAL AREA IMPACT	MITIGATION MEASURE	RESPONSIBLE PARTY	MONITORING ACTION	1. ENFORCEMENT AGENCY 2. MONITORING AGENCY 3. MONITORING PHASE
resource pursuant to § 15064.5.	to recover, analyze, and curate the find(s). The qualified archaeologist will recommend the extent of archaeological monitoring necessary to ensure the protection of any other resources that may be in the area. Any identified cultural resources shall be recorded on the appropriate DPR 523 (A L) form and filed with the South Central Coastal Information Center. Construction activities may continue on other parts of the project site while evaluation and treatment of prehistoric archaeological resources takes place.			3. During construction activities
Threshold 4.5 c): Disturb any human remains, including those interred outside of formal cemeteries.	MM CUL2: If human remains are encountered during excavations associated with this project, all work will stop within a 30-foot radius of the discovery and the Los Angeles County Coroner will be notified (§ 5097.98 of the Public Resources Code). The Coroner will determine whether the remains are recent human origin or older Native American ancestry. If the coroner, with the aid of the supervising archaeologist, determines that the remains are prehistoric, they will contact the NAHC. The NAHC will be responsible for designating the Most Likely Descendant (MLD). The MLD (either an individual or sometimes a committee) will be responsible for the ultimate disposition of the remains, as required by § 7050.5 of the California Health and Safety Code. The MLD will make recommendations within 24 hours of their notification by the NAHC. These recommendations may include scientific removal and nondestructive analysis of human remains and items associated with Native American burials (§ 7050.5 of the Health and Safety Code).	• Project Contractor • Qualified Archaeologist • Los Angeles County Coroner	• Field Verification	1. City of West Covina 2. City of West Covina 3. During project construction activities
4.7 Geology and Soils				
Threshold 4.7 f): Would the project directly or indirectly destroy a unique paleontological	MM GEO-1: Prior to the issuance of the grading permit, the applicant shall provide a letter to the City of West Covina Planning Division, or designee, from a qualified paleontologist stating that the paleontologist has been retained to provide services for the project. The paleontologist shall develop, as needed, a	• Project Applicant • Qualified Paleontologist	• Monitoring • Assessment • Recovery	1. City of West Covina 2. City of West Covina



❖ SECTION 7.0 – MITIGATION MONITORING AND REPORTING PROGRAM ❖

TOPICAL AREA IMPACT	MITIGATION MEASURE	RESPONSIBLE PARTY	MONITORING ACTION	1. ENFORCEMENT AGENCY 2. MONITORING AGENCY 3. MONITORING PHASE
resource or site or unique geologic feature?	Paleontological Resources Impact Mitigation Plan (PRIMP) to mitigate the potential impacts to unknown buried paleontological resources that may exist onsite for the review and approval by the City. The PRIMP shall require that the paleontologist perform paleontological monitoring of any ground disturbing activities within undisturbed native sediments during mass grading, site preparation, and underground utility installation. The project paleontologist may reevaluate the necessity for paleontological monitoring after 50 percent or greater of the excavations have been completed. In the event paleontological resources are encountered, ground-disturbing activity within 50 feet of the area of the discovery shall cease. The paleontologist shall examine the materials encountered, assess the nature and extent of the find, and recommend a course of action to further investigate and protect or recover and salvage those resources that have been encountered. Criteria for discard of specific fossil specimens will be made explicit. If the qualified paleontologist determines that impacts to a sample containing significant paleontological resources cannot be avoided by project planning, then recovery may be applied. Actions may include recovering a sample of the fossiliferous material prior to construction, monitoring work and halting construction if a significant fossil needs to be recovered, and/or cleaning, identifying, and cataloging specimens for curation and research purposes. Recovery, salvage and treatment shall be done at the Applicant's expense. All recovered and salvaged resources shall be prepared to the point of identification and permanent preservation by the paleontologist. Resources shall be identified and curated into an established accredited professional repository. The paleontologist shall have a repository agreement in hand prior to initiating recovery of the resource.	• Construction Contractor	• Curation	3. Prior to the issuance of the grading permit



❖ SECTION 7.0 – MITIGATION MONITORING AND REPORTING PROGRAM ❖

TOPICAL AREA IMPACT	MITIGATION MEASURE	RESPONSIBLE PARTY	MONITORING ACTION	1. ENFORCEMENT AGENCY 2. MONITORING AGENCY 3. MONITORING PHASE
4.9 Hazards and Hazardous Materials				
Threshold 4.9 a): Would the project create a significant hazard to the public or the environment through the routine transport, use, or disposal of hazardous materials?	MM HAZ-1: During project site grading on the Valero gas station site the project proponent shall periodically have soil samples tested for TPH-g, TH-d, MTBE, and TBA. Upon finding samples with concentrations of any of the contaminants at concentrations over environmental screening levels (ESLs) for commercial use, the project proponent shall: halt grading operations; shall retain a qualified environmental assessor to conduct soil sampling and testing to determine the extent of soil contaminated with concentrations over ESLs; and shall then retain an environmental remediation company to remediate and/or remove the contaminated soil.	• Project Applicant • Qualified Environmental Assessor	• Field Verification	1. City of West Covina 2. City of West Covina 3. During Construction
4.18 Tribal Cultural Resources				
Threshold 4.18 b): Cause a substantial adverse change in the significance of a tribal cultural resource that is listed or eligible for listing in the California Register of Historical Resources or in a local register of historical resources as defined in Public Resources Code § 5020.1(k)?	MM TCR-1: Retain a Native American Monitor Prior to Commencement of Ground-Disturbing Activities A. The project applicant/lead agency shall retain a Native American Monitor from or approved by the Gabrieleño Band of Mission Indians – Kizh Nation. The monitor shall be retained prior to the commencement of any “ground-disturbing activity” for the subject project at all project locations (i.e., both on-site and any off-site locations that are included in the project description/definition and/or required in connection with the project, such as public improvement work). “Ground disturbing activity” shall include, but is not limited to, demolition, pavement removal, potholing, auguring, grubbing, tree removal, boring, grading, excavation, drilling, and trenching. B. A copy of the executed monitoring agreement shall be submitted to the lead agency prior to the earlier of the commencement of any ground-disturbing activity, or the issuance of any permit necessary to commence	• Project Contractor • Qualified Archaeologist Los Angeles County Coroner	• Field Verification	1. City of West Covina 2. City of West Covina 3. During project construction activities



❖ SECTION 7.0 – MITIGATION MONITORING AND REPORTING PROGRAM ❖

TOPICAL AREA IMPACT	MITIGATION MEASURE	RESPONSIBLE PARTY	MONITORING ACTION	1. ENFORCEMENT AGENCY 2. MONITORING AGENCY 3. MONITORING PHASE
	a ground-disturbing activity. C. The monitor will complete daily monitoring logs that will provide descriptions of the relevant ground-disturbing activities, the type of construction activities performed, locations of ground disturbing activities, soil types, cultural-related materials, and any other facts, conditions, materials, or discoveries of significance to the Tribe. Monitor logs will identify and describe any discovered TCRs, including but not limited to, Native American cultural and historical artifacts, remains, places of significance, etc., (collectively, tribal cultural resources, or “TCR”), as well as any discovered Native American (ancestral) human remains and burial goods. Copies of monitor logs will be provided to the project applicant/lead agency upon written request to the Tribe. D. On-site tribal monitoring shall conclude upon the latter of the following (1) written confirmation to the Kizh from a designated point of contact for the project applicant/lead agency that all ground-disturbing activities and phases that may involve ground-disturbing activities on the project site or in connection with the project are complete; or (2) a determination and written notification by the Kizh to the project applicant/lead agency that no future, planned construction activity and/or development/construction phase at the project site possesses the potential to impact Kizh TCRs.			
	MM TCR-2: Unanticipated Discovery of Tribal Cultural Resource Objects (Non-Funerary/Non-Ceremonial) A. Upon discovery of any TCRs, all construction activities in the immediate vicinity of the discovery shall cease (i.e., not less than the surrounding 50 feet) and shall not resume until the discovered TCR has been fully assessed by the Kizh monitor and/or Kizh archaeologist. The Kizh will recover and retain all discovered TCRs in the form and/or manner the Tribe deems appropriate, in the Tribe’s sole discretion, and	• Project Contractor • Qualified Archaeologist • Los Angeles County Coroner	• Field Verification	1. City of West Covina 2. City of West Covina 3. During project construction activities



❖ SECTION 7.0 – MITIGATION MONITORING AND REPORTING PROGRAM ❖

TOPICAL AREA IMPACT	MITIGATION MEASURE	RESPONSIBLE PARTY	MONITORING ACTION	1. ENFORCEMENT AGENCY 2. MONITORING AGENCY 3. MONITORING PHASE
	for any purpose the Tribe deems appropriate, including for educational, cultural and/or historic purposes.			
	MM TCR 3: As specified by California Health and Safety Code § 7050.5, if human remains are found on the project site during construction or during archaeological work, the Los Angeles County Coroner's office shall be immediately notified and no further excavation or disturbance of the discovery or any nearby area reasonably suspected to overlie adjacent remains shall occur until the Coroner has made the necessary findings as to origin and disposition pursuant to Public Resources Code § 5097.98. The Coroner would determine within two working days of being notified if the remains are subject to his or her authority. If the Coroner recognizes the remains to be Native American, he or she shall contact the Native American Heritage Commission (NAHC) within 24 hours. The NAHC would make a determination as to the Most Likely Descendent.	• Project Contractor • Qualified Archaeologist • Los Angeles County Coroner	• Field Verification	1. City of West Covina 2. City of West Covina 3. During project construction activities