
APPENDIX J: NOISE ASSESSMENT



NOISE MONITORING DATA

Measurement Report

Report Summary

Meter's File Name	S_T_Data.044.s	Computer's File Name	LxT_0005425-20250823 195414-S_T_Data.044.lbin		
Meter	LxT1 0005425	Firmware	2.404		
User	J.R.	Location	ST-1		
Job Description	PLSD-02.0				
Note					
Start Time	2025-08-23 19:54:14	Duration	0:15:00.0		
End Time	2025-08-23 20:09:14	Run Time	0:15:00.0	Pause Time	0:00:00.0
Pre-Calibration	2025-08-23 19:52:27	Post-Calibration	None	Calibration Deviation	---

Results

Overall Metrics

LA _{eq}	46.2 dB		
LAE	75.7 dB	SEA	--- dB
EA	4.2 µPa²h		
EA8	133.4 µPa²h		
EA40	667.0 µPa²h		
LZ _{peak}	97.1 dB	2025-08-23 20:07:55	
LAS _{max}	61.6 dB	2025-08-23 20:05:59	
LAS _{min}	39.9 dB	2025-08-23 20:07:37	
LA _{eq}	46.2 dB		
LC _{eq}	59.4 dB	LC _{eq} - LA _{eq}	13.2 dB
LA _l _{eq}	47.6 dB	LA _l _{eq} - LA _{eq}	1.4 dB

Exceedances

	Count	Duration
LAS > 85.0 dB	0	0:00:00.0
LAS > 115.0 dB	0	0:00:00.0
LZpk > 135.0 dB	0	0:00:00.0
LZpk > 137.0 dB	0	0:00:00.0
LZpk > 140.0 dB	0	0:00:00.0

Community Noise

L _{DN}	L _{Day}	L _{Night}
--- dB	--- dB	0.0 dB
L _{DEN}	L _{Day}	L _{Eve}
--- dB	--- dB	--- dB
		L _{Night}
		--- dB

Any Data

	A		C		Z	
	Level	Time Stamp	Level	Time Stamp	Level	Time Stamp
	---	None	59.4 dB	None	---	None
L _{Peak(max)}	---	None	---	None	---	None
	---	None	---	None	97.1 dB	2025-08-23 20:07:55

Overloads

Count	Duration
0	0:00:00.0

Statistics

	
LAS 90.0	41.3 dB
LAS 99.0	40.4 dB



Measurement Report

Report Summary

Meter's File Name	S_T_Data.045.s	Computer's File Name	LxT_0005425-20250823 201529-S_T_Data.045.lbin		
Meter	LxT1 0005425	Firmware	2.404		
User	J.R.	Location	ST-2		
Job Description	PLSD-02.0				
Note					
Start Time	2025-08-23 20:15:29	Duration	0:15:00.0		
End Time	2025-08-23 20:30:29	Run Time	0:15:00.0	Pause Time	0:00:00.0
Pre-Calibration	2025-08-23 19:52:26	Post-Calibration	None	Calibration Deviation	---

Results

Overall Metrics

LA _{eq}	48.0 dB		
LAE	77.5 dB	SEA	--- dB
EA	6.3 µPa²h		
EA8	201.9 µPa²h		
EA40	1.0 mPa²h		
LZ _{peak}	87.3 dB	2025-08-23 20:16:21	
LAS _{max}	61.6 dB	2025-08-23 20:26:15	
LAS _{min}	42.0 dB	2025-08-23 20:18:18	
LA _{eq}	48.0 dB		
LC _{eq}	58.0 dB	LC _{eq} - LA _{eq}	10.0 dB
LA _l _{eq}	52.2 dB	LA _l _{eq} - LA _{eq}	4.2 dB

Exceedances

	Count	Duration
LAS > 85.0 dB	0	0:00:00.0
LAS > 115.0 dB	0	0:00:00.0
LZpk > 135.0 dB	0	0:00:00.0
LZpk > 137.0 dB	0	0:00:00.0
LZpk > 140.0 dB	0	0:00:00.0

Community Noise

L _{DN}	L _{Day}	L _{Night}
--- dB	--- dB	0.0 dB
L _{DEN}	L _{Day}	L _{Eve}
--- dB	--- dB	--- dB
		L _{Night}
		--- dB

Any Data

	A		C		Z	
	Level	Time Stamp	Level	Time Stamp	Level	Time Stamp
	---	2025-08-23 20:16:21	58.0 dB	None	---	None
L _{Peak(max)}	---	2025-08-23 20:18:18	---	None	---	None
		None	---	None	87.3 dB	2025-08-23 20:16:21

Overloads

Count	Duration
0	0:00:00.0

Statistics

	
LAS 90.0	43.9 dB
LAS 99.0	42.6 dB



C O N S T R U C T I O N M O D E L I N G R E S U L T S

Roadway Construction Noise Model (RCNM),Version 1.1

Report date: 09/17/2025
Case Description: SPLSD-02.0 - Site Preparation

**** Receptor #1 ****

Description	Land Use	Baselines (dBA)		
		Daytime	Evening	Night
Receptor at 50 feet	Residential	65.0	60.0	55.0

Description	Impact Device	Usage (%)	Equipment			
			Spec Lmax (dBA)	Actual Lmax (dBA)	Receptor Distance (feet)	Estimated Shielding (dBA)
Dozer	No	40		81.7	50.0	0.0
Backhoe	No	40		77.6	50.0	0.0
Front End Loader	No	40		79.1	50.0	0.0

Results

Equipment	Noise Limits (dBA)									Noise Limit Exceedance (dBA)					
	Calculated (dBA)		Day			Evening		Night		Day		Evening		Night	
	Lmax	Leq	Lmax	Leq		Lmax	Leq	Lmax	Leq	Lmax	Leq	Lmax	Leq	Lmax	Leq
Dozer	81.7	77.7	N/A	N/A		N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Backhoe	77.6	73.6	N/A	N/A		N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Front End Loader	79.1	75.1	N/A	N/A		N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Total	81.7	80.6	N/A	N/A		N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

Roadway Construction Noise Model (RCNM),Version 1.1

Report date: 09/17/2025
Case Description: PLSD-02.0 - Grading

**** Receptor #1 ****

Description	Land Use	Baselines (dBA)		
		Daytime	Evening	Night
Receptor at 50 feet	Residential	65.0	60.0	55.0

Description	Impact Device	Usage (%)	Equipment			
			Spec Lmax (dBA)	Actual Lmax (dBA)	Receptor Distance (feet)	Estimated Shielding (dBA)
Grader	No	40	85.0		50.0	0.0
Excavator	No	40		80.7	50.0	0.0
Scraper	No	40		83.6	50.0	0.0

Results

		Noise Limits (dBA)								Noise Limit Exceedance (dBA)					
		Calculated (dBA)		Day		Evening		Night		Day		Evening		Night	
		Lmax	Leq	Lmax	Leq	Lmax	Leq	Lmax	Leq	Lmax	Leq	Lmax	Leq	Lmax	Leq
Equipment															
Grader		85.0	81.0	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Excavator		80.7	76.7	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Scraper		83.6	79.6	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Total		85.0	84.2	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

Roadway Construction Noise Model (RCNM),Version 1.1

Report date: 09/17/2025
Case Description: PLSD-02.0 - Building Construction

**** Receptor #1 ****

Description	Land Use	Baselines (dBA)		
		Daytime	Evening	Night
Receptor at 50 feet	Residential	65.0	60.0	55.0

Description	Impact Device	Usage (%)	Equipment			
			Spec Lmax (dBA)	Actual Lmax (dBA)	Receptor Distance (feet)	Estimated Shielding (dBA)
Crane	No	16		80.6	50.0	0.0
Man Lift	No	20		74.7	50.0	0.0
Backhoe	No	40		77.6	50.0	0.0

Results

		Noise Limits (dBA)								Noise Limit Exceedance (dBA)					
		Calculated (dBA)		Day		Evening		Night		Day		Evening		Night	
		Lmax	Leq	Lmax	Leq	Lmax	Leq	Lmax	Leq	Lmax	Leq	Lmax	Leq	Lmax	Leq
Equipment															
Crane		80.6	72.6	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Man Lift		74.7	67.7	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Backhoe		77.6	73.6	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Total		80.6	76.7	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

Roadway Construction Noise Model (RCNM),Version 1.1

Report date: 09/17/2025
Case Description: PLSD-02.0 - Architectural Coating

**** Receptor #1 ****

Description	Land Use	Baselines (dBA)		
		Daytime	Evening	Night
Receptor at 50 feet	Residential	65.0	60.0	55.0

Description	Impact Device	Usage (%)	Equipment			
			Spec Lmax (dBA)	Actual Lmax (dBA)	Receptor Distance (feet)	Estimated Shielding (dBA)
Compressor (air)	No	40		77.7	50.0	0.0

		Noise Limits (dBA)								Noise Limit Exceedance (dBA)					
		Calculated (dBA)		Day		Evening		Night		Day		Evening		Night	
		Lmax	Leq	Lmax	Leq	Lmax	Leq	Lmax	Leq	Lmax	Leq	Lmax	Leq	Lmax	Leq
Equipment															
Compressor (air)		77.7	73.7	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Total		77.7	73.7	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

Roadway Construction Noise Model (RCNM),Version 1.1

Report date: 09/17/2025
Case Description: PLSD-02.0 - Architectural Coating

**** Receptor #1 ****

Description	Land Use	Baselines (dBA)		
		Daytime	Evening	Night
Receptor at 50 feet	Residential	65.0	60.0	55.0

Description	Impact Device	Usage (%)	Equipment			
			Spec Lmax (dBA)	Actual Lmax (dBA)	Receptor Distance (feet)	Estimated Shielding (dBA)
Paver	No	50		77.2	50.0	0.0
Roller	No	20		80.0	50.0	0.0

Results														
			Noise Limits (dBA)						Noise Limit Exceedance (dBA)					
Calculated (dBA)			Day		Evening		Night		Day		Evening		Night	
Equipment	Lmax	Leq	Lmax	Leq	Lmax	Leq	Lmax	Leq	Lmax	Leq	Lmax	Leq	Lmax	Leq
Paver	77.2	74.2	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Roller	80.0	73.0	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Total	80.0	76.7	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

PLSD-02 - Construction Noise Modeling Attenuation Calculations			
Phase 1		Levels in dBA Leq	
Phase	RCNM Reference Noise Level	Receptor to North	Receptor to West
	<i>Distance in feet</i>	<i>50</i>	<i>275</i>
Site Prep	81	66	56
Grading	84	69	59
<i>Distance in feet</i>	<i>50</i>	<i>165</i>	<i>730</i>
Building Construction	77	66	53
Architectural Coating	74	63	50
<i>Distance in feet</i>	<i>50</i>	<i>60</i>	<i>125</i>
Paving	77	75	69
Attenuation calculated through Inverse Square Law: $L_p(R2) = L_p(R1) - 20\text{Log}(R2/R1)$			

PLSD-02 - Construction Noise Modeling Attenuation Calculations				
Phase 2		Levels in dBA Leq		
Phase	RCNM	Receptor to North	Receptor to West	On Site Receptor
	Reference Noise Level			
	<i>Distance in feet</i>	<i>50</i>	<i>165</i>	<i>730</i>
Building Construction	77	66	53	64
Architectural Coating	74	63	50	61
	<i>Distance in feet</i>	<i>50</i>	<i>60</i>	<i>125</i>
Paving	77	75	69	65
Attenuation calculated through Inverse Square Law: $L_p(R2) = L_p(R1) - 20\text{Log}(R2/R1)$				

PLSD-02 - Construction Noise Modeling Attenuation Calculations				
Phase 3 Levels in dBA Leq				
RCNM				
Phase	Reference Noise Level	Receptor to North	Receptor to West	On-Site Receptor
<i>Distance in feet</i>	50	440	1110	390
Site Prep	81	62	54	63
Grading	84	65	57	66
<i>Distance in feet</i>	50	165	730	50
Building Construction	77	66	53	77
Architectural Coating	74	63	50	74
<i>Distance in feet</i>	50	60	125	50
Paving	77	75	69	77
Attenuation calculated through Inverse Square Law: $L_p(R2) = L_p(R1) - 20\log(R2/R1)$				

PLSD-02 - Construction Noise Modeling Attenuation Calculations				
Phase 4		Levels in dBA Leq		
Phase	RCNM Reference	Receptor to North	Receptor to West	On-Site Receptor
	Noise Level			
	<i>Distance in feet</i>	<i>50</i>	<i>165</i>	<i>730</i>
Building Construction	77	66	53	77
Architectural Coating	74	63	50	74
	<i>Distance in feet</i>	<i>50</i>	<i>60</i>	<i>125</i>
Paving	77	75	69	77
Attenuation calculated through Inverse Square Law: $L_p(R2) = L_p(R1) - 20\text{Log}(R2/R1)$				

PLSD-02 - Vibration Damage Attenuation Calculations				
Levels, PPV (in/sec)				
	Vibration Reference Level	Receptor to North	Receptor to West	On-Site Receptor
<i>Distance in feet</i>	<i>at 25 feet</i>	<i>45</i>	<i>135</i>	<i>30</i>
Vibratory Roller	0.21	0.087	0.017	0.160
Clam shovel	0.202	0.084	0.016	0.154
Hoe Ram	0.089	0.037	0.007	0.068
Large Bulldozer	0.089	0.037	0.007	0.068
Caisson Drilling	0.089	0.037	0.007	0.068
Loaded Trucks	0.076	0.031	0.006	0.058
Jackhammer	0.035	0.014	0.003	0.027
Small Bulldozer	0.003	0.001	0.000	0.002

T R A F F I C M O D E L I N G R E S U L T S

Traffic Noise Calculator: FHWA 77-108																										
Plumas Lake Middle School (PLSD-02) Existing 2025 Traffic Noise Traffic Conditions																										
ID	Output						Inputs															Auto Inputs				
	dBA at 50 feet			Distance to CNEL Contour			Roadway			Segment From - To			ADT	Posted Speed Limit	Grade	% Autos	% Med Trucks	% Heavy Trucks	% Daytime	% Evening	% Night	Number of Lanes	Site Condition	Distance to Receiver	Ground Absorption	Lane Distance
	L _{eq,24hr}	L _{dn}	CNEL	70 dBA	65 dBA	60 dBA																				
1	64.2	67.4	67.9	36	78	169	River Oaks Blvd	the North	Plumas Lake Blvd	7770	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44			
2	61.5	64.7	65.2	24	52	112	River Oaks Blvd	Plumas Lake Blvd	Zanes Dr	4170	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44			
3	61.4	64.6	65.1	24	51	110	River Oaks Blvd	Zanes Dr	Hidden Creek Way	4060	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44			
4	60.7	63.9	64.5	21	46	99	River Oaks Blvd	Hidden Creek Way	Leighton Grove Dr	3490	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44			
5	62.3	65.6	66.1	27	59	127	River Oaks Blvd	Leighton Grove Dr	Kensington Dr	5070	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44			
6	62.2	65.4	66.0	27	58	125	River Oaks Blvd	Kensington Dr	Cimarron Dr	4950	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44			
7	62.5	65.7	66.3	28	61	131	River Oaks Blvd	Cimarron Dr	Santa Cruz/Lockwood	5440	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20			
8	60.9	64.1	64.6	22	47	102	River Oaks Blvd	Santa Cruz/Lockwood	Feather River Blvd	3730	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20			
9	61.3	64.5	65.0	23	50	108	River Oaks Blvd	Feather River Blvd	the South	4100	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20			
10	58.7	61.9	62.4	16	34	73	Plumas Lake Blvd	the West	River Oaks Blvd	3960	35	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20			
11	60.7	63.9	64.5	21	46	99	Plumas Lake Blvd	River Oaks Blvd	the East	6140	35	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44			
12	51.9	55.1	55.6	6	12	26	Zanes Drive	River Oaks Blvd	the West	1620	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20			
13	52.5	55.7	56.2	6	13	28	Hidden Creek Way	River Oaks Blvd	the West	1860	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20			
14	49.5	52.8	53.3	4	8	18	Leighton Grove Dr	River Oaks Blvd	the East	950	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20			
15	52.1	55.3	55.9	6	12	26	Kensington Dr	River Oaks Blvd	the East	1710	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20			
16	54.2	57.4	58.0	8	17	37	Cimarron Dr	River Oaks Blvd	the East	2780	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20			
17	47.9	51.1	51.7	3	6	14	Santa Cruz/Lockwood	River Oaks Blvd	the West	650	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20			
18	47.2	50.4	50.9	3	6	12	Santa Cruz/Lockwood	River Oaks Blvd	the East	550	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20			
19	62.3	65.5	66.1	27	59	127	Feather River Blvd	River Oaks Blvd	SR-70 Southbound Ramps	5040	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44			
20	63.8	67.0	67.6	34	74	159	Feather River Blvd	SR-70 Southbound Ramps	SR-70 Northbound Ramps	7110	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44			
21	61.7	65.0	65.5	25	54	116	Feather River Blvd	SR-70 Northbound Ramps	Chalice Creek Rd	4420	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44			
22	59.5	62.7	63.2	18	38	82	Feather River Blvd	Chalice Creek Rd	the East	2630	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44			

Traffic Noise Calculator: FHWA 77-108																							
Plumas Lake Middle School (PLSD-02) Opening Year 2027 No Project Traffic Noise Traffic Conditions																							
ID	Output						Inputs															Auto Inputs	
	dBA at 50 feet			Distance to CNEL Contour			Roadway	Segment From - To	ADT	Posted Speed Limit	Grade	% Autos	% Med Trucks	% Heavy Trucks	% Daytime	% Evening	% Night	Number of Lanes	Site Condition	Distance to Receiver	Ground Absorption	Lane Distance	
L _{eq,24hr}	L _{dn}	CNEL	70 dBA	65 dBA	60 dBA																		
1	64.9	68.1	68.7	41	88	190	River Oaks Blvd	the North	Plumas Lake Blvd	9,220	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
2	62.3	65.6	66.1	27	59	127	River Oaks Blvd	Plumas Lake Blvd	Zanes Dr	5,070	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
3	61.7	65.0	65.5	25	54	117	River Oaks Blvd	Zanes Dr	Hidden Creek Way	4,450	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
4	61.1	64.3	64.9	23	49	106	River Oaks Blvd	Hidden Creek Way	Leighton Grove Dr	3,830	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
5	62.6	65.8	66.4	29	62	133	River Oaks Blvd	Leighton Grove Dr	Kensington Dr	5,410	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
6	63.3	66.5	67.0	32	68	148	River Oaks Blvd	Kensington Dr	Cimarron Dr	6,330	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
7	63.0	66.2	66.7	30	65	141	River Oaks Blvd	Cimarron Dr	Santa Cruz/Lockwood	6,070	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
8	61.3	64.5	65.0	23	50	108	River Oaks Blvd	Santa Cruz/Lockwood	Feather River Blvd	4,100	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
9	61.9	65.1	65.7	26	55	119	River Oaks Blvd	Feather River Blvd	the South	4,750	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
10	59.6	62.8	63.3	18	39	84	Plumas Lake Blvd	the West	River Oaks Blvd	4,880	35	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
11	61.5	64.8	65.3	24	52	113	Plumas Lake Blvd	River Oaks Blvd	the East	7,420	35	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
12	52.2	55.5	56.0	6	13	27	Zanes Drive	River Oaks Blvd	the West	1,760	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
13	52.7	55.9	56.5	6	14	29	Hidden Creek Way	River Oaks Blvd	the West	1,970	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
14	49.8	53.1	53.6	4	9	19	Leighton Grove Dr	River Oaks Blvd	the East	1,020	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
15	54.6	57.9	58.4	8	18	39	Kensington Dr	River Oaks Blvd	the East	3,080	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
16	55.1	58.4	58.9	9	20	42	Cimarron Dr	River Oaks Blvd	the East	3,440	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
17	48.2	51.4	51.9	3	7	14	Santa Cruz/Lockwood	River Oaks Blvd	the West	690	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
18	47.4	50.6	51.2	3	6	13	Santa Cruz/Lockwood	River Oaks Blvd	the East	580	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
19	63.0	66.3	66.8	31	66	142	Feather River Blvd	River Oaks Blvd	SR-70 Southbound Ramps	5,990	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
20	64.5	67.8	68.3	38	83	178	Feather River Blvd	SR-70 Southbound Ramps	SR-70 Northbound Ramps	8,420	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
21	62.5	65.8	66.3	28	61	131	Feather River Blvd	SR-70 Northbound Ramps	Chalice Creek Rd	5,310	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
22	59.9	63.2	63.7	19	41	88	Feather River Blvd	Chalice Creek Rd	the East	2,940	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44

Traffic Noise Calculator: FHWA 77-108																											Plumas Lake Middle School (PLSD-02) Opening Year 2027 with Project Traffic Noise Traffic Conditions																										
ID	Output						Inputs																			Auto Inputs																											
	dBA at 50 feet			Distance to CNEL Contour			Roadway			Segment From - To			ADT	Posted Speed Limit	Grade	% Autos	% Med Trucks	% Heavy Trucks	% Daytime	% Evening	% Night	Number of Lanes	Site Condition	Distance to Receiver	Ground Absorption	Lane Distance																											
	L _{eq,24hr}	L _{day}	CNEL	70 dBA	65 dBA	60 dBA																																															
1	65.0	68.2	68.8	41	89	192	River Oaks Blvd	the North	Plumas Lake Blvd	9,402	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44																														
2	62.5	65.7	66.2	28	60	130	River Oaks Blvd	Plumas Lake Blvd	Zanes Dr	5,237	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44																														
3	61.7	65.0	65.5	25	54	117	River Oaks Blvd	Zanes Dr	Hidden Creek Way	4,450	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44																														
4	61.1	64.3	64.9	23	49	106	River Oaks Blvd	Hidden Creek Way	Leighton Grove Dr	3,830	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44																														
5	62.6	65.8	66.4	29	62	133	River Oaks Blvd	Leighton Grove Dr	Kensington Dr	5,410	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44																														
6	63.3	66.5	67.0	32	68	148	River Oaks Blvd	Kensington Dr	Cimarron Dr	6,330	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44																														
7	63.0	66.2	66.7	30	65	141	River Oaks Blvd	Cimarron Dr	Santa Cruz/Lockwood	6,070	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20																														
8	61.3	64.5	65.0	23	50	108	River Oaks Blvd	Santa Cruz/Lockwood	Feather River Blvd	4,100	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20																														
9	61.9	65.1	65.7	26	55	119	River Oaks Blvd	Feather River Blvd	the South	4,750	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20																														
10	59.6	62.8	63.3	18	39	84	Plumas Lake Blvd	the West	River Oaks Blvd	4,880	35	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20																														
11	61.5	64.8	65.3	24	52	113	Plumas Lake Blvd	River Oaks Blvd	the East	7,420	35	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44																														
12	52.2	55.5	56.0	6	13	27	Zanes Drive	River Oaks Blvd	the West	1,760	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20																														
13	52.7	55.9	56.5	6	14	29	Hidden Creek Way	River Oaks Blvd	the West	1,970	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20																														
14	49.8	53.1	53.6	4	9	19	Leighton Grove Dr	River Oaks Blvd	the East	1,020	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20																														
15	54.6	57.9	58.4	8	18	39	Kensington Dr	River Oaks Blvd	the East	3,080	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20																														
16	55.1	58.4	58.9	9	20	42	Cimarron Dr	River Oaks Blvd	the East	3,440	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20																														
17	48.2	51.4	51.9	3	7	14	Santa Cruz/Lockwood	River Oaks Blvd	the West	690	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20																														
18	47.4	50.6	51.2	3	6	13	Santa Cruz/Lockwood	River Oaks Blvd	the East	580	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20																														
19	63.0	66.3	66.8	31	66	142	Feather River Blvd	River Oaks Blvd	SR-70 Southbound Ramps	5,990	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44																														
20	64.5	67.8	68.3	38	83	178	Feather River Blvd	SR-70 Southbound Ramps	SR-70 Northbound Ramps	8,420	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44																														
21	62.5	65.8	66.3	28	61	131	Feather River Blvd	SR-70 Northbound Ramps	Chalice Creek Rd	5,310	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44																														
22	59.9	63.2	63.7	19	41	88	Feather River Blvd	Chalice Creek Rd	the East	2,940	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44																														

Traffic Noise Calculator: FHWA 77-108																							
Plumas Lake Middle School (PLSD-02) Cumulative Year 2040 no Project Traffic Noise Traffic Conditions																							
ID	Output						Inputs														Auto Inputs		
	dBA at 50 feet			Distance to CNEL Contour			Roadway		Segment From - To		ADT	Posted Speed Limit	Grade	% Autos	% Med Trucks	% Heavy Trucks	% Daytime	% Evening	% Night	Number of Lanes	Site Condition	Distance to Receiver	Ground Absorption
L _{eq,24hr}	L _{dn}	CNEL	70 dBA	65 dBA	60 dBA																		
1	68.0	71.2	71.8	65	141	304	River Oaks Blvd	the North	Plumas Lake Blvd	18,710	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
2	65.6	68.9	69.4	46	98	211	River Oaks Blvd	Plumas Lake Blvd	Zanes Dr	10,860	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
3	63.4	66.6	67.1	32	70	150	River Oaks Blvd	Zanes Dr	Hidden Creek Way	6,480	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
4	62.6	65.9	66.4	29	62	133	River Oaks Blvd	Hidden Creek Way	Leighton Grove Dr	5,450	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
5	63.6	66.8	67.4	33	72	155	River Oaks Blvd	Leighton Grove Dr	Kensington Dr	6,810	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
6	64.7	67.9	68.4	39	85	183	River Oaks Blvd	Kensington Dr	Cimarron Dr	8,740	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
7	63.7	67.0	67.5	34	74	158	River Oaks Blvd	Cimarron Dr	Santa Cruz/Lockwood	7,260	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
8	62.9	66.2	66.7	30	65	140	River Oaks Blvd	Santa Cruz/Lockwood	Feather River Blvd	6,020	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
9	64.4	67.7	68.2	38	82	176	River Oaks Blvd	Feather River Blvd	the South	8,490	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
10	63.0	66.3	66.8	31	66	142	Plumas Lake Blvd	the West	River Oaks Blvd	10,840	35	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
11	64.8	68.0	68.5	40	86	186	Plumas Lake Blvd	River Oaks Blvd	the East	15,680	35	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
12	53.5	56.7	57.2	7	15	33	Zanes Drive	River Oaks Blvd	the West	2,340	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
13	53.9	57.1	57.7	8	16	35	Hidden Creek Way	River Oaks Blvd	the West	2,600	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
14	51.2	54.4	55.0	5	11	23	Leighton Grove Dr	River Oaks Blvd	the East	1,390	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
15	56.9	60.1	60.6	12	26	55	Kensington Dr	River Oaks Blvd	the East	5,140	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
16	54.8	58.1	58.6	9	19	40	Cimarron Dr	River Oaks Blvd	the East	3,210	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
17	50.1	53.4	53.9	4	9	20	Santa Cruz/Lockwood	River Oaks Blvd	the West	1,090	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
18	49.4	52.6	53.1	4	8	17	Santa Cruz/Lockwood	River Oaks Blvd	the East	910	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
19	65.9	69.2	69.7	48	103	222	Feather River Blvd	River Oaks Blvd	SR-70 Southbound Ramps	11,650	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
20	67.3	70.5	71.1	59	127	273	Feather River Blvd	SR-70 Southbound Ramps	SR-70 Northbound Ramps	15,950	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
21	65.3	68.6	69.1	44	94	202	Feather River Blvd	SR-70 Northbound Ramps	Chalice Creek Rd	10,140	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
22	61.3	64.5	65.1	23	51	109	Feather River Blvd	Chalice Creek Rd	the East	4,020	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44

Traffic Noise Calculator: FHWA 77-108																							
Plumas Lake Middle School (PLSD-02) Cumulative Year 2040 With Project Traffic Noise Traffic Conditions																							
ID	Output						Inputs														Auto Inputs		
	dBA at 50 feet			Distance to CNEL Contour			Roadway		Segment From - To		ADT	Posted Speed Limit	Grade	% Autos	% Med Trucks	% Heavy Trucks	% Daytime	% Evening	% Night	Number of Lanes	Site Condition	Distance to Receiver	Ground Absorption
L _{eq,24hr}	L _{dn}	CNEL	70 dBA	65 dBA	60 dBA																		
1	68.0	71.2	71.8	66	141	305	River Oaks Blvd	the North	Plumas Lake Blvd	18,787	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
2	65.6	68.9	69.4	46	98	211	River Oaks Blvd	Plumas Lake Blvd	Zanes Dr	10,860	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
3	63.4	66.6	67.1	32	70	150	River Oaks Blvd	Zanes Dr	Hidden Creek Way	6,480	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
4	62.6	65.9	66.4	29	62	133	River Oaks Blvd	Hidden Creek Way	Leighton Grove Dr	5,450	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
5	63.6	66.8	67.4	33	72	155	River Oaks Blvd	Leighton Grove Dr	Kensington Dr	6,810	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
6	64.7	67.9	68.4	39	85	183	River Oaks Blvd	Kensington Dr	Cimarron Dr	8,740	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
7	63.7	67.0	67.5	34	74	158	River Oaks Blvd	Cimarron Dr	Santa Cruz/Lockwood	7,260	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
8	62.9	66.2	66.7	30	65	140	River Oaks Blvd	Santa Cruz/Lockwood	Feather River Blvd	6,020	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
9	64.4	67.7	68.2	38	82	176	River Oaks Blvd	Feather River Blvd	the South	8,490	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
10	63.0	66.3	66.8	31	66	142	Plumas Lake Blvd	the West	River Oaks Blvd	10,840	35	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
11	64.8	68.0	68.5	40	86	186	Plumas Lake Blvd	River Oaks Blvd	the East	15,680	35	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
12	53.5	56.7	57.2	7	15	33	Zanes Drive	River Oaks Blvd	the West	2,340	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
13	53.9	57.1	57.7	8	16	35	Hidden Creek Way	River Oaks Blvd	the West	2,600	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
14	51.2	54.4	55.0	5	11	23	Leighton Grove Dr	River Oaks Blvd	the East	1,390	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
15	56.9	60.1	60.6	12	26	55	Kensington Dr	River Oaks Blvd	the East	5,140	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
16	54.8	58.1	58.6	9	19	40	Cimarron Dr	River Oaks Blvd	the East	3,210	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
17	50.1	53.4	53.9	4	9	20	Santa Cruz/Lockwood	River Oaks Blvd	the West	1,090	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
18	49.4	52.6	53.1	4	8	17	Santa Cruz/Lockwood	River Oaks Blvd	the East	910	25	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	2	Soft	50	0.5	20
19	65.9	69.2	69.7	48	103	222	Feather River Blvd	River Oaks Blvd	SR-70 Southbound Ramps	11,650	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
20	67.3	70.5	71.1	59	127	273	Feather River Blvd	SR-70 Southbound Ramps	SR-70 Northbound Ramps	15,950	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
21	65.3	68.6	69.1	44	94	202	Feather River Blvd	SR-70 Northbound Ramps	Chalice Creek Rd	10,140	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44
22	61.3	64.5	65.1	23	51	109	Feather River Blvd	Chalice Creek Rd	the East	4,020	45	0.0%	96.0%	2.5%	1.5%	75.0%	12.7%	12.3%	4	Soft	50	0.5	44

This page is intentionally left blank.