

NOTICE OF EXEMPTION

TO: Office of Planning and Research
CEQAnet Web Portal
<https://ceqasubmit.opr.ca.gov/>

FROM: San Joaquin County
Department of Public Works
1810 East Hazelton Avenue
Stockton, California 95205

County Clerk
County of San Joaquin California
44 North San Joaquin Street, Suite 260
Stockton, California 95202

Project Title: Liberty Road and Sowles Road Resurfacing

Project Location: See attached vicinity map

Description of Nature, Purpose, and Beneficiaries: See attached project description

Public Agency Approving Project: San Joaquin County Public Works Department

Name of Agency Carrying Out Project: San Joaquin County Public Works Department

This is to advise that the San Joaquin County Public Works Department has approved the above described project on 8/26/2025 and has made the determination that the project is exempt due to the following:

Exempt Status (check one):

- Ministerial (Sec. 21080 (b) (1); 15268)
- Declared Emergency (Sec. 21080 (b) (3); 15269(a))
- Emergency Project (Sec. 21080 (B) (4); 15269(b) (c))
- Categorical Exemption: Existing Facilities (Sec. 15301 (c))
- Statutory Exemption (Sec. 15282(l))

Reason(s) why project is exempt: The project will repair existing roads and will not result in any major alterations to the configuration of the roads. No additional vehicle travel lanes will be constructed.

Lead Agency Contact Person: Fatima Gutierrez, Assistant Planner, (209) 468-3035

Signature: Fatima Gutierrez Title: Assistant Planner Date: 9/3/2025

Filed Doc #: 39-09042025-259
09/04/2025 09:43:08 AM
Steve J. Bestolarides
San Joaquin County Clerk

LIBERTY ROAD AND SOWLES ROAD RESURFACING

Project Description

Project Location:

Liberty Road: Dustin Road to Elliot Road; Sowles Road: Collier Road to Liberty Road. **See attached Vicinity Map.**

Project Justification:

Liberty Road's original roadway was constructed in 1948 with an unknown structural section. In 1973, it was reconstructed to a 24-foot-wide roadway with 2 inches of Asphalt Concrete (AC) over 6 inches of Aggregate Base (AB). In 1985, the road was resurfaced from Dustin Road to Elliot Road with 2 inches of AC. In 1999, the road was resurfaced from Dustin Road to Bruella Road with 3 inches of AC. In 2001, the road was resurfaced from Bruella Road to Elliot Road with 3 inches of AC. The existing roadway has been maintained with periodic chip seals with the most recent chip seal in 2021.

Sowles Road's original 18-foot-wide roadway was constructed by Road Maintenance in 1971 with 2 inches of AC over 6 inches of AB. The existing roadway has been maintained with periodic chip seals with the most recent chip seal in 2021.

The existing pavement consists of some rutting and transverse, longitudinal, and edge cracking throughout the project limits.

Scope of Work:

The project will consist of:

1. Resurfacing existing roadway on Liberty Road (24 feet wide) with 0.17 feet of Hot Mix Asphalt (HMA) (Type A) and on Sowles Road (18 feet wide) with 0.25 feet of HMA (Type A).
2. Repairing pavement structural failure areas with full depth 0.25 feet of HMA (Type A).
3. Replenishing 4-foot-wide Shoulder Backing: 2 feet (8%) and 2 feet to conform.
4. Applying Penetration Treatment at all intersection radii plus 50 feet or to conform.
5. Constructing HMA (Type A) driveways.
6. Adjusting monument frames and covers.

Environmental Setting:

In these portions of the San Joaquin County, land usage is **rural with single family homes**.

There are many large trees adjacent to the project area. Nesting and migratory birds, protected by the Migratory Bird Treaty Act, may nest within these trees. Furthermore, the Swainson's Hawk, a raptor species of concern within the State of California and listed as threatened may nest adjacent to or within the project area. A pre-construction survey for nesting Swainson's Hawks and other migratory birds is recommended if construction is scheduled to occur from February 15th to September 1st.

Beneficiaries:

The public will see increased safety and fewer hazards with these well-maintained roads. Overall, there will be reduced maintenance concerns and more reliability within the project area.

SACRAMENTO COUNTY

SAN JOAQUIN COUNTY
LIMITS

PROJECT
LOCATION

LIBERTY ROAD

DUSTIN RD

BRUELLA RD

ELLIOT RD

COLLIER RD

SOWLES ROAD


JAHANT RD

San Joaquin
County

D4

District No. 4

NO SCALE



Vicinity Map

LIBERTY ROAD AND SOWLES ROAD RESURFACING

(Liberty Road: Dustin Road to Elliott Road;
Sowles Road: Collier Road to Liberty Road)

