

Project Description Continuation Page:

The new MGS at the bridge locations will be connected to a new concrete barrier transition at the beginning and the end of each bridge railing. The concrete barrier transition will be attached through drilling and bonding into the existing bridge railing. Asbestos testing may be required for the existing bridge railing. No other bridge work is planned. Below is the list of all bridges that require concrete barrier transition:

- Gas Line Wash – Bridge No. 54-0715 R/L;
- Twin Hills Wash – Bridge No. 54-0716 R/L;
- Crest Wash – Bridge No. 54-0717 R/L;
- W Newberry Road Undercrossing – Bridge No. 54-0708 R/L;
- Newberry Road Overcrossing – Bridge No. 54-0709;
- Fort Cady Road Overcrossing – Bridge No. 54-0710

All work is expected to be performed within the existing Caltrans right of way.