

Appendix F Sewer Study

APPENDIX

This page is intentionally left blank.

RECEIVED
SEP 16 2025
PLANNING DIV

SEWER SYSTEM HYDRAULIC ANALYSIS
FOR
AMWAY SITE AT BUENA PARK
VTTM 19419
5600 BEACH BLVD
BUENA PARK, CA 90621
APN NO. 066-572-08
RICK Job Number 20101

Carson P. Edgington

RCE 76519

Prepared By:

RICK

5620 Friars Road

San Diego, California 92110

(619) 291-0707

Prepared For:

City of Buena Park

Public Works Department

6650 Beach Blvd.

Buena Park, California 90621

September 2, 2025

TABLE OF CONTENTS

Section 1: Introduction 1

1.1 Purpose of the Study	1
1.2 Project Description.....	1
1.3 Existing and Proposed Conditions	1

Section 2: Design Methodology 2

Section 3: Conclusion 3

Appendices

Appendix A- Site Plan

Appendix B- ADS Flow Monitoring Report

Appendix C- Sewer Generation Factor Guidelines

Appendix D- Hydraulic Analysis Reports

Appendix E- Existing City Sewer Plans

Section 1: Introduction

1.1 Purpose of Study

The purpose of this report is to evaluate the impact of the proposed private sewer mains and public sewer connections for the proposed site development as it relates to the existing sewer condition that currently serves the Amway Site. It is not for recommendations for sewer upgrades but to determine if the Amway Site triggers any deficiencies in the existing City of Buena Park sewer system with the sewer flows from the development.

1.2 Project Description

The project site is located on the northeast side of Beach Boulevard and Dr. Sam Way in the City of Buena Park. This development consists of 50 residential affordable housing units and 231 residential townhouse units as shown in the Site Plan, Appendix A. Below is a summary breakdown of housing units by lateral connection:

Lateral Connection 1: 146 Residential Units

Lateral Connection 2: 135 Residential Units


1.3 Existing and Proposed Conditions

Existing Conditions:

The existing sewer flow from the Amway site that will be removed flows into the public sewer main in Dr. Sam Way in and Beach Boulevard in 8" sewer mains. From the intersection, existing flows transition to a 10" pipe and continue south through Beach Boulevard into Franklin Street. From there, the sewer flows west in a 10" sewer main.

Proposed Conditions:

The proposed sewer conveys sewer flows from multifamily residential units into the existing 8" sewer lateral connections to the Amway site at Beach Blvd at MH 07-57, and replaces the sewer main in Dr. Sam Way to serve the site into the existing lateral, which ties into MH 07-54 in Beach Blvd.



LEGEND:

PROPOSED SEWER — S —

EXISTING SEWER — S —



RICK

5620 FRIARS ROAD
SAN DIEGO, CA 92110
619-291-0707
rickengineering.com

AMWAY SITE - BUENA PARK

SEWER FLOW NODE DIAGRAM

PROJECT NO:	20101	SCALE:	1"=80'
DRAWN BY:	WW	DATE:	9/2/2025

Section 2: Design Methodology

Under the direction of the City of Buena Park, sewer metering was conducted at two locations by ADS Environmental Services. The first location was at MH 07-55, the intersection of Dr. Sam Way and Darlington Avenue. This data would show the existing flows upstream from the site. The second location was at MH 07-31, the intersection of Fullerton Avenue and Franklin Street. This data would show the existing flows downstream from our site. The data provided in the ADS report, shown in Appendix B, shows real data on existing flows being generated prior to the development introducing any proposed flows. Note that MH 07-55 captures some of the existing site flow as MH 07-56 contains the end of a siphon system and is unable to be monitored, and MH 07-31 includes flows from the existing site and other developments as well so the study will be a more conservative assessment.

The results are shown in Appendix B and show that the existing system has capacity for the proposed development. Table 1 summarizes the existing City sewer flow results from the ADS monitoring report. At its peak, the city's 10" sewer main on Franklin Street is flowing at 37%.

The proposed development sewer flow contributions to the existing City public sewer were determined using a sewer generation factor per direction of the City of Buena Park as shown in email attached in Appendix C. The wastewater generation factor of 250 gallons per day (GPD) per dwelling unit was used in this analysis. The proposed additional average sewer flows were converted to cubic feet per second (cfs), with a peak factor (PF) of 2.0 to determine the estimated peak sewer flow for this development as shown in Table 2.

Next, the flow depth was calculated through the public sewer system using Manning's equation. Sewer flow analysis table using King's handbook of hydraulics is summarized in Table 4. The equation used to determine flows with King's handbook is as follows:

$$K = \frac{Q_n}{\frac{8}{3}s^{\frac{1}{2}}}$$

The results from the Flow Monitoring Study and the proposed additional sewer flows were then input into Hydraulic Toolbox 5.4 computer program to analyze the effects on the City sewer capacity. To provide a conservative approach, the maximum or peak measured depth were used

rather than the calculated quantity from the flow monitoring study. The results of the hydraulic analysis are found in Appendix D – Hydraulic Analysis Reports (Hydraulic Toolbox 5.4 Results Tables).

The existing sewer as-built plans for Franklin Street and Beach Boulevard were obtained from the City of Buena Park Sewer Service Division website, maps attached in Appendix E.

Conclusion

This sewer system capacity study was completed to determine the anticipated wastewater flow demands that will be produced by the development per the Preliminary Site Plan attached in Appendix A and determine if the existing City sewers in the vicinity have the capacity to accept the additional development flows.

The city of Buena Park existing 8” and 10” sewer mains were determined to have a peak depth of 4.45” and 4.70”, respectively, and a maximum sewer flow of 0.317 cfs and 0.444 cfs. The public sewer mains are flowing at 44% and 37% in the existing condition. Note that the flow monitor placements for this study are unable to fully isolate the existing site with the nearest manholes we were able to access upstream and downstream, so the study is more conservative. The proposed development will add a total additional 0.217 cfs peak flow. The combined flow results in a peak flow of 0.655 cfs at 55% full in the 10” sewer main downstream, as summarized in Table 3.

Based on our analysis there is sufficient capacity available in the existing City sewer mains to accept the anticipated flow of the Amway site.

<p>Table 1 City of Buena Park Amway Site Existing Sewer Flow Summary</p>									
Street Name	Manhole No.	ADS Manhole No.	Item	Pipe Diameter (in)	Depth (in)	Velocity (ft/s)	Flow (mgd)	Flow (cfs)	Percent Full (%)
Dr. Sam Way	07-55	BP07-55		8					
			Average		3.31	1.21	0.109	0.169	
			Minimum		2.20	0.80	0.040	0.062	
			Maximum		4.45	1.61	0.205	0.317	44%
Franklin St	07-31	BP07-31		10					
			Average		3.50	1.46	0.164	0.254	
			Minimum		2.37	1.02	0.067	0.104	
			Maximum		4.70	1.80	0.287	0.444	37%

<p>Table 2 City of Buena Park Amway Site Proposed Sewer Flows</p>								
Lateral No.	Manhole No.	Use Type	No. of Units	Average Daily Flow (gpd/unit)	Total Daily Flow (gpd)	Total Flow (cfs)	Peaking Factor	Total Peak Flow (cfs)
1	1, 2, 3, 07-57	Multi Residential	138	250	34500	0.05	2	0.11
2	07-56, 4, 5, 6, 7, 8, 07-54	Multi Residential	135	250	33750	0.05	2	0.10

<p>Table 3 City of Buena Park Amway Site Existing and Proposed Sewer Flow Summary</p>								
Street Name	Manhole No.	ADS Manhole No.	Item	Pipe Diameter (in)	Depth (in)	Velocity (ft/s)	Flow (cfs)	Percent Full (%)
Dr. Sam Way	07-55	BP07-55	Existing	8	4.45	1.61	0.317	44%
			Proposed Flow	8			0.104	
			Total	8	4.79	1.93	0.421	58%
Franklin St	07-31	BP07-31	Existing	10	4.70	1.80	0.444	37%
			Proposed Flow	10			0.217	
			Total	10	5.76	2.02	0.661	55%

Table 4
City of Buena Park
Amway Site
Sewer Flow Analysis

	Upstream MH	Downstream MH	Peak Design Flow													
LINE	From MH	To MH	Diameter	Upstream DU's	In Line Du's*	Total Du's	GPD per DU	ADWF (gpd)	Dry Weather Peaking	PDWF (gpd) ²	Peak Dry Weather Flow	Slope (%)	dn (FT)	dn/D	Rh	Velocity (fps)
L1	1	2	6	77.0	69	146	250.0	36,500	2.00	73,000.00	0.11	1.00	0.15	0.30	0.09	2.24
L2	2	3	6	146.0	0	146	250.0	36,500	2.00	73,000.00	0.11	2.00	0.13	0.25	0.07	2.86
L3	3	07-57	8	146.0	0	146	360.0	52,560	2.00	105,120.00	0.16	1.41	0.15	0.23	0.09	2.73
L4	07-57	07-54	8	146.0	0	146	360.0	52,560	2.00	105,120.00	0.16	0.55	0.19	0.29	0.11	1.95
L5	07-56	4	8	-	-	-	-	-	-	-	0.32	0.36	0.31	0.46	0.16	2.01
L6	4	5	8	0.0	44	44	250.0	11,000	2.00	22,000.00	0.35	0.36	0.33	0.49	0.17	2.06
L7	5	6	8	44.0	40	84	360.0	30,240	2.00	60,480.00	0.41	0.36	0.36	0.54	0.17	2.15
L8	6	7	8	84.0	51	135	360.0	48,600	2.00	97,200.00	0.47	0.36	0.39	0.59	0.18	2.21
L9	7	8	8	135.0	0	135	360.0	48,600	2.00	97,200.00	0.47	0.36	0.39	0.59	0.18	2.21
L10	8	07-54	8	135.0	0	135	360.0	48,600	2.00	97,200.00	0.47	0.36	0.39	0.59	0.18	2.21
L10	07-54	07-32	10	281.0	0	281	360.0	101,160	2.00	202,320.00	0.63	0.20	0.49	0.59	0.23	1.91
L11	07-32	07-31	10	281.0	0	281	360.0	101,160	2.00	202,320.00	0.76	0.30	0.48	0.58	0.23	2.33

APPENDIX A

Site Plan



- Legend**
- 1. Property Line
 - 2. Parking Space - 9'x20'
 - 3. Accessible Parking Space
 - 4. Trash Enclosure
 - 5. Accessible Path of Travel
 - 6. Accessible Ground Floor Unit
 - 8. Affordable Units
 - 9. Transformers
 - 10. Setback Line
 - 11. Electrical Cabinet and Fire Riser

Overall Site Summary	
Gross Site Area	13.750 Acres (599,105 SqFt)
Affordable Units	50 du (0.85 Ac/36,908 SqFt)
Townhome / Duplex Units	231 du (12.9 Ac/562,197 SqFt)
Total Dwelling Units	281 du
Gross Density	20.4 Du/Ac
Product Type	3 Story Duplex / Townhomes Affordable Bldg
Occupancy Type	CRC Townhomes & 2 Family Dwelling
Construction Type	Towns / Duplex: Type VB Affordable: VA
Sprinkler Type	Towns/Duplex: NFPA 13D Affordable: NFPA 13
Building Height	Towns / Duplex: 39' Affordable: 48'
Front Setback	19' Required 20' Proposed
Side / Rear Setback	10' Required 10' Proposed

Overall Building Summary				
Building Type	Quantity	Bldg Footprint Area	Gross Bldg Area	Total Area
Building A3 - Affordable	1	10,900 sf	31,460 sf	31,460 sf
Product B - 4 Plex Bldg A	3	3,179 sf	9,598 sf	28,794 sf
Product B - 5 Plex Bldg B	9	3,758 sf	11,618 sf	104,562 sf
Product B - 5 Plex Bldg C	3	3,978 sf	12,063 sf	36,189 sf
Product B - 6 Plex Bldg D	7	4,526 sf	13,986 sf	97,902 sf
Product C - Duets	58	1,689 sf	4,957 sf	287,506 sf
Product C - Duet Single	1	872 sf	4,140 sf	4,140 sf
Pool Building	1	437 sf	437 sf	437 sf
Total	83	197,146 sf 32.9%		590,990 sf
FAR				0.99
Lot Coverage			34.9%	209,306 sf

Plan Summary						
Plan	Beds	Net Unit Area	Quantity	%	Total Net Area	Avg. Unit Size
Affordable - P1	1	400 sf	44	15.7%		
Affordable - P2	2	469 sf	6	2.1%		
Subtotal A Affordable			50	18%		
B Townhomes - P1	2	1,238 sf	16	5.7%		
B Townhomes - P2	3	1,523 sf	16	5.7%		
B Townhomes - P3	3	1,646 sf	35	12.5%		
B Townhomes - P4	4	1,863 sf	47	16.7%		
Subtotal B Townhomes			114	41%		
C Duets - P1	3	1,694 sf	59	21.0%		
C Duets - P2	4	1,947 sf	58	20.6%		
Subtotal C Duets			117	42%		
Total			281	100%	422,633 sf	1,504 sf
Unit Mix						
			Quantity	%		
Affordable 1 Bedroom Total			44	15.7%		
Affordable 2 Bedroom Total			6	2.1%		
2 Bedroom Total			16	5.7%		
3 Bedroom Total			110	39.1%		
4 Bedroom Total			105	37.4%		
Total			281	100.0%		

Parking Summary (per State Density Bonus Law)			
Parking Required	Quantity	Ratio Req'd	Spaces Req'd
Affordable - P1	57	1.00 Spaces/Unit	57
Affordable - P2	3	1.00 Spaces/Unit	3
2 Bed	16	1.50 Spaces/Unit	24
3 Bed	110	1.50 Spaces/Unit	165
4 Bed	105	2.50 Spaces/Unit	263
Total Residential Parking Req'd		1.82 Spaces/Unit	512
Parking Provided		Ratio Provided	Spaces Provided
Garage Spaces		1.64	462
On Site / Guest Spaces		0.37	105
Total Residential Parking Provided		2.02	567
Accessible Parking Required		Ratio Req'd	Spaces Req'd
Resident Open Spaces	105	5%	6
Open Space Summary			
Private Balcony Open Space (6'x6' min.)	5,973 sf	21 sf/Unit	
Private Ground Floor Open Space 10x10	3,574 sf	13 sf/Unit	
Common Open Space	170,792 sf	608 sf/Unit	
Total Open Space Provided	180,339 sf	642 sf/Unit	

- Enhanced Elevations
- Privacy Duets
- Building Number
- Building Type
- Unit Number
- Plan Type

APPENDIX B

ADS Flow Monitoring Report

Amway Sewer Flow Monitoring, Buena Park 2025

Final Report Submitted to **Rick Engineering**
August 29, 2025



ADS ENVIRONMENTAL
SERVICES



August 29, 2025

Carson P. Edgington, P.E.
Rick Engineering
5620 Friars Road
San Diego, CA 92110

SUBJECT: Amway Sewer Flow Monitoring, Buena Park 2025

Dear Carson P. Edgington,

ADS is pleased to submit the report for the Amway Sewer Flow Monitoring, Buena Park 2025 completed on behalf of Rick Engineering. The metering was conducted at two (2) location(s). The study was conducted during the period of Saturday, 26 July 2025 to Friday, 08 August 2025.

The report contains depth, velocity, and quantity hydrographs as well as daily long tables for the metering period. An Excel file containing depth, quantity, and velocity entities for the monitoring location in 5-minute format was provided previously.

In addition, we would be happy to further explain any details about the report that may seem unclear. Should you have any questions or comments, you may contact the Project Manager, Paul Mitchell at (714)920-5518.

It has been our pleasure to be of service to you in the performance of this project. Thank you for choosing ADS products and services to meet your flow monitoring needs.

Sincerely,

ADS ENVIRONMENTAL SERVICES

Latisha Bennett
Senior Hydraulic Data Analyst

Saturday, 26 July 2025 to Friday, 08 August 2025



Amway Sewer Flow Monitoring, Buena Park 2025

Prepared For:

Carson P. Edgington, PE
Rick Engineering
5620 Friars Road
San Diego, CA 92110

Prepared By:



ADS, LLC
340 The Bridge Street, Suite 204
Huntsville, AL 35806



Introduction

Rick Engineering entered into an agreement with ADS Environmental Services to conduct flow monitoring at two (2) locations in Buena Park, CA. The study was scheduled for a period of two (2) weeks. Once in place, the flow monitoring equipment was used to measure depth, velocity, and to quantify flows. The objective of this study was to confirm flows for planning purposes.

Project Scope

The scope of this study involved using a flow monitor to quantify wastewater flow at the designated location for the 2 weeks period. Specifically, the study included the following key components.

- Investigate the proposed flow-monitoring site for adequate hydraulic conditions
- Flow monitor installation
- Flow monitor confirmations and data collections
- Flow data analysis

Equipment installation was completed on July 25, 2025. The monitoring period began on July 26, 2025, and was completed on August 8, 2025. Upon completion of the study, the equipment was removed from the system by August 15, 2025.

Flow Monitoring Equipment



The ADS Triton+ monitor was selected for this project. This flow monitor is an area velocity flow monitor that uses both the Continuity and Manning's equations to measure flow.

The ADS Triton+ monitor consists of data acquisition sensors and a battery-powered microcomputer. The microcomputer includes a processor unit, data storage, and an on-board clock to control and synchronize the sensor recordings. The monitor was programmed to acquire and store depth of flow and velocity readings at 5-minute intervals.

The Triton+ monitor features cross-checking using multiple technologies in each sensor for continuous running of comparisons and tolerances. The Triton+ monitor can support two (2) sets of sensors. The sensor option used for this project was:

The Peak Combo Sensor installed at the bottom of the pipe includes three types of data acquisition technologies.

The ***up looking ultrasonic depth*** uses sound waves from two independent transceivers to measure the distance from the sensor upward toward the flow surface; applying the speed of sound in the water and the temperature measured by sensor to calculate depth.

The **pressure depth** is calculated by using a piezo-resistive crystal to determine the difference between hydrostatic and atmospheric pressure. The pressure sensor is temperature compensated and vented to the atmosphere through a desiccant filled breather tube.

To obtain **peak velocity**, the sensor sends an ultrasonic signal at an angle upward through the widest cross-section of the oncoming flow. The signal is reflected by suspended particles, air bubbles, or organic matter with a frequency shift proportional to the velocity of the reflecting objects. The reflected signal is received by the sensor and processed using digital spectrum analysis to determine the peak flow velocity.

Installation

Installation of flow monitoring equipment typically proceeds in four steps. First, the site is investigated for safety and to determine physical and hydraulic suitability for the flow monitoring equipment. Second, the equipment is physically installed at the selected location. Third, the monitor is tested to assure proper operation of the velocity and depth of flow sensors and verify that the monitor clock is operational and synchronized to the master computer clock. Fourth, the depth and velocity sensors are confirmed, and line confirmations are performed.

In pipes up to 42 inches in diameter, the sensors were mounted on expandable stainless-steel rings, inserted at least a foot upstream into influent pipes and tightened against the inside walls of the pipes. Influent pipe installations reduce the influences of turbulence and backwater often caused by changes in channel geometry in manholes.



Data Collection, Confirmation, and Quality Assurance

Data collects were done remotely via wireless connect on a weekly basis. As needed, during the monitoring period, field crews visit each monitoring location to verify proper monitor operation and document field conditions. The following quality assurance steps are taken to assure the integrity of the collected data:

Measure power supplies: monitors were powered by dry cell battery packs. Voltages were recorded and battery packs replaced, as necessary. Separate batteries provided back-up power to memory allowing primary batteries to be replaced without loss of data.

Clock synchronization: Field crews synchronized monitor clocks to master clocks.

Confirm depth and velocity readings: Field crews descended into meter manholes to manually measure depths and velocities and compare the meter readings to confirm that they agreed. The site met the criteria for confirmation for depth and velocity unless noted otherwise in the site commentary section. They also measured silt levels, if any, in the inverts of the pipes. Silt areas were subtracted from flow areas to compute true areas of flow.

Confirm average velocities through cross-sectional velocity profiles: Since ADS velocity sensors measure peak velocity, field crews collected cross-sectional velocity profiles in order to develop a relationship between peak and average velocity in lines that meet the hydraulic criteria.

Upload and Review Data: Data collected from the monitors were uploaded and reviewed by a Data Analyst for completeness, outliers, and deviations in the flow patterns, which indicate system anomalies or equipment failure.

Flow Quantification Methods

There are two main equations used to measure open channel flow: the **Continuity Equation** and the **Manning Equation**. The Continuity Equation, which is considered the most accurate, can be used if both depth of flow and velocity are available. In cases where velocity measurements are not available or not practical to obtain, the Manning Equation can be used to estimate velocity from the depth data based on certain physical characteristics of the pipe (i.e., the slope and roughness of the pipe being measured). However, the Manning equation assumes uniform, steady flow hydraulic conditions with non-varying roughness, which are typically invalid assumptions in most sanitary sewers. The Continuity Equation was used exclusively for this study.

Continuity Equation

The Continuity Equation states that the flow quantity (Q) is equal to the wetted area (A) multiplied by the average velocity (V) of the flow.

$$Q = A * V$$

This equation is applicable in a variety of conditions including backwater, surcharge, and reverse flow.

Data Analysis and Presentation

Data Analysis

A flow monitor is typically programmed to collect data at 5-minute intervals throughout the monitoring period. The monitor stores raw data consisting of (1) the ultrasonic depth, (2) the peak velocity and (3) the pressure depth. The data is imported into ADS's proprietary software and is examined by a data analyst to verify its integrity. The data analyst also reviews the daily field reports and site visit records to identify conditions that would affect the collected data.

Velocity profiles and the line confirmation data developed by the field personnel are reviewed by the data analyst to identify inconsistencies and verify data integrity. Velocity profiles are reviewed and an average to peak velocity ratio is calculated for the site. This ratio is used in converting the peak velocity measured by the sensor to the average velocity used in the Continuity equation. The data analyst selects which depth sensor entity will be used to calculate the final depth information. Silt levels present at each site visit are reviewed and representative silt levels established.

Occasionally the velocity sensor's performance may be compromised resulting in invalid readings sporadically during the monitoring period. This is generally caused by excessive debris (silt) blocking the sensor's crystals, shallow flows ($\sim < 1"$) that may drop below the top of the sensor or very clear flows lacking the particles needed to measure rate. In order to use the Continuity equation to quantify the flow during these periods, a Data Analyst and/or Engineer will use the site's historical pipe curve (depth vs. velocity) data along with valid field confirmations to reconstitute and replace the false velocity recordings with expected velocity readings for a given historical depth along the curve.

Selections for the above parameters can be constant or can change during the monitoring period. While the data analysis process is described in a linear manner, it often requires an iterative approach to accurately complete.

Data Presentation

This type of flow monitoring project generates a large volume of data. To facilitate review of the data, results have been provided in graphical and tabular formats. The flow data is presented graphically in the form of scattergraphs and hydrographs. Hydrographs are based on fifteen-minute averaging. Tables are provided in daily average format. These tables show the flow rate for each day, along with the daily minimum and maximums, the times they were observed, the total daily flow, and total flow for the month (or monitoring period). The following explanation of terms may aid in interpretation of the flow data table and hydrograph.

DEPTH - Final calculated depth measurement (in inches)

QUANTITY - Final calculated flow rate (in MGD)

VELOCITY - Final calculated flow velocity (in feet per second)

REPORT TOTAL - Total volume of flow recorded for the indicated time period (in MG)

BP07-31

Site Commentary

SITE INFORMATION

Pipe	Round (10 in H)
Silt	0.00 (in)

OBSERVATIONS

The site functioned under normal conditions during the study period. No surcharge conditions were experienced at this location.

This location is downstream of location BP07-55. A review of the balancing details indicates no problem.

Average flow depth, velocity, and quantity data observed during **Saturday, 26 July 2025 to Friday, 08 August 2025**, along with observed minimum and maximum data, are provided in the following table.

Observed Flow Conditions			
Item	DFINAL (in)	VFINAL (ft/s)	QFINAL (MGD - Total MG)
Average	3.50	1.46	0.164
Minimum	2.37	1.02	0.067
Maximum	4.70	1.80	0.287
Min Time	08/03/2025 4:45:00 AM	07/31/2025 3:25:00 AM	08/03/2025 4:45:00 AM
Max Time	07/30/2025 9:45:00 PM	07/28/2025 9:40:00 PM	07/30/2025 9:50:00 PM

Based upon the quality and consistency of the observed flow depth and velocity data, the Continuity equation was used to calculate flow rate and quantities during the monitoring period.

Values in the Observed Flow Conditions are based on the none average.

Values in the graphical reports are based on the fifteen minutes average.

Values in the tabular report are based on the none average.

DATA UPTIME

Data uptime observed during **Saturday, 26 July 2025 to Friday, 08 August 2025** is provided in the following table:




Percent Uptime	
DFINAL (in)	100
VFINAL (ft/s)	100
QFINAL (MGD - Total MG)	100






F-20



Project Name: Buena.Rick.TFM.CA25		City: Buena Park		Agency: Buena Park		FM Initials: VM	
Site Name: BP07-31		Install Date: 07/24/2025		Monitor Type		Peak Doppler	
Address/Location: Fullerton Ave & Franklin St				Monitor Model		Triton +	
				Data Acquisition		Manual/Wireless Collect	
				Manhole ID		07-31	
Access: Drive		Type of System:		Pipe Height:		10.00 "	
		Sanitary ☒ Storm ☐ Combined ☐		Pipe Width:		10.00 "	



Investigation Information:		Manhole Information:				
Date/Time of Investigation:	07/24/2025 @ 03:40 AM	Manhole Depth:	11'-4"			
Site Hydraulics:	Good Straight through flow	Manhole Material / Condition	Brick/Good			
Upstream Input: (L/S, P/S)	--	Pipe Material / Condition:	VCP/Good			
Upstream Manhole:	Not Investigated	Land Use:	Residential ☒	Commercial ☐	Industrial ☐	Other ☐
Downstream Manhole:	Not investigated	Oxygen: 20.9	H2S: 0	LEL: 0	CO: 0	
Depth of Flow:	3.00 " +/- 0.25"	Safety Notes: 2 man crew required and one blower is to be operated at all times.				
Range (Air DOF):	+/-					
Peak Velocity:	1.42 fps					
Silt:	0.00 Inches					



Installation Information		Backup	Yes	No	?	Distance
Installation Type:	Standard	Trunk	☐	☒	☐	
Sensors Devices:	Ultrasonic/Velocity/Pressure	Lift / Pump Station	☐	☒	☐	
Surcharge Height:	0	WWTP	☐	☒	☐	
Rain Gauge Zone:		Other	☐	☒	☐	


Additional Site Information / Comments:

Standard Traffic Control with No Safety Concerns

Hydrograph Report

BP07-31


Flow Monitor
BP07-31



Report Period
07/26/2025
To
08/08/2025

Legend
— DFINAL
— VFINAL
— QFINAL

ADS ENVIRONMENTAL
SERVICES



Scattergraph Report

BP07-31


Flow Monitor
BP07-31

Pipe Height
10.00
in

Report Period
07/26/2025
To
08/08/2025

Legend
○ DFINAL - VFINAL
--- Iso-QTM
▼ Min-Max Depth

ADS ENVIRONMENTAL
SERVICES®



Daily Tabular Report

07/26/2025 00:00 - 08/08/2025 23:59

BP07-31 Pipe: Round (10 in H), Silt 0.00 in

Date	DFINAL (in)					VFINAL (ft/s)					QFINAL (MGD - Total MG)					Total
	Time	Min	Time	Max	Avg	Time	Min	Time	Max	Avg	Time	Min	Time	Max	Avg	
07/26/2025	04:30	2.54	14:05	3.81	3.28	04:00	1.22	14:10	1.66	1.48	04:30	0.086	14:05	0.204	0.151	0.151
07/27/2025	05:55	2.48	21:05	4.18	3.37	05:55	1.16	17:40	1.68	1.48	05:55	0.079	21:05	0.232	0.158	0.158
07/28/2025	02:25	2.52	21:40	4.55	3.46	02:30	1.06	21:40	1.80	1.46	02:30	0.075	21:40	0.281	0.162	0.162
07/29/2025	03:25	2.70	20:20	4.34	3.62	02:45	1.25	20:25	1.80	1.54	03:25	0.099	20:20	0.258	0.179	0.179
07/30/2025	03:00	2.56	21:45	4.70	3.60	03:00	1.08	21:50	1.77	1.47	03:00	0.077	21:50	0.287	0.171	0.171
07/31/2025	03:25	2.45	20:30	4.48	3.64	03:25	1.02	21:50	1.76	1.49	03:25	0.068	21:50	0.266	0.176	0.176
08/01/2025	03:15	2.78	11:10	4.19	3.62	05:10	1.23	07:10	1.72	1.46	03:15	0.101	07:10	0.223	0.170	0.170
08/02/2025	02:10	2.52	21:20	4.04	3.37	02:15	1.07	21:15	1.67	1.41	02:10	0.075	21:15	0.223	0.151	0.151
08/03/2025	04:45	2.37	20:30	4.11	3.39	04:45	1.05	20:30	1.68	1.42	04:45	0.067	20:30	0.230	0.153	0.153
08/04/2025	03:25	2.38	21:35	4.27	3.43	03:25	1.09	23:25	1.67	1.44	03:25	0.070	21:35	0.237	0.157	0.157
08/05/2025	04:25	2.60	21:30	4.53	3.57	05:05	1.14	21:35	1.73	1.45	05:05	0.083	21:30	0.267	0.167	0.167
08/06/2025	02:55	2.47	22:30	4.56	3.59	02:55	1.15	21:10	1.71	1.46	02:55	0.078	21:10	0.264	0.168	0.168
08/07/2025	02:45	2.68	20:00	4.37	3.59	04:05	1.11	21:15	1.75	1.47	04:05	0.085	18:15	0.249	0.170	0.170
08/08/2025	03:10	2.67	09:30	4.01	3.49	04:55	1.24	10:55	1.69	1.47	03:10	0.095	21:45	0.210	0.163	0.163

07/26/2025 00:00 - 08/08/2025 23:59

	DFINAL (in)	VFINAL (ft/s)	QFINAL (MGD - Total MG)
Total			2.294
Average	3.50	1.46	0.164

BP07-55

Site Commentary

SITE INFORMATION

Pipe	Round (8 in H)
Silt	0.00 (in)

OBSERVATIONS

The site functioned under normal conditions during the study period. No surcharge conditions were experienced at this location.

This location is upstream of location BP07-31. See location B. 07-31 for balancing details.

Average flow depth, velocity, and quantity data observed during **Saturday, 26 July 2025 to Friday, 08 August 2025**, along with observed minimum and maximum data, are provided in the following table.

Observed Flow Conditions			
Item	DFINAL (in)	VFINAL (ft/s)	QFINAL (MGD - Total MG)
Average	3.31	1.21	0.109
Minimum	2.20	0.80	0.040
Maximum	4.45	1.61	0.205
Min Time	08/06/2025 3:35:00 AM	07/31/2025 3:00:00 AM	08/06/2025 3:40:00 AM
Max Time	07/30/2025 9:40:00 PM	08/04/2025 9:25:00 PM	07/30/2025 9:40:00 PM

Based upon the quality and consistency of the observed flow depth and velocity data, the Continuity equation was used to calculate flow rate and quantities during the monitoring period.

Values in the Observed Flow Conditions are based on the none average.

Values in the graphical reports are based on the fifteen minutes average.

Values in the tabular report are based on the none average.

DATA UPTIME

Data uptime observed during **Saturday, 26 July 2025 to Friday, 08 August 2025** is provided in the following table:



F-25





Percent Uptime	
DFINAL (in)	100
VFINAL (ft/s)	100
QFINAL (MGD - Total MG)	100






F-26



Project Name: Buena.Rick.TFM.CA25		City: Buena Park		Agency: Buena Park		FM Initials: VM	
Site Name: BP07-55		Install Date: 07/25/2025		Monitor Type		Peak Doppler	
Address/Location: 5600 Beach Blvd.				Monitor Model		Triton +	
				Data Acquisition		Manual/Wireless Collect	
				Manhole ID		07-55	
Access: Drive	Type of System:	Sanitary	Storm	Combined	Pipe Height:		8.00 "
		☒	☐	☐	Pipe Width:		8.00 "



Investigation Information:		Manhole Information:				
Date/Time of Investigation:	07/25/2025 @ 09:20 AM	Manhole Depth:	5'-9"			
Site Hydraulics:	Good Straight through flow	Manhole Material / Condition	PreCast/Good			
Upstream Input: (L/S, P/S)	--	Pipe Material / Condition:	VCP/Good			
Upstream Manhole:	Not Investigated	Land Use:	Residential ☐	Commercial ☐	Industrial ☒	Other ☐
Downstream Manhole:	Not investigated	Oxygen: 20.9	H2S: 0	LEL: 0	CO: 0	
Depth of Flow:	3.38 " +/- 0.25"	Safety Notes: 2 man crew required and one blower is to be operated at all times.				
Range (Air DOF):	+/-					
Peak Velocity:	1.49 fps					
Silt:	0.00 Inches					



Installation Information		Backup	Yes	No	?	Distance
Installation Type:	Standard	Trunk	☐	☒	☐	
Sensors Devices:	Ultrasonic/Velocity/Pressure	Lift / Pump Station	☐	☒	☐	
Surcharge Height:	0	WWTP	☐	☒	☐	
Rain Gauge Zone:		Other	☐	☒	☐	


Additional Site Information / Comments:

Standard Traffic Control with No Safety Concerns

Hydrograph Report
BP07-55

Flow Monitor

BP07-55



Pipe Height
8.00
in


Report Period

07/26/2025
To
08/08/2025

Legend

- DFINAL
- VFINAL
- QFINAL





Scattergraph Report

BP07-55


Flow Monitor
BP07-55

Pipe Height
8.00
in

Report Period
07/26/2025
To
08/08/2025

Legend
○ DFINAL - VFINAL
--- Iso-Qth
▼ Min-Max Depth

ADS ENVIRONMENTAL
SERVICES



Daily Tabular Report

07/26/2025 00:00 - 08/08/2025 23:59
BP07-55 Pipe: Round (8 in H), Silt 0.00 in

Date	DFINAL (in)					VFINAL (ft/s)					QFINAL (MGD - Total MG)					Total
	Time	Min	Time	Max	Avg	Time	Min	Time	Max	Avg	Time	Min	Time	Max	Avg	
07/26/2025	02:30	2.72	21:40	4.05	3.49	02:25	0.97	09:15	1.45	1.27	02:30	0.066	21:40	0.166	0.122	0.122
07/27/2025	04:10	2.37	20:40	4.35	3.39	04:15	0.84	20:45	1.56	1.23	04:15	0.047	20:40	0.194	0.116	0.116
07/28/2025	04:10	2.30	21:30	4.32	3.26	04:10	0.80	21:30	1.55	1.18	04:10	0.043	21:30	0.192	0.105	0.105
07/29/2025	05:00	2.37	21:10	4.32	3.30	03:30	0.86	21:10	1.57	1.20	05:00	0.048	21:10	0.195	0.108	0.108
07/30/2025	04:40	2.31	21:40	4.45	3.25	04:40	0.83	21:40	1.59	1.18	04:40	0.045	21:40	0.205	0.105	0.105
07/31/2025	03:30	2.26	20:55	4.17	3.32	03:00	0.80	20:50	1.53	1.21	03:00	0.042	20:55	0.181	0.111	0.111
08/01/2025	03:25	2.39	21:30	3.94	3.31	04:35	0.85	21:45	1.43	1.20	04:10	0.048	21:40	0.158	0.108	0.108
08/02/2025	04:40	2.35	21:05	4.15	3.33	04:55	0.83	21:05	1.52	1.21	04:55	0.046	21:05	0.179	0.110	0.110
08/03/2025	05:15	2.33	21:20	4.17	3.34	05:15	0.85	21:25	1.49	1.23	05:15	0.046	21:25	0.177	0.113	0.113
08/04/2025	03:40	2.33	21:20	4.41	3.27	04:55	0.86	21:25	1.61	1.21	03:40	0.047	21:20	0.205	0.107	0.107
08/05/2025	03:35	2.28	21:20	4.24	3.22	03:45	0.85	21:50	1.54	1.19	03:35	0.045	21:25	0.187	0.104	0.104
08/06/2025	03:35	2.20	22:25	4.19	3.23	03:40	0.80	20:50	1.58	1.18	03:40	0.040	20:50	0.186	0.104	0.104
08/07/2025	03:10	2.35	22:35	4.18	3.30	03:10	0.87	22:40	1.53	1.21	03:10	0.048	22:35	0.180	0.109	0.109
08/08/2025	03:35	2.33	20:35	4.01	3.28	03:45	0.85	21:15	1.44	1.20	03:40	0.047	20:35	0.162	0.107	0.107

07/26/2025 00:00 - 08/08/2025 23:59

	DFINAL (in)	VFINAL (ft/s)	QFINAL (MGD - Total MG)
Total			1.530
Average	3.31	1.21	0.109

APPENDIX C

Sewer Generation Factor Guidelines

William Wang

From: Guzman, Hector <hguzman@buenapark.com>
Sent: Tuesday, August 26, 2025 5:20 PM
To: William Wang
Cc: Carson Edgington; Scott Patton
Subject: RE: GP-25-1 Amway Site Sewer Study

Good afternoon William,

I know we had a placeholder of 300 GPD per dwelling, but after discussing with our Sewer Superintendent, you can go ahead and use 250 GPD while keeping the peak factor at 2. That should be sufficient. Please let me know if you have any questions.

Best regards,

Hector



Hector Guzman
Assistant Engineer
Public Works Department

P: (714) 562-3688
hguzman@buenapark.com
www.buenapark.com

6650 Beach Blvd. | Buena Park, CA | 90621

City Hall Offices are closed every Friday.

From: William Wang <wwang@rickengineering.com>
Sent: Tuesday, August 26, 2025 2:27 PM
To: Guzman, Hector <hguzman@buenapark.com>
Cc: Carson Edgington <cedgington@rickengineering.com>; Scott Patton <spatton@rickengineering.com>
Subject: GP-25-1 Amway Site Sewer Study

Hello Hector,

ADS has completed the sewer monitoring and we are working to prepare the sewer study for the next resubmittal. I couldn't locate the proposed GPD requirement in my emails so I believe we spoke on the phone about this, could you please confirm that we are to use 300 GPD per dwelling unit for our study?

Could you also please confirm if we are to apply a peaking factor to this flow rate to determine peak flow? I saw in another report that 2.0 was used, is this typical?

Please let me know if you have any questions or would like to discuss. Thank you!

William Wang PE

APPENDIX D

Hydraulic Analysis Reports

Hydraulic Analysis Report

Project Data

Project Title: Amway

Designer: Rick Engineering Company

Project Date: Tuesday, September 2, 2025

Project Units: U.S. Customary Units

Channel Analysis: 07-55 With Proposed Flows

Input Parameters

Channel Type: Circular

Pipe Diameter 0.67 ft

Longitudinal Slope: 0.0036 ft/ft

Manning's n: 0.0130

Flow 0.4210 cfs

Result Parameters

Depth 0.3646 ft

Area of Flow 0.1954 ft²

Wetted Perimeter 1.1100 ft

Hydraulic Radius 0.1761 ft

Average Velocity 2.1543 ft/s

Top Width 0.6641 ft

Froude Number: 0.6999

Critical Depth 0.3026 ft

Critical Velocity 2.7320 ft/s

Critical Slope: 0.0068 ft/ft

Critical Top Width 0.66 ft

Calculated Max Shear Stress 0.0819 lb/ft²

Calculated Avg Shear Stress 0.0395 lb/ft²

Channel Analysis: 07-31 With Proposed Flows

Input Parameters

Channel Type: Circular

Pipe Diameter 0.83 ft

Longitudinal Slope: 0.0030 ft/ft

Manning's n: 0.0130

Flow 0.6550 cfs

Result Parameters

Depth 0.4391 ft

Area of Flow 0.2913 ft²

Wetted Perimeter 1.3537 ft

Hydraulic Radius 0.2152 ft

Average Velocity 2.2484 ft/s

Top Width 0.8318 ft

Froude Number: 0.6695

Critical Depth 0.3559 ft

Critical Velocity 2.9480 ft/s

Critical Slope: 0.0062 ft/ft


Critical Top Width 0.82 ft

Calculated Max Shear Stress 0.0822 lb/ft²

Calculated Avg Shear Stress 0.0403 lb/ft²

APPENDIX E

Existing Sewer Plans



- ~LEGEND~**
- On this Sheet: (L) Indicates Standard LAMPPOLE
 - (M) Indicates Standard Manhole - see Sheet
 - Drop Manhole " 2
 - Flusher " 2
 - Letters used to Designate Lines
 - (S) Small Numbers in Circles show Sheet Number
 - On Plan: --- Chimneys to be Constructed
 - On Profile: --- Sewer Line to be Constructed
 - Indicates Elevation of Ground Surface
 - 0.30% --- Sewer Invert

NO.	DATE	REVISION
1	1915	Original
2	1916	Revised
3	1917	Revised
4	1918	Revised
5	1919	Revised
6	1920	Revised
7	1921	Revised
8	1922	Revised
9	1923	Revised
10	1924	Revised
11	1925	Revised
12	1926	Revised
13	1927	Revised
14	1928	Revised
15	1929	Revised
16	1930	Revised
17	1931	Revised
18	1932	Revised
19	1933	Revised
20	1934	Revised
21	1935	Revised
22	1936	Revised
23	1937	Revised
24	1938	Revised
25	1939	Revised
26	1940	Revised
27	1941	Revised
28	1942	Revised
29	1943	Revised
30	1944	Revised
31	1945	Revised
32	1946	Revised
33	1947	Revised
34	1948	Revised
35	1949	Revised
36	1950	Revised
37	1951	Revised
38	1952	Revised
39	1953	Revised
40	1954	Revised
41	1955	Revised
42	1956	Revised
43	1957	Revised
44	1958	Revised
45	1959	Revised
46	1960	Revised
47	1961	Revised
48	1962	Revised
49	1963	Revised
50	1964	Revised
51	1965	Revised
52	1966	Revised
53	1967	Revised
54	1968	Revised
55	1969	Revised
56	1970	Revised
57	1971	Revised
58	1972	Revised
59	1973	Revised
60	1974	Revised
61	1975	Revised
62	1976	Revised
63	1977	Revised
64	1978	Revised
65	1979	Revised
66	1980	Revised
67	1981	Revised
68	1982	Revised
69	1983	Revised
70	1984	Revised
71	1985	Revised
72	1986	Revised
73	1987	Revised
74	1988	Revised
75	1989	Revised
76	1990	Revised
77	1991	Revised
78	1992	Revised
79	1993	Revised
80	1994	Revised
81	1995	Revised
82	1996	Revised
83	1997	Revised
84	1998	Revised
85	1999	Revised
86	2000	Revised
87	2001	Revised
88	2002	Revised
89	2003	Revised
90	2004	Revised
91	2005	Revised
92	2006	Revised
93	2007	Revised
94	2008	Revised
95	2009	Revised
96	2010	Revised
97	2011	Revised
98	2012	Revised
99	2013	Revised
100	2014	Revised
101	2015	Revised
102	2016	Revised
103	2017	Revised
104	2018	Revised
105	2019	Revised
106	2020	Revised
107	2021	Revised
108	2022	Revised
109	2023	Revised
110	2024	Revised
111	2025	Revised
112	2026	Revised
113	2027	Revised
114	2028	Revised
115	2029	Revised
116	2030	Revised
117	2031	Revised
118	2032	Revised
119	2033	Revised
120	2034	Revised
121	2035	Revised
122	2036	Revised
123	2037	Revised
124	2038	Revised
125	2039	Revised
126	2040	Revised
127	2041	Revised
128	2042	Revised
129	2043	Revised
130	2044	Revised
131	2045	Revised
132	2046	Revised
133	2047	Revised
134	2048	Revised
135	2049	Revised
136	2050	Revised
137	2051	Revised
138	2052	Revised
139	2053	Revised
140	2054	Revised
141	2055	Revised
142	2056	Revised
143	2057	Revised
144	2058	Revised
145	2059	Revised
146	2060	Revised
147	2061	Revised
148	2062	Revised
149	2063	Revised
150	2064	Revised
151	2065	Revised
152	2066	Revised
153	2067	Revised
154	2068	Revised
155	2069	Revised
156	2070	Revised
157	2071	Revised
158	2072	Revised
159	2073	Revised
160	2074	Revised
161	2075	Revised
162	2076	Revised
163	2077	Revised
164	2078	Revised
165	2079	Revised
166	2080	Revised
167	2081	Revised
168	2082	Revised
169	2083	Revised
170	2084	Revised
171	2085	Revised
172	2086	Revised
173	2087	Revised
174	2088	Revised
175	2089	Revised
176	2090	Revised
177	2091	Revised
178	2092	Revised
179	2093	Revised
180	2094	Revised
181	2095	Revised
182	2096	Revised
183	2097	Revised
184	2098	Revised
185	2099	Revised
186	2100	Revised
187	2101	Revised
188	2102	Revised
189	2103	Revised
190	2104	Revised
191	2105	Revised
192	2106	Revised
193	2107	Revised
194	2108	Revised
195	2109	Revised
196	2110	Revised
197	2111	Revised
198	2112	Revised
199	2113	Revised
200	2114	Revised
201	2115	Revised
202	2116	Revised
203	2117	Revised
204	2118	Revised
205	2119	Revised
206	2120	Revised
207	2121	Revised
208	2122	Revised
209	2123	Revised
210	2124	Revised
211	2125	Revised
212	2126	Revised
213	2127	Revised
214	2128	Revised
215	2129	Revised
216	2130	Revised
217	2131	Revised
218	2132	Revised
219	2133	Revised
220	2134	Revised
221	2135	Revised
222	2136	Revised
223	2137	Revised
224	2138	Revised
225	2139	Revised
226	2140	Revised
227	2141	Revised
228	2142	Revised
229	2143	Revised
230	2144	Revised
231	2145	Revised
232	2146	Revised
233	2147	Revised
234	2148	Revised
235	2149	Revised
236	2150	Revised
237	2151	Revised
238	2152	Revised
239	2153	Revised
240	2154	Revised
241	2155	Revised
242	2156	Revised
243	2157	Revised
244	2158	Revised
245	2159	Revised
246	2160	Revised
247	2161	Revised
248	2162	Revised
249	2163	Revised
250	2164	Revised
251	2165	Revised
252	2166	Revised
253	2167	Revised
254	2168	Revised
255	2169	Revised
256	2170	Revised
257	2171	Revised
258	2172	Revised
259	2173	Revised
260	2174	Revised
261	2175	Revised
262	2176	Revised
263	2177	Revised
264	2178	Revised
265	2179	Revised
266	2180	Revised
267	2181	Revised
268	2182	Revised
269	2183	Revised
270	2184	Revised
271	2185	Revised
272	2186	Revised
273	2187	Revised
274	2188	Revised
275	2189	Revised
276	2190	Revised
277	2191	Revised
278	2192	Revised
279	2193	Revised
280	2194	Revised
281	2195	Revised
282	2196	Revised
283	2197	Revised
284	2198	Revised
285	2199	Revised
286	2200	Revised
287	2201	Revised
288	2202	Revised
289	2203	Revised
290	2204	Revised
291	2205	Revised
292	2206	Revised
293	2207	Revised
294	2208	Revised
295	2209	Revised
296	2210	Revised
297	2211	Revised
298	2212	Revised
299	2213	Revised
300	2214	Revised
301	2215	Revised
302	2216	Revised
303	2217	Revised
304	2218	Revised
305	2219	Revised
306	2220	Revised
307	2221	Revised
308	2222	Revised
309	2223	Revised
310	2224	Revised
311	2225	Revised
312	2226	Revised
313	2227	Revised
314	2228	Revised
315	2229	Revised
316	2230	Revised
317	2231	Revised
318	2232	Revised
319	2233	Revised
320	2234	Revised
321	2235	Revised
322	2236	Revised
323	2237	Revised
324	2238	Revised
325	2239	Revised
326	2240	Revised
327	2241	Revised
328	2242	Revised
329	2243	Revised
330	2244	Revised
331	2245	Revised
332	2246	Revised
333	2247	Revised
334	2248	Revised
335	2249	Revised
336	2250	Revised
337	2251	Revised
338	2252	Revised
339	2253	Revised
340	2254	Revised
341	2255	Revised
342	2256	Revised
343	2257	Revised
344	2258	Revised
345	2259	Revised
346	2260	Revised
347	2261	Revised
348	2262	Revised
349	2263	Revised
350	2264	Revised
351	2265	Revised
352	2266	Revised
353	2267	Revised
354	2268	Revised
355	2269	Revised
356	2270	Revised
357	2271	Revised
358	2272	Revised
359	2273	Revised
360	2274	Revised
361	2275	Revised
362	2276	Revised
363	2277	Revised
364	2278	Revised
365	2279	Revised
366	2280	Revised
367	2281	Revised
368	2282	Revised
369	2283	Revised
370	2284	Revised
371	2285	Revised
372	2286	Revised
373	2287	Revised
374	2288	Revised
375	2289	Revised
376	2290	Revised
377	2291	Revised
378	2292	Revised
379	2293	Revised
380	2294	Revised
381	2295	Revised
382	2296	Revised
383	2297	Revised
384	2298	Revised
385	2299	Revised
386	2300	Revised
387	2301	Revised
388	2302	Revised
389	2303	Revised
390	2304	Revised
391	2305	Revised
392	2306	Revised
393	2307	Revised
394	2308	Revised
395	2309	Revised
396	2310	Revised
397	2311	Revised
398	2312	Revised
399	2313	Revised
400	2314	Revised
401	2315	Revised
402	2316	Revised
403	2317	Revised
404	2318	Revised
405	2319	Revised
406	2320	Revised
407	2321	Revised
408	2322	Revised
409	2323	Revised
410	2324	Revised
411	2325	Revised
412	2326	Revised
413	2327	Revised
414	2328	Revised
415	2329	Revised
416	2330	Revised
417	2331	Revised
418	2332	Revised
419	2333	Revised
420	2334	Revised
421	2335	Revised
422	2336	Revised
423	2337	Revised
424	2338	Revised
425	2339	Revised
426	2340	Revised
427	2341	Revised
428	2342	Revised
429	2343	Revised
430	2344	Revised
431	2345	Revised
432	2346	Revised
433	2347	Revised
434	2348	Revised
435	2349	Revised
436	2350	Revised
437	2351	Revised
438	2352	Revised
439	2353	Revised
440	2354	Revised
441	2355	Revised
442	2356	Revised
443		