Print From

Summary Form for Electronic Document Submittal

Form F

Lead agencies may include 15 hardcopies of this document when submitting electronic copies of Environmental Impact Reports, Negative Declarations, Mitigated Negative Declarations, or Notices of Preparation to the State Clearinghouse (SCH). The SCH also accepts other summaries, such as EIR Executive Summaries prepared pursuant to CEQA Guidelines Section 15123. Please include one copy of the Notice of Completion Form (NOC) with your submission and attach the summary to each electronic copy of the document.

SCH #: _____

Project Title: El Dorado 2R Rehabilitation

Lead Agency: Caltrans

Contact Name: Judith Lopez

Email: judith.lopez@dot.ca.gov Phone Number: 559-240-5068

Project Location: Coalinga (*City*) Fresno (*County*)

Project Description (Proposed actions, location, and/or consequences).

The project would cold plane the existing pavement and replace it with a leveling course consisting of 0.15 foot of Rubberized or Geosynthetic Pavement Interlayer Hot-Mix Asphalt, 0.25 foot of Hot-Mix Asphalt, and a 0.25-foot layer of Rubberized Gap-Graded Hot-Mix Asphalt. Other project work would include installing inside and outside shoulder rumble strips and placing shoulder backing. Any severely distressed underlying Portland cement concrete panels will be replaced with Hot-Mix Asphalt. Additionally, guardrail systems, existing drainage systems, dikes, roadside signs, and Traffic Management System elements will be upgraded or replaced as needed.

Identify the project's significant or potentially significant effects and briefly describe any proposed mitigation measures that would reduce or avoid that effect.

Biological Resources: Avoidance and minimization measures will be incorporated to minimize impacts to multiple species. Prior to the start of work/ground disturbance, a qualified biologist will provide worker environmental awareness training for all construction personnel. The training will provide an overview of the status of all the species, how to identify the species and their habitat, and what to do if an individual is encountered during construction. Pre-construction surveys will be required no more than 30 days prior to the start of construction. Nighttime lighting would be used and directed toward the active work area.

If applicable, describe any of the project's areas of controversy known to the Lead Agency, including issues raised by agencies and the public.

There are no known controversies on this project.

Provide a list of the responsible or trustee agencies for the project.

Caltrans - District 6 Fresno