APPENDIX A

PROJECT PLANS



NEW

1. BALL FIELD (60' & 75' BASES)
2. RESTROOM WITH REMOTE LOCKING MECHANISM
3. EXERCISE STATIONS
4. PLAZA & LARGE SHADE SAIL FOR PROGRAMMED RECREATION
5. GAME TABLES & LARGE SHADE SAIL
6. CONCRETE CORN HOLE
7. CONCRETE PING PONG TABLES
8. PICNIC SHELTER
9. D.G. WALKING PATH WITH INFORMATIONAL SIGNAGE
10. RUBBERIZED WALKING PATH WITH MILEAGE SIGNS
11. TRASH ENCLOSURE
12. BIRD AND BUTTERFLY GARDEN
13. PARKING
14. ENTRY COURTYARD
15. BENCH - TYP.
16. COVERED BLEACHERS
17. SYNTHETIC SOCCER FIELD WITH FENCING

RENOVATED

18. RENOVATE EXISTING HANDBALL COURTS & PROTECT MURAL
19. RENOVATE EXISTING CONCESSION & RESTROOM BUILDING
20. RESURFACE & RESTRIPE EXISTING BASKETBALL COURTS
21. RESURFACE & RESTRIPE EXISTING PARKING

EXISTING

22. TREE - TYP.
23. ELECTRICAL UTILITY ENCLOSURE
24. BUILDING
25. NEW PLAY GROUND (IN PROCESS)

- EXISTING CONCRETE
- NEW CONCRETE
- NEW PERMEABLE PAVERS
- NEW LOW WATER USE LANDSCAPE AREA W/ BIOSWALES
- NEW TURF
- PROPOSED WALKWAY LIGHT

LANDSCAPE NOTE

ALL PLANT MATERIAL WILL CONSIST OF CALIFORNIA-FRIENDLY, LOW WATER USE PLANT MATERIAL WITH ALL PLANTS CHOSEN FROM THE LOW WATER USE CATEGORY ACCORDING TO WUCOLS. ALL LANDSCAPE AREAS WILL CONFORM TO THE CURRENT CITY OF PICO RIVERA LANDSCAPE GUIDELINES

THE IRRIGATION DESIGN WILL INCORPORATE THE LATEST IN SMART IRRIGATION TECHNOLOGIES. ALL NEW LANDSCAPE AREAS WILL INCLUDE HIGH EFFICIENCY IRRIGATION METHODS TO INCLUDE SUB-SURFACE DRIP, STREAM BUBBLERS, AND ROTARY NOZZLES . ALL POP UP STREAM BUBBLERS SHALL HAVE PC SCREENS AND BE INSTALLED ON SEPARATE VALVES. A SMART IRRIGATION CONTROLLER WITH A RAIN SHUT OFF DEVICE WILL ALSO BE INCORPORATED. BARK MULCH WILL BE USED TO RETAIN MOISTURE AND REDUCE EVAPORATION AND AN IRRIGATION SCHEDULE WILL BE PROVIDED TO PROGRAM THE CONTROLLER. THE IRRIGATION SYSTEM WILL COMPLY WITH ALL CURRENT CITY OF PICO RIVERA GUIDELINES.

RIO HONDO PARK

Preliminary Concept

January 27, 2021

0' 40' 80' 120'

RHA LANDSCAPE ARCHITECTS PLANNERS, INC.