

Summary Form for Electronic Document Submittal

Form F

Lead agencies may include 15 hardcopies of this document when submitting electronic copies of Environmental Impact Reports, Negative Declarations, Mitigated Negative Declarations, or Notices of Preparation to the State Clearinghouse (SCH). The SCH also accepts other summaries, such as EIR Executive Summaries prepared pursuant to CEQA Guidelines Section 15123. Please include one copy of the Notice of Completion Form (NOC) with your submission and attach the summary to each electronic copy of the document.

SCH #: _____

Project Title: Sewer Lift Station S-7 Reconstruction Project

Lead Agency: Long Beach Utilities Department

Contact Name: Myung Chun

Email: myung.chun@lbwater.org Phone Number: 562.570.2357

Project Location: Long Beach Los Angeles County
City *County*

Project Description (Proposed actions, location, and/or consequences).

The proposed project involves the reconstruction of the existing Sewer Lift Station S-7 to conform with current City standards and facilitate continued, long-term use. Proposed improvements include a new circular wet well with submersible pumps and a rectangular valve vault and flow meter vault. Additionally, a new 8-inch-diameter sewer main would be constructed to connect the existing sanitary sewer infrastructure to the new wet well. The total length of pipeline installed would be approximately 1,450 linear feet in existing City rights-of-way. The proposed project would also install a new generator building with associated electrical equipment. Upon completion, the proposed project would provide a total pumping capacity of 860 gallons per minute and a force main flow velocity of between 3 to 6 feet per second.

Identify the project's significant or potentially significant effects and briefly describe any proposed mitigation measures that would reduce or avoid that effect.

Aesthetics: Mitigation measures include screening staging areas and restoring disturbed areas.

Biological Resources: Mitigation measures include standard BMPs, avoidance measures, and pre-construction surveys.

Cultural Resources: Mitigation measures include retention of a qualified archaeologist and standard inadvertent discovery measures.

Geology/Soils: Mitigation measures include standard pipeline failure contingency measures and an inadvertent discovery clause for paleontological resources.

Hazards/Hazardous Materials: Mitigation measures include pre-demolition investigation and accidental discovery protocols.

Hydrology/Water Quality: A SWPPP would be required and implemented to minimize water quality impacts

Noise: Mitigation measures include temporary noise barriers, compliance with applicable ordinances, vibration monitoring, and offering lodging for temporary relocation to residents during construction.

Traffic: A traffic control plan would be implemented to mitigate traffic impacts.

Tribal Cultural Resources: Mitigation measures have been provided by local tribes and include monitoring and unanticipated discovery protocols.

Please refer to IS/MND and MMRP for a detailed discussion of project impacts and full text of mitigation measures.

If applicable, describe any of the project's areas of controversy known to the Lead Agency, including issues raised by agencies and the public.

No areas of controversy were identified during the initial scoping process for this initial study and none have been identified during preparation of this document.

Provide a list of the responsible or trustee agencies for the project.

City of Long Beach/Long Beach Utilities Department
Regional Water Quality Control Board - Santa Ana Region
California Department of Fish and Wildlife
State Water Resources Control Board
California Coastal Commission
Los Angeles County Flood Control District