Print From

Summary Form for Electronic Document Submittal

Form F

Lead agencies may include 15 hardcopies of this document when submitting electronic copies of Environmental Impact Reports, Negative Declarations, Mitigated Negative Declarations, or Notices of Preparation to the State Clearinghouse (SCH). The SCH also accepts other summaries, such as EIR Executive Summaries prepared pursuant to CEQA Guidelines Section 15123. Please include one copy of the Notice of Completion Form (NOC) with your submission and attach the summary to each electronic copy of the document.

SCH #: _____

Project Title: Paint Waste Area/ Unexploded Ordnance Site 13 Record of Decision/Final Remedial Action Plan

Lead Agency: Department of Toxic Substances Control

Contact Name: Franklin Mark, P.E.

Email: Franklin.Mark@dtsc.ca.gov Phone Number: (916) 255-3584

Project Location: Mare Island - Vallejo *City* Solano *County*

Project Description (Proposed actions, location, and/or consequences).

See Attachment 1

Identify the project's significant or potentially significant effects and briefly describe any proposed mitigation measures that would reduce or avoid that effect.

No mitigation measures are required.

Revised September 2011

If applicable, describe any of the project's areas of controversy known to the Lead Agency, including issues raised by agencies and the public.

Not applicable

Provide a list of the responsible or trustee agencies for the project.

Regional WQCB #2
Caltrans District # 4
Fish & Game Region # 4
Native American Heritage Commission
SWRCB: Water Quality

ATTACHMENT 1

Paint Waste Area/ Unexploded Ordnance Site 13 Record of Decision/Final Remedial Action Plan

Project Description:

The California Department of Toxic Substances Control (DTSC) is considering approval of the Record of Decision (ROD)/Final Remedial Action Plan (Final RAP) for the Paint Waste Area (PWA), also identified as Unexploded Ordnance (UXO) Site 13, located at the Former Mare Island Naval Shipyard (MINS) in Vallejo, California. Within the PWA, the remaining paint waste debris and associated soil contamination, and the potential for incidental munitions and explosives of concern (MEC) hazards beneath the detection depth limits of available technology will be addressed by the remedial action described in the ROD/Final RAP. The actions consist of soil excavation and offsite disposal for the PWA Target Treatment Zone (TTZ) A and Institutional Controls (ICs) for incidental MEC for both TTZ A and TTZ B to restrict certain sensitive uses of the property and prohibit ground-penetration.

The remaining paint waste debris and lead contamination within TTZ A will be excavated, mechanically screened to remove MEC, and transported to a permitted offsite waste disposal facility. Soil will be removed to an estimated depth up to 4.5 feet below ground surface (bgs). The impacted soil is estimated at 818 bank cubic yards (cy) from TTZ A with an additional estimated 182 cy of overburden or extra soil from benching the excavations. After excavation is completed and no visual deposits of paint waste remain, lead confirmation samples will be collected at the extent of the excavations.

The excavations will be backfilled with clean imported soil (approximately 1,000 bank cy), compacted, and restored to match pre-excavation conditions. Excavated areas will be hydroseeded with native grasses to prevent erosion and revegetated with wetland plant species, such as pickleweed cuttings and salt grass, to promote appropriate nontidal wetland habitat and monitored to confirm that agreed-upon wetland revegetation criteria are met.