THE CITY OF SAN DIEGO

Date of Notice: October 30, 2026

NOTICE OF AVAILABILITY
DRAFT MITIGATED NEGATIVE DETERMINATION

ENGINEERING & CAPITAL PROJECTS DEPARTMENT

WBS No. B-13016

The City of San Diego (City), as the Lead Agency, has prepared a draft Mitigated Negative Declaration (MND) for the following proposed project and is inviting your comments regarding the adequacy of the document. The draft MND and associated technical appendices have been placed on the City's California Environmental Quality Act (CEQA) website at https://www.sandiego.gov/ceqa/draft.

HOW TO SUBMIT COMMENTS: Comments on this draft MND must be received by close of business on November 29, 2026, to be included in the final document considered by the decision-making body. When submitting comments, please reference the project name and number, **Campus Point Drive Storm Drain Replacement / WBS No. B-13016**, in the subject line. The City requests that all comments be provided electronically via email at: CIP-CEQA@sandiego.gov. However, if a hard copy submittal is necessary, it may be submitted to: Marissa Mariscal, City of San Diego Engineering and Capital Projects, 8525 Gibbs Drive, Suite 208, MS 912, San Diego, CA 92123.

GENERAL PROJECT INFORMATION:

- Project Name: Campus Point Drive Storm Drain Replacement
- Project No.: B-13016
- SCH NO.: N/A
- Community Planning Area: University
- Council District: 6

Project Description: The proposed project is a Site Development Permit (SDP) and contract award for the installation of approximately 328 linear feet of 24-inch diameter reinforced concrete pipe (RCP) storm drains. The project would demolish approximately 160 linear feet of existing 18-inch corrugated metal pipe storm drain and two existing catch basins. The project would also include the installation of associated cut-off walls, two catch basins, and one concrete energy dissipator. One cleanout would be installed upstream behind the concrete energy dissipator to accommodate the change in pipe vertical alignment. The project would demolish and replace approximately 50 linear feet of existing damaged concrete brow ditches. The project is located northeast of 9900 Campus Point Drive, beginning west at the edge of Campus Point Drive and extending into an undeveloped canyon. **The site is not included on any list compiled pursuant to Government Code Section 65962.5 for hazardous waste sites.**

APPLICANT: City of San Diego

RECOMMENDED FINDING: The draft Mitigated Negative Declaration determined the proposed project would result in significant environmental effects in the following areas: **Biological Resources, Archaeological Resources** and **Tribal/Cultural Resources.**

AVAILABILITY IN ALTERNATIVE FORMAT: To request this Notice, the draft Mitigated Negative Declaration, and/or supporting documents in an alternative format, please email the Engineering and Capital Projects Department at CIP-CEQA@sandiego.gov. Your request should include the suggested recommended format that will assist with the review of documents.

Additional Information: For environmental review information, contact Marissa Mariscal at MMariscal@sandiego.gov. For information about public meetings/hearings on this project, contact Development Project Manager III, Tyler Sherer, at TSherer@sandiego.gov. This Notice was published in the SAN DIEGO DAILY TRANSCRIPT and distributed on October 30, 2026.

Carrie Purcell
Deputy Director
Engineering and Capital Projects