Vector Environmental Consulting Inc.
18851 Bardeen Avenue Suite 205
Irvine, CA 92612
Phone: (949) 526-4510

Lead Inspection Report

Site Information:

1-5 Polaris Way
Aliso Viejo, CA 92656

Owner Information:

Lennar
c/o Johnna Dalby
2000 Five Point, 3rd Floor
Irvine, CA 92618

Date: August 5th, 2026

Vector Environmental Consulting Inc.
18851 Bardeen Avenue Suite 205
Irvine, CA 92612
Phone: (949) 526-4510

Date: August 5th, 2026

Site Information: 1-5 Polaris Way
Aliso Viejo, CA 92656

Owner Information: Lennar
c/o Johnna Dalby
2000 Five Point, 3rd Floor
Irvine, CA 92618

Subject: Lead Inspection Report

Vector Environmental Consulting Inc. conducted a comprehensive lead inspection at the above referenced address. All major paint systems were sampled in accordance with the regulations. Sampling methodology, XRF data, and recommendations can be found on subsequent pages of this report.

Regulatory Information

The HUD/EPA standard for lead-based paint of equal to or greater than 1.0 mg/cm2 or 0.5% by weight, as defined by Title X of the Housing and Community Development Act of 1992.

For purposes of the HUD/EPA Lead-Based Paint Disclosure Rule, 1.0 milligrams per square centimeter (mg/cm^2) or 0.5% by weight are the standards that must be used. If a State or local government has an EPA-authorized plan for certifying lead-based paint inspectors and has lower lead standards, those lower lead standards would apply to inspections (but not to the Lead Disclosure Rule; paint with lead below the federal threshold is not considered lead-based paint for purposes of that Rule).

Although, there is no official standard for lead in school buildings, Los Angeles County and Los Angeles Unified School District have set a standard of 0.7 mg/cm^2. For lead containing materials within this region this standard has determined this to be the action level for abatement activities.

Definitions

Lead-based paint inspection – Title X of the Housing and Community Development Act of 1992, defines lead-based paint inspection as the following:

A surface-by-surface investigation to determine the presence of lead-based paint as provided in section 302(c) of the Lead-Based Paint Poisoning Prevention Act and the provision of a report explaining the results of the investigation. (15 U.S.C. 2681 (7), for use by EPA and its stakeholders; and 42 U.S.C. 4851(12), for use by HUD and its stakeholders.

Lead abatement – The United States Environmental Protection Agency (EPA) defines lead abatement as the following:

Lead abatement projects are designed to permanently eliminate existing lead-based paint hazards. They may be ordered by a state or local government in response to a lead-poisoned child or other reason or may be undertaken voluntarily at any time. Lead-based activities are regulated differently than renovation, repair and painting jobs (RRP), even though, in some cases, the activities are similar. Lead-based paint removal is only considered abatement if the removal is instigated for the purposes of removing lead-based paint, not for renovation purposes.

Renovation, Repair and Painting (RRP) – The United States Environmental Protection Agency (EPA) defines the RRP rule as the following:

RRP projects are typically performed at the option of the property owner for aesthetic or other reasons, or as an interim control to minimize lead hazards. It is NOT designed to permanently eliminate lead-based paint hazards. Since RRP projects can disturb lead-based paint in homes and buildings build before 1978, thus creating new lead hazards, individual renovators must be trained and certified lead-safe RRP practices, and firms must be certified.

Lead Abatement vs RRP Projects

	Lead Abatement Activities	**Similar or Different**	**RRP Projects**
Purpose	Permanently eliminate existing lead-based paint hazards	Different	Conduct renovations, repairs or painting to reduce lead-based paint hazards
Initiated by	State or local government or Voluntary request by property Owner	Different	Voluntary request by property owner
Certifications	Individuals must be trained and certified in lead abatement activities – Firms must be certified to conduct lead abatement activities	Similar	Individuals must be trained and certified in RRP activities – Firms must be certified to conduct RRP activities
Occupation Protection	Firms are required to make sure occupants are out of the home, childcare facility or preschool	Different	Firms are not required to make sure occupants are out of the home, childcare facility or preschool – Firms must distribute EPA's The Lead Safe Certified Guide to Renovate Right before starting renovation work.

OSHA Compliance

OSHA (Occupational Safety and Health Administration) through the regulation 1532.1 further delineates requirements for lead activities. 1532.1 defines "trigger tasks" (e.g., manual demolition, etc.) that disturb lead paint and the contractor responsibilities to its employees. The regulation specifically addresses PEL's (permissible exposure limits) to staff disturbing lead paint. This regulation is initiated when "trigger task" work is implemented on paint systems with .06% or 600 ppm (parts per million). It should be noted that this level (.06%) is virtually any amount of lead paint. As of January 2002, OSHA now requires all contractors to notify the department when disturbing lead paint above 1.0mg/cm2. This level is the same threshold for abatement by HUD.

OSHA requires that the employer is required to protect their employees to the level stipulated in the Standard, or to do an exposure assessment. An exposure assessment is the air monitoring of an employee during lead work to determine his exposure and ultimately to determine the level of protection required. This assessment is applicable to paint systems above .06% or 600 ppm.

Sampling Methodology

Inspection by X-Ray Fluorescents

Portable XRF lead-based paint analyzers are the most common primary analytical method for inspections in housing because of the demonstrated ability to determine if lead-based paint is present on many surfaces and to measure the paint without destructive sampling or paint removal, as well as the high speed and low cost per sample. Portable XRF instruments expose a building component to electromagnetic radiation in the form of X-rays or gamma radiation. In response to radiation, each element, including lead, emits energy at a fixed and characteristic level. Emission of characteristic x-rays is called "X-Ray Fluorescence," or XRF. The energy released is measured by the instrument's fluorescence detector and displayed. The inspector must then compare this displayed value (reading) with the threshold or inconclusive range specified in the XRF Performance Characteristic Sheet (PCS) for the specific XRF instrument being used, and the specific substrate beneath the painted surface.

- If the reading is less than the threshold, then the reading is considered negative for lead-based paint.

- If the reading is greater than or equal to the threshold, then the reading is considered positive. For instrument – substrate combinations that have an inconclusive range:

- If the reading is less than the lower boundary of the inconclusive range, then the reading is considered negative.

- If the reading is within the inconclusive range, including its boundary values, then the reading is considered inconclusive.

- If the reading is greater than the upper boundary of the inconclusive range, then the reading is considered positive

Inspection by Paint-Chip Analysis

Laboratory analysis of paint-chip samples is recommended for inaccessible areas or building components with irregular (non-flat) surfaces that cannot be tested using XRF instrumentation. Laboratory analysis is also recommended to confirm inconclusive XRF results, as specified on the applicable XRF Performance Characteristic Sheet, or at the inspector's professional judgment. Only laboratories recognized under the EPA NLLAP may be used for analyzing samples of paint in target housing or pre-1978 child occupied facilities. Laboratory analysis is more accurate and precise than XRF, but only if great care is used to collect and analyze the paint-chip sample. Laboratory results of paint chip samples should be reported as mg/cm^2. The dimensions of the area from which a paint-chip sample is removed must be measured as accurately as possible (to the nearest millimeter or 1/16th of an inch) and the sample must include every layer of paint with minimal substrate included.

Although laboratory results can also be reported as a percentage of lead by weight of the paint sample, precents should only be used when it is not feasible to use mg/cm^2. These two units of measure are not interchangeable. Laboratory results should be reported as mg/cm^2 if the surface area can be accurately measured and if all paint within that area is collected.

Determining Sample Locations

A testing combination is a unique combination of room equivalent, building component type, and substrate. Visible color may not be an accurate predictor of painting history and is not included in the definition of a testing combination. The list is not intended to be exhaustive. Unlisted components that are coated with paint, varnish, shellac, wallpaper, stain, or other coating should also be considered as a separate testing combination.

Certain building components that are adjacent to each other and not likely to have different painting histories can be grouped together into a single testing combination, as follows:

- Window casings, stops, jambs and aprons are typically a single testing combination
- Interior window mullions and window sashes are a single testing combination
- Exterior window mullions and window sashes are a single testing combination
- Door jambs, stops, transoms, casings and other door frame parts are a single testing combination
- Door stiles, rails, panels, mullions and other door parts are a single testing combination
- Baseboards and associated trim (such as quarter-round or other caps) are a single testing combination (do not group chair rails, crown molding or walls with baseboards)
- Painted electrical sockets, switches or plates can be grouped with walls

Each of these building parts should be tested separately if there is some specific reason to believe that they have a different painting history. In most cases, separate testing will not be necessary

Sample Results

The lead-based paint inspection conducted at 1-5 Polaris Way included 452 XRF readings and 0 Paint Chip Samples, covering representative building components, substrates and paint colors on or in the building.

The following table lists the higher lead containing components that could likely require demolition and/or removal. These items would certainly require "abatement procedures" be implemented.

Subsequent tables illustrate all of the paint systems at the school site. Regulations may apply to other components with lower levels of lead. The contractor is required to review and verify the scope of work for the project and determine the impact of activities on lead painted surfaces (at any level).

The following table lists the components that are above the HUD regulated level of 1.0 mg/cm^2

Building	Component	Location	Quantity
No Lead Detected at This Level			

The following table lists the components that are above the Los Angeles County and LAUSD standard of 0.7 mg/cm^2

Building	Component	Location	Quantity
No Lead Detected at This Level			

Summary & Recommendations

Depending on the scope of work for the project; contractors should determine the level of contractor licensing for the abatement and/or work disturbing lead paint systems.

We recommend "lead certified" painting contractors for the painting of buildings coated with lead paint. Preparation of these surfaces falls under the "trigger task" category of OSHA 1532.1. Preparation of painted surfaces and the ultimate "guarantee" of the final painted product is better completed by a "single" contractor.

RRP certified firms should be considered for incidental work that disturbs small amounts of lead paint. These categories of work may include concrete coring (through lead paint) and structure welding (door hinges etc.).

Abatement companies with CDPH (California Department of Public Health) lead certified staff will be required for all abatement work. The companies selected will have to insure that a certified lead supervisor be present during abatement preparation and be within two hours (response time) during abatement activities.

Painting contractors will be required to collect all paint chips from the preparation activities. The contractor will sample and categorize the waste for disposal. Proof of sampling and waste disposal will be required.

Metal components (coated with lead paint) will likely be recycled. A letter (stating acceptance of material) will be required from the contractor's recycling facility.

All other waste produced from abatement activities will be separated and staged in a safe storage area at the project site during the sampling process. The characterization of the waste can take up to two weeks and an area will need to be allocated for this purpose. The contractor will be required to conduct and pay all costs associated with the characterization of the waste. Copies (proof) of all characterization of waste will be demanded on completion and before waste transport.

Vector Environmental Consulting Inc.

David G Johnson
President
Disabled Veteran Business Enterprise # 2026880
Certified Asbestos Consultant #22-6940
Lead Inspector/ Assessor #9289

Sampling Data

Vector Environmental Consulting Inc.
18851 Bardeen Avenue, Suite 205,
Irvine, CA 92612

Inspection Site: 1 - 5 Polaris Way,
Aliso Viejo, CA 92656

Inspection Date: 08/04/2026 - 08/05/2026

Instrument Type:

Action Level: 1.0 (mg/cm²)

Job Number:

Notes:

Inspection Site:
1 - 5 Polaris Way,
Aliso Viejo, CA 92656

Inspection Date: 08/04/2026 - 08/05/2026
Total Readings: 452
Action Level: 1.0 (mg/cm²)

Unit Started: 08/04/2026 09:23:02
Unit Ended: 08/05/2026 09:22:06
Classification Level: 1.0 (mg/cm²)

Test #	Date/Time	Result	Job Number	Room	Room Choices	Structure	Choice	Substrate	Color	Condition	Condition Choices	Lead (mg/cm²)	Mode
1 (CAL)	08/04/26 09:23:02	PCS Pass										1.1	Timed
2 (CAL)	08/04/26 09:23:07	PCS Pass										1.0	Timed
3 (CAL)	08/04/26 09:23:12	PCS Pass										1.0	Timed
4 (CAL)	08/04/26 09:23:13	PCS Pass										1.0	Timed
5	08/04/26 09:40:59	Negative	1	Room	Office	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
6	08/04/26 09:41:46	Negative	1	Room	Office	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
7	08/04/26 09:42:48	Negative	1	Room	Office	Wall	Interior Wall	Drywall	White	Intact		-0.0	Quick
8	08/04/26 09:43:02	Negative	1	Room	Office	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
9	08/04/26 09:44:07	Negative	1	Room	Office	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
10	08/04/26 09:44:22	Negative	1	Room	Office	Wall	Interior Wall	Drywall	White	Intact		-0.0	Quick
11	08/04/26 09:44:38	Negative	1	Room	Office	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
12	08/04/26 09:45:22	Negative	1	Room	Office	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
13	08/04/26 09:45:57	Negative	1	Room	Office	Wall	Interior Wall	Drywall	Gray	Intact		0.0	Quick
14	08/04/26 09:46:27	Negative	1	Room	Office	Wall	Interior Wall	Drywall	Gray	Intact		0.0	Quick
15	08/04/26 09:46:45	Negative	1	Room	Office	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
16	08/04/26 09:47:18	Negative	1	Room	Office	Wall	Interior Wall	Drywall	White	Intact		-0.0	Quick
17	08/04/26 09:47:51	Negative	1	Room	Office	Wall	Interior Wall	Drywall	Blue	Intact		0.0	Quick
18	08/04/26 09:48:23	Negative	1	Room	Office	Wall	Interior Wall	Drywall	Green	Intact		0.0	Quick
19	08/04/26 09:48:56	Negative	1	Room	Office	Wall	Interior Wall	Drywall	Red	Intact		0.0	Quick
20	08/04/26 09:49:22	Negative	1	Room	Office	Wall	Interior Wall	Drywall	White	Intact		-0.0	Quick

Inspection Site:
1 - 5 Polaris Way,
Aliso Viejo, CA 92656

Inspection Date: 08/04/2026 - 08/05/2026
Total Readings: 452
Action Level: 1.0 (mg/cm²)

Unit Started: 08/04/2026 09:23:02
Unit Ended: 08/05/2026 09:22:06
Classification Level: 1.0 (mg/cm²)

Test #	Date/Time	Result	Job Number	Room	Room Choices	Structure	Choice	Substrate	Color	Condition	Condition Choices	Lead (mg/cm²)	Mode
21	08/04/26 09:50:23	Negative	1	Room	Hallway	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
22	08/04/26 09:50:49	Negative	1	Room	Hallway	Wall	Interior Wall	Drywall	Blue	Intact		-0.0	Quick
23	08/04/26 09:51:30	Negative	1	Room	Hallway	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
24	08/04/26 09:53:00	Negative	1	Room	Break Room	Wall	Interior Wall	Drywall	Gray	Intact		0.0	Quick
25	08/04/26 09:54:05	Negative	1	Room	Break Room	Wall	Interior Wall	Drywall	Yellow	Intact		0.0	Quick
26	08/04/26 09:54:34	Negative	1	Room	Break Room	Wall	Interior Wall	Drywall	Yellow	Intact		-0.0	Quick
27	08/04/26 09:54:55	Negative	1	Room	Break Room	Wall	Interior Wall	Ceramic	Yellow	Intact		0.0	Quick
28	08/04/26 09:55:56	Negative	1	Room	Hallway	Door	Frame	Metal	Black	Intact		-0.0	Quick
29	08/04/26 09:56:35	Negative	1	Room	Hallway	Door	Frame	Metal	Gray	Intact		0.0	Quick
30	08/04/26 09:57:19	Negative	1	Room	Hallway	Door	Frame	Metal	Gray	Intact		-0.0	Quick
31	08/04/26 09:57:46	Negative	1	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
32	08/04/26 09:58:57	Negative	1	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
33	08/04/26 09:59:36	Negative	1	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
34	08/04/26 09:59:52	Negative	1	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
35	08/04/26 10:00:33	Negative	1	Room	Office	Door	Frame	Metal	Gray	Intact		-0.0	Quick
36	08/04/26 10:01:22	Negative	1	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
37	08/04/26 10:01:45	Negative	1	Room	Electrical Room	Door	Frame		Gray	Intact		0.0	Quick
38	08/04/26 10:02:10	Negative	1	Room	Electrical Room	Door	Frame	Metal	Blue	Intact		0.0	Quick
39	08/04/26 10:03:16	Negative	1	Room	Custodian	Door	Frame	Metal	Blue	Intact		0.0	Quick
40	08/04/26 10:04:07	Negative	1	Room	Custodian	Door		Wood	Blue	Intact		0.0	Quick

Inspection Site:
1 - 5 Polaris Way,
Aliso Viejo, CA 92656

Inspection Date: 08/04/2026 - 08/05/2026
Total Readings: 452
Action Level: 1.0 (mg/cm²)

Unit Started: 08/04/2026 09:23:02
Unit Ended: 08/05/2026 09:22:06
Classification Level: 1.0 (mg/cm²)

Test #	Date/Time	Result	Job Number	Room	Room Choices	Structure	Choice	Substrate	Color	Condition	Condition Choices	Lead (mg/cm²)	Mode
41	08/04/26 10:04:32	Negative	1	Room	Electrical Room	Door		Wood	Blue	Intact		0.0	Quick
42	08/04/26 10:04:49	Negative	1	Room	Electrical Room	Door		Wood	Brown	Intact		-0.0	Quick
43	08/04/26 10:05:21	Negative	1	Room	Hallway	Door		Wood	Brown	Intact		0.0	Quick
44	08/04/26 10:05:39	Negative	1	Room	Hallway	Door		Wood	Brown	Intact		-0.0	Quick
45	08/04/26 10:05:59	Negative	1	Room	Hallway	Door		Wood	Brown	Intact		-0.0	Quick
46	08/04/26 10:06:27	Negative	1	Room	Office	Door		Wood	Brown	Intact		0.0	Quick
47	08/04/26 10:06:38	Negative	1	Room	Office	Door		Wood	Brown	Intact		-0.0	Quick
48	08/04/26 10:06:58	Negative	1	Room	Office	Door		Wood	Brown	Intact		0.0	Quick
49	08/04/26 10:07:30	Negative	1	Room	Office	Door		Wood	White	Intact		-0.0	Quick
50	08/04/26 10:07:45	Negative	1	Room	Office	Door		Wood	White	Intact		-0.0	Quick
51	08/04/26 10:08:26	Negative	1	Room	Office	Door		Wood	Brown	Intact		0.0	Quick
52	08/04/26 10:08:55	Negative	1	Room	Office	Door		Wood	Brown	Intact		0.0	Quick
53	08/04/26 10:09:51	Negative	1	Room	Office	Window	Sill	Metal	White	Intact		0.0	Quick
54	08/04/26 10:10:07	Negative	1	Room	Office	Window	Sill	Metal	White	Intact		0.0	Quick
55	08/04/26 10:10:30	Negative	1	Room	Office	Window	Sill	Metal	White	Intact		0.0	Quick
56	08/04/26 10:10:57	Negative	1	Room	Office	Window	Sill	Metal	White	Intact		0.0	Quick
57	08/04/26 10:11:10	Negative	1	Room	Office	Window	Sill	Metal	White	Intact		0.0	Quick
58	08/04/26 10:11:23	Negative	1	Room	Office	Window	Sill	Metal	White	Intact		0.0	Quick
59	08/04/26 10:11:37	Negative	1	Room	Office	Window	Sill	Metal	White	Intact		0.0	Quick
60	08/04/26 10:12:02	Negative	1	Room	Office	Window	Frame	Metal	White	Intact		-0.0	Quick

Inspection Site:
1 - 5 Polaris Way,
Aliso Viejo, CA 92656

Inspection Date: 08/04/2026 - 08/05/2026
Total Readings: 452
Action Level: 1.0 (mg/cm²)

Unit Started: 08/04/2026 09:23:02
Unit Ended: 08/05/2026 09:22:06
Classification Level: 1.0 (mg/cm²)

Test #	Date/Time	Result	Job Number	Room	Room Choices	Structure	Choice	Substrate	Color	Condition	Condition Choices	Lead (mg/cm²)	Mode
61	08/04/26 10:12:17	Negative	1	Room	Office	Window	Frame	Metal	White	Intact		0.0	Quick
62	08/04/26 10:12:43	Negative	1	Room	Office	Window	Frame	Metal	White	Intact		0.0	Quick
63	08/04/26 10:12:57	Negative	1	Room	Office	Window	Frame	Metal	White	Intact		0.0	Quick
64	08/04/26 10:13:15	Negative	1	Room	Office	Window	Frame	Metal	White	Intact		0.0	Quick
65	08/04/26 10:13:28	Negative	1	Room	Office	Window	Frame	Metal	White	Intact		0.0	Quick
66	08/04/26 10:13:42	Negative	1	Room	Office	Window	Frame	Metal	White	Intact		0.0	Quick
67	08/04/26 10:15:00	Negative	1	Room	Electrical Room	Electric Panel	Door	Metal	Gray	Intact		-0.0	Quick
68	08/04/26 10:15:23	Negative	1	Room	Electrical Room	Electric Panel	Door	Metal	Gray	Intact		0.0	Quick
69	08/04/26 10:15:48	Negative	1	Room	Electrical Room	Electric Panel	Frame	Metal	Gray	Intact		-0.0	Quick
70	08/04/26 10:16:06	Negative	1	Room	Electrical Room	Electric Panel	Frame	Metal	Gray	Intact		0.0	Quick
71	08/04/26 10:18:10	Negative	1	Room	Hallway	Stair	Railing	Metal	Gray	Intact		0.0	Quick
72	08/04/26 10:18:42	Negative	1	Room	Hallway	Stair	Balusters	Metal	Gray	Intact		0.1	Quick
73	08/04/26 10:19:26	Negative	1	Room	Hallway	Stair	Risers	Metal	Gray	Intact		0.1	Quick
74	08/04/26 10:20:37	Negative	1	Room	Break Room	Counter	Top	Marble	Black	Intact		0.0	Quick
75	08/04/26 10:21:56	Negative	1	Room	Restroom	Restroom	Counter	Marble	Black	Intact		0.0	Quick
76	08/04/26 10:22:26	Negative	1	Room	Restroom	Restroom	Floor Tile	Ceramic	Gray	Intact		0.0	Quick
77	08/04/26 10:22:49	Negative	1	Room	Restroom	Restroom	Floor Tile	Ceramic	White	Intact		-0.0	Quick
78	08/04/26 10:23:20	Negative	1	Room	Restroom	Restroom	Wall Tile	Ceramic	Gray	Intact		0.0	Quick
79	08/04/26 10:23:44	Negative	1	Room	Restroom	Restroom	Wall Tile	Ceramic	Tan	Intact		0.0	Quick
80	08/04/26 10:24:14	Negative	1	Room	Restroom	Restroom	Urinal	Porcelain	White	Intact		0.0	Quick

Inspection Site:
1 - 5 Polaris Way,
Aliso Viejo, CA 92656

Inspection Date: 08/04/2026 - 08/05/2026
Total Readings: 452
Action Level: 1.0 (mg/cm²)

Unit Started: 08/04/2026 09:23:02
Unit Ended: 08/05/2026 09:22:06
Classification Level: 1.0 (mg/cm²)

Test #	Date/Time	Result	Job Number	Room	Room Choices	Structure	Choice	Substrate	Color	Condition	Condition Choices	Lead (mg/cm²)	Mode
81	08/04/26 10:24:29	Negative	1	Room	Restroom	Restroom	Urinal	Porcelain	White	Intact		0.0	Quick
82	08/04/26 10:24:58	Negative	1	Room	Restroom	Restroom	Toilet	Porcelain	White	Intact		0.0	Quick
83	08/04/26 10:25:10	Negative	1	Room	Restroom	Restroom	Toilet	Porcelain	White	Intact		0.0	Quick
84	08/04/26 10:25:22	Negative	1	Room	Restroom	Restroom	Toilet	Porcelain	White	Intact		0.0	Quick
85	08/04/26 10:25:35	Negative	1	Room	Restroom	Restroom	Toilet	Porcelain	White	Intact		0.0	Quick
86	08/04/26 10:25:48	Negative	1	Room	Restroom	Restroom	Toilet	Porcelain	White	Intact		0.0	Quick
87	08/04/26 10:26:00	Negative	1	Room	Restroom	Restroom	Toilet	Porcelain	White	Intact		0.0	Quick
88	08/04/26 10:26:31	Negative	1	Room	Restroom	Restroom	Sink	Porcelain	White	Intact		0.0	Quick
89	08/04/26 10:26:43	Negative	1	Room	Restroom	Restroom	Sink	Porcelain	White	Intact		0.0	Quick
90	08/04/26 10:26:55	Negative	1	Room	Restroom	Restroom	Sink	Porcelain	White	Intact		0.0	Quick
91	08/04/26 10:42:51	Negative	1	Room	Lobby	Floor	Tile	Ceramic	White	Intact		0.0	Quick
92	08/04/26 10:43:07	Negative	1	Room	Lobby	Floor	Tile	Ceramic	Black	Intact		0.0	Quick
93	08/04/26 10:51:18	Negative	1	Exterior	Structure Exterior	Wall	Exterior Wall	Stucco	Tan	Intact		0.0	Quick
94	08/04/26 10:51:33	Negative	1	Exterior	Structure Exterior	Wall	Exterior Wall	Stucco	Tan	Intact		0.0	Quick
95	08/04/26 10:51:51	Negative	1	Exterior	Structure Exterior	Wall	Exterior Wall	Stucco	Tan	Intact		-0.0	Quick
96	08/04/26 10:52:07	Negative	1	Exterior	Structure Exterior	Wall	Exterior Wall	Stucco	Tan	Intact		0.0	Quick
97	08/04/26 10:52:34	Negative	1	Exterior	Structure Exterior	Window	Frame	Metal	Tan	Intact		-0.0	Quick
98	08/04/26 10:52:53	Negative	1	Exterior	Structure Exterior	Window	Frame	Metal	Tan	Intact		0.0	Quick
99	08/04/26 10:53:08	Negative	1	Exterior	Structure Exterior	Window	Frame	Metal	Tan	Intact		0.0	Quick
100	08/04/26 10:53:26	Negative	1	Exterior	Structure Exterior	Door	Frame		Tan	Intact		0.0	Quick

Inspection Site:
1 - 5 Polaris Way,
Aliso Viejo, CA 92656

Inspection Date: 08/04/2026 - 08/05/2026
Total Readings: 452
Action Level: 1.0 (mg/cm²)

Unit Started: 08/04/2026 09:23:02
Unit Ended: 08/05/2026 09:22:06
Classification Level: 1.0 (mg/cm²)

Test #	Date/Time	Result	Job Number	Room	Room Choices	Structure	Choice	Substrate	Color	Condition	Condition Choices	Lead (mg/cm²)	Mode
101	08/04/26 10:53:39	Negative	1	Exterior	Structure Exterior	Door	Frame	Metal	Tan	Intact		0.0	Quick
102	08/04/26 10:54:12	Negative	1	Exterior	Structure Exterior	Door		Metal	Tan	Intact		0.0	Quick
103	08/04/26 10:54:23	Negative	1	Exterior	Structure Exterior	Door		Metal	Tan	Intact		-0.0	Quick
104 (CAL)	08/05/26 01:23:34	PCS Pass										1.0	Timed
105 (CAL)	08/05/26 01:23:39	PCS Pass										1.0	Timed
106 (CAL)	08/05/26 01:23:43	PCS Pass										1.0	Timed
107 (CAL)	08/05/26 01:23:44	PCS Pass										1.0	Timed
108	08/05/26 01:26:05	Negative	1	Room	Custodian	Sink	Basin	Porcelain	White	Intact		0.0	Quick
109	08/05/26 01:27:14	Negative	1	Exterior	Structure Exterior	Fire Hydrant	Exterior	Metal	Yellow	Intact		0.7	Quick
110	08/05/26 01:27:44	Negative	3	Exterior	Structure Exterior	Fire Hydrant	Exterior	Metal	Yellow	Intact		0.8	Quick
111	08/05/26 01:28:49	Negative	4	Exterior	Parking Lot	Parking Lot	Curb	Concrete	Red	Intact		0.0	Quick
112	08/05/26 01:29:17	Negative	4	Exterior	Parking Lot	Parking Lot	Curb	Concrete	Red	Intact		0.0	Quick
113	08/05/26 01:30:03	Negative	4	Exterior	Parking Lot	Parking Lot	Striping	Concrete	White	Intact		0.0	Quick
114	08/05/26 01:30:17	Negative	4	Exterior	Parking Lot	Parking Lot	Striping	Concrete	White	Intact		0.0	Quick
115	08/05/26 01:30:40	Negative	4	Exterior	Parking Lot	Parking Lot	Striping	Concrete	Blue	Intact		0.0	Quick
116	08/05/26 01:30:53	Negative	4	Exterior	Parking Lot	Parking Lot	Striping	Concrete	Blue	Intact		0.0	Quick
117	08/05/26 01:31:13	Negative	4	Exterior	Parking Lot	Parking Lot	Striping	Concrete	Yellow	Intact		-0.0	Quick
118	08/05/26 01:31:27	Negative	4	Exterior	Parking Lot	Parking Lot	Striping	Concrete	Yellow	Intact		0.0	Quick
119 (CAL)	08/05/26 07:01:59	PCS Pass										1.0	Timed
120 (CAL)	08/05/26 07:02:05	PCS Pass										1.0	Timed

Inspection Site:
1 - 5 Polaris Way,
Aliso Viejo, CA 92656

Inspection Date: 08/04/2026 - 08/05/2026
Total Readings: 452
Action Level: 1.0 (mg/cm²)

Unit Started: 08/04/2026 09:23:02
Unit Ended: 08/05/2026 09:22:06
Classification Level: 1.0 (mg/cm²)

Test #	Date/Time	Result	Job Number	Room	Room Choices	Structure	Choice	Substrate	Color	Condition	Condition Choices	Lead (mg/cm²)	Mode
121 (CAL)	08/05/26 07:02:11	PCS Pass										1.0	Timed
122 (CAL)	08/05/26 07:02:12	PCS Pass										1.0	Timed
123	08/05/26 07:04:44	Negative	2	Exterior	Structure Exterior	Wall	Exterior Wall	Stucco	Tan	Intact		-0.0	Quick
124	08/05/26 07:04:56	Negative	2	Exterior	Structure Exterior	Wall	Exterior Wall	Stucco	Tan	Intact		0.0	Quick
125	08/05/26 07:05:06	Negative	2	Exterior	Structure Exterior	Wall	Exterior Wall	Stucco	Tan	Intact		0.0	Quick
126	08/05/26 07:05:17	Negative	2	Exterior	Structure Exterior	Wall	Exterior Wall	Stucco	Tan	Intact		0.0	Quick
127	08/05/26 07:07:40	Negative	2	Exterior	Structure Exterior	Window	Frame	Metal	Tan	Intact		0.0	Quick
128	08/05/26 07:07:54	Negative	2	Exterior	Structure Exterior	Window	Frame	Metal	Tan	Intact		0.0	Quick
129	08/05/26 07:08:12	Negative	2	Exterior	Structure Exterior	Window	Frame	Metal	Tan	Intact		-0.0	Quick
130	08/05/26 07:08:40	Negative	2	Exterior	Structure Exterior	Door	Frame	Metal	Tan	Intact		-0.0	Quick
131	08/05/26 07:08:52	Negative	2	Exterior	Structure Exterior	Door	Frame	Metal	Tan	Intact		0.0	Quick
132	08/05/26 07:09:36	Negative	2	Exterior	Structure Exterior	Door		Metal	Tan	Intact		-0.0	Quick
133	08/05/26 07:09:51	Negative	2	Exterior	Structure Exterior	Door		Metal	Tan	Intact		-0.0	Quick
134	08/05/26 07:13:23	Negative	2	Room	Office	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
135	08/05/26 07:13:36	Negative	2	Room	Office	Wall	Interior Wall	Drywall	White	Intact		-0.0	Quick
136	08/05/26 07:13:46	Negative	2	Room	Office	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
137	08/05/26 07:14:02	Negative	2	Room	Office	Wall	Interior Wall	Drywall	White	Intact		-0.0	Quick
138	08/05/26 07:14:15	Negative	2	Room	Office	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
139	08/05/26 07:14:44	Negative	2	Room	Office	Wall	Interior Wall	Drywall	Gray	Intact		0.0	Quick
140	08/05/26 07:15:02	Negative	2	Room	Office	Wall	Interior Wall	Drywall	Gray	Intact		-0.0	Quick

Inspection Site:
1 - 5 Polaris Way,
Aliso Viejo, CA 92656

Inspection Date: 08/04/2026 - 08/05/2026
Total Readings: 452
Action Level: 1.0 (mg/cm²)

Unit Started: 08/04/2026 09:23:02
Unit Ended: 08/05/2026 09:22:06
Classification Level: 1.0 (mg/cm²)

Test #	Date/Time	Result	Job Number	Room	Room Choices	Structure	Choice	Substrate	Color	Condition	Condition Choices	Lead (mg/cm²)	Mode
141	08/05/26 07:15:20	Negative	2	Room	Office	Wall	Interior Wall	Drywall	Gray	Intact		0.0	Quick
142	08/05/26 07:15:50	Negative	2	Room	Office	Wall	Interior Wall	Drywall	Green	Intact		0.0	Quick
143	08/05/26 07:16:19	Negative	2	Room	Office	Wall	Interior Wall	Drywall	Blue	Intact		-0.0	Quick
144	08/05/26 07:16:46	Negative	2	Room	Office	Wall	Interior Wall	Drywall	Tan	Intact		-0.0	Quick
145	08/05/26 07:18:06	Negative	2	Room	Break Room	Wall	Interior Wall	Drywall	Gray	Intact		-0.0	Quick
146	08/05/26 07:18:23	Negative	2	Room	Break Room	Wall	Interior Wall	Drywall	Gray	Intact		-0.0	Quick
147	08/05/26 07:18:58	Negative	2	Room	Break Room	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
148	08/05/26 07:25:17	Negative	2	Room	Hallway	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
149	08/05/26 07:25:44	Negative	2	Room	Hallway	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
150	08/05/26 07:26:08	Negative	2	Room	Hallway	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
151	08/05/26 07:26:24	Negative	2	Room	Hallway	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
152	08/05/26 07:27:18	Negative	2	Room	Hallway	Door	Frame	Metal	Gray	Intact		0.0	Quick
153	08/05/26 07:27:38	Negative	2	Room	Hallway	Door	Frame	Metal	Gray	Intact		0.0	Quick
154	08/05/26 07:27:59	Negative	2	Room	Hallway	Door	Frame	Metal	Gray	Intact		0.0	Quick
155	08/05/26 07:28:28	Negative	2	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
156	08/05/26 07:29:06	Negative	2	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
157	08/05/26 07:29:23	Negative	2	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
158	08/05/26 07:29:46	Negative	2	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
159	08/05/26 07:30:10	Negative	2	Room	Office	Door	Frame	Metal	White	Intact		0.0	Quick
160	08/05/26 07:30:33	Negative	2	Room	Office	Door	Frame	Metal	White	Intact		0.0	Quick

Inspection Site:
1 - 5 Polaris Way,
Aliso Viejo, CA 92656

Inspection Date: 08/04/2026 - 08/05/2026
Total Readings: 452
Action Level: 1.0 (mg/cm²)

Unit Started: 08/04/2026 09:23:02
Unit Ended: 08/05/2026 09:22:06
Classification Level: 1.0 (mg/cm²)

Test #	Date/Time	Result	Job Number	Room	Room Choices	Structure	Choice	Substrate	Color	Condition	Condition Choices	Lead (mg/cm²)	Mode
161	08/05/26 07:31:01	Negative	2	Room	Office	Door		Wood	White	Intact		0.0	Quick
162	08/05/26 07:31:28	Negative	2	Room	Office	Door		Wood	White	Intact		0.0	Quick
163	08/05/26 07:31:50	Negative	2	Room	Office	Door		Wood	Brown	Intact		-0.0	Quick
164	08/05/26 07:32:05	Negative	2	Room	Office	Door		Wood	Brown	Intact		0.0	Quick
165	08/05/26 07:32:18	Negative	2	Room	Office	Door		Wood	Brown	Intact		0.0	Quick
166	08/05/26 07:32:47	Negative	2	Room	Hallway	Door		Wood	Brown	Intact		-0.0	Quick
167	08/05/26 07:32:58	Negative	2	Room	Hallway	Door		Wood	Brown	Intact		-0.0	Quick
168	08/05/26 07:33:12	Negative	2	Room	Hallway	Door		Wood	Brown	Intact		0.0	Quick
169	08/05/26 07:33:32	Negative	2	Room	Hallway	Door		Wood	White	Intact		0.0	Quick
170	08/05/26 07:34:20	Negative	2	Room	Office	Window	Sill	Metal	Gray	Intact		0.0	Quick
171	08/05/26 07:34:49	Negative	2	Room	Office	Window	Sill	Metal	Gray	Intact		0.0	Quick
172	08/05/26 07:37:33	Negative	2	Room	Office	Window	Sill	Metal	Gray	Intact		0.0	Quick
173	08/05/26 07:37:55	Negative	2	Room	Office	Window	Frame	Metal	Gray	Intact		0.0	Quick
174	08/05/26 07:38:05	Negative	2	Room	Office	Window	Frame	Metal	Gray	Intact		0.0	Quick
175	08/05/26 07:38:16	Negative	2	Room	Office	Window	Frame	Metal	Gray	Intact		0.0	Quick
176	08/05/26 07:38:27	Negative	2	Room	Office	Window	Frame	Metal	Gray	Intact		0.0	Quick
177	08/05/26 07:38:41	Negative	2	Room	Office	Window	Frame	Metal	Gray	Intact		0.0	Quick
178	08/05/26 07:38:54	Negative	2	Room	Office	Window	Frame	Metal	Gray	Intact		0.0	Quick
179	08/05/26 07:39:47	Negative	2	Room	Custodian	Sink	Basin	Porcelain	White	Intact		-0.0	Quick
180	08/05/26 07:40:37	Negative	2	Room	Electrical Room	Electric Panel	Door	Metal	Gray	Intact		0.0	Quick

Inspection Site:
1 - 5 Polaris Way,
Aliso Viejo, CA 92656

Inspection Date: 08/04/2026 - 08/05/2026
Total Readings: 452
Action Level: 1.0 (mg/cm²)

Unit Started: 08/04/2026 09:23:02
Unit Ended: 08/05/2026 09:22:06
Classification Level: 1.0 (mg/cm²)

Test #	Date/Time	Result	Job Number	Room	Room Choices	Structure	Choice	Substrate	Color	Condition	Condition Choices	Lead (mg/cm²)	Mode
181	08/05/26 07:40:56	Negative	2	Room	Electrical Room	Electric Panel	Frame		Gray	Intact		0.0	Quick
182	08/05/26 07:41:54	Negative	2	Room	Restroom	Restroom	Counter	Marble	Black	Intact		0.0	Quick
183	08/05/26 07:42:38	Negative	2	Room	Restroom	Restroom	Floor Tile	Ceramic	Gray	Intact		-0.0	Quick
184	08/05/26 07:42:58	Negative	2	Room	Restroom	Restroom	Wall Tile	Ceramic	Gray	Intact		0.0	Quick
185	08/05/26 07:43:30	Negative	2	Room	Restroom	Restroom	Urinal	Porcelain	White	Intact		0.0	Quick
186	08/05/26 07:43:53	Negative	2	Room	Restroom	Restroom	Toilet	Porcelain	White	Intact		0.0	Quick
187	08/05/26 07:44:08	Negative	2	Room	Restroom	Restroom	Toilet	Porcelain	White	Intact		0.0	Quick
188	08/05/26 07:44:26	Negative	2	Room	Restroom	Restroom	Toilet	Porcelain	White	Intact		0.0	Quick
189	08/05/26 07:44:48	Negative	2	Room	Restroom	Restroom	Sink	Porcelain	White	Intact		0.0	Quick
190	08/05/26 07:45:59	Negative	2	Room	Lobby	Floor	Tile	Ceramic	Gray	Intact		0.0	Quick
191	08/05/26 07:47:09	Negative	3	Room	Office	Wall	Interior Wall	Drywall	Gray	Intact		0.0	Quick
192	08/05/26 07:47:25	Negative	3	Room	Office	Wall	Interior Wall	Drywall	Gray	Intact		-0.0	Quick
193	08/05/26 07:47:41	Negative	3	Room	Office	Wall	Interior Wall	Drywall	Gray	Intact		0.0	Quick
194	08/05/26 07:48:00	Negative	3	Room	Office	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
195	08/05/26 07:48:17	Negative	3	Room	Office	Wall	Interior Wall	Drywall	White	Intact		-0.0	Quick
196	08/05/26 07:48:33	Negative	3	Room	Office	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
197	08/05/26 07:48:47	Negative	3	Room	Office	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
198	08/05/26 07:49:02	Negative	3	Room	Office	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
199	08/05/26 07:49:21	Negative	3	Room	Office	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
200	08/05/26 07:49:38	Negative	3	Room	Office	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick

Inspection Site:
1 - 5 Polaris Way,
Aliso Viejo, CA 92656

Inspection Date: 08/04/2026 - 08/05/2026
Total Readings: 452
Action Level: 1.0 (mg/cm²)

Unit Started: 08/04/2026 09:23:02
Unit Ended: 08/05/2026 09:22:06
Classification Level: 1.0 (mg/cm²)

Test #	Date/Time	Result	Job Number	Room	Room Choices	Structure	Choice	Substrate	Color	Condition	Condition Choices	Lead (mg/cm²)	Mode
201	08/05/26 07:50:05	Negative	3	Room	Hallway	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
202	08/05/26 07:50:18	Negative	3	Room	Hallway	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
203	08/05/26 07:50:36	Negative	3	Room	Hallway	Wall	Interior Wall	Drywall	White	Intact		-0.0	Quick
204	08/05/26 07:50:55	Negative	3	Room	Hallway	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
205	08/05/26 07:51:40	Negative	3	Room	Office	Wall	Interior Wall	Drywall	Blue	Intact		-0.0	Quick
206	08/05/26 07:51:54	Negative	3	Room	Office	Wall	Interior Wall	Drywall	Blue	Intact		0.0	Quick
207	08/05/26 07:52:10	Negative	3	Room	Office	Wall	Interior Wall	Drywall	Blue	Intact		0.0	Quick
208	08/05/26 07:52:43	Negative	3	Room	Office	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
209	08/05/26 07:53:19	Negative	3	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
210	08/05/26 07:53:32	Negative	3	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
211	08/05/26 07:53:44	Negative	3	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
212	08/05/26 07:53:56	Negative	3	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
213	08/05/26 07:54:11	Negative	3	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
214	08/05/26 07:54:30	Negative	3	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
215	08/05/26 07:54:55	Negative	3	Room	Hallway	Door	Frame	Metal	White	Intact		0.0	Quick
216	08/05/26 07:55:10	Negative	3	Room	Hallway	Door	Frame	Metal	White	Intact		0.0	Quick
217	08/05/26 07:55:24	Negative	3	Room	Hallway	Door	Frame	Metal	White	Intact		0.0	Quick
218	08/05/26 07:55:44	Negative	3	Room	Hallway	Door	Frame	Metal	Gray	Intact		0.0	Quick
219	08/05/26 07:55:58	Negative	3	Room	Hallway	Door	Frame	Metal	Gray	Intact		0.0	Quick
220	08/05/26 07:56:24	Negative	3	Room	Hallway	Door	Frame	Metal	Gray	Intact		0.0	Quick

Inspection Site:
1 - 5 Polaris Way,
Aliso Viejo, CA 92656

Inspection Date: 08/04/2026 - 08/05/2026
Total Readings: 452
Action Level: 1.0 (mg/cm²)

Unit Started: 08/04/2026 09:23:02
Unit Ended: 08/05/2026 09:22:06
Classification Level: 1.0 (mg/cm²)

Test #	Date/Time	Result	Job Number	Room	Room Choices	Structure	Choice	Substrate	Color	Condition	Condition Choices	Lead (mg/cm²)	Mode
221	08/05/26 07:56:57	Negative	3	Room	Hallway	Door		Wood	Brown	Intact		0.0	Quick
222	08/05/26 07:57:08	Negative	3	Room	Hallway	Door		Wood	Brown	Intact		-0.0	Quick
223	08/05/26 07:57:17	Negative	3	Room	Hallway	Door		Wood	Brown	Intact		-0.0	Quick
224	08/05/26 07:57:32	Negative	3	Room	Hallway	Door		Wood	Brown	Intact		0.0	Quick
225	08/05/26 07:57:53	Negative	3	Room	Hallway	Door		Wood	White	Intact		0.0	Quick
226	08/05/26 07:58:03	Negative	3	Room	Hallway	Door		Wood	White	Intact		0.0	Quick
227	08/05/26 07:58:14	Negative	3	Room	Hallway	Door		Wood	White	Intact		0.0	Quick
228	08/05/26 07:58:56	Negative	3	Room	Hallway	Door		Wood	White	Intact		0.0	Quick
229	08/05/26 07:59:47	Negative	3	Room	Office	Door		Wood	Brown	Intact		-0.0	Quick
230	08/05/26 08:00:00	Negative	3	Room	Office	Door		Wood	Brown	Intact		0.0	Quick
231	08/05/26 08:00:21	Negative	3	Room	Office	Door		Wood	Brown	Intact		0.0	Quick
232	08/05/26 08:00:39	Negative	3	Room	Office	Door		Wood	Brown	Intact		0.0	Quick
233	08/05/26 08:00:52	Negative	3	Room	Office	Door		Wood	Brown	Intact		-0.0	Quick
234	08/05/26 08:01:07	Negative	3	Room	Office	Door		Wood	Brown	Intact		0.0	Quick
235	08/05/26 08:01:24	Negative	3	Room	Office	Door		Wood	Brown	Intact		0.0	Quick
236	08/05/26 08:02:12	Negative	3	Room	Office	Window	Sill	Metal	White	Intact		0.0	Quick
237	08/05/26 08:02:28	Negative	3	Room	Office	Window	Sill	Metal	White	Intact		-0.0	Quick
238	08/05/26 08:02:40	Negative	3	Room	Office	Window	Sill	Metal	White	Intact		0.0	Quick
239	08/05/26 08:02:52	Negative	3	Room	Office	Window	Sill	Metal	White	Intact		0.0	Quick
240	08/05/26 08:03:13	Negative	3	Room	Office	Window	Sill	Metal	Gray	Intact		0.0	Quick

Inspection Site:
1 - 5 Polaris Way,
Aliso Viejo, CA 92656

Inspection Date: 08/04/2026 - 08/05/2026
Total Readings: 452
Action Level: 1.0 (mg/cm²)

Unit Started: 08/04/2026 09:23:02
Unit Ended: 08/05/2026 09:22:06
Classification Level: 1.0 (mg/cm²)

Test #	Date/Time	Result	Job Number	Room	Room Choices	Structure	Choice	Substrate	Color	Condition	Condition Choices	Lead (mg/cm²)	Mode
241	08/05/26 08:03:36	Negative	3	Room	Office	Window	Sill	Metal	Gray	Intact		0.0	Quick
242	08/05/26 08:03:48	Negative	3	Room	Office	Window	Sill	Metal	Gray	Intact		0.0	Quick
243	08/05/26 08:04:02	Negative	3	Room	Office	Window	Sill	Metal	Gray	Intact		0.0	Quick
244	08/05/26 08:04:24	Negative	3	Room	Office	Window	Frame	Metal	Gray	Intact		0.0	Quick
245	08/05/26 08:04:37	Negative	3	Room	Office	Window	Frame	Metal	Gray	Intact		0.0	Quick
246	08/05/26 08:05:01	Negative	3	Room	Office	Window	Frame	Metal	Gray	Intact		0.0	Quick
247	08/05/26 08:05:15	Negative	3	Room	Office	Window	Frame	Metal	Gray	Intact		0.0	Quick
248	08/05/26 08:05:30	Negative	3	Room	Office	Window	Frame	Metal	Gray	Intact		0.0	Quick
249	08/05/26 08:05:47	Negative	3	Room	Office	Window	Frame	Metal	White	Intact		0.0	Quick
250	08/05/26 08:05:59	Negative	3	Room	Office	Window	Frame	Metal	White	Intact		0.0	Quick
251	08/05/26 08:06:12	Negative	3	Room	Office	Window	Frame	Metal	White	Intact		-0.0	Quick
252	08/05/26 08:06:25	Negative	3	Room	Office	Window	Frame	Metal	White	Intact		0.0	Quick
253	08/05/26 08:07:15	Negative	3	Room	Custodian	Sink	Basin	Porcelain	White	Intact		-0.0	Quick
254	08/05/26 08:07:59	Negative	3	Room	Electrical Room	Electric Panel	Frame	Metal	Gray	Intact		0.0	Quick
255	08/05/26 08:08:30	Negative	3	Room	Electrical Room	Electric Panel	Door	Metal	Gray	Intact		0.0	Quick
256	08/05/26 08:09:11	Negative	3	Room	Restroom	Restroom	Floor Tile	Ceramic	Gray	Intact		-0.0	Quick
257	08/05/26 08:09:29	Negative	3	Room	Restroom	Restroom	Floor Tile	Ceramic	Gray	Intact		0.0	Quick
258	08/05/26 08:09:51	Negative	3	Room	Restroom	Restroom	Wall Tile	Ceramic	Gray	Intact		0.0	Quick
259	08/05/26 08:10:30	Negative	3	Room	Restroom	Restroom	Counter	Marble	Black	Intact		-0.0	Quick
260	08/05/26 08:11:00	Negative	3	Room	Restroom	Restroom	Urinal	Porcelain	White	Intact		0.0	Quick

Inspection Site:
1 - 5 Polaris Way,
Aliso Viejo, CA 92656

Inspection Date: 08/04/2026 - 08/05/2026
Total Readings: 452
Action Level: 1.0 (mg/cm²)

Unit Started: 08/04/2026 09:23:02
Unit Ended: 08/05/2026 09:22:06
Classification Level: 1.0 (mg/cm²)

Test #	Date/Time	Result	Job Number	Room	Room Choices	Structure	Choice	Substrate	Color	Condition	Condition Choices	Lead (mg/cm²)	Mode
261	08/05/26 08:11:22	Negative	3	Room	Restroom	Restroom	Toilet	Porcelain	White	Intact		0.0	Quick
262	08/05/26 08:11:34	Negative	3	Room	Restroom	Restroom	Toilet	Porcelain	White	Intact		-0.0	Quick
263	08/05/26 08:11:46	Negative	3	Room	Restroom	Restroom	Toilet	Porcelain	White	Intact		0.0	Quick
264	08/05/26 08:12:08	Negative	3	Room	Restroom	Restroom	Sink	Porcelain	White	Intact		0.0	Quick
265	08/05/26 08:12:24	Negative	3	Room	Restroom	Restroom	Sink	Porcelain	White	Intact		0.0	Quick
266	08/05/26 08:13:56	Negative	3	Exterior	Structure Exterior	Wall	Exterior Wall	Stucco	Tan	Intact		0.0	Quick
267	08/05/26 08:14:10	Negative	3	Exterior	Structure Exterior	Wall	Exterior Wall	Stucco	Tan	Intact		0.0	Quick
268	08/05/26 08:14:23	Negative	3	Exterior	Structure Exterior	Wall	Exterior Wall	Stucco	Tan	Intact		0.0	Quick
269	08/05/26 08:15:08	Negative	3	Exterior	Structure Exterior	Window	Frame	Metal	Tan	Intact		0.0	Quick
270	08/05/26 08:15:28	Negative	3	Exterior	Structure Exterior	Window	Frame	Metal	Tan	Intact		-0.0	Quick
271	08/05/26 08:15:45	Negative	3	Exterior	Structure Exterior	Window	Frame	Metal	Tan	Intact		0.0	Quick
272	08/05/26 08:16:01	Negative	3	Exterior	Structure Exterior	Window	Frame	Metal	Tan	Intact		0.0	Quick
273	08/05/26 08:16:38	Negative	3	Exterior	Structure Exterior	Door	Frame	Metal	Tan	Intact		0.0	Quick
274	08/05/26 08:16:51	Negative	3	Exterior	Structure Exterior	Door	Frame	Metal	Tan	Intact		0.0	Quick
275	08/05/26 08:17:14	Negative	3	Exterior	Structure Exterior	Door		Metal	Tan	Intact		0.0	Quick
276	08/05/26 08:17:29	Negative	3	Exterior	Structure Exterior	Door		Metal	Tan	Intact		0.0	Quick
277	08/05/26 08:19:02	Negative	4	Exterior	Structure Exterior	Door		Metal	Tan	Intact		0.0	Quick
278	08/05/26 08:19:22	Negative	4	Exterior	Structure Exterior	Door		Metal	Tan	Intact		0.0	Quick
279	08/05/26 08:19:49	Negative	4	Exterior	Structure Exterior	Door	Frame	Metal	Tan	Intact		0.0	Quick
280	08/05/26 08:20:05	Negative	4	Exterior	Structure Exterior	Door	Frame	Metal	Tan	Intact		0.0	Quick

Inspection Site:
1 - 5 Polaris Way,
Aliso Viejo, CA 92656

Inspection Date: 08/04/2026 - 08/05/2026
Total Readings: 452
Action Level: 1.0 (mg/cm²)

Unit Started: 08/04/2026 09:23:02
Unit Ended: 08/05/2026 09:22:06
Classification Level: 1.0 (mg/cm²)

Test #	Date/Time	Result	Job Number	Room	Room Choices	Structure	Choice	Substrate	Color	Condition	Condition Choices	Lead (mg/cm²)	Mode
281	08/05/26 08:20:41	Negative	4	Exterior	Structure Exterior	Window	Frame	Metal	Tan	Intact		0.0	Quick
282	08/05/26 08:20:55	Negative	4	Exterior	Structure Exterior	Window	Frame	Metal	Tan	Intact		0.0	Quick
283	08/05/26 08:21:07	Negative	4	Exterior	Structure Exterior	Window	Frame	Metal	Tan	Intact		0.0	Quick
284	08/05/26 08:21:23	Negative	4	Exterior	Structure Exterior	Window	Frame	Metal	Tan	Intact		0.0	Quick
285	08/05/26 08:21:54	Negative	4	Exterior	Structure Exterior	Wall	Exterior Wall	Stucco	Tan	Intact		0.0	Quick
286	08/05/26 08:22:05	Negative	4	Exterior	Structure Exterior	Wall	Exterior Wall	Stucco	Tan	Intact		0.0	Quick
287	08/05/26 08:22:20	Negative	4	Exterior	Structure Exterior	Wall	Exterior Wall	Stucco	Tan	Intact		0.0	Quick
288	08/05/26 08:22:32	Negative	4	Exterior	Structure Exterior	Wall	Exterior Wall	Stucco	Tan	Intact		0.0	Quick
289	08/05/26 08:23:27	Negative	4	Room	Office	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
290	08/05/26 08:23:42	Negative	4	Room	Office	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
291	08/05/26 08:23:57	Negative	4	Room	Office	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
292	08/05/26 08:24:19	Negative	4	Room	Office	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
293	08/05/26 08:24:38	Negative	4	Room	Office	Wall	Interior Wall	Drywall	White	Intact		-0.0	Quick
294	08/05/26 08:24:58	Negative	4	Room	Office	Wall	Interior Wall	Drywall	Gray	Intact		0.0	Quick
295	08/05/26 08:25:16	Negative	4	Room	Office	Wall	Interior Wall	Drywall	Gray	Intact		0.0	Quick
296	08/05/26 08:25:31	Negative	4	Room	Office	Wall	Interior Wall	Drywall	Gray	Intact		0.0	Quick
297	08/05/26 08:25:47	Negative	4	Room	Office	Wall	Interior Wall	Drywall	Gray	Intact		0.0	Quick
298	08/05/26 08:26:13	Negative	4	Room	Office	Wall	Interior Wall	Drywall	Gray	Intact		-0.0	Quick
299	08/05/26 08:26:37	Negative	4	Room	Office	Wall	Interior Wall	Drywall	Gray	Intact		0.0	Quick
300	08/05/26 08:26:54	Negative	4	Room	Office	Wall	Interior Wall	Drywall	Gray	Intact		0.0	Quick

Inspection Site:
1 - 5 Polaris Way,
Aliso Viejo, CA 92656

Inspection Date: 08/04/2026 - 08/05/2026
Total Readings: 452
Action Level: 1.0 (mg/cm²)

Unit Started: 08/04/2026 09:23:02
Unit Ended: 08/05/2026 09:22:06
Classification Level: 1.0 (mg/cm²)

Test #	Date/Time	Result	Job Number	Room	Room Choices	Structure	Choice	Substrate	Color	Condition	Condition Choices	Lead (mg/cm²)	Mode
301	08/05/26 08:27:08	Negative	4	Room	Office	Wall	Interior Wall	Drywall	Gray	Intact		0.0	Quick
302	08/05/26 08:27:39	Negative	4	Room	Hallway	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
303	08/05/26 08:27:54	Negative	4	Room	Hallway	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
304	08/05/26 08:28:13	Negative	4	Room	Hallway	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
305	08/05/26 08:28:27	Negative	4	Room	Hallway	Wall	Interior Wall	Drywall	White	Intact		-0.0	Quick
306	08/05/26 08:28:40	Negative	4	Room	Hallway	Wall	Interior Wall	Drywall	White	Intact		-0.0	Quick
307	08/05/26 08:28:57	Negative	4	Room	Hallway	Wall	Interior Wall	Drywall	White	Intact		-0.0	Quick
308	08/05/26 08:29:09	Negative	4	Room	Hallway	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
309	08/05/26 08:29:22	Negative	4	Room	Hallway	Wall	Interior Wall	Drywall	White	Intact		-0.0	Quick
310	08/05/26 08:29:35	Negative	4	Room	Hallway	Wall	Interior Wall	Drywall	White	Intact		-0.0	Quick
311	08/05/26 08:30:39	Negative	4	Room	Office	Door	Frame	Metal	Gray	Intact		0.6	Quick
312	08/05/26 08:31:04	Negative	4	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
313	08/05/26 08:31:22	Negative	4	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
314	08/05/26 08:31:38	Negative	4	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
315	08/05/26 08:32:12	Negative	4	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
316	08/05/26 08:32:46	Negative	4	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
317	08/05/26 08:32:57	Negative	4	Room	Office	Door	Frame	Metal	Gray	Intact		-0.0	Quick
318	08/05/26 08:33:10	Negative	4	Room	Office	Door	Frame	Metal	Gray	Intact		-0.0	Quick
319	08/05/26 08:33:21	Negative	4	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
320	08/05/26 08:33:32	Negative	4	Room	Office	Door	Frame	Metal	Gray	Intact		-0.0	Quick

Inspection Site:
1 - 5 Polaris Way,
Aliso Viejo, CA 92656

Inspection Date: 08/04/2026 - 08/05/2026
Total Readings: 452
Action Level: 1.0 (mg/cm²)

Unit Started: 08/04/2026 09:23:02
Unit Ended: 08/05/2026 09:22:06
Classification Level: 1.0 (mg/cm²)

Test #	Date/Time	Result	Job Number	Room	Room Choices	Structure	Choice	Substrate	Color	Condition	Condition Choices	Lead (mg/cm²)	Mode
321	08/05/26 08:33:53	Negative	4	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
322	08/05/26 08:34:22	Negative	4	Room	Hallway	Door	Frame	Metal	White	Intact		-0.0	Quick
323	08/05/26 08:34:38	Negative	4	Room	Hallway	Door	Frame	Metal	White	Intact		0.0	Quick
324	08/05/26 08:34:59	Negative	4	Room	Hallway	Door	Frame	Metal	White	Intact		-0.0	Quick
325	08/05/26 08:35:43	Negative	4	Room	Hallway	Door	Frame	Metal	White	Intact		-0.0	Quick
326	08/05/26 08:35:54	Negative	4	Room	Hallway	Door	Frame	Metal	White	Intact		-0.0	Quick
327	08/05/26 08:36:05	Negative	4	Room	Hallway	Door	Frame	Metal	White	Intact		-0.0	Quick
328	08/05/26 08:36:20	Negative	4	Room	Hallway	Door	Frame	Metal	White	Intact		0.0	Quick
329	08/05/26 08:36:51	Negative	4	Room	Hallway	Door		Wood	White	Intact		-0.0	Quick
330	08/05/26 08:37:09	Negative	4	Room	Hallway	Door		Wood	White	Intact		-0.0	Quick
331	08/05/26 08:37:29	Negative	4	Room	Hallway	Door		Wood	White	Intact		-0.0	Quick
332	08/05/26 08:37:51	Negative	4	Room	Hallway	Door		Wood	White	Intact		-0.0	Quick
333	08/05/26 08:38:05	Negative	4	Room	Hallway	Door		Wood	White	Intact		0.0	Quick
334	08/05/26 08:38:40	Negative	4	Room	Office	Door		Wood	Brown	Intact		0.0	Quick
335	08/05/26 08:39:05	Negative	4	Room	Office	Door		Wood	Brown	Intact		0.0	Quick
336	08/05/26 08:39:18	Negative	4	Room	Office	Door		Wood	Brown	Intact		-0.0	Quick
337	08/05/26 08:39:32	Negative	4	Room	Office	Door		Wood	Brown	Intact		-0.0	Quick
338	08/05/26 08:39:44	Negative	4	Room	Office	Door		Wood	Brown	Intact		-0.0	Quick
339	08/05/26 08:39:57	Negative	4	Room	Office	Door			Brown	Intact		0.0	Quick
340	08/05/26 08:40:29	Negative	4	Room	Office	Door		Wood	Brown	Intact		0.0	Quick

Inspection Site:
1 - 5 Polaris Way,
Aliso Viejo, CA 92656

Inspection Date: 08/04/2026 - 08/05/2026
Total Readings: 452
Action Level: 1.0 (mg/cm²)

Unit Started: 08/04/2026 09:23:02
Unit Ended: 08/05/2026 09:22:06
Classification Level: 1.0 (mg/cm²)

Test #	Date/Time	Result	Job Number	Room	Room Choices	Structure	Choice	Substrate	Color	Condition	Condition Choices	Lead (mg/cm²)	Mode
341	08/05/26 08:40:46	Negative	4	Room	Office	Door		Wood	Brown	Intact		0.0	Quick
342	08/05/26 08:41:03	Negative	4	Room	Office	Door		Wood	Brown	Intact		-0.0	Quick
343	08/05/26 08:41:18	Negative	4	Room	Office	Door		Wood	Brown	Intact		0.0	Quick
344	08/05/26 08:42:02	Negative	4	Room	Office	Window	Sill	Metal	Gray	Intact		0.0	Quick
345	08/05/26 08:42:18	Negative	4	Room	Office	Window	Sill	Metal	Gray	Intact		0.0	Quick
346	08/05/26 08:42:36	Negative	4	Room	Office	Window	Sill	Metal	Gray	Intact		0.0	Quick
347	08/05/26 08:42:51	Negative	4	Room	Office	Window	Sill	Metal	Gray	Intact		0.0	Quick
348	08/05/26 08:43:09	Negative	4	Room	Office	Window	Sill	Metal	Gray	Intact		0.0	Quick
349	08/05/26 08:43:23	Negative	4	Room	Office	Window	Sill	Metal	Gray	Intact		0.0	Quick
350	08/05/26 08:43:37	Negative	4	Room	Office	Window	Sill	Metal	Gray	Intact		0.0	Quick
351	08/05/26 08:43:55	Negative	4	Room	Office	Window	Sill	Metal	Gray	Intact		0.0	Quick
352	08/05/26 08:44:19	Negative	4	Room	Office	Window	Frame	Metal	Gray	Intact		0.0	Quick
353	08/05/26 08:44:38	Negative	4	Room	Office	Window	Frame	Metal	Gray	Intact		0.0	Quick
354	08/05/26 08:44:54	Negative	4	Room	Office	Window	Frame	Metal	Gray	Intact		0.0	Quick
355	08/05/26 08:45:10	Negative	4	Room	Office	Window	Frame	Metal	Gray	Intact		0.0	Quick
356	08/05/26 08:45:25	Negative	4	Room	Office	Window	Frame	Metal	Gray	Intact		0.0	Quick
357	08/05/26 08:45:39	Negative	4	Room	Office	Window	Frame	Metal	Gray	Intact		0.0	Quick
358	08/05/26 08:45:54	Negative	4	Room	Office	Window	Frame	Metal	Gray	Intact		0.0	Quick
359	08/05/26 08:46:44	Negative	4	Room	Custodian	Sink	Basin	Porcelain	White	Intact		0.0	Quick
360	08/05/26 08:47:41	Negative	4	Room	Electrical Room	Electric Panel	Frame	Metal	Gray	Intact		-0.0	Quick

Inspection Site:
1 - 5 Polaris Way,
Aliso Viejo, CA 92656

Inspection Date: 08/04/2026 - 08/05/2026
Total Readings: 452
Action Level: 1.0 (mg/cm²)

Unit Started: 08/04/2026 09:23:02
Unit Ended: 08/05/2026 09:22:06
Classification Level: 1.0 (mg/cm²)

Test #	Date/Time	Result	Job Number	Room	Room Choices	Structure	Choice	Substrate	Color	Condition	Condition Choices	Lead (mg/cm²)	Mode
361	08/05/26 08:48:02	Negative	4	Room	Electrical Room	Electric Panel	Door	Metal	Gray	Intact		0.0	Quick
362	08/05/26 08:49:01	Negative	4	Room	Lobby	Floor	Tile	Ceramic	Tan	Intact		0.0	Quick
363	08/05/26 08:51:08	Negative	4	Room	Restroom	Restroom	Counter	Marble	Black	Intact		0.0	Quick
364	08/05/26 08:51:35	Negative	4	Room	Restroom	Restroom	Floor Tile	Ceramic	Gray	Intact		-0.0	Quick
365	08/05/26 08:51:58	Negative	4	Room	Restroom	Restroom	Wall Tile	Ceramic	Gray	Intact		0.0	Quick
366	08/05/26 08:52:26	Negative	4	Room	Restroom	Restroom	Urinal	Porcelain	White	Intact		0.0	Quick
367	08/05/26 08:52:48	Negative	4	Room	Restroom	Restroom	Toilet	Porcelain	White	Intact		-0.0	Quick
368	08/05/26 08:53:03	Negative	4	Room	Restroom	Restroom	Toilet	Porcelain	White	Intact		0.0	Quick
369	08/05/26 08:53:16	Negative	4	Room	Restroom	Restroom	Toilet	Porcelain	White	Intact		-0.0	Quick
370	08/05/26 08:53:27	Negative	4	Room	Restroom	Restroom	Toilet	Porcelain	White	Intact		0.0	Quick
371	08/05/26 08:53:52	Negative	4	Room	Restroom	Restroom	Sink	Porcelain	White	Intact		-0.0	Quick
372	08/05/26 08:54:04	Negative	4	Room	Restroom	Restroom	Sink	Porcelain	White	Intact		0.0	Quick
373	08/05/26 08:55:37	Negative	5	Exterior	Structure Exterior	Wall	Exterior Wall	Stucco	Blue	Intact		0.0	Quick
374	08/05/26 08:55:50	Negative	5	Exterior	Structure Exterior	Wall	Exterior Wall	Stucco	Blue	Intact		0.0	Quick
375	08/05/26 08:56:06	Negative	5	Exterior	Structure Exterior	Wall	Exterior Wall	Stucco	Tan	Intact		0.0	Quick
376	08/05/26 08:56:30	Negative	5	Exterior	Structure Exterior	Door	Frame	Metal	Tan	Intact		0.0	Quick
377	08/05/26 08:56:45	Negative	5	Exterior	Structure Exterior	Door	Frame	Metal	Tan	Intact		0.0	Quick
378	08/05/26 08:57:08	Negative	5	Exterior	Structure Exterior	Door		Metal	Tan	Intact		0.0	Quick
379	08/05/26 08:57:22	Negative	5	Exterior	Structure Exterior	Door		Metal	Tan	Intact		0.0	Quick
380	08/05/26 08:59:07	Negative	5	Exterior	Structure Exterior	Window	Frame	Metal	Tan	Intact		0.0	Quick

Inspection Site:
1 - 5 Polaris Way,
Aliso Viejo, CA 92656

Inspection Date: 08/04/2026 - 08/05/2026
Total Readings: 452
Action Level: 1.0 (mg/cm²)

Unit Started: 08/04/2026 09:23:02
Unit Ended: 08/05/2026 09:22:06
Classification Level: 1.0 (mg/cm²)

Test #	Date/Time	Result	Job Number	Room	Room Choices	Structure	Choice	Substrate	Color	Condition	Condition Choices	Lead (mg/cm²)	Mode
381	08/05/26 08:59:20	Negative	5	Exterior	Structure Exterior	Window	Frame	Metal	Tan	Intact		-0.0	Quick
382	08/05/26 09:00:15	Negative	5	Exterior	Structure Exterior	Window	Frame	Metal	Tan	Intact		0.0	Quick
383	08/05/26 09:00:27	Negative	5	Exterior	Structure Exterior	Window	Frame	Metal	Tan	Intact		0.0	Quick
384	08/05/26 09:00:41	Negative	5	Exterior	Structure Exterior	Window	Frame	Metal	Tan	Intact		0.0	Quick
385	08/05/26 09:01:23	Negative	5	Room	Hallway	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
386	08/05/26 09:01:39	Negative	5	Room	Hallway	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
387	08/05/26 09:01:50	Negative	5	Room	Hallway	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
388	08/05/26 09:02:03	Negative	5	Room	Hallway	Wall	Interior Wall	Drywall	White	Intact		-0.0	Quick
389	08/05/26 09:02:22	Negative	5	Room	Hallway	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
390	08/05/26 09:02:35	Negative	5	Room	Hallway	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
391	08/05/26 09:03:22	Negative	5	Room	Office	Wall	Interior Wall	Drywall	Gray	Intact		-0.0	Quick
392	08/05/26 09:03:35	Negative	5	Room	Office	Wall	Interior Wall	Drywall	Gray	Intact		0.0	Quick
393	08/05/26 09:03:45	Negative	5	Room	Office	Wall	Interior Wall	Drywall	Gray	Intact		0.0	Quick
394	08/05/26 09:03:56	Negative	5	Room	Office	Wall	Interior Wall	Drywall	Gray	Intact		0.0	Quick
395	08/05/26 09:04:07	Negative	5	Room	Office	Wall	Interior Wall	Drywall	Gray	Intact		-0.0	Quick
396	08/05/26 09:04:19	Negative	5	Room	Office	Wall	Interior Wall	Drywall	Gray	Intact		0.0	Quick
397	08/05/26 09:04:35	Negative	5	Room	Office	Wall	Interior Wall	Drywall	White	Intact		-0.0	Quick
398	08/05/26 09:04:46	Negative	5	Room	Office	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
399	08/05/26 09:05:07	Negative	5	Room	Office	Wall	Interior Wall	Drywall	White	Intact		-0.0	Quick
400	08/05/26 09:05:20	Negative	5	Room	Office	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick

Inspection Site:
1 - 5 Polaris Way,
Aliso Viejo, CA 92656

Inspection Date: 08/04/2026 - 08/05/2026
Total Readings: 452
Action Level: 1.0 (mg/cm²)

Unit Started: 08/04/2026 09:23:02
Unit Ended: 08/05/2026 09:22:06
Classification Level: 1.0 (mg/cm²)

Test #	Date/Time	Result	Job Number	Room	Room Choices	Structure	Choice	Substrate	Color	Condition	Condition Choices	Lead (mg/cm²)	Mode
401	08/05/26 09:05:33	Negative	5	Room	Office	Wall	Interior Wall	Drywall	White	Intact		-0.0	Quick
402	08/05/26 09:05:45	Negative	5	Room	Office	Wall	Interior Wall	Drywall	White	Intact		0.0	Quick
403	08/05/26 09:05:56	Negative	5	Room	Office	Wall	Interior Wall	Drywall	White	Intact		-0.0	Quick
404	08/05/26 09:06:08	Negative	5	Room	Office	Wall	Interior Wall	Drywall	White	Intact		-0.0	Quick
405	08/05/26 09:06:18	Negative	5	Room	Office	Wall	Interior Wall	Drywall	White	Intact		-0.0	Quick
406	08/05/26 09:06:58	Negative	5	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
407	08/05/26 09:07:10	Negative	5	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
408	08/05/26 09:07:22	Negative	5	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
409	08/05/26 09:07:35	Negative	5	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
410	08/05/26 09:07:47	Negative	5	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
411	08/05/26 09:07:57	Negative	5	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
412	08/05/26 09:08:08	Negative	5	Room	Office	Door	Frame	Metal	Gray	Intact		0.0	Quick
413	08/05/26 09:08:38	Negative	5	Room	Hallway	Door	Frame	Metal	White	Intact		0.0	Quick
414	08/05/26 09:08:48	Negative	5	Room	Hallway	Door	Frame	Metal	White	Intact		0.0	Quick
415	08/05/26 09:09:04	Negative	5	Room	Hallway	Door	Frame	Metal	White	Intact		0.0	Quick
416	08/05/26 09:09:16	Negative	5	Room	Hallway	Door	Frame	Metal	White	Intact		0.0	Quick
417	08/05/26 09:09:43	Negative	5	Room	Hallway	Door		Wood	White	Intact		0.0	Quick
418	08/05/26 09:09:57	Negative	5	Room	Hallway	Door		Wood	White	Intact		-0.0	Quick
419	08/05/26 09:10:12	Negative	5	Room	Hallway	Door		Wood	White	Intact		-0.0	Quick
420	08/05/26 09:10:27	Negative	5	Room	Hallway	Door		Wood	Brown	Intact		0.0	Quick

Inspection Site:
1 - 5 Polaris Way,
Aliso Viejo, CA 92656

Inspection Date: 08/04/2026 - 08/05/2026
Total Readings: 452
Action Level: 1.0 (mg/cm²)

Unit Started: 08/04/2026 09:23:02
Unit Ended: 08/05/2026 09:22:06
Classification Level: 1.0 (mg/cm²)

Test #	Date/Time	Result	Job Number	Room	Room Choices	Structure	Choice	Substrate	Color	Condition	Condition Choices	Lead (mg/cm²)	Mode
421	08/05/26 09:10:55	Negative	5	Room	Office	Door		Wood	Brown	Intact		0.0	Quick
422	08/05/26 09:11:14	Negative	5	Room	Office	Door		Wood	Brown	Intact		0.0	Quick
423	08/05/26 09:11:27	Negative	5	Room	Office	Door		Wood	Brown	Intact		0.0	Quick
424	08/05/26 09:11:38	Negative	5	Room	Office	Door		Wood	Brown	Intact		0.0	Quick
425	08/05/26 09:11:53	Negative	5	Room	Office	Door		Wood	Brown	Intact		-0.0	Quick
426	08/05/26 09:12:06	Negative	5	Room	Office	Door		Wood	Brown	Intact		-0.0	Quick
427	08/05/26 09:12:53	Negative	5	Room	Office	Door		Wood	Brown	Intact		0.0	Quick
428	08/05/26 09:13:06	Negative	5	Room	Office	Door		Wood	Brown	Intact		0.0	Quick
429	08/05/26 09:13:45	Negative	5	Room	Office	Door		Wood	Brown	Intact		-0.0	Quick
430	08/05/26 09:14:18	Negative	5	Room	Office	Window	Sill	Metal	White	Intact		0.0	Quick
431	08/05/26 09:14:29	Negative	5	Room	Office	Window	Sill	Metal	White	Intact		0.0	Quick
432	08/05/26 09:14:39	Negative	5	Room	Office	Window	Sill	Metal	White	Intact		0.0	Quick
433	08/05/26 09:14:50	Negative	5	Room	Office	Window	Sill	Metal	White	Intact		0.0	Quick
434	08/05/26 09:15:02	Negative	5	Room	Office	Window	Sill	Metal	White	Intact		0.0	Quick
435	08/05/26 09:15:21	Negative	5	Room	Office	Window	Frame	Metal	White	Intact		0.0	Quick
436	08/05/26 09:15:32	Negative	5	Room	Office	Window	Frame	Metal	White	Intact		0.0	Quick
437	08/05/26 09:15:43	Negative	5	Room	Office	Window	Frame	Metal	White	Intact		0.0	Quick
438	08/05/26 09:15:53	Negative	5	Room	Office	Window	Frame	Metal	White	Intact		0.0	Quick
439	08/05/26 09:16:03	Negative	5	Room	Office	Window	Frame	Metal	White	Intact		0.0	Quick
440	08/05/26 09:17:08	Negative	5	Room	Electrical Room	Electric Panel	Frame	Metal	Gray	Intact		0.0	Quick

Inspection Site:
1 - 5 Polaris Way,
Aliso Viejo, CA 92656

Inspection Date: 08/04/2026 - 08/05/2026
Total Readings: 452
Action Level: 1.0 (mg/cm²)

Unit Started: 08/04/2026 09:23:02
Unit Ended: 08/05/2026 09:22:06
Classification Level: 1.0 (mg/cm²)

Test #	Date/Time	Result	Job Number	Room	Room Choices	Structure	Choice	Substrate	Color	Condition	Condition Choices	Lead (mg/cm²)	Mode
441	08/05/26 09:17:20	Negative	5	Room	Electrical Room	Electric Panel	Frame	Metal	Gray	Intact		0.0	Quick
442	08/05/26 09:17:46	Negative	5	Room	Electrical Room	Electric Panel	Door	Metal	Gray	Intact		0.0	Quick
443	08/05/26 09:18:10	Negative	5	Room	Electrical Room	Electric Panel	Door	Metal	Gray	Intact		0.0	Quick
444	08/05/26 09:18:50	Negative	5	Room	Custodian	Sink	Basin	Porcelain	White	Intact		0.0	Quick
445	08/05/26 09:19:25	Negative	5	Room	Restroom	Restroom	Counter	Marble	Black	Intact		0.0	Quick
446	08/05/26 09:20:03	Negative	5	Room	Restroom	Restroom	Urinal	Porcelain	White	Intact		-0.0	Quick
447	08/05/26 09:20:31	Negative	5	Room	Restroom	Restroom	Toilet	Porcelain	White	Intact		0.0	Quick
448	08/05/26 09:20:49	Negative	5	Room	Restroom	Restroom	Toilet	Porcelain	White	Intact		0.0	Quick
449	08/05/26 09:21:00	Negative	5	Room	Restroom	Restroom	Toilet	Porcelain	White	Intact		0.0	Quick
450	08/05/26 09:21:38	Negative	5	Room	Restroom	Restroom	Floor Tile	Ceramic	Gray	Intact		0.0	Quick
451	08/05/26 09:21:48	Negative	5	Room	Restroom	Restroom	Floor Tile	Ceramic	Gray	Intact		0.0	Quick
452	08/05/26 09:22:06	Negative	5	Room	Restroom	Restroom	Wall Tile	Ceramic	Gray	Intact		0.0	Quick

--- End of Readings ---

Certifications

STATE OF CALIFORNIA
DEPARTMENT OF PUBLIC HEALTH

LEAD-RELATED CONSTRUCTION CERTIFICATE

INDIVIDUAL:	CERTIFICATE TYPE:	NUMBER:	EXPIRATION DATE:
David Johnson	Lead Inspector/Assessor	LRC-00009289	10/8/2027

Disclaimer: This document alone should not be relied upon to confirm certification status. Compare the individual's photo and name to another valid form of government issued photo identification. Verify the individual's certification status by searching for Lead-Related Construction Professionals at www.cdph.ca.gov/programs/clppb or calling (800) 597-LEAD

Certificate of Training

David G Johnson

Of Vector Environmental has completed the SciAps instrument operator and Radiation Training for the

X550 Pb HUD/EPA Lead Paint Analyzer provided by Rick Rainville.

SciAps

Instrument Operator Training and Radiation Training for the

X550 Pb HUD/EPA Lead Paint Analyzer

I confirm that the above-named individual has received the training listed on this certificate.

Rick Rainville
Name

April 03, 2025
Date

Certified Trainer
Title

I certify that I have received the stated training and understand the content presented.

David G Johnson
Name

April 03, 2025
Date

Certificate of Training

Levi M Misenhimer

Of Vector Environmental has completed the SciAps instrument operator and Radiation Training for the

X550 Pb HUD/EPA Lead Paint Analyzer provided by Rick Rainville.

SciAps

Instrument Operator Training and Radiation Training for the

X550 Pb HUD/EPA Lead Paint Analyzer

I confirm that the above-named individual has received the training listed on this certificate.

Rick Rainville
Name

April 03, 2025
Date

Certified Trainer
Title

I certify that I have received the stated training and understand the content presented.

Levi M Misenhimer
Name

April 03, 2025
Date